70/70A SERIES REPAIR MANUAL COMPLETE CONTENTS

SECTION 00 - GENERAL INFORMATION 2

SECTION 10 - ENGINE 2

SECTION 21 - TRANSMISSION 7

SECTION 23 - DRIVE LINES 12

SECTION 25 - FRONT MECHANICAL DRIVE 12

SECTION 27 - REAR DRIVE AXLE 15

SECTION 31 - POWER TAKE-OFF 16

SECTION 33 - BRAKES AND CONTROLS 17

SECTION 35 - HYDRAULIC SYSTEMS 20

SECTION 41 - STEERING 29

SECTION 44 - TWO-WHEEL DRIVE AXLE AND WHEELS 30

SECTION 50 - CLIMATE CONTROL 32

SECTION 55 - ELECTRICAL SYSTEMS 33

SECTION 90 - PLATFORM, CAB, AND BODYWORK 40

The following pages are the collation of the contents pages from each section and chapter of the 70/70A Series Repair manual.

The sections used through out all New Holland product Repair manuals may not be used for each product. Each Repair manual will be made up of one or several books. Each book will be labeled as to which sections are in the overall Repair manual and which sections are in each book.

The sections listed above are the sections utilized for the 70/70A Series Tractors.

© 2002 NEW HOLLAND NORTH AMERICA, INC.
Printed In U.S.A.

87018730 6/02

SECTION 00 - GENERAL INFORMATION

BOOK 1 - 87018723

Chapter 1 - General Information

CONTENTS

Section	Description	Page
00 000	Forward	2
	Precautionary Statements	3
	Safety Precautions	4
	Health and Safety Precautions	7
	Tractor Identification	14
	Service Techniques	21
	Sealer Specifications	23
	Hardware Torque Values	23
	Lubrication	26
	Recommended Lubricants and Coolants	26

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 1 – Engine and Lubrication System

CONTENTS

Section	Description	Page
10 000	Specifications	3
	Torque Values	12
	Grease and Sealants	14
	Special Tools	15
	Description of Operation	16
	Cylinder Head Assembly	22
	Camshaft Assembly	22
	Crankshaft Assembly	22
	Connecting Rods	22
	Pistons	22
	Manifolds	22
	Cylinder Block Assembly	22
	Timing Gears	22

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 1 – Engine and Lubrication System (Continued)

CONTENTS

Section	Description	Page
	Engine Lubrication	23
	Troubleshooting	27
	Disassembly and Repair	30
	Cylinder Head	30
	Cylinder Head Reassembly	42
	Additional Information	45
	Crankcase Front Cassette Seal	47
	Parts Affected	47
	Additional Information	47
	Removal of Old Style Seal and Installation of the New Cassette Seal	47
	Front Cassette Seal Removal	53
	Engine Front Cover and Timing Gear	58
	Oil Pan	60
	Connecting Rods, Bearings, Pistons and Rings	61
	Cylinder Block Overhaul	64
	Piston Assembly Installation	69
	Main Bearings, Flywheel and Crankshaft	70
	Rear Cover Plate	72
	Oil Pump	75
	Oil Filter Support Assembly	77
	Crankshaft	78
	Camshaft	82
	Engine Timing Gears	84
	Engine Compression Test	85
	Test Procedure	85
	Test Reading	85
	Test Conclusion	85

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 2 – Cooling System

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	4
	Cooling System	4
	Troubleshooting	6
	Disassembly and Repair	7
	Radiator	7
	Thermostat	9
	Temperature Warning Sender	10
	Fan Blade	10
	Viscous Clutch Assembly	10
	Fan Belt Tensioner	11
	Idler Pulley	11
	Water Pump	12

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 3 – Induction System

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	4
	Air Cleaner	4
	Turbocharger	6
	Intercooler	9
	Troubleshooting	10
	Intercooler Leak Test	12
	Disassembly and Repair	13
	Air Cleaner	13
	Turbocharger	15
	Intercooler	21

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 4 – Fuel System

CONTENTS

Section	Description	Page
10 000	Specifications	3
	Fuel System Torque Chart	4
	Special Tools	4
	Description of Operation	5
	Testing and Diagnosis	19
	Low Pressure Fuel System	20
	Fuel Tank Valves	20
	Filter Inlet and Outlet Pressure Tests	20
	High Pressure Fuel System	25
	Injection Timing Check	25
	Fuel Injector Nozzle Check	28
	Injector Assembly Bench Testing	28
	Preliminary Setup Procedure	29
	Perform Opening Pressure Test	29
	Perform Nozzle Seat Leakage Test	30
	Perform Chatter and Spray Pattern Test	31
	Surging	31
	Fuel Shutoff Diagnosis	32
	Shutoff Solenoid Specifications	32
	Preliminary Checks	32
	Checking Electrical Feed	32
	Adjustments	34
	Bleeding the Fuel System	34
	Adjustment of Foot and Hand Throttle Cables	35
	Adjustment of High Idle Speed	35
	Adjustment of Low Idle and Antisurge	36
	Removal and Installation	37
	Fuel Lift Pump	37
	Fuel Shutoff Solenoid	38
	Fuel Injection Pump	39
	Fuel Injection Lines	47
	Low-pressure Fuel Injection Lines	47
	High-pressure Fuel Lines	48

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 4 – Fuel System (Continued)

CONTENTS

Injector Leak-off Line 50
Fuel Filter 51
Fuel Filter Manifold 52
Injection Nozzles 53

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 5 – Engine Removal

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Engine Removal	4
	Engine Installation	8

SECTION 10 – ENGINE

BOOK 1 - 87018723

Chapter 6 – Fuel Tank Removal

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Lower Tank Removal	4
	Lower Tank Installation	5
	Top Tank Removal	6
	Top Tank Installation	6

SECTION 21 - TRANSMISSION

BOOK 1 - 87018723

Chapter 1 - Operation and Overview

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Powershift Transmission	2
	Gear Ratios	2
	Ground Speed	3
	Electrical System	5
	Description of Operation	6
	Transmission Housing	7
	Powershift Transmission Controls	8
	Digital Display	8
	Inching Pedal	9
	Starting the Engine and Moving Forward	10
	Starting the Engine and Moving in Reverse	11
	Shuttle Operations	12
	Speed Matching	13
	Auto Shift	14
	Creeper Gears (optional)	15
	Programmable Upshift - Downshift	15
	Transmission Components	17
	Clutches	17
	Speed Clutches	17
	Directional Clutches	21
	Clutch Engagement	22
	Troubleshooting and Diagnosis	33

SECTION 21 – TRANSMISSION

BOOK 1 - 87018723

Chapter 2 – Separating the Engine and Front Axle from the Transmission

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Engine and Side Rail Separation from the Transmission	4
	Four-wheel Drive Shaft Removal (if equipped)	8
	Engine and Side Rail Reassembly	10

SECTION 21 – TRANSMISSION

BOOK 1 - 87018723

Chapter 3 – Separating the Rear Axle from the Transmission

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Rear Axle to Transmission Separation	4
	Reassembly	8
	MInimum Hardware Tightening Torques	9

SECTION 21 – TRANSMISSION

BOOK 1 - 87018723

Chapter 4 – Mechanical System

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Torque Specifications	3
	Special Tools	4
	Description of Operation	5
	Troubleshooting and Diagnosis	6
	Disassembly and Repair	7
	Removal and Disassembly	7
	Rear Housing and Directional Clutches - Removal	8
	Front Housing and Speed Clutches - Removal	12
	Main Input Gear Assembly - Removal	14
	Speed Clutches - Disassembly	16
	Speed Clutches - Inspection	21
	Directional Clutches - Disassembly	23
	Directional Clutches - Inspection and Overhaul	26
	Speed/Directional Clutch - Reassembly	27
	Main Input Gear and Oil Seal - Disassembly Inspection, Overhaul and Reassemble	29
	Two Gear Clusters in Front and Rear Housing - Disassembly, Inspection and Reassembly	30
	Front and Rear Housings and Center Section - Inspection and Overhaul	30
	Torque Limiting Clutch and Sprung Damper Hub Drive Assembly - Removal, Inspection and Replacement	32
	Reassembly	33
	Speed Clutches and Front Housing	33
	Directional Clutches and Rear Housing	34
	Transmission Shimming	36
	Front Housing Shimming	36
	Rear Housing Shimming	37
	Shimming the Output Shaft	38
	Creeper Gear	39
	Creeper Gear Repair	41
	Installation	44

SECTION 21 – TRANSMISSION

BOOK 1 - 87018723

Chapter 5 – Hydraulic System

CONTENTS

Section	Description	Page
21 000	Specifications	3
	Low-pressure Hydraulic System	3
	Special Tools	4
	Description of Operation	5
	Regulator Valve Operation	7
	Clutch Valve Operation	7
	Modulator Valve Operation	8
	Electro-hydraulic Pilot Line	9
	Troubleshooting and Diagnosis	10
	70/70A Series Transmission Test Sheet	11
	Electrical/Electronic System Checks	11
	Hydraulic System Checks	13
	Clutch Apply Pressure Chart	14
	Pressure Testing and Adjustments	15
	Clutch Apply Circuit Pressure Testing	17
	Transmission Pressure Checklist	19
	Transmission Programming	21
	Programming the Programmable Upshift, Downshift	21
	Programming Reverse Gear Ratios	23
	Transmission Calibration	25
	Check Powershift Transmission Clutch Calibration	25
	Calibration Review	26
	Calibrate F1 Directional Clutch	26
	Calibrate F2 Directional Clutch	27
	Calibrate Reverse Directional Clutch	27
	Exit Calibration Mode	28

SECTION 21 – TRANSMISSION

BOOK 1 - 87018723

Chapter 6 – Electrical System

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Electrical System	2
	Description of Operation	3
	Clutch Apply Circuits	4
	Modulation Solenoids	4
	Shift Control Lever	5
	Inching Pedal	6
	Speed Sensors	6, 10
	Display Module	6
	Troubleshooting and Diagnosis	7
	Transmission Solenoid and Pressure Testing	8
	Disassembly and Repair	9
	Control Valve Solenoids	9
	Chassis Control Module	11
	Inching Pedal Switches	12
	Transmission Shift Control	14
	Calibration of Shift Constant	28
	Disassembly and Repair	31
	Removal and Disassembly	31
	Removal of the Complete Valve Assembly from the Tractor	31
	Disassembly	33
	Solenoid and Valve Assembly	34
	Speed and Directional Clutch Circuit Valves	34
	Modulator Valves	35
	Regulator Valve	37
	Lubrication and Cooling Circuit Relief Valve	39
	Removal	39
	Installation	39
	Inspection	40
	Reassembly	40
	Installation	41

SECTION 23 - DRIVE LINES

BOOK 2 - 87018724

Chapter 1 - Four-wheel Drive Clutch

CONTENTS

Section	Description	Page
23 202	Description of Operation	2
	70 Series FWD Electronic Control Operation	4
	70A Series FWD Electronic Control Operation	5
	Engaging and Disengaging Four Wheel Drive	5
	FWD Operating Precautions	5
	Disassembly and Repair	8
	Removal	8
	Disassembly	12
	Inspection	13
	Reassembly	15
	Installation	18
	Pressure Testing	23

SECTION 25 - FRONT MECHANICAL DRIVE

BOOK 2 - 87018724

Chapter 1 - Four-Wheel Drive Dana Axle

CONTENTS

Section	Description	Page
25 000	Specifications	2
	Special Tools	4
25 100	Description of Operation	6
	Troubleshooting	15
41 106	Adjustments	16
41 106	Wheel Toe-in	16
25 108	FWD Steering Stop	17
25 108	Hub Bearing Preload Adjustment	18
25 102	Check for Correct Pinion to Ring Gear Tooth Contact	21
25 102	Wrong Tooth Contact Pattern	21
25 108	Swivel Pin Bearing Adjustment	23
25 104	FWD Ratios	23

SECTION 25 – FRONT MECHANICAL DRIVE

BOOK 2 - 87018724

Chapter 1 – Four-Wheel Drive Dana Axle (Continued)

CONTENTS

Section	Description	Page
25 104	FWD Tire vs Gear Ratios	24
	Four Wheel Drive Lead Factor	28
	Front Axle Serviceability	30
00 400	Lubrication	30
	Disassembly and Repair	35
25 100	Front Axle	35
41 216	Steering Cylinders	38
25 108	Planetary Reduction	40
25 108	Hub	44
25 108	Swivel Housing	47
25 108	Center Housing Swivel Bearing	50
25 108	Drive Shaft	51
25 108	Outer Yoke	54
25 102	Differential	56
25 102	Crown Wheel to Backlash Adjustment	69

SECTION 25 – FRONT MECHANICAL DRIVE

BOOK 2 - 87018724

Chapter 2 – Dana Supersteer™ Linkage

CONTENTS

Section	Description	Page
25 100	Description of Operation	2
25 100	Supersteer Linkage Removal	3
25 100	Removal of Rear Support Assembly and Spherical Ball Bushing	5
41 106	Supersteer Linkage Adjustment	9

SECTION 25 - FRONT MECHANICAL DRIVE

BOOK 2 - 87018724

Chapter 3 - Four Wheel Drive Carraro Axle

CONTENTS

Section	Description	Page
	Specifications	2
	Special Tools	3
	General Information	7
	Front Axle Differential Line	8
	Overall Dimensions	11
	General Checks Prior to Disassembly	16
	Disassembly Operations	17
25 100	Front Axle Removal/Installation	17
41 216	Steering Cylinders Group Disassembly	17
41 216	Steering Cylinders Group Assembly	23
25 310	Final Drive Removal	25
25 108	Wheel Hub Disassembly	27
25 108	Wheel Hub Assembly	29
25 108	Swivel Housing Removal	32
25 100	Swivel Housing Assembly	33
25 100	Axle Housing Swivel Bearing	34
25 102	Differential Support Group Disassembly	36
25 102	Differential Support Group Assembly	38
25 102	Input Flange End Play Adjustment	39
25 102	Limited Slip Differential Removal	40
25 102	Limited Slip Pinion Disassembly	41
25 104	Limited Slip Differential Disassembly	43
25 104	Limited Slip Differential Assembly	45
25 102	Lockable Differential Removal	48
25 102	Lockable Pinion Disassembly	50
25 104	Lockable Differential Disassembly	52
25 104	Lockable Differential Assembly	54
25 102	Adjustment - Pinion Shaft	57
25 104	Differential - Adjustments	61
25 102	Pinion to Ring Gear Tooth Contact Adjustment	64
	Wrong Tooth Contact Pattern	64
25 108	Swivel Housing Bearing Adjustment	66
41 106	Standard Steer/Toe-In Adjustment	67
41 106	Supersteer Linkage Adjustment	68
25 108	Potentiometer Removal	70
25 108	Potentiometer Installation	70
25 108	Potentiometer Calibration	72
	Mode 12: Tractor Features Configuration	72
	Mode 13: Steering Angle Sensor Operation/Calibration	73
	New Parameter Code	74
	New Fault Codes	77
	Testing After Assembly	78
	Troubleshooting	79

SECTION 27 - REAR DRIVE AXLE

BOOK 2 - 87018724

Chapter 1 - Rear Axle Assembly

CONTENTS

Section	Description	Page
27 000	Specifications	2
	Special Tools	3
	Description of Operation	10
	Differential Carrier	12
	Final Reduction Drive	13
	Differential Lock Mechanical Operation	14
	70 Series Differential Lock Control System Operation	15
	70A Series Differential Lock Control System Operation	16
	Differential Lock Electrical Circuit Operation	17
	Differential Lock Hydraulic Circuit Operation	19
	Front Axle Differential Line	19
	Troubleshooting	21
	Adjustments	30
	Disassembly and Repair	51
27 100	Axle Assembly	51
27 120	Axle Housing	64
27 120	Planetary Overhaul	85
	Axle Seal	91
	Top Cover	93
27 106	Differential Assembly	95
27 106	Pinion Assembly	112
27 110	Differential Lock Solenoid	125
	Pressure Testing	127
	Circuit Pressure Test	129

SECTION 31 – POWER TAKE-OFF

BOOK 3 - 87018725

Chapter 1 – Mechanical System

CONTENTS

Section	Description	Page
31 000	Specifications	2
	Special Tools	3
	Description of Operation	4
	Introduction	4
	Power Flow - All Models	5
	Engaging and Disengaging the PTO	7
	Troubleshooting and Diagnosis	8
	Disassembly and Repair	9
	PTO Assembly - Removal and Installation	9
	Upper PTO Input Shaft - Removal and Installation	15
	PTO Output Shaft and Driven Gear - Overhaul	30
	PTO Clutch Assembly - Overhaul	39

SECTION 31 – POWER TAKE-OFF

BOOK 3 - 87018725

Chapter 2 – Electro-hydraulic System

CONTENTS

Section	Description	Page
31 000	Specifications	2
	Special Tools	3
	Description of Operation	4
	Introduction	4
	Engaging and Disengaging the PTO	5
	PTO Hydraulic System Operation	6
	PTO Control Valve Operation	8
	Lubrication Oil	12
	PTO Electrical System Operation	14
	Troubleshooting	22

SECTION 31 – POWER TAKE-OFF

BOOK 3 - 87018725

Chapter 2 – Electro-hydraulic System (Continued)

CONTENTS

Section	Description	Page
	PTO will not Engage	23
	PTO will not Disengage	25
	PTO Clutch Slips Under Load	30
	PTO Shaft Continually Turns Slowly with Engine Running when PTO is Turned Off	32
	PTO Retaining Ring is Difficult to Replace	33
	Adjustments	34
	PTO Clutch Brake Band	34
	Disassembly and Repair	35
	PTO Solenoid	35
	PTO Control Valve Assembly	38
	PTO System Pressure Testing	44
	Introduction	44
	Pre-test Preparation	44
	Pilot Oil Circuit Pressure Test	45
	Clutch Apply Circuit Pressure Test	46
	PTO Lubrication Circuit Pressure Test	47

SECTION 33 – BRAKES AND CONTROLS

BOOK 3 - 87018725

Chapter 1 – Power Brakes

CONTENTS

Section	Description	Page
33 202	Specifications	2
	Description of Operation	4
	Boosters	7
	Master Cylinders	11
	Rear Axle Brake Assemblies	15
	Four Wheel Braking	17
	Troubleshooting	18

SECTION 33 – BRAKES AND CONTROLS

BOOK 3 - 87018725

Chapter 1 – Power Brakes (Continued)

CONTENTS

Section	Description	Page
	Adjustments	21
	Bleeding the Brakes	21
	Brake Pedal Adjustment	25
	Brake Switch Adjustment	25
	Disassembly and Repair	26
	Power Brake Valve - Overhaul	26
	Inspection	33
	Reassembly	34
	Installation of the Brake Lube Kit	39
	Rear Axle Brakes - Overhaul	44
	Hydraulic Trailer Brake	SEE SECTION 35

SECTION 33 – BRAKES AND CONTROLS

BOOK 3 - 87018725

Chapter 2 – Parking Brake

CONTENTS

Section	Description	Page
33 110	Specifications	2
	Special Tools	2
	Description of Operation	3
	Adjustments	4
	Adjust the Park Brake	4
	Troubleshooting	5
	Disassembly and Repair	6
	Parking Brake - Overhaul	6

SECTION 33 – BRAKES AND CONTROLS

BOOK 3 - 87018725

Chapter 3 – Trailer Air Brakes (Not Used in North America)

CONTENTS

Section	Description	Page
33 000	Specifications	2
	Torque Specifications	3
	Safety	7
	General Air Brake Safety	7
	General Maintenance Instructions	7
	Description of Operation	8
	System Operation	9
	Air Compressor	10
	Unloader Valve	10
	Reservoir Tank	14
	Right Hand Brake Lamp Switch	14
	Solenoid Valve	14
	Dual Control Valve	15
	Single Control Valve	20
	Air Pressure Switch	24
	Trailer Brake Solenoid Power	24
	Disassembly and Repair	25
	Air Compressor	25
	Air Compressor Lubrication Supply Line	29
	Air Compressor Lubrication Return Line	29
	Air Pressure Supply LIne	32
	Unloader/Valve Silencer	33
	Reservoir	34
	Pressure Switch	34
	Single Control Valve	35
	Dual Control Valve	38
	Solenoid Control Valve	39
	Coupler Connectors	41
	Adjustments	42
	Adjusting the Air Brake Parking Brake	42
	System Testing	44
	Troubleshooting - Air Brake System	47
	Towed Vehicle	51
	Troubleshooting - Towed Vehicle	52

SECTION 33 – BRAKES AND CONTROLS

BOOK 3 - 87018725

Chapter 4 – Trailer Air Brake Electrical System (Not Used in North America)

CONTENTS

Section	Description	Page
33 000	Description of Operation	2
	Trailer Brake light	2
	Low Pressure Alarm	2
	Air Pressure Switch Power	3
	Harness Removal and Installation	4
	Cab Trailer Wiring Harness	4
	Rear Trailer Harness	8
	Troubleshooting	11

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 1 – Introduction

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	4
	Introduction	4
	Closed Center Load Sensing (CCLS) Pump and Remote Valve System	5
	Standard Flow Hydraulic System	13
	Megaflow Hydraulic System	15
	Variable Displacement Pump	16
	Priority Flow Divider	16
	Remote Control Valves	17
	Standard Flow Tractors	17
	Megaflow Tractor	17
	Low-pressure Return Circuit	18

SECTION 35 - HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 2 - Low-Pressure System

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	3
	Hydraulic Pump Drive Assembly	3
	Tandem Gear Pump Assembly	4
	Tandem Gear Pump Fluid Supply	6
	Oil Filters	7
	Oil Reservoir	7
	Oil Cooler and Bypass Valve	8
	Low-Pressure Control Hydraulic Schematic	11
35 260	Removal and Disassembly	12
27 170	Hydraulic Pump Inlet Screen	12
27 170	Charge Pressure Regulator Valve	12
21 102	Filters	14
21 102	Filter Head	15
21 136	Cooler Bypass Valve	16
10 408	Hydraulic Oil Cooler	19
33 202	Accumulator	21
	Hydraulic Pump Driven Gear Case	22
	Repairing the Pump Drive Gear Case Bearings	23

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 3 – Tandem Gear Pump

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Operation	4
35 105	Disassembly and Repair	5
	Removal	5
	Disassembly	7
	Inspection of Parts	12
	Assembly	16
	Performance Testing	21
	Installation	22

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 4 – Axial Piston Pump

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
35 106	Disassembly and Repair	16
	Removal	16
	Tools Required	17
	Disassembly	17
	Input Shaft Seal Replacement	17
	Seal Installation	18
	Compensator Valve Disassembly	20
	Main Pump Disassembly	24

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 4 – Axial Piston Pump (Continued)

CONTENTS

Section	Description	Page
	Swash Plate Removal	28
	Input Shaft	31
	Pump Reassembly	34
	Rotating Group Assembly	37
	Flow and Pressure Compensator Valves	41
	Pump Installation	43

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 5 – Flow Divider

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	3
	Priority Flow Divider	3
41 200	Disassembly and Repair	6
	Removal	6
	Teardown	7
	Assembly	8

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 6 – 70 Series Remote Valves

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Remote Valve Assembly	3
	Remote Valve Section (Series Logic)	9
	Remote Valve Section (Parallel Logic)	15
	Control Cables	21
	Return Tube	22
	Primary and Secondary Shuttles	22
	Order of Priority Operation	28

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 7 – 70A Series Electro-Hydraulic Remote Valves

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Electro Hydraulic Remote Valves	3
	Control Switches	3
	Flow Control Adjustment	4
	Description of Operation	4
	Flow Control Operation	9
	Order of Priority Operation	14

SECTION 35 - HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 8 - Remote Valve Couplers

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Coupler Mounting Block and Coupler Repair (70 Series BSN D408953)	3
	Coupler Mounting Block and Coupler Repair (70 Series ASN D408952)	9

SECTION 35 - HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 9 - Remote Valve Removal and Repair

CONTENTS

Section	Description	Page
35 000	Removal	2
	Remote Valve Removal	2
	Removing Individual Valve Assemblies	6
	Valve Reassembly	11
35 204	Teardown and Reassembly	16
	Individual Valve Section Disassembly	16
	Valve Section Overhaul (70 Series)	19
	Detent Release Overhaul (70 Series)	22

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 10 – Three-Point Hitch

CONTENTS

Section	Description	Page
35 000	Specifications	1
	Description of Operation	2
	Three-Point Hitch	2
	Three-Point Hitch External Linkage Components	15
	Quick Hitch	19
	Troubleshooting	20
	Disassembly and Repair	24
	Rockshaft Removal	24
	Seal and Bushing Replacement	26
	Rockshaft Installation	27
	Lift Cylinder Removal	29

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 11 – Power-Beyond Applicators

CONTENTS

Section	Description	Page
	Special Tools	2
35 204	Power-Beyond Applications	3

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 12 – Hydraulic Brake System

CONTENTS

Section	Description	Page
35 000	Closed Center Load Sensing (CCLS) Hydraulic Brake System	4
35 000	Operation of the European Trailer Brake System	4
	Operation of the 10 Bar (147 PSI) Trailer Brake System (Italian Market Only)	6
	Trailer Brake Valve Pilot Head Operation	9
	Trailer Brake Valve Operation	10
	Trailer Brake Valve	18
	Specifications	18
	Torques	18
	Special Tools	18
	Description	18
	Trailer Brake Valve Removal	19
	Trailer Brake Valve Disassembly	20
	Inspection and Repair	23
	Re-Assembly and Installation	23
	Bleeding the Brakes	24
	Bleeding Rear Axle Brakes	24
	Trailer Brake Valve Bleed Screws	25
	Trailer Brake Pressure Test	25

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 13 – Pressure and Flow Testing

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	4
	Description of Operation	5
35 105	Low-pressure System Testing	6
	Testing Low-pressure System	6
35 106	High-pressure System Testing	9
	Axial Piston Pump	9
	Steering Flow Divider Relief Pressure	14
	Steering Flow Divider Flow Test	15
	Remote Valve	16
	Detent Release Operation	17
	Timed Detent Release Operation	18
	Three-point Hitch	19
	Three-point Hitch and Remote Valve Troubleshooting Aid Tool	24

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 14 – EHR Calibration, Diagnostics and Hydraulic System Troubleshooting

CONTENTS

Section	Description	Page
35 000	Calibration of the Electro-hydraulic Control System (EHR)	2
	Functions of the PDT	2
	Set Up	3
	Start Calibration	7
	Set Defaults	8
	Deadband	9
	Calibration of the Pod Levers	10

SECTION 35 – HYDRAULIC SYSTEMS

BOOK 4 - 87018726

Chapter 14 – EHR Calibration, Diagnostics and Hydraulic System Troubleshooting

CONTENTS

Section	Description	Page
	Set Currents	13
	Setting the Flow Control Potentiometer	17
	Changing the Lever Deadband	18
	Diagnostics of the Electro-hydraulic Remote Valve Control System	19
	Solenoid Errors	19
	Lever Errors	20
	System Errors	20
	Other Screens	21
	Troubleshooting Electro-hydraulic Self Test	22
	Troubleshooting Hydraulic System	23
	Hydraulic System Quick Checks	28

SECTION 41 – STEERING

BOOK 5 - 87018727

Chapter 1 – Hydrostatic Steering

CONTENTS

Section	Description	Page
41 000	Specifications	2
	Minimum Hardware Tightening Torques	3
	Description of Operation	5
	Steering System Control Valve	7
	Steering Control Valve Types	11
	Steering Cylinders	12
	Troubleshooting	13
	Removal and Disassembly	18
	Steering Control Valve	18
	Parts Inspection	23
	Assembling the Steering Control Unit	24
	Installing the Steering Control Valve	29

SECTION 44 – TWO-WHEEL DRIVE AXLE AND WHEELS

BOOK 5 - 87018727

Chapter 1 – Two-wheel Drive Front Axle

CONTENTS

Section	Description	Page
44 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Two-wheel Drive Front Axle	3
	Troubleshooting	6
	Adjustments	7
	Front Wheel Track Spacing	7
	2WD Axle Adjustment	9
	Front Wheel Position	10
	Front Wheel Toe-in	11
	Disassembly and Repair	13
	Axle Removal	13
	Axle Installation	17
	Axle Center Beam Bushing Replacement	21
	Axle Extension Installation	21
	Spindle Removal and Disassembly	21
	Axle Extention/Spindle Bushing Replacement	22
	Spindle Reassembly	22
	Front Wheel Bearing	23
	Steering Cylinder	25
	Center Steering Arm	30
	Steering Rod	32

SECTION 44 – TWO-WHEEL DRIVE AXLE AND WHEELS

BOOK 5 - 87018727

Chapter 2 – Four Wheel Drive (FWD) Front Axle Track Spacing

CONTENTS

Section	Description	Page
44 520	Specifications	2
	Four Wheel Drive (FWD) Front Axle Track Spacing	3
	Four Wheel Drive Track Adjustment	3
	Front Wheel Positions	4

SECTION 44 – TWO-WHEEL DRIVE AXLE AND WHEELS

BOOK 5 - 87018727

Chapter 3 – Rear Wheel Track Spacing

CONTENTS

Section	Description	Page
44 000	Specifications	2
	Special Tools	2
	Rear Wheel Track Spacing	3
	Introduction	3
	Model 8670/8670A Tractors	5
	Model 8770/8770A, 8870/8870A and 8970/8970A Tractors	6
	Rear Wheel Track Adjustment	7
	Adjusting Rear Wheels	8
	Dual Rear Wheels	10

SECTION 44 – TWO-WHEEL DRIVE AXLE AND WHEELS

BOOK 5 - 87018727

Chapter 4 – Rear Wheel Removal/Replacement

CONTENTS

Section	Description	Page
44 520	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	3
	Removal	3
	Installation	5

SECTION 50 – CLIMATE CONTROL

BOOK 5 - 87018727

Chapter 1 – Climate Control Systems

CONTENTS

Section	Description	Page
50 000	Introduction	2
	Specifications	3
	Tightening Torques	5
	Description of Operation	6
	Air Conditioning System Components	10
	Troubleshooting and Servicing Air Conditioning System	25
	Primary Troubleshooting and Testing	27
	Diagnosis Chart	28
	A/C System Performance Test and Diagnosis Chart	37
50 000	Component Removal and Installation	54

SECTION 55 - ELECTRICAL SYSTEMS

BOOK 6 - 87018728

Chapter 1 - Electronic Instrument Cluster (EIC) and System Overview

CONTENTS

Section	Description	Page
55 418	Specifications	3
	Description of Operation	4
	Main Distribution Panel	7
	Service Diagnostics	9
	Electronic Instrument Cluster (EIC)	11
	Central LCDs	12
	Tractor Performance Monitor	12
	Automatic Engine Shutdown	13
	70 Series Indicator, Warning Lamps and Audible Alarm	14
	70A Series Indicator, Warning Lamps and Audible Alarm	15
	Air Filter Restriction	17
	Differential Lock	17
	Cold Start Assist (Ether)	18
	Cold Start Assist (air inlet)	18
	Coolant Level Low	19
	Alternator Charge Indicator	19
	Intercooler Overheated	20
	Transmission Pressure Low	20
	Transmission, Rear Axle/Hydraulic Oil Temperature	20
	Hydraulic/Transmission Filters Restricted	21
	PTO Engaged	22
	Programmable Up Shift	22
	Programmable Down Shift	22
	70 Series FWD On	23
	FWD Auto	23
	70A Series FWD On	23
	FWD Auto	23
	Four Wheel Drive (FWD) Switch (if equipped)	23

SECTION 55 - ELECTRICAL SYSTEMS

BOOK 6 - 87018728

Chapter 1 - Electronic Instrument Cluster (EIC) and System Overview (Continued)

CONTENTS

Section	Description	Page
	Headlight High Beam	24
	System Status	24
	Parking Brake	24
	Bar Graph Displays (LCD)	25
	Stop and Audible Alarm Conditions	26
	Central Display (LCD)	29
	Lower Selectable Display	31
	Electronic Instrument Cluster - Tractor Performance Monitor (TPM)	33
	Automatic Display Information	34
	Selectable Display Information	35
	EIC Lighting Display	39
	Troubleshooting and Diagnostics	40
	EIC Harness Tool	41
	MODE 1, Operator Calibrations	41
	MODE 2, View Stored Fault Codes	50
	MODE 3, All Module Input Parameters	53
	MODE 4, EIC Output Diagnostics	56
	MODE 5, RHC Output Diagnostics	57
	MODE 6, EDC Output Diagnostics	58
	MODE 7, ETC Output Diagnostics	59
	MODE 8, EIC Full Display Test	60
	MODE 9, Hardware/Software Revision Level	61
	MODE 10, Transmission Calibration Review and Programming	63
	MODE 11, 3-Point Hitch and EDC Calibration	66
	MODE 12, Tractor Features Configuration	69
	MODE 13, Steering Angle Sensor Operation/Calibration (70A Series)	72

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 6 - 87018728

Chapter 2 – Fault Codes and Diagnostics

CONTENTS

Section	Description	Page
55 000	Description of Operation	2
	70/70A Series Diagnostics Procedure Overview and Checklist	2
	System Grounds	3
	70 Series Electrical System Grounds	4
	Troubleshooting Checklist	5
	Special Tool for Testing Electrical Systems	7
	Electrical Test Procedures #1 through #4	8
	Fault Codes F001 to F099, 3-Point Hitch/EDC	14
	Fault Codes F100 to F199, Right-hand Controls	88
	Fault Codes F200 to F299, EIC Module	112
	Fault Codes F300 to F399, ETC Transmission Control	134
	Fault Codes F400 to F499, Engine Control	292

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 3 – Starting System

CONTENTS

Section	Description	Page
55 201	Specifications	2
	Description of Operation	3
	Introduction	3
	Batteries	4
	Cold Start System - Ether Operation (BSN D414644)	5
	Ether Cold Start Circuit Troubleshooting	7
	Cold Start System - Air inlet Heater (ASN D414643)	8
	Air Inlet Heater Troubleshooting	12
	Fuel Stop Solenoid and Override System	13
	Shutdown Override	14
	Troubleshooting the Cranking Circuit	15
	Disassembly and Repair	18

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 3 – Starting System (Continued)

CONTENTS

Section	Description	Page
	Cleaning	22
	Armature Servicing	23
	Field Coil Checks	24
	Field Coil Removal	24
	Solenoid Checks	25
	Three-Terminal Solenoid	26
	Reassembly	27
	Lubrication	27
	PInion Clearance	28

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 4 – Charging System

CONTENTS

Section	Description	Page
55 301	Specifications	2
	Torque Specifications	3
	Description of Operation	4
	Introduction	4
	Features	4
	Operating Principles	5
	Troubleshooting and Diagnosis	6
	Disassembly and Repair	13
	Unit Repair	13
	Disassembly and Bench Checks	14
	Generator Assembly	19

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 5 – LIGHTING, AUXILIARY POWER AND RADIOS

CONTENTS

Section	Description	Page
55 404	Specifications	3
	Description of Operation	5
	Controls	5
	Multi-function Switch	6
	Hazard Warning Lights	6
	Light Operation	7
	Work Lights	8
	Auxiliary Power	10
	Auxiliary Control Mounting Locations	11
	Auxiliary Control Cable Routing	11
	Radio Installation	12
	Troubleshooting	13
	Fuse and Relay Identification	15
	Circuit Diagrams	16
	Brake Lights	17
	Head Lights	19
	Hazard Warning Lights	21
	70 Series Turn Signals	23
	70A Series Turn Signals	25
	Taillights	26
	Work Lights	27
	Work Lights #1	28
	Work Lights #2	29
	Work Lights #3	30
	Work Lights #4	31
	Interior Lights	32
	Auxiliary Power Sockets	33
	70 Series Seven-pin Trailer Connector	34
	70A Series Seven-pin Trailer Connector	35
	Disassembly and Repair	36
	Replace Headlight Assembly Bulbs	36

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 5 – LIGHTING, AUXILIARY POWER AND RADIOS (Continued)

CONTENTS

Section	Description	Page
	Replace Work Sealed Beam Units	36
	Replace Roof Mounted Turn Signal Bulbs	37
	Replace the Fender Mounted Turn Signal and Stop Light/Parking Light Bulbs	37
	Electronic Instrument Cluster (EIC) Bulb Replacement	38
	Harness Repair	39
	Connector Repair and Replacement	39
	Main Harness Routing	39

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 6 – Wiring Diagrams

CONTENTS

Section	Description	Page
55 100	Description of Operation	1
	Harness and Connectors	2
	Wiring Diagram Index and Key	16
	Wiring Diagram Circuit Explanation	18
	Glossary of Terms/Abbreviations	19
	Component Index	20
	Naso Schematic (North American Version)	22
	Iso Schematic (European Version)	43

SECTION 55 – ELECTRICAL SYSTEMS

BOOK 7 - 87018729

Chapter 7 – Electro-Hydraulic Remote Valve Control System

CONTENTS

Section	Description	Page
55 301	System Description	2
	Electrical Operation	2
	Electro-hydraulic Remote Valve Switch Control Pod Locations	3
	The Switch Control Pod Components	3
	Remote Valve Solenoid Connections	4
	Programmable Controller Location	4
	Switch Valve Color-coding	5
	Electro-hydraulic Control Switch Function Positions	6
	Electro-hydraulic Flow Control Knob	7
	Manual Programmable Operation Switch	7
	Electro-hydraulic Remote Valve Engagement Switch	7
	Fuse Panel Location	8
	Fuse Panel Access	8
	Fuse Location	9
	Control Relays	10
	Main Fuse Panel Location	11
	Main Fuse Panel Access	11
	Main Fuses	12
	Manual Operation	12
	Programmable Mode	14
	Flow Control	17
	Continuity Test - Short to Ground	18
	EHR Electrical Test Procedures	18
	Continuity Test - Check for Open Circuits	19
	Voltage Measurement or Short to Positive Supply Volts	21
	Removal of the Electro-hydraulic Remote Control Valve Switch Pod Assembly	23
	Reassemble of the Electro-hydraulic Remote Control Valve Switch Pod Assembly	25
	Removal of the Electro-hydraulic Remote Control Valve Programmable Controller	25
	Installation of the Electro-hydraulic Remote Control Valve Programmable Controller	25

SECTION 90 – PLATFORM, CAB, AND BODYWORK

BOOK 7 - 87018729

Chapter 1 – Cab Components

CONTENTS

Section	Description	Page
90 000	Description	2
	Disassembly and Assembly	3
90 160	Headliner	3
90 160	Cab Trim	6
90 124	Seat	8
90 154	Door Removal	28
90 156	Rear Window	29
90 110	Instrument Cluster	30
41 204	Steering Column	30
35 204	Right-hand Console	34
	Procedures For Right-hand Console Upgrade	37

SECTION 90 – PLATFORM, CAB, AND BODYWORK

BOOK 7 - 87018729

Chapter 2 – Engine Hood Removal

CONTENTS

Section	Description	Page
90 100	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Hood	4
	Hood and Upper Engine Frame	9

SECTION 90 – PLATFORM, CAB, AND BODYWORK

BOOK 7 - 87018729

Chapter 3 – Cab Removal

CONTENTS

Section	Description	Page
90 150	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Cab Removal	4
	Cab Installation	10

SECTION 00 - GENERAL INFORMATION

Chapter 1 - General Information

CONTENTS

Section	Description	Page
00 000	Forward	2
	Precautionary Statements	3
	Safety Precautions	4
	Health and Safety Precautions	7
	Tractor Identification	14
	Service Techniques	21
	Sealer Specifications	23
	Hardware Torque Values	23
	Lubrication	26
	Recommended Lubricants and Coolants	26

FOREWORD

Appropriate service methods and correct repair procedures are essential for the safe, reliable operation of all equipment, as well as the personal safety of the individual performing the repair.

This Service Manual provides troubleshooting, overhaul, and pressure-testing instructions using recommended procedures and equipment. Following these instructions will ensure the safe, efficient, and timely completion of the service or repair.

There are numerous variations in procedures, techniques, tools, and parts for servicing machines, as well as in the skill of the individual doing the work. This manual cannot possibly anticipate all such variations and provide advice or cautions as to each. Accordingly, anyone who departs from the instructions provided in this manual must first establish that their personal safety, the safety of others, and the integrity of the machine will not be compromised by the choice of methods, tools or parts.

The manual is divided into sections which are subdivided into chapters. Each chapter contains information on general operating principles, detailed inspection, overhaul and, where applicable, specific troubleshooting, special tools, and specifications.

Any reference in this manual to right, left, rear, front, top, or bottom is as viewed from the operator's seat, looking forward.

All data and illustrations in this manual are subject to variations in build specification. This information was correct at the time of issue, but New Holland policy is one of continuous improvement, and the right to change specifications, equipment, or design at any time, without notice, is reserved.

PRECAUTIONARY STATEMENTS

PERSONAL SAFETY

Throughout this manual and on machine decals, you will find precautionary statements ("**CAUTION**", "**WARNING**", and "**DANGER**") followed by specific instructions. These precautions are intended for the personal safety of you and those working with you. Please take the time to read them.

⚠ CAUTION ⚠

The word "CAUTION" is used where a safe behavioral practice according to operating and maintenance instructions and common safety practices will protect the operator and others from accident involvement.

⚠ WARNING ⚠

The word "WARNING" denotes a potential or hidden hazard which has a potential for serious injury. It is used to warn operators and others to exercise every appropriate means to avoid a surprise involvement with machinery.

⚠ DANGER ⚠

The word "DANGER" denotes a forbidden practice in connection with a serious hazard.

FAILURE TO FOLLOW THE "**CAUTION**", "**WARNING**", AND "**DANGER**" INSTRUCTIONS MAY RESULT IN SERIOUS BODILY INJURY OR DEATH.

MACHINE SAFETY

Additional precautionary statements ("**ATTENTION**" and "**IMPORTANT**") are followed by specific instructions. These statements are intended for machine safety.

ATTENTION: *The word "**ATTENTION**" is used to warn the operator of potential machine damage if a certain procedure is not followed.*

IMPORTANT: *The word "**IMPORTANT**" is used to inform the reader of something he needs to know to prevent minor machine damage if a certain procedure is not followed.*

SAFETY PRECAUTIONS

Practically all service work involves the need to drive the tractor. The operator's manual, supplied with each tractor, contains detailed safety precautions relating to driving, operating, and servicing that tractor. These precautions are as applicable to the service technician as they are to the operator and should be read, understood and practiced by all personnel.

Prior to undertaking any maintenance, repair, overhaul, dismantling or reassembly operations, whether within a workshop facility or in the field, consideration should be given to factors that may have an effect upon safety, not only upon the mechanic carrying out the work, but also upon bystanders.

PERSONAL CONSIDERATIONS

The wrong clothes or carelessness in dress can cause accidents. Check to see that you are suitable clothed.

Some jobs require special protective equipment.

Skin Protection
Used motor oil may cause skin cancer. Follow work practices that minimize the amount of skin exposed and length of time used oil stays on your skin.

Eye Protection
The smallest eye injury may cause loss of vision. Injury can be avoided by wearing eye protection when engaged in chiselling, grinding, discing, welding, and painting.

Breathing Protection
Fumes, dust, and paint spray are unpleasant and harmful. These can be avoided by wearing respiratory protection.

Hearing Protection
Loud noise may damage your hearing, and the greater the exposure the worse the damage. If the noise is excessive, wear ear protection.

Lifting Protection
Avoid injury by correctly handling components. Make sure you are capable of lifting the object. If in doubt get help.

Hand Protection
It is advisable to use a protective cream before work to prevent irritation and skin contamination. After work clean your hands with soap and water. Solvents such as mineral spirit and kerosene may harm the skin.

Foot Protection
Substantial or protective footwear with reinforced toe caps will protect your feet from falling objects. Additionally, oil-resistant soles will help to avoid slipping.

Special Clothing
For certain work it may be necessary to wear flame or acid-resistant clothing.

EQUIPMENT CONSIDERATIONS

Machine Guards
Before using any machine, check to ensure that the machine guards are in position and serviceable. These guards not only prevent parts of the body or clothing coming in contact with the moving parts of the machine, but also ward off objects that might fly off the machine and cause injury.

Lifting Devices
Always ensure that lifting equipment, such as chains, slings, lifting brackets, hooks and eyes, are thoroughly checked before use. If in doubt, select stronger equipment than is necessary.

Never stand under a suspended load or raised implement.

Compressed Air
The pressure from a compressed-air line often exceeds 690 bar (100 PSI). It is perfectly safe if used correctly. Any misuse may cause injury.

Never use compressed air to blow dust, filing, and dirt away from your work area unless the correct type of nozzle is fitted.

Compressed air is not a cleaning agent; it will only move dust from one place to another. Look around before using an air hose as bystanders may get grit into their eyes, ears, or skin.

Hand Tools
Many cuts, abrasions and injuries are caused by defective tools. Never use the wrong tool for the job, as this generally leads either to some injury or to a poor job.

When removing or replacing hardened pins, use a copper or brass drift rather than a hammer.

For dismantling, overhaul, and assembly of major and sub-components, always use the Special Service Tools recommended. These will reduce the work effort, labor time, and the repair cost.

Electricity
Electricity has become so familiar in day to day usage, that its potentially dangerous properties are often overlooked. Misuse of electrical equipment can endanger life.

Before using any electrical equipment - particularly portable appliances - make a visual check to make sure that the wiring is not worn or frayed and that the plugs and sockets are intact. Make sure you know where the nearest isolating switch for your equipment is located.

GENERAL CONSIDERATIONS

Solvents
Use cleaning fluids and solvents that are known to be safe. Certain types of fluids can cause damage to components, such as seals, and can cause skin irritation. Solvents should be checked that they are suitable not only for the cleaning of components and individual parts, but also that they do not affect the personal safety of the user.

Housekeeping
Many injuries result from tripping over or slipping on objects or material left lying around by a careless worker. Prevent these accidents from occurring. If you notice a hazard, don't ignore it - remove it.

A clean, hazard-free place of work improves the surroundings and daily environment for everybody.

Fire
Fire has no respect for persons or property. The destruction that a fire can cause is not always fully realized. Everyone must be constantly on guard.

Extinguish matches, cigars, and cigarettes before throwing them away.

Work cleanly, disposing of waste material into proper containers.

Locate the fire extinguishers and find out how to operate them.

Do not panic - warn those near and raise the alarm.

Do not allow or use an open flame near the tractor fuel tank, battery, or component parts.

First Aid
In the type of work that mechanics are engaged in, dirt, grease, and fine dusts settle upon the skin and clothing. If a cut, abrasion or burn is disregarded it may become infected within a short time. Seek medical aid immediately.

Cleanliness
Cleanliness of the tractor hydraulic system is essential for optimum performance. When carrying out service and repairs, plug all hose ends and component connections to prevent dirt entry.

Clean the exterior of all components before carrying out any form of repair. Dirt and abrasive dust can reduce the efficiency and working life of a component and lead to costly replacement. Use of a high-pressure washer or steam cleaner is recommended.

OPERATIONAL CONSIDERATIONS

Stop the engine, if at all possible, before performing any service.

Place a warning sign on tractors which, due to service or overhaul, would be dangerous to start. Disconnect the battery leads if leaving such a unit unattended.

Do not attempt to start the engine while standing beside the tractor or attempt to bypass the safety start switch.

Avoid prolonged running of the engine in a closed building or in an area with inadequate ventilation as exhaust fumes are highly toxic.

Always turn the radiator cap to the first stop to allow pressure in the system to dissipate when the coolant is hot.

Never work beneath a tractor which is on soft ground. Always take the unit to an area which has a hard working surface, preferably concrete.

If it is found necessary to raise the tractor for ease of servicing or repair, make sure that safe and stable supports are installed beneath axle housings, casings, etc., before starting work.

Certain repair or overhaul procedures may necessitate separating the tractor, either at the engine/transmission or transmission/rear axle location. These operations are simplified by the use of the Tractor Splitting Stands. Should this equipment not be available, every consideration must be given to stability, balance and weight of the components, especially if a cab is installed.

Use footsteps or working platforms when servicing those areas of a tractor that are not within easy reach.

Before loosening any hoses or tubes connecting implements to remote control valves, etc., switch off the engine, remove all pressure in the lines by operating levers several times. This will remove the danger of personal injury by oil pressure.

Prior to pressure testing, make sure all hoses and connectors of the tractor and the test equipment are in good condition and tightly sealed. Pressure readings must be taken with the gauges specified. The correct procedure should be rigidly observed to prevent damage to the system or the equipment, and to eliminate the possibility of personal injury.

⚠ WARNING ⚠

Escaping hydraulic/diesel fluid under pressure can penetrate the skin causing serious injury.

Do not use your hand to check for leaks. Use a piece of cardboard or paper to search for leaks.

Stop the engine and relieve pressure before connecting or disconnecting lines.

Tighten all connections before starting the engine or pressurizing lines.

If any fluid is injected into the skin, obtain medical attention immediately or gangrene may result.

Use “position control” when equipment or implements are required to be attached to the hydraulic linkage either for testing purposes or for transportation.

Always lower equipment to the ground when leaving the tractor.

If high lift attachments are installed on a tractor, beware of overhead power, electric or telephone cables when traveling. Drop the attachment near to ground level to increase stability and minimize risks.

Do not park or attempt to service a tractor on an incline. If unavoidable, take extra care and block all wheels.

Observe recommended precautions as indicated in this Service Manual when dismantling the air-conditioning system as escaping refrigerant can cause frostbite.

Prior to removing wheels and tires from a tractor, check to determine whether additional ballast (liquid or weights) has been added. Seek assistance and use suitable equipment to support the weight of the wheel assembly.

When inflating tires, beware of over inflation - constantly check the pressure. Overinflation can cause tires to burst and result in personal injury.

HEALTH AND SAFETY PRECAUTIONS

Many of the procedures associated with vehicle maintenance and repair involve physical hazards or other risks to health. This section lists, alphabetically, some of these hazardous operations, materials and equipment associated with them. The precautions necessary to avoid these hazards are identified.

The list is not inclusive; all operations, procedures, and handling of materials should be carried out with health and safety in mind.

ACIDS AND ALKALIS (See Battery Acids, i.e., Caustic Soda, Sulfuric Acid)

Used in batteries and cleaning materials.

Irritating and corrosive to the skin, eyes, nose and throat. Causes burns.

Avoid splashes to the skin, eyes, and clothing. Wear suitable protective gloves and goggles. Can destroy ordinary protective clothing. Do not breathe mists.

Ensure access to water and soap is readily available for splashing accidents.

ADHESIVES AND SEALERS (See Fire)

⚠ CAUTION ⚠

HIGHLY FLAMMABLE, COMBUSTIBLE.

Generally should be stored in "NO SMOKING" areas; cleanliness and tidiness while in use should be observed, i.e., from applications where possible, disposable paper should be dispensed to cover benches. Containers, including secondary containers, should be labeled.

Solvent-Based Adhesives/Sealers (See Solvents)
Follow manufacturer's Instructions

Water-Based Adhesives/Sealers
Those based on polymer emulsions and rubber lattices may contain small amounts of volatile toxic and harmful chemicals.

Skin and eye contact should be avoided, and adequate ventilation provided during use.

Follow manufacturer's Instructions

Resin-Based Adhesive/Sealers (i.e., Epoxide and Formaldehyde Resin Based)
Mixing should only be carried out in well- ventilated areas as harmful or toxic volatile chemicals may be released.

Skin contact with uncured resins and hardeners can result in irritation, dermatitis, and absorption of toxic, or harmful chemicals through the skin. Splashes can damage the eyes.

Provide adequate ventilation; avoid skin and eye contact. Follow manufacturer's instructions.

Anaerobic, Cyanoacrylate and other Acrylic Adhesives
Many are irritating, sensitizing, or harmful to the skin. Some are eye irritants.

Skin and eye contact should be avoided and the manufacturer's instructions followed.

Cyanoacrylate adhesives (super-glues) must not contact the skin or eyes. If skin or eye tissue is bonded, cover with a clean moist pad and get medical attention. Do not attempt to pull tissue apart. Use in well-ventilated areas as vapors can cause irritation of the nose and eyes.

For two-part systems: See Resin-Based Adhesive/ Sealers

Isocyanate (Polyurethane) Adhesive/Sealers (See Resin-Based Adhesives)
Individuals suffering from asthma or respiratory allergies should not work with, or near, these materials as sensitivity reactions can occur.

Any spraying should preferably be carried out in exhaust ventilated booths removing vapors and spray droplets from the breathing zone. Individuals working with spray applications should wear supplied air respirators.

ANTIFREEZE (See Fire, Solvents, i.e., Isopropanol, Ethylene Glycol, Methanol)

⚠ CAUTION ⚠

HIGHLY FLAMMABLE, COMBUSTIBLE.

Used in vehicle coolant systems, brake air pressure systems, and windshield washing solutions.

Vapors given off from coolant antifreeze (Glycol) arise only when heated.

Antifreeze may be absorbed through the skin in toxic or harmful quantities. Swallowed antifreeze is fatal if not treated; medical attention must be sought immediately.

BATTERY ACIDS (See Acids and Alkalis)

Gases released during charging are explosive. Never use an open flame or allow sparks near charging or recently charged batteries.

BRAKE AND CLUTCH LININGS AND PADS (See Legal Aspects)

These items may contain asbestos which, if inhaled, may cause lung damage and, in some cases, cancer.

The normal handling and fitting of these items should not cause any hazard, but any drilling, grinding, or filling of friction materials may produce asbestos dust and should only be carried out under strictly controlled conditions.

The dust in brake drums, etc., contains very little asbestos, but care should be taken to avoid inhalation of this dust during servicing of brakes and clutches. The use of drum cleaning units, vacuum cleaning, or damp wiping is preferred to the use of air jets for “blowing-out.”

The dust should be collected in a sealed plastic bag and disposed appropriately, according to local laws and regulations.

BRAZING (See Welding)

CHEMICAL MATERIALS - GENERAL (See Legal Aspects)

Chemical materials such as solvents, sealers, adhesives, paints, resin foams, battery acids, antifreeze, oils, and grease should always be used with caution, stored and handled with care. They may be toxic, harmful, corrosive, irritating, or highly flammable, causing hazardous fumes and dusts.

The effects of excessive exposure to chemicals may be immediate or delayed, briefly experienced or permanent, cumulative, superficial, life threatening, or may reduce life expectancy.

CLUTCH LININGS AND PADS (See Brake and Clutch Linings and Pads)

CORROSION PROTECTION MATERIALS (See Solvents, Fire)

⚠ CAUTION ⚠

HIGHLY FLAMMABLE, COMBUSTIBLE.

These materials are varied; the manufacturer’s instructions should be followed. They may contain solvents, resins, and petroleum products. Skin and eye contact should be avoided. They should only be sprayed in conditions of adequate ventilation, and not in confined spaces.

CUTTING (See Welding)

DEWAXING (See Solvents and Fuels - Kerosene)

DO’S

Do remove chemical materials from the skin and clothing as soon as practicable. Change heavily soiled clothing and have it cleaned.

Do carefully read and observe hazard and precaution warnings given on material containers (labels) and in any accompanying leaflets, poster or other instructions. Material health and safety data sheets can be obtained from manufacturers.

Do organize work practices by wearing protective clothing and safety devices to avoid contact with chemical materials; breathing vapors, aerosols, dusts, and fumes; inadequate container labeling; or fire and explosion hazards.

Do wash before job breaks, before eating, smoking, drinking, or using toilet facilities when handling chemical materials.

Do keep work areas clean, uncluttered, and free of spills.

Do store according to national and local regulations.

Do keep chemical materials out of reach of children.

DON’TS

Do not mix chemical materials except under the manufacturer’s instructions; some chemicals can form other toxic or harmful chemicals, releasing toxic or harmful fumes, or be explosive when mixed together.

Do not spray chemical materials, particularly those based on solvents, in confined spaces, i.e., when people are inside a vehicle.

Do not apply heat or flame to chemical materials, except under the manufacturer's instructions. Some are highly flammable, and some may release toxic or harmful fumes.

Do not leave containers open. Escaping fumes can build up to toxic, harmful, or explosive concentrations. Some fumes are heavier than air and will accumulate in confined areas, pits, etc.

Do not transfer chemical materials to unlabeled containers.

Do not clean hands or clothing with chemical materials. Chemicals, particularly solvents and fuels, will dry the skin, and may cause irritation with dermatitis. Some can be absorbed through the skin in toxic or harmful quantities.

Do not use emptied containers for other materials, except when they have been cleaned under supervised conditions.

Do not sniff or smell chemical materials. Brief exposure to high concentrations of fumes can be harmful or toxic.

DUSTS

Powder or dusts may be an irritant, harmful or toxic. Avoid breathing dusts from powdery chemical materials, or those arising from dry abrasion operations. Wear respiratory protection if ventilation is inadequate.

ELECTRIC SHOCK

Electric shocks can result from the use of faulty electrical equipment or from the misuse of equipment even in good condition.

Ensure electrical equipment is maintained in good condition and frequently tested.

Ensure flexes, cables, plugs and sockets are not frayed, kinked, cut, cracked, or otherwise damaged.

Ensure electric equipment is protected by the correct rated fuse.

Never use electrical equipment or any other equipment which is in any way faulty. The results could be fatal.

Use reduced voltage equipment for inspection and working lights, where possible.

Ensure the cables of mobile electrical equipment cannot get trapped and damaged, such as in a vehicle hoist.

In Cases of Electrocution:

- Switch off electricity before approaching victim.
- If this is not possible, push or drag the victim from the source of electricity using dry non-conductive material.
- Commence resuscitation if trained to do so.
- **SUMMON MEDICAL ASSISTANCE IMMEDIATELY**

EXHAUST FUMES

These contain asphyxiating, harmful and toxic chemicals, and particles such as carbon oxides, nitrogen oxides, aldehydes, lead, and aromatic hydrocarbons. Engines should only run under conditions of adequate extraction, or general ventilation, not in confined spaces.

Diesel Engine
Soot, discomfort, and irritation usually give adequate warning signs of hazardous fume concentration.

FIBER INSULATION (See Dusts)

Used in noise and sound insulation.

The fibrous nature of surfaces and cut edge can cause skin irritation. This is usually a physical, not a chemical effect.

Precautions should be taken to avoid excessive skin contact through careful organization of work practices and the use of gloves.

FIRE (See Welding, Foams, Legal Aspects)

Many of the materials found on, or associated with, the repair of vehicles are highly flammable. Some release toxic or harmful fumes if burned.

Observe strict fire safety when storing and handling flammable materials or solvents, particularly near electrical equipment or welding processes.

Before using electrical or welding equipment, be sure there is no fire hazard present.

Have a suitable fire extinguisher available when using welding or heating equipment.

FIRST AID

Apart from meeting any legal requirements, it is desirable for someone in the workshop to be trained in first aid procedures.

Splashes in the eye should be flushed with clean water for at least ten minutes.

Soiled skin should be washed with soap and water.

Inhalation affected individuals should be removed to fresh air immediately.

If chemicals are swallowed, consult a doctor immediately with (label) information on material used.

Do not induce vomiting, unless indicated by manufacturer.

FOAMS - POLYURETHANE (See Fire)

Used in sound and noise insulation. Cured foams are used in seat and trim cushioning.

Follow manufacturer's instructions.

Unreacted components are irritating and may be harmful to the skin and eyes. Wear gloves and goggles.

Individuals with chronic respiratory diseases, asthma, bronchial medical problems, or histories of allergic diseases should not work with or near uncured materials.

The component's vapors and spray mists can cause direct irritation and/or sensitivity reactions and may be toxic or harmful.

Vapors and spray mists must not be breathed. These materials must be applied with adequate ventilation and respiratory protection. Do not remove respirator immediately after spraying, wait until vapor/mists have cleared.

Burning of the uncured components and the cured foams can generate toxic and harmful fumes.

Smoking, open flames, or the use of electrical equipment should not be allowed during foaming operations until vapors/mists have completely cleared. Any heat cutting of cured foams or partially cured foams should be conducted with extraction ventilation (see Legal Aspects).

FUELS (See Fire, Legal Aspects, Chemicals - General, Solvents)

Used as fuels and cleaning agents.

Gasoline (Petrol)

CAUTION

HIGHLY FLAMMABLE, COMBUSTIBLE.

Swallowing can result in mouth and throat irritation; absorption from the stomach can result in drowsiness and unconsciousness. Small amounts can be fatal to children. Aspiration of liquid into the lungs, i.e., through vomiting, is a very serious hazard.

Prolonged or repeated contact with gasoline dries the skin and causes irritation and/or dermatitis. Liquid in the eye causes severe pain.

Motor gasoline may contain high quantities of benzene which is toxic upon inhalation; the concentrations of gasoline vapors must be kept very low. High concentrations will cause eye, nose and throat irritation, nausea, headache, depression and symptoms of drunkenness. Very high concentrations will result in rapid loss of consciousness.

Ensure there is adequate ventilation when handling and using gasoline. Great care must be taken to avoid the serious consequences of inhalation in the event of vapor buildup arising from spillages in confined spaces.

Special precautions apply to cleaning and maintenance operations on gasoline storage tanks.

Gasoline should not be used as a cleaning agent. It must not be siphoned by mouth.

Kerosene (Paraffin)

Used also as heating fuel, solvent, and cleaning agent.

CAUTION

FLAMMABLE

Irritation of the mouth and throat may result from swallowing. The main hazard from swallowing arises if liquid aspiration into the lungs occurs. Liquid contact dries the skin and can cause irritation and/or dermatitis. Splashes in the eye may be slightly irritating.

In normal circumstances, the low volatility does not give rise to harmful vapors. Exposure to mists and vapors from kerosene at elevated temperatures should be avoided (mists may arise in dewaxing). Avoid skin and eye contact; be sure there is adequate ventilation.

Diesel Fuel (Gas-Oil) (See Fuels -Kerosene)

CAUTION

COMBUSTIBLE

Gross or prolonged skin contact with high boiling gas oils may cause serious skin disorders, including skin cancer.

GAS CYLINDERS (See Fire)

Gases such as oxygen, acetylene, carbon dioxide, argon, and propane are normally stored in cylinders at pressures of up to 137.8 bar (2000 PSI). Great care should be taken in handling these cylinders to avoid mechanical damage to them or the valve gear attached. The contents of each cylinder should be clearly identified by appropriate markings.

Cylinders should be stored in well-ventilated enclosures and protected from ice, snow, or direct sunlight. Fuel gases, i.e., acetylene and propane, should not be stored in close proximity to oxygen cylinders.

Care should be exercised to prevent leaks from gas cylinders and lines and to avoid sources of ignition.

Only trained personnel should undertake work involving gas cylinders.

GASES (See Gas Cylinder)

GAS SHIELDING WELDING (See Welding)

GAS WELDING (See Welding)

GENERAL WORKSHOP TOOLS AND EQUIPMENT

It is essential that all tools and equipment are maintained in good condition and the correct safety equipment used where required.

Never use tools or equipment for any purpose other than for which they were designed.

Never overload equipment such as hoists, jacks, axle and chassis stands, or lifting slings. Damage caused by overloading is not always immediately apparent and may result in a fatal failure the next time the equipment is used.

Do not use damaged, defective tools or equipment, particularly high-speed equipment such as grinding wheels. A damaged grinding wheel can disintegrate without warning causing serious injury.

Wear suitable eye protection when using grinding, chiseling, or sandblasting equipment.

Wear a suitable breathing mask when using sandblasting equipment, working with asbestos based materials, or using spraying equipment.

GLUES (See Adhesive and Sealers)

HIGH-PRESSURE AIR, LUBRICATION AND OIL TEST EQUIPMENT (See Lubricants and Greases)

Always keep high-pressure equipment in good condition and regularly maintained, particularly joint and unions.

Never direct a high-pressure nozzle at the skin, as the fluid may penetrate to the underlying tissue and can cause serious injury.

LEGAL ASPECTS

Many laws and regulations make requirements relating to health and safety in the use of materials and equipment in workshops.

Workshops should be familiar, in detail, with these laws and regulations.

LUBRICANTS AND GREASES

Avoid all prolonged and repeated contact with mineral oils, especially used oils. Gross and prolonged skin contact with used oils contaminated during service, i.e., routine service change sump oils, are more irritating and more likely to cause serious effects, including skin cancer.

Wash skin thoroughly after work involving oil. Proprietary hand cleaners may be of value provided they can be removed from the skin with water. Do not use petrol, paraffin, or other solvents to remove oil from the skin.

Lubricants and greases may be slightly irritating to the eyes.

Repeated or prolonged skin contact should be avoided by wearing protective clothing, if necessary. Particular care should be taken with used oils and greases containing lead. Do not allow work clothing to be contaminated with oil. Dry clean or launder such clothing at regular intervals. Discard oil-soaked shoes.

Do not use previously used engine oils as lubricants or for any application where major skin contact is likely to occur. Used oils may only be disposed of in accordance with local regulations.

NOISE INSULATION MATERIAL (See Foams, Fiber Insulation)

PAINTS (See Solvents and Chemical Materials - General)

CAUTION

HIGHLY FLAMMABLE

Paints can contain harmful or toxic pigments, driers, and other components, as well as solvents. Spraying should only be carried out with adequate ventilation.

Two-part or catalyzed paints can also contain harmful and toxic unreacted resins and resin-hardening agents. The manufacturer's instructions should be followed and the section on resin-based adhesives, isocyanate containing adhesive and foams should be consulted.

Spraying should preferably be carried out in exhausted ventilated booths, removing vapor and spray mists from the breathing zone. Individuals working in booths should wear respiratory protection. Those doing small-scale repair work in the open shop should wear supplied air respirators.

PAINT THINNERS (See Solvents)

PRESSURIZED EQUIPMENT (See High-Pressure Air, Lubrication and Oil Test Equipment)

RESISTANCE WELDING (See Welding)

SEALERS (See Adhesives and Sealers)

SOLDER (See Welding)

Solders are mixtures of metals in which the melting point of the mixture is below that of constituent metals (normally lead and tin). Solder application does not normally give rise to toxic lead fumes, provided a gas/air flame is used. Oxyacetylene flames should not be used, as they are much hotter and will cause lead fumes to be released.

Some fumes may be produced by the application of any flame to surfaces coated with grease, etc., and inhalation of these should be avoided.

Removal of excess solder should be undertaken with care to ensure fine lead dust is not produced, which can cause toxic effects if inhaled. Respiratory protection may be necessary.

Solder spillage and filing should be collected and removed promptly to prevent general air contamination by lead.

High standards of personal hygiene are necessary in order to avoid ingestion of lead or inhalation of solder dust from clothing.

SOLVENTS (See Chemical Materials - General, Fuels [Kerosene], Fire)

Acetone, White spirit, Toluene, Xylene, Trichlorethane.

Used in cleaning materials, dewaxing, paints, plastics, resins, thinners, etc.

CAUTION

HIGHLY FLAMMABLE

Skin contact will degrease the skin and may result in irritation and/or dermatitis following repeated or prolonged contact. Some can be absorbed through the skin in toxic or harmful quantities.

Splashes in the eye may cause severe irritation and could lead to loss of vision.

Brief exposure to high concentrations of vapors or mists will cause eye and throat irritation, drowsiness, dizziness, headaches and, in the worst circumstances, unconsciousness.

Repeated or prolonged exposures to excessive, but lower concentrations of vapors or mists, for which there might not be adequate warning indications, can cause more serious toxic or harmful effects. Aspiration into the lungs, i.e., through vomiting, is the most serious consequence.

Avoid splashes to the skin, eyes, and clothing. Wear protective gloves, goggles, and clothing if necessary.

Ensure good ventilation when in use, avoid breathing fumes, vapors, and spray mists. Keep containers tightly sealed. Do not use in confined spaces.

When the spraying material contains solvents, e.g., paints, adhesives, and coatings, use extraction ventilation or personal respiratory protection in the absence of adequate general ventilation.

Do not apply heat or flame, except under specific and detailed manufacturer's instructions.

SOUND INSULATION (See Fiber Insulation, Foams)

SPOT WELDING (See Welding)

SUSPENDED LOADS

There is always a danger when loads are lifted or suspended. Never work under an unsupported, suspended, or raised load, e.g., jacked-up vehicle, suspended engine, etc.

Always ensure lifting equipment such as jacks, hoists, axle stands, slings, etc., are adequate and suitable for the job, in good condition, and regularly maintained.

Never improvise lifting tackle.

UNDER SEAL (See Corrosion Protection)

WELDING (See Fire, Electric Shock, Gas Cylinders)

Welding processes include Resistance Welding (Spot Welding), Arc Welding, and Gas Welding.

Resistance Welding
This process may cause particles of molten metal to be emitted at high velocity; the eyes and skin must be protected.

Arc Welding
This process emits a high level of ultraviolet radiation which may cause eye and skin burns to the welder and to other persons nearby. Gas-shielded welding processes are particularly hazardous in this respect. Personal protection must be worn and screens used to shield other people.

Metal spatter will also occur; appropriate eye and skin protection is necessary.

The heat of the welding arc will produce fumes and gases from the metals being welded and from any applied coatings or contamination of the surfaces being worked on. These gases and fumes may be toxic; inhalation should always be avoided. The use of extraction ventilation to remove the fumes from the working area may be necessary, particularly in cases where the general ventilation is poor, or where considerable welding work is anticipated. In extreme cases where adequate ventilation cannot be provided, supplied air respirators may be necessary.

Gas Welding
Oxyacetylene torches may be used for welding and cutting; special care must be taken to prevent leakage of these gases, subsequently reducing the risk of fire and explosion.

The process will produce metal spatter; eye and skin protection is necessary.

The flame is bright and eye protection should be used, but the ultraviolet emission is much less than that from arc welding, and lighter filters may be used.

The process itself produces few toxic fumes, but such fumes and gases may be produced from coatings on the work, particularly during cutting away of damaged parts. Inhalation of the fumes should be avoided.

In brazing, toxic fumes may be released from the metals in the brazing rod. A severe hazard may arise if brazing rods containing cadmium are used. In this event, particular care must be taken to avoid inhalation of fumes; an expert's advice may be required.

SPECIAL PRECAUTIONS MUST BE TAKEN BEFORE ANY WELDING OR CUTTING TAKES PLACE ON VESSELS WHICH HAVE CONTAINED COMBUSTIBLE MATERIALS, I.E., "BOILING" OR "STEAMING OUT" THE INSIDE OF FUEL TANKS.

WHITE SPIRIT (See Solvents)

TRACTOR IDENTIFICATION

TRACTOR IDENTIFICATION DATA

The tractor and major components are identified using serial numbers and/or manufacturing codes. The following provides the locations of the identification data.

NOTE: *Tractor identification data must be supplied when requesting parts or service.*


Identification data is needed to aid in identifying the tractor if it is ever stolen.

VEHICLE IDENTIFICATION PLATE

The vehicle identification plate on the 70 Series, is located inside the right front lower side panel of the hood at 1.

The vehicle identification plate on the 70A Series, is located inside the upper right side panel of the hood at 2.

Owners should record the information on the sample ID plate.



1

The ID plate is stamped with the following information:

TRACTOR NUMBER - Serial number prefixed by the letter “D.”

MODEL - Production model code.

UNIT - Production unit date code.*****

ENGINE - Serial number.

TRANSMISSION - Serial number.

REAR AXLE - Rear axle serial number.


FRONT AXLE - Serial number.

HYDRAULIC PUMP - Serial number.


HYDRAULIC LIFT - Blank

FWD FACTOR - Four-wheel-drive factor.

SPECIAL ORDER - Blank



2



3

***KEY TO PRODUCTION DATE CODES:**

The unit heading on the ID plate represents the production date of the tractor.

Two types of production date codes are used. One style starts with a numeral (example 4A03B) while the second style starts with a letter (example A0314).

The following examples explain each code. Refer to the style code used on the tractor being worked on.

Example of Production Unit Code 4A03B:

4 = Year of production
(4 = 1994, 5 = 1995)

A = Month of year
(A = January, B = February, ... H = August, J = September, ... M = December)
NOTE: "I" is not used.

03 = Day of month
(03 = third, 04 = fourth, ... 31 = thirty-first)

B = Shift
(A = night, B = day, C = afternoon)

Example of Production Unit Code A0314:

A = Month of year
(A = January, B = February, ... H = August, J = September, ... M = December)
NOTE: "I" is not used.


03 = Day of month
(03 = third, 04 = fourth, ... 31 = thirty-first)

1 = Shift
(1 = day, 2 = afternoon, 3 = night)

4 = Year of production
(4 = 1994, 5 = 1995)

TRACTOR IDENTIFICATION STAMPING


The serial number and identification information, 1, is stamped on the top of the front support.



4


FOUR WHEEL DRIVE (FWD) FRONT AXLE IDENTIFICATION

The serial number and axle type for the 70 Series is on the plate, 1, located on the front of the axle housing.



5


The serial number and axle type for the 70A Series is on the plate located on the right rear of the axle housing, 2.



6


ENGINE IDENTIFICATION

The engine identification information for the 70 Series, is located on a tag, 1, on the right side of the engine rocker cover.



7

The engine identification information for the 70A Series, is located on a tag, 2, on the top front of the engine rocker cover.




8

FUEL INJECTION PUMP IDENTIFICATION

NOTE: *70 Series art shown in Figure 9.*

The serial number and pump information are on the plate, 1, on the pump.


NOTE: *The plate location differs slightly for all the models.*



9

The following is a key to the identification plate:


- 011 = Factory code (Germany)
- 36202 01323 15194 = Serial number
- 0400876405 = Supplier order number
- PES6A95D410RS2835 = Alphanumeric production designation
  - PE = Inline injection pump with camshaft
  - S = Flange-mounted
  - 6 = Number of cylinders
  - A = Size pump (A - 8670 and 8770, P - 8870 and 8970)
  - 95 = Plunger diameter in 1/10 mm (915 mm)
  - D = Pump model (“D” is the latest version of “A” size pumps)
  - 410 = Number code for location of feed pump and governor
  - R = Rotation of pump as seen from drive end (right hand = clockwise)
  - S2835 = Application number (indicates what model New Holland tractor this is used on)



10

STARTER MOTOR IDENTIFICATION


The serial number and starter information are on the plate, 1, on the starter housing.



11

TRANSMISSION IDENTIFICATION


The serial number and type are located on the plate, 1, on the lower right side of the transmission.



12

TANDEM GEAR PUMP IDENTIFICATION


The serial number and pump identification information are on the plate, 1, on the pump housing.



13

AXIAL PISTON PUMP IDENTIFICATION


The serial number and pump identification information are on the plate, 1, on the pump housing next to the case drain port.



14

REAR AXLE IDENTIFICATION


The serial number, 1, is stamped on the left side of the PTO boss on the rear axle housing.



15

CAB IDENTIFICATION

The serial number is on the certification plate, 1, on the rear crossbar.



16

SERVICE TECHNIQUES

GENERAL

Clean the exterior of all components before carrying out any form of repair. Dirt and abrasive dust can reduce the efficient working life of a component and lead to costly replacement.

Time spent on the preparation and cleanliness of working surfaces will pay dividends in making the job easier and safer and will result in overhauled components being more reliable and efficient in operation.

Use cleaning fluids which are known to be safe. Certain types of fluid can cause damage to O rings and cause skin irritation. Solvents should be checked that they are suitable for the cleaning of components and also that they do not risk the personal safety of the user.

Replace O rings, seals or gaskets whenever they are disturbed. Never mix new and old seals or O rings, regardless of condition. Always lubricate new seals and O rings with hydraulic oil before installation.

When replacing component parts, use the correct tool for the job.

HOSES AND TUBES

Always replace hoses and tubes if the cone end or the end connections on the hose are damaged.

When installing a new hose, loosely connect each end and make sure the hose takes up the designed position before tightening the connection. Clamps should be tightened sufficiently to hold the hose without crushing and to prevent chafing.

After hose replacement to a moving component, check that the hose does not foul by moving the component through the complete range of travel.

Be sure any hose which has been installed is not kinked or twisted.

Hose connections which are damaged, dented, crushed or leaking, restrict oil flow and the productivity of the components being served. Connectors which show signs of movement from the original swaged position have failed and will ultimately separate completely.

A hose with a chafed outer cover will allow water entry. Concealed corrosion of the wire reinforcement will subsequently occur along the hose length with resultant hose failure.

Ballooning of the hose indicates an internal leakage due to structural failure. This condition rapidly deteriorates and total hose failure soon occurs.

Kinked, crushed, stretched or deformed hoses generally suffer internal structural damage which can result in oil restriction, a reduction in the speed of operation and ultimate hose failure.

Free-moving, unsupported hoses must never be allowed to touch each other or related working surfaces. This causes chafing which reduces hose life.

O RING FLAT FACE SEAL FITTINGS

When repairing O ring face seal connectors, the following procedures should be observed.

WARNING

Never disconnect or tighten a hose or tube that is under pressure. If in doubt, actuate the operating levers several times with the engine switched off prior to disconnecting a hose or tube.

1. Release the fittings and separate the hose or tube assembly, then remove and discard the O ring seal from the fitting.
2. Dip a new O ring seal into clean hydraulic oil prior to installation. Install a new O ring into the fitting and, if necessary, retain in position using petroleum jelly.
3. Assemble the new hose or tube assembly and tighten the fitting finger tight, while holding the tube or hose assembly to prevent it from turning.
4. Use two suitable wrenches and tighten the fitting to the specified torque according to the size of the fitting. Refer to the following torque chart.

NOTE: *To ensure a leak-free joint is obtained, it is important that the fittings are not over or under torqued.*

O RING FLAT FACE SEAL FITTING TORQUE VALUES

NOMINAL TUBE O.D		DASH SIZE	THREAD SIZE	SWIVEL NUT TORQUE	
(mm)	(in.)		(in.)	N·m	Ft. Lbs.
6.35	0.250	-4	9/16-18	16	12
9.52	0.375	-6	11/16-16	24	18
12.70	0.500	-8	13/16-16	50	37
15.88	0.625	-10	1-14	69	51
19.05	0.750	-12	1 3/16-12	102	75
22.22	0.875	-14	1 3/16-12	102	75
25.40	1.000	-16	1 7/16-12	142	105
31.75	1.250	-20	1 11/16-12	190	140
38.10	1.500	-24	2-12	217	160

SEALER SPECIFICATIONS

The following sealers should be used as directed in the manual:

Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595 or 596 LOCTITE ULTRA BLUE 587 DOW CORNING SILASTIC 732 GENERAL ELECTRIC RTV 103 OR 108
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)

HARDWARE TORQUE VALUES

Check the tightness of hardware periodically.

Use the following charts to determine the correct torque when checking, adjusting or replacing hardware on the tractor.

IMPORTANT: *DO NOT use the values listed in the charts if a different torque value or tightening procedure is specified in this manual for a specific application. Torque values listed are for general use only.*

Make sure fastener threads are clean and not damaged.

NOTE: *A torque wrench is necessary to properly torque hardware.*

MINIMUM HARDWARE TIGHTENING TORQUES


IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

METRIC HARDWARE AND LOCKNUTS


NOMINAL SIZE	CLASS 5.8		CLASS 8.8		CLASS 10.9		LOCKNUT CL.8 W/CL8.8 BOLT
	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	
M4	15* (1.7)	19* (2.2)	23* (2.6)	30* (3.4)	33* (3.7)	42* (4.8)	16* (1.8)
M6	51* (5.8)	67* (7.6)	79* (8.9)	102* (12)	115* (13)	150* (17)	56* (6.3)
M8	124* (14)	159* (18)	195* (22)	248* (28)	274* (31)	354* (40)	133* (15)
M10	21 (28)	27 (36)	32 (43)	41 (56)	45 (61)	58 (79)	22 (30)
M12	36 (49)	46 (63)	55 (75)	72 (97)	79 (107)	102 (138)	39 (53)
M16	89 (121)	117 (158)	137 (186)	177 (240)	196 (266)	254 (344)	97 (131)
M20	175 (237)	226 (307)	277 (375)	358 (485)	383 (519)	495 (671)	195 (265)
M24	303 (411)	392 (531)	478 (648)	619 (839)	662 (897)	855 (1160)	338 (458)

NOTE: Torque values shown with * are inch pounds.

IDENTIFICATION
HEX CAP SCREW AND CARRIAGE BOLTS
CLASSES 5.6 AND UP



HEX NUTS AND LOCKNUTS
CLASSES 05 AND UP



MINIMUM HARDWARE TIGHTENING TORQUES

IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

INCH HARDWARE AND LOCKNUTS

NOMINAL SIZE	SAE GRADE 2		SAE GRADE 5		SAE GRADE 8		LOCKNUTS		NOMINAL SIZE
	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	GR.B w/GR5 BOLT	GR.C w/GR8 BOLT	
1/4	55* (6.2)	72* (8.1)	86* (9.7)	112* (13)	121* (14)	157* (18)	61* (6.9)	86* (9.8)	1/4
5/16	115* (13)	149* (17)	178* (20)	229* (26)	250* (28)	324* (37)	125* (14)	176* (20)	5/16
3/8	17 (23)	22 (30)	26 (35)	34 (46)	37 (50)	48 (65)	19 (26)	26 (35)	3/8
7/16	27 (37)	35 (47)	42 (57)	54 (73)	59 (80)	77 (104)	30 (41)	42 (57)	7/16
1/2	42 (57)	54 (73)	64 (87)	83 (113)	91 (123)	117 (159)	45 (61)	64 (88)	1/2
9/16	60 (81)	77 (104)	92 (125)	120 (163)	130 (176)	169 (229)	65 (88)	92 (125)	9/16
5/8	83 (112)	107 (145)	128 (174)	165 (224)	180 (244)	233 (316)	90 (122)	127 (172)	5/8
3/4	146 (198)	189 (256)	226 (306)	293 (397)	319 (432)	413 (560)	160 (217)	226 (306)	3/4
7/8	142 (193)	183 (248)	365 (495)	473 (641)	515 (698)	667 (904)	258 (350)	364 (494)	7/8
1	213 (289)	275 (373)	547 (742)	708 (960)	773 (1048)	1000 (1356)	386 (523)	545 (739)	1

NOTE: Torque values shown with * are inch pounds.

IDENTIFICATION
CAP SCREWS AND CARRIAGE BOLTS




SAE GRADE 2




SAE GRADE 5



SAE GRADE 8



REGULAR NUTS




SAE GRADE 5 HEX NUTS



SAE GRADE 8 HEX NUTS

LOCKNUTS



GRADE IDENTIFICATION

GRADE A NO NOTCHES

GRADE B ONE CIRCUMFERENTIAL NOTCH

GRADE C TWO CIRCUMFERENTIAL NOTCHES




GRADE IDENTIFICATION

GRADE A NO MARKS

GRADE B THREE MARKS

GRADE C SIX MARKS

MARKS NEED NOT BE LOCATED AT CORNERS



GRADE A NO MARK
GRADE B LETTER B
GRADE C LETTER C

GRADE IDENTIFICATION

LUBRICATION

New Holland (North America)

Adequate lubrication and maintenance on a regular schedule is vital to maintaining your equipment. To ensure long service and efficient operation, follow the lubrication and maintenance schedules outlined in this manual. The use of proper fuels, oils, grease and filters, as well as keeping the systems clean, will also extend machine and component life.

IMPORTANT: *Always use genuine* ***New Holland*** *replacement parts, oils and filters to ensure proper operation, filtration of engine and hydraulic systems. See your* ***New Holland*** *dealer for additional oil quantities.*

RECOMMENDED LUBRICANTS AND COOLANTS

Lubricant	Location Used	Type and Description	Part Number	Quart or Liter	Gallon or Tube
Oil	Engine and Pivot Points without Grease Fittings, Chains	SAE 30 API CF-2SJ	9613286	1Qt.	
		SAE 30 API CF-2SJ	9613289		2.5 Gal.
		SAE 30 API CF-2SJ	9613366*	4 L	
		5W-30 API SG/CD	9673589DS	1 Qt.	
		5W-30 API SG/CD	9624590*	4 L	
		10W-30 API SG/CD	9613313	1 Qt.	
		10W-30 API SG/CD	9613314		2.5 Gal.
		10W-30 API SG/CD	9673508DS		5 Gal.
		10W-30 API SG/CD	9613358*	1 L	
		10W-30 API SG/CD	9613359*	4 L	
		15W-40 API CF-4	9613290	1 Qt.	
		15W-40 API CF-4	9673730DS		1 Gal.
		15W-40 API CF-4	9613303		2.5 Gal.
		15W-40 API CF-4	9613292		5 Gal.
		15W-40 API CF-4	9613350*	1 L	
		15W-40 API CF-4	9613351*	4 L	
Coolant	Engine	ESE-M97B18-D, Ethylene Glycol New Holland Spec. Coolant Concentrate	FGCC2701DS		1 Gal.
		Propylene Glycol Concentrate	FGCC2711DS		1 Gal.
Hydraulic Oil	Hydraulic System, Hydrostatic System Front Axle Oil	134D – ESN-M2C134-D New Holland Spec. Hydraulic oil	9624450		2.5 Gal.
		134D – ESN-M2C134-D	9624451		5 Gal.
		134D – ESN-M2C134-D	9613367*	4 L	
		134D – ESN-M2C134-D	9624785*	10 L	
Hydraulic Oil	Optional, Multi-Seasonal Use, Recommended for Low Temperatures	F200	86523625DS	1 Qt.	
		F200	86523626DS		5 Gal.
		F200	86509446*	20 L	
Gear Oil	Gearboxes	80W90 EP Gear Oil API GL5	9613295	1 Qt.	
		80W90 EP Gear Oil API GL5	9613294		2.5 Gal.
		80W90 EP Gear Oil API GL5	9613375*	5 L	
		85W140 EP Gear Oil API GL5	9613297	1 Qt.	
		85W140 EP Gear Oil API GL5	9613296		2.5 Gal.
		85W140 EP Gear Oil API GL5	9613376*	4 L	
Grease	All Grease Fittings	Lithium base EP high temperature	9861804DS		Tube
		Lithium base EP high temperature	9861804CDS*		Tube
Brake Fluid		Mineral Based Oil	1QM6C34A or 86541699DS	1 Qt.	

**** NOTE:*** *Canada Part Numbers ONLY.*

Europe (All Markets Except North America)

Adequate lubrication and maintenance on a regular schedule is vital to maintaining your equipment. To ensure long service and efficient operation, follow the lubrication and maintenance schedules outlined in this manual. The use of proper fuels, oils, grease and filters, as well as keeping the systems clean, will also extend machine and component life.

IMPORTANT: *Always use genuine* ***New Holland*** *replacement parts, oils and filters to ensure proper operation, filtration of engine and hydraulic systems. See your* ***New Holland*** *dealer for oil quantities.*

RECOMMENDED LUBRICANTS AND COOLANTS

Lubricant	Location Used	Type and Description	Part Number
Oil	Engine and Pivot Points without Grease Fittings, Chains	SAE 30	Ambra Super 30
		5W-30 API SG/CD	Ambra Super Gold 5W-30
		10W-30 API SG/CD	Ambra Super Gold 10W-30
		15W-40 API CF-4	Ambra Super Gold 15W-40
Coolant	Engine	ESE-M97B18-D, Ethylene Glycol New Holland Spec. Coolant Concentrate	Ambra Agriflu (50% mix)
		Propylene Glycol Concentrate	
Hydraulic Oil	Hydraulic System Hydrostatic System Front Axle	134D – ESN-M2C134-D New Holland Spec. Hydraulic oil	Ambra Multi G Transmission Oil
		134D – ESN-M2C134-D New Holland Spec. Hydraulic oil	Ambra Multi F Transmission Oil
Hydraulic Oil	Optional, Multi-Seasonal Use, Recommended for Low Temperatures	F200	Ambra Multi H Transmission Oil
		F200	Ambra Multi F/10 Transmission Oil
Gear Oil	Gearboxes	80W90	Hypoide 90 LS
Grease	All Grease Fittings	Lithium base EP high temperature	Ambra GR75MD9
Brake Fluid		Mineral Based Oil	Ambra Brake LHM

SECTION 10 – ENGINE

Chapter 1 – Engine and Lubrication System

CONTENTS

Section	Description	Page
10 000	Specifications	3
	Torque Values	12
	Grease and Sealants	14
	Special Tools	15
	Description of Operation	16
	Cylinder Head Assembly	22
	Camshaft Assembly	22
	Crankshaft Assembly	22
	Connecting Rods	22
	Pistons	22
	Manifolds	22
	Cylinder Block Assembly	22
	Timing Gears	22
	Engine Lubrication	23
	Troubleshooting	27
	Disassembly and Repair	30
	Cylinder Head	30
	Cylinder Head Reassembly	42
	Additional Information	45
	Crankcase Front Cassette Seal	47
	Parts Affected	47
	Additional Information	47
	Removal of Old Style Seal and Installation of the New Cassette Seal	47
	Front Cassette Seal Removal	53

Engine Front Cover and Timing Gear 58
Oil Pan 60
Connecting Rods, Bearings, Pistons and Rings 61
Cylinder Block Overhaul 64
Piston Assembly Installation 69
Main Bearings, Flywheel and Crankshaft 70
Rear Cover Plate 72
Oil Pump 75
Oil Filter Support Assembly 77
Crankshaft 78
Camshaft 82
Engine Timing Gears 84
Engine Compression Test 85
Test Procedure 85
Test Reading 85
Test Conclusion 85

SPECIFICATIONS

TRACTOR MODEL	8670/8670A	8770*/8770A	8870/8870A	8970/8970A
NO. OF CYLINDERS	6 IN-LINE	6 IN-LINE	6 IN-LINE	6 IN-LINE
BORE (in.) (mm)	 4.4 111.8	 4.4 111.8	 4.4 111.8	 4.4 111.8
STROKE (in.) (mm)	 5.0 127.0	 5.0 127.0	 5.0 127.0	 5.0 127.0
DISPLACEMENT (cu in) (L)	 456 7.5	 456 7.5	 456 7.5	 456 7.5
COMPRESSION RATIO	17.5-1	17.5-1	17.5-1	17.5-1
TURBOCHARGED	Yes	Yes	Yes	Yes
INTERCOOLED	No	No*, Yes	Yes	Yes
FIRING ORDER	153624	153624	153624	153624
LOW IDLE SPEED RPM	900 +/- 25	900 +/- 25	815 +/- 25	815 +/- 25
HIGH IDLE SPEED RPM	2305 +/- 25	2305 +/- 25	2305 +/- 25	2305 +/- 25
RATED ENGINE SPEED RPM	2100	2100	2100	2100
PTO HORSEPOWER	145	160	180	210

CYLINDER BLOCK

Taper of Cylinder Bore	0.025 mm (0.001″) Repair Limit 0.127 mm (0.005″) Wear Limit
Cylinder Bore Out of Round	0.03 mm (0.0015″) Repair Limit 0.127 mm (0.005″) Wear Limit
Cylinder Bore Diameters	111.778 - 111.841 mm (4.4007 - 4.4032″)
Rear Oil Seal Retainer Bore Diameter	140.77 - 140.87 mm (5.542 - 5.546″)
Block to Head Surface Flatness	0.08 mm (0.003″) in any 152 mm (6″) 0.03 mm (0.001″) in any 25.40 mm (1″)

* Units built after Jan. 1996 are intercooled.

CYLINDER HEAD

Valve Guide Bore Diameter	9.469 - 9.495mm (0.3728 - 0.3738″)
Head to Block Surface Flatness	0.03 mm (0.001″) in any 25.4 mm (1″) or 0.08 mm (0.003″) in any 152 mm (6″) section

EXHAUST VALVES

Face Angle	44°15′ - 44°30′ Relative to the Head of Valve
Stem Diameter	Std: 9.401 - 9.421 mm (0.3701 - 0.3709″) 0.076 mm (0.003″) Oversize: 9.477 - 9.497 mm (0.3731 - 0.3739″) 0.38 mm (0.015″) Oversize: 9.781 - 9.802 mm (0.3851 - 0.3859″) 0.76 mm (0.030″) Oversize: 10.163 - 10.183 mm (0.4001 - 0.4009″)
Head Diameter	42.88 - 43.13 mm (1.688 - 1.698″)
Stem to Guide Clearance	0.048 - 0.094 mm (0.0019 - 0.0037″)
Lash Clearance (Cold)	0.43 - 0.53 mm (0.017 - 0.021″)

INTAKE VALVES

Face Angle	29°15′ - 29°30′ Relative to Head of Valve
Stem Diameter	Std: 9.426 - 9.446 mm (0.3711 - 0.3719″) 0.076 mm (0.003″) Oversize: 9.502 - 9.522 mm (0.3741 - 0.3749″) 0.381 mm (0.015″) Oversize: 9.807 - 9.827 mm (0.3861 - 0.3869″) 0.762 mm (0.030″) Oversize: 10.188 - 10.208 mm (0.4011 - 0.4019″)
Head Diameter	47.37 - 47.63 mm (1.865 - 1.875″)
Stem to Guide Clearance	0.023 - 0.069 mm (0.0009 - 0.0027″)
Lash Clearance (Cold)	0.36 - 0.46 mm (0.014 - 0.018″)

VALVE SPRINGS

Number per Valve	1
Installed Height	1.95 - 1.86
Free Length	60.7 mm (2.39″)
Length, loaded at 27.7 - 31.3 kg (61 - 69 lbs)	48.26 mm (1.900″)
Length, loaded at 61 - 69 kg (135 - 153 lbs)	35.69 mm (1.405″)

NOTE: *For engines in service, installed height can be adjusted with use of shims, 0.030″ Part#C5NE-6A526-A*

VALVE TIMING

Intake Opening	12° Before Top Dead Center
Intake Closing	38° After Bottom Dead Center
Exhaust Opening	48° Before Bottom Dead Center
Exhaust Closing	12° After Top Dead Center

CAMSHAFT LOBE LIFT

Intake	8.38 mm (0.330″)
Exhaust	8.38 mm (0.330″)

INSTALLED VALVE RECESSION

Intake	0.86 - 1.32 mm (0.034 - 0.052″)
Exhaust	1.17 - 1.65 mm (0.046 - 0.065″)

VALVE INSERTS

Insert Oversize	Counterbore Diameter in Cylinder Head	
	Exhaust Valve Insert	Intake Valve Seat Insert
0.254 mm (0.010″)	44.17 - 44.20 mm (1.739 - 1.740″)	50.01 - 50.04 mm (1.969 - 1.970″)
0.508 mm (0.020″)	44.42 - 44.45 mm (1.749 - 1.750″)	50.27 - 50.29 mm (1.979 - 1.980″)
0.762 mm (0.030″)	44.68 - 44.70 mm (1.759 - 1.760″)	50.52 - 50.55 mm (1.989 - 1.990″)

VALVE SEATS

Exhaust Valve Seat Angle	45°00′ - 45°30′
Intake Valve Seat Angle	30°00′ - 30°30′
Interference Valve Face Angle to Valve Seat Angle	0°30′ - 1°15′
Concentricity With Guide Diameter	0.051 mm (0.002″) Total Indicator Reading Max
Seat Width	
Exhaust Valve	1.8 - 2.3 mm (0.072 - 0.092″)
Intake Valve	1.9 - 2.5 mm (0.078 - 0.098″)

CAMSHAFT IDLER GEAR

Number of teeth	47
End Play	0.076 - 0.35 mm (0.003 - 0.014″)
Bushing Inside Diameter	50.813 - 50.838 mm (2.0005 - 2.0015″)
Adaptor Outside Diameter	50.762 - 50.775 mm (1.9985 - 1.9990″)
Backlash with Crankshaft Gear	0.10 - 0.36 mm (0.004 - 0.014″)
Backlash with Camshaft Gear	0.10 - 0.36 mm (0.004 - 0. 014″)
Backlash with Fuel Injection Pump	0.10 - 0.48 mm (0.004 - 0.019″)

CAMSHAFT GEAR

Number of Teeth	52
Timing Gear Backlash	0.10 - 0.36 mm (0.004 - 0.014″)

ROCKER ARM SHAFT

Shaft Diameter	25.40 - 25.43 mm (1.000 - 1.001″)
Shaft Support Internal Diameter	25.45 - 25.20 mm (1.002 - 1.004″)

ROCKER ARM

Inside Diameter	25.48 - 25.50 mm (1.003 - 1.004″)

TAPPETS

Clearance to Bore	0.015 - 0.053 mm (0.0006 - 0.0021″)
Tappet Diameter	25.118 - 25.130 mm (0.9889 - 0.9894″)
Tappet Bore Diameter	25.15 - 25.17 mm (0.9900 - 0.9910″)

CAMSHAFT

Bearing Journal Diameter	60.693 - 60.719 mm (2.3895 -2.3905″)
Bearing Clearance	0.076 - 0.1270 mm (0.003 - 0.005″)
End Play	0.051 - 0.18 mm (0.0020 - 0.0070″)

CONNECTING RODS

Small End Bushing (Internal Diameter)	44.458 - 44.465 mm (1.7503 - 1.7506″)
Big End Bearing Clearance	0.038 - 0.104 mm (0.0015 - 0.0041″)
Clearance Bushing to Piston Pin	0.013 - 0.025 mm (0.0005 - 0.0010″)
Side Float	0.13 - 0.33 mm (0.0050 - 0.0130″)
Maximum Twist	0.30 mm (0.0120″)
Maximum Bend	0.10 mm (0.0040″)

PISTON PIN

Outside Diameter	44.44 - 44.62 mm (1.7497 -1.7499″)

PISTONS

Skirt to Cylinder Clearance	0.152 - 0.182 mm (0.0060 - 0.0072″)
Taper (Out of Round)	0.063 - 0.127 mm (0.0025 - 0.0050″)
Grading Diameter (at Right Angles to Piston Pin)	111.64 - 111.74 mm (4.3951 - 4.3991″) in increments of 0.0127 mm (0.0005″)
Piston Pin Clearance	0.0127 - 0.0254 mm (0.0005 - 0.0010″) at 21°C (70°F)
Piston Crown to Block Face, Measure through center line of piston, parallel to crankshaft	0.0 - 0.3 mm (0.0 - 0.012″)

PISTON RINGS

2 Compression,	Location -1st and 2nd from the top of the piston
Top Compression Ring	Keystone Tapered With Letter “O” to the Top - All Models
2nd Compression Ring	Straight Face-Inner Step, Internal Chamfer Toward Bottom - Models 8670 and 8770
2nd Compression Ring	Keystone Tapered With Letter “O” to the Top - Models 8870 and 8970
1 Oil Control,	Location - Directly above the Piston Pin,
Type	Slotted With Expander - All Models
Side Face Clearance to Ring Groove	
Top Compression Ring	Keystone - use gauge #FNH00180 - All Models
2nd Compression Ring	0.102 - 0.152 mm (0.0040 - 0.0060″) - Models 8670 and 8770
2nd Compression Ring	Keystone - use gauge #FNH00180 - Models 8870 and 8970
Oil Control Ring	0.061 - 0.112 mm (0.0024 - 0.0044″) - All Models
Gap Width	
Top Compression Ring	0.36 - 0.66 mm (0.014 - 0.026″) - All Models
2nd Compression Ring	0.36 - 0.66 mm (0.014 - 0.026″) - All Models
Oil Control Ring	0.36 - 0.66 mm (0.014 - 0.026″) - All Models

CRANKSHAFT

Main Journal Diameter-Blue	85.631 - 85.644 mm (3.3713 - 3.3718″)
-Red	85.644 - 85.656 mm (3.3718 - 3.3723″)
Main Journal Length (except thrust, and rear)	36.96 - 37.21 mm (1.455 - 1.465″)
Thrust Bearing Journal Length	37.06 - 37.11 mm (1.459 - 1.461″)
Rear Bearing Journal Length	37.97 - 38.10 mm1.495 - 1.505″ ()
Main Journal Wear Limits	0.127 mm (0.005″) Maximum
Main and Crankpin Fillet Radius	0.25 mm (0.01″)
Intermediate Bearing Journal Length	36.96 - 37.21 mm (1.455 - 1.465″)
Crankpin Journal Length	42.62 - 42.72 mm (1.678 - 1.682″)
Crankpin Diameter - Blue	69.840 - 69.850 mm (2.749 - 2.7500″)
- Red	69.850 - 69.860 mm (2.750 - 2.7504″)
End Play	0.10 - 0.36 mm (0.004 - 0.014″)
Crankpin Out of Round	0.005 mm (0.0002″) Total Indicator Reading
Taper Surface Parallel to Center Line of Main Journal	0.005 mm (0.0002″)
Crankshaft Rear Oil Seal Journal Diameter	122.12 - 122.28 mm (4.808 - 4.814″)
Crankshaft Pulley Journal Diameter	51.788 - 51.808 mm (2.0389 - 2.0397″)
Crankshaft Timing Gear Journal Diameter	52.131 - 52.146 mm (2.0524 - 2.0530″)
Crankshaft Flange Runout	0.038 mm (0.0015″) Max

CRANKSHAFT DRIVE GEAR

Number of teeth	26
Installation Temperature	203° C (400° F)

MAIN BEARING

Liner length (except thrust liner)	27.94 - 28.19 mm (1.10 - 1.11″)
Liner Length (thrust liner)	39.91 - 39.96 mm (1.453 - 1.455″)
Vertical Assembled Bearing Clearance	0.055 - 0.117 mm (0.0022 - 0.0049″)

CRANKPIN BEARINGS

Liner Length	31.50 - 31.75 mm (1.240 - 1.250″)
Vertical Assembled Bearing Clearance	0.038 - 0.104 mm (0.0015 - 0.0041″)
Bearing Clearance - Service Limit	0.127 mm (0.005″)

TORSIONAL VIBRATION DAMPENER (FRONT PULLEY)

Interference Fit with Crankshaft	0.023 - 0.064 mm (0.0009 - 0.0025″)
Installation Force Required (Coat crankshaft with graphite lubricant prior to installation)	5000.0 - 9545.5 kg (11,000 - 21,000 lbs)

CRANKSHAFT REGRINDING

When regrinding a crankshaft, the main and crankpin journal diameters should be reduced the same amount as the undersize bearings used, and the following dimensions apply. The rear end of the crankshaft should be located on the 60° chamfer of the pilot bearing bore.

Undersize Bearing Available	**Main Journal Diameters**
0.051 mm (0.002″)	85.580 - 85.593 mm (3.3693 - 3.3698″)
0.254 mm (0.010″)	85.390 - 85.402 mm (3.3618 - 3.3623″)
0.508 mm (0.020″)	85.136 - 85.148 mm (3.3518 - 3.3523″)
0.762 mm (0.030″)	84.882 - 84.894 mm (3.3418 - 3.3423″)
1.016 mm (0.040″)	84.628 - 84.640 mm (3.3318 - 3.3323″)
Undersize Bearing Available	**Crankpin Journal Diameters**
0.051 mm (0.002″)	69.789 - 69.799 mm (2.7476 - 2.7480″)
0.254 mm (0.010″)	69.956 - 69.606 mm (2.7400 - 2.7404″)
0.508 mm (0.020″)	69.342 - 69.352 mm (2.7300 - 2.7304″)
0.762 mm (0.030″)	69.088 - 69.098 mm (2.7200 - 2.7204″)
1.016 mm (0.040″)	68.834 - 68.844 mm (2.7100 - 2.7104″)

FLYWHEEL

Runout of Clutch Face (Between Outer Edge of Friction Surface and Mounting Bolt Holes)	0.127 mm (0.005″)
Ring Gear Runout	0.63 mm (0.025″)

OIL PUMP

Flow Rate	20 GPM @ 2100 Engine RPM and 20 PSI
Rotor Clearance	0.025 - 0.15 mm (0.001 - 0.006″)
Rotor to Pump Housing Clearance	0.15 - 0.28 mm (0.006 - 0.011″)
Rotor End Play	0.025 - 0.089 mm (0.001 - 0.0035″)
Pump Gear to Camshaft Gear Backlash	0.40 - 0.56 mm (0.016 - 0.022″)

OIL PRESSURE WITH ENGINE AT OPERATING TEMPERATURE

Minimum at Low Idle	12 PSI
Rated Engine Speed	
Minimum	35 PSI
Maximum	80 PSI

ENGINE OIL SPECIFICATIONS

Engine API CF-4 15W40	ESE-M2C153-E

Use an oil which meets both Ford specification ESE-M2C153-E and API service category CF-4 (preferred), CF-4/SF or CF-4/SG. If API CF-4 oils are not available, the API CE or CE/SF, or CE/SG category may be used. For low temperatures (below -18° C [0° F]), use an SAE 5W-30 SG/CD.

Selecting the Right Viscosity

To choose the right viscosity grade, one must consider the temperature in which the vehicle will be operated. If regularly operated in temperatures that are consistently above -12° C (10° F), use SAE 15W-40 oil. If regularly operating in temperatures that are below -18° C (0° F), use SAE 5W30.

IMPORTANT: *Using oil quality and/or viscosity grades other than those recommended may result in engine damage.*

ENGINE OIL CAPACITY

With Oil Filter	21.3 L (22.5 U.S. qts.)

THERMOSTAT

Opening Temperature	81° C (178° F)
Fully Open	95° C (203° F)

WATER PUMP

Type	Centrifugal
Drive	Poly V Belt
Coolant Flow at Rated Engine Speed	291.4 L/min (77 U.S. GPM)

FAN BELT

Belt Tension	Maintained by Tensioner

VEHICLE COOLING SYSTEM CAPACITIES

Engine Only	21.3 L (22.5 U.S. qts.)
System	26.5 L (28.0 U.S. qts.) - Models 8870/8870A and 8970/8970A 25 L (26.5 U.S. qts.) - Models 8670/8670A and 8770/8770A

COOLING FLUID

The 70 Series and 70A Series before serial number #D423202, antifreeze ESEM97B-18C/D or SSM-97B-9101A (green in color) was used. Mix with an equal amount of clean water and change every 2400 hours or 24 months (whichever occurs first). Change the coolant filter at the same time.

The 70A Series after serial number #D423202, the anti-freeze is purple in color. The anti-freeze meets or exceeds the ASTM 06210/6211 and TMC RP 329 standards. It can be mixed with the old anti-freeze but is not recommended because it would dilute the effects of the additives plus create a murky color.

Clean water only (only applicable to hot countries where antifreeze is not available).

Change coolant and coolant filter every 1200 hours or 24 months (whichever occurs first).

IMPORTANT: *The new filter contains a measured amount of chemical inhibitor in paste form. The amount of conditioner and the size of the filter element are matched to the cooling capacity of the tractor. It is important that this filter is changed every 1200 hours if total protection of the engine cooling system is to be maintained. The use of a non-approved filter may jeopardize this protection.*

IMPORTANT: *Install a new filter/conditioner in the event of a large coolant loss such as a failed coolant hose.*

IMPORTANT: *Do not replace the filter/conditioner more frequently than specified unless a large coolant loss occurs.*

IMPORTANT: *Anti-leak additives should not be used. The clogging properties of these additives could affect the performance of the filter and conditioner.*

IMPORTANT: *If it becomes necessary to replace the filter before the 1,200 hour change interval, or if less than one-half of the coolant is lost, a filter without a conditioner should be installed.*

NOTE: *In order to reduce deposits and corrosion, water used in the cooling system should not exceed the following limits:*

Total hardness	*300 parts per million*
Chlorides	*100 parts per million*
Sulfates	*100 parts per million*

TORQUE VALUES

The following general nut and bolt installation torque requirements (lubricated) apply to any operation not previously listed.

TORQUE VALUES - INCH HARDWARE	N·m	FT LBS
1/4 - 20	11	8
1/4 - 28	11	8
5/16 -18	19	14
5/16 -24	23	17
3/4 - 16	31	23
3/4 - 24	45	33
7/16 -14	65	48
7/16 -20	75	55
1/2 - 13	88	65
1/2 - 20	102	75
9/16 -18	122	90
5/8 -18	190	140
TORQUE VALUES - CYLINDER BLOCK PLUGS		
1/8 - 27 NPT	11	8
1/4 - 18 NPT	29.8	22
3/8 - 18 NPT	61	45
3/4 - 14 NPT	27	20

TORQUE VALUES - VARIOUS	N·m	FT LBS
Camshaft Gear Bolt	69	51
Camshaft Gear Plate Bolts	47	35
Camshaft Idler Drive Gear-to-Block	237	175
Connecting Rod Bolts	149	110
Coolant Bypass Tube Rear Clamp Bolt	65	48
Cover Bolts (Blanks Oil Drilling)	31	23
Crankshaft Pulley-to-Crankshaft	224	210
Crankshaft Rear Oil Seal Retainer - Initial Tightening Final Tightening	 12.2 20.3	 9 15
Cylinder Head Bolts (with Engine Cold)	217	160
Exhaust Manifold-to-Cylinder Head	38	28
Flywheel-to-Crankshaft	244	180
Front Adaptor Plate-to-Cylinder Block	24	18
Front Cover Mounting Bolts (See drawing)	25	18
Injector Attachment Bolts	23	17
Injector Line Nuts	24	18
Injection Pump Drive Gear	38	28
Injection Pump Rear Mounting Bolts	38	28
Injection Pump-to-Front Adaptor Plate	38	28
Injection Pump-to-Gear Drive Bolts	67	50
Injection Timing Gear Access Cover	38	28
Intake Manifold-to-Cylinder Head	38	28
Leak-off Tube Banjo Fitting Bolts	5.4	4
Main Bearing Bolts	197	145
Oil Cooler Cover Bolts	44.7	33
Oil Filter Cooler/Adaptor to Block Bolts	42	31
Oil Filter Mounting Bolt Insert	42	31
Oil Pan Drain Plug	41	30
Oil Pan-to-Cylinder Block	33	25
Oil Pickup Tube to Block	32	24
Oil Pump Drive Gear Rear of Camshaft	70	52
Oil Pump to Block	23	17
Self-Locking Screw - Valve Rocker Arm	24	18
Spin-on Oil Filter	20.3	15
Starting Motor-to-Rear Adaptor Plate	54.2	40
Thermostat Top Cover Bolts	24	18
Thermostat/Fan Mount Housing-to-Cylinder Block Bolts	65	48
Timing Gear Cover	38	28
Turbocharger-to-Flange Nut	47.5	35
Turbocharger-to-Flange Stud.	11	8
Valve Rocker Cover Bolts	24	18
Water Pump-to-Cylinder Block	65	48

GREASE AND SEALANTS

Code	Number	Name
A	NLG1 Grade 2	Grease
B	ESF-M1C43-A	Grease-Silicone Light Consistency
C	ESE-M4G194-B	Sealer-Anaerobic Low strength
D	ESE-M4G195-A	Sealer-Silicone
E	SP-M4G9112-A	Sealer-Polyester Urethane
F	SP-M4G9112-C	Sealer-Polyester Urethane
G	ESE-M4G217-A	Sealer-Anaerobic
J	SP-M2G9121-B	Sealer-RTV Silicone rubber

SPECIAL TOOLS

(Prior tool numbers, where applicable, are shown in brackets)

DESCRIPTION	V.L. CHURCHILL TOOL #	NUDAY TOOL #	CNH (OTC) TOOL #
Push/Puller	938	9506	FNH09506
Shaft Protectors	625-A	9212	FNH09212
Step Plate Adaptors	630-S	9210	FNH09210
Bushing Kit	818	9514	FNH09514
Valve Guide Reamer Kit	(SW-502)	2136	FNH02136
Camshaft Bearings - Remover/Installer Handle	 SW-24A N6261-A	 1255 1442	 FNH01225 FNH01442
Water Pump Seal Replacer	N/A	4672	FNH04672
Connecting Rod Bushing - Removal Installation	N/A	N/A	FNH 00035 OTC 134-00002
Crankshaft Seal Replacer Front Seal (non-cassette style) Rear Seal	 630-16 FT 6212	 N/A 1301	 T87T-6019-A FNH 01301
Front Cassette Crankshaft Seal Remover Installer	 N/A N/A	 N/A N/A	 380000212 NH01417
Valve Guide Seal Grinder for new Seals	N/A	N/A	CNH297669
Ring Groove Wear Gauge	N/A	N/A	FNH00180
Compression Test Adapter	N/A	N/A	FNH00882
Universal Pressure Kit	N/A	N/A	FTC213312
Master Fitting Kit	N/A	N/A	FTC61682
Torque Angle Indicator	N/A	N/A	OEM7415


DESCRIPTION OF OPERATION

This chapter provides an overview of all the engine systems used on the 70 and 70A Series tractors. A general troubleshooting section is included in this chapter. Once the particular system causing the concern is identified, more detailed troubleshooting can be found in the appropriate system's section of this manual.

All engines used on the 70 and 70A Series tractors are of similar design, and many service procedures are common throughout the range. Each engine model is a 6-cylinder turbocharged, having a bore of 111.8 mm (4.4″) and a stroke of 127 mm (5.0″) which generates a displacement of 456 cu. in. Increased power levels of the various models from the base engine are achieved by tailored fuel systems and the addition of an intercooler. While of similar dimensions, internal components on the higher horsepower models are stronger to withstand greater stresses. General engine specifications are in the chart below.


TRACTOR MODEL	8670/8670A	8770*/8770A	8870/8870A	8970/8970A
NO. OF CYLINDERS	6 IN-LINE	6 IN-LINE	6 IN-LINE	6 IN-LINE
BORE (in.) (mm)	 4.4 111.8	 4.4 111.8	 4.4 111.8	 4.4 111.8
STROKE (in.) (mm)	 5.0 127.0	 5.0 127.0	 5.0 127.0	 5.0 127.0
DISPLACEMENT (cu in) (L)	 456 7.5	 456 7.5	 456 7.5	 456 7.5
COMPRESSION RATIO	17.5-1	17.5-1	17.5-1	17.5-1
TURBOCHARGED	Yes	Yes	Yes	Yes
INTERCOOLED	No	No*, Yes	Yes	Yes
FIRING ORDER	153624	153624	153624	153624
LOW IDLE SPEED RPM	900 +/- 25	900 +/- 25	815 +/- 25	815 +/- 25
HIGH IDLE SPEED RPM	2305 +/- 25	2305 +/- 25	2305 +/- 25	2305 +/- 25
RATED ENGINE SPEED RPM	2100	2100	2100	2100
PTO HORSEPOWER	145	160	180	210

***** Units built after Jan. 1996 are intercooled.



70-110-1853


1



2

Left Side View (70 Series)


1. Turbocharger
2. Engine oil filter
3. Engine oil dipstick
4. Engine oil filler cap
5. Coolant expansion chamber
6. Air conditioning compressor
7. Coolant conditioning filter



3

Right Side View (70 Series)


1. Radiator
2. Alternator
3. Bosch inline fuel injection pump
4. Throttle control cable
5. Fuel shutoff solenoid
6. Fuel filter element
7. Starter motor
8. Diesel fuel hand priming pump
9. Muffler
10. Dry air filter



4

Left Side View (70A Series)

1. Turbocharger
2. Engine oil filter
3. Engine oil dipstick
4. Engine oil filler cap
5. Coolant expansion chamber
6. Air conditioning compressor
7. Coolant conditioning filter



5

Right Side View (70A Series)

1. Radiator
2. Alternator
3. Bosch inline fuel injection pump
4. Throttle control cable
5. Fuel shutoff solenoid
6. Fuel filter element
7. Starter motor
8. Diesel fuel hand priming pump
9. Muffler
10. Dry air filter

CYLINDER HEAD ASSEMBLY

The cylinder head incorporates valves and springs with the valve rocker arm shaft assembly bolted to the cylinder block through the cylinder head. Cylinder head retaining bolts are evenly spaced with a six-point pattern around each cylinder. This ensures an even clamping load across the cylinder head area.

The intake and exhaust manifolds are bolted to the head. The intake manifold is mounted on the right-hand side of the engine with the injectors mounted outside the rocker cover. The exhaust manifold is mounted on the left-hand side of the engine, water outlet connections and thermostats being attached to the front of the cylinder block directly behind the radiator.

Valve guides are integral in the cylinder head and valves with oversized stems are available in service. All valves are fitted with positive valve rotators, with both intake and exhaust valves using umbrella-type oil seals. Valve lash is maintained by adjustment of the self-locking adjusting screw mounted at each of the rock arms.

CAMSHAFT ASSEMBLY

The camshaft runs in 5 replaceable bearings. The camshaft drive gear is in mesh and driven by the camshaft idler gear and crank shaft timing gear.

Camshaft end thrust is controlled by a thrust plate bolted to the block and located between the camshaft gear and the front camshaft journal.

A helical gear is mounted on the rear of the camshaft and drives the engine oil lubrication pump mounted forward of the flywheel.

CRANKSHAFT ASSEMBLY

The crankshaft assembly is made of steel and is supported in the cylinder block by 7 main bearings. End thrust is controlled by a thrust bearing incorporated in the center main bearing of the crankshaft. A crankshaft dampener to control torsional vibration is fitted externally to the crankshaft to ensure smooth running. Front and rear crankshaft oil seals are a one-piece design for long life and durability.

CONNECTING RODS

The wedge- or teepee-shaped connecting rods are designed to reduce the reciprocating weight at the piston end and provide increased bearing area at the piston pin. The connecting rods are assembled as a matched set to each engine attached to the crankshaft by means of insert-type copper/lead or aluminum tin alloy bearings.

The small end of the connecting rod is fitted with a replaceable bronze bushing, through which a free-floating piston pin is fitted. The steel pin is held in place within the piston by two snap rings.

PISTONS

Pistons of increased weight and strength are constructed of an aluminium silicon alloy with an iron insert for the top ring and on the Models 8870 and 8970 the second ring. The combustion chamber is recessed into the piston crowns.

Each piston has two compression rings and one oil control ring to reduce friction and increase positive sealing. All rings are located above the piston pin.

MANIFOLDS


The intake manifold is aluminum and is a plenum type to provide better flow into the engine. Opposing manifolds ensure minimum heat transfer to the intake manifold. The intake manifold is tapped for an ether cold starting aid.

CYLINDER BLOCK ASSEMBLY

The cylinder block is an alloy cast iron with deep cylinder skirts and water jackets for cooling the cylinders. The cylinder bores are machined integral with the cylinder block during the manufacturing process. They can be bored oversize for the fitment of sleeves or oversized pistons, which are available in Parts.

TIMING GEARS


The crankshaft timing gear is heated and press fitted onto the front of the crankshaft to a high degree of accuracy during manufacturing. This enables precise timing to be maintained during the life of the engine. The crankshaft drives the camshaft idler gear which is attached to the front of the cylinder block. The idler gear then drives the camshaft and the injection pump via meshing helical gears.



6


ENGINE LUBRICATION

The lubrication of the engine is maintained by a rotor-type 22 GPM oil pump mounted in the rear of the engine block, 1, forward of the flywheel on the left-hand side of the engine.



7


The oil pump is driven from the rear of the camshaft and draws oil from the oil pan through a suction tube and screen assembly.



8


A spring-loaded regulating valve is integral with the oil filter base, 1, mounted on the left-hand side of the engine block. The spring, 3, and valve, 2, are accessed by removing a retaining plug, 4.

The spin-type oil filter mounted on the left-hand side of the engine is easily accessible. Oil flows from the filter to the main oil gallery which runs the length of the cylinder block and intersects the camshaft follower chamber.




9

The main gallery also supplies oil to the crankshaft main bearings, connecting rods, big end and small end bearings. The underside of the the pistons and pins are lubricated by oil pressure jets mounted adjacent to each main journal housing. The camshaft gear bushing is pressure lubricated through a drilled passage from the front main bearing. The gear has small oil passages machined on both sides allowing excess oil to escape.




10

Timing gears are lubricated by splashed oil from the cam follower chamber and the pressure lubricated camshaft drive gear bushing.




11

An intermittent flow of oil is directed to the valve rocker arm shaft assembly via a drilled passage in the cylinder block. This is located vertically above #1 camshaft bearing, 1, and aligns to a hole in the cylinder head. The rotation of the camshaft allows a controlled intermediate flow of lubrication.



12


The turbocharger is supplied with oil from the oil filter support housing mounted on the left-hand side of the engine.



13

NOTE: *70 Series art shown in Figure 14.*

The fuel injection pump is pressure lubricated from a port, 1, on the right-hand side of the engine block. This passage intersects the #3 main bearing supply gallery.



14

TROUBLESHOOTING

Correct diagnosis of a problem is much easier to find by following a series of systematic troubleshooting sequences. It is important to observe any symptoms that the tractor may have along with warning lights and specific error codes that may appear on the instrument cluster.

IMPORTANT: *Before making a repair, it is important to investigate the problem thoroughly to ensure a suitable correction without repeat failures.*

The following table lists the problems and their possible causes with recommended action.

PROBLEM	POSSIBLE CAUSE	CORRECTION
Engine does not develop full power	Clogged air cleaner	Clean or renew element
	Fuel line obstructed	Clean
	Faulty injectors	Clean and reset
	Incorrect valve lash adjustment	Check and reset
	Burnt, worn, or sticking valves	Replace valves with new or oversize and/or machine the valve guide bores.
	Blown head gasket	Check head flatness and fit new gasket
	Incorrect fuel delivery	Check injectors and pump
	Low compression	Renew piston rings or rebore/resleeve as necessary
Engine knock	Diluted or thin oil	Check crankshaft bearings for damage, change as required. Drain and refill with specified oil and renew filter. Determine cause of dilution
	Insufficient oil supply	Check oil level and top up as necessary. Overhaul or renew pump as necessary. Check oil filter is not clogged
	Low oil pressure	Overhaul pump or relief valve as necessary
	Excessive crankshaft end play	Install new thrust bearing liner
	Flywheel or ring gear runout excessive	Skim flywheel or fit new ring gear
	Excessive connecting rod or main bearing clearance	Install new bearing inserts and/or regrind crankshaft
	Bent or twisted connecting rods	Renew connecting rods
	Crankshaft journals out of round	Regrind crankshaft and fit oversized bearing inserts
	Excessive piston to cylinder bore clearance	Rebore/resleeve block and fit new pistons
	Excessive piston ring clearance	Fit new pistons and rings

PROBLEM	POSSIBLE CAUSE	CORRECTION
Engine knock (continued)	Broken rings	Fit new rings, check bore and pistons for damage
	Excessive piston pin clearance	Fit new piston and/or pin
	Piston pin retainer loose or missing	Install new retainer and/or check bore/pistons for damage
	Excessive camshaft play	Install new thrust plate
	Imperfections on timing gear teeth	Renew timing gear
	Excessive timing gear backlash	Renew timing gear
Engine overheats	Hose connection leaking or collapsed	Tighten hose connections, renew hose if damaged
	Radiator cap defective or not sealing	Renew radiator cap
	Radiator leakage	Repair/renew radiator
	Improper fan belt tension	Check automatic tensioner or belt stretch
	Radiator fins restricted	Clean with compressed air
	Faulty thermostat	Renew thermostat
	Internal engine leakage	Check for source of leakage, renew gasket or defective parts
	Water pump faulty	Overhaul water pump
	Exhaust gas leakage into cooling system	Renew cylinder head gasket, check head for damage or distortion
	Coolant aeration	Tighten all connections and check coolant level is correct. Ensure cylinder head gasket has not blown
	Cylinder head gasket improperly installed	Renew cylinder head gasket
	Hot spot due to rust and scale or clogged water jackets	Reverse flush entire cooling system
	Obstruction to radiator air flow	Remove the obstruction
	Extended engine idling	Do not allow the engine to idle for long periods
	Oil cooler tube blocked	Clean
	Radiator core tubes blocked	Check free flow
	Engine oil pressure low	Top up as necessary

PROBLEM	POSSIBLE CAUSE	CORRECTION
Low oil pressure	Wrong grade oil	Drain and refill with the correct grade of oil
	Blocked oil pump sump screen	Clean pump screen
	Oil pressure relief valve faulty	Fit new relief valve
	Oil pump worn	Renew oil pump
	Excessive oil pump rotor and shaft assembly clearance	Overhaul pump
	Excessive main or connecting rod bearing clearance	Install new bearing inserts and/or regrind crankshaft
	Engine oil level too high	Reduce oil level
Excessive oil consumption	External oil leaks	Renew gasket and seals where necessary. Check mating surfaces for damage or distortion
	Worn valve guides or bores	Renew
	Cylinder head gasket leaking	Renew gasket. Check head for damage or distortion
	Oil loss past the piston rings	Renew rings and/or rebore sleeve block as necessary
	Oil cooler leaks	Repair/renew oil cooler assembly
Engine tends to keep firing after the engine is shut off	Air cleaner dirty or restricted	Clean or renew element
	Oil leak on compressor side of turbocharger	Overhaul turbocharger
Oil pressure warning light fails to operate	Bulb burnt out	Renew bulb
	Warning light pressure switch faulty	Renew pressure switch
	Warning light circuit faulty	Check and renew wiring
Engine fails to reach normal operating temperature	Faulty temperature sender	Renew sender switch
	Incorrect or faulty thermostat	Renew thermostat
	Faulty water temperature gauge	Renew temperature gauge
Excessive exhaust smoke	Oil leak on compressor or turbine side of turbocharger	Overhaul turbocharger
	Exhaust leak on exhaust side of turbocharger	Fit new gasket
	Air cleaner dirty or restricted	Clean
	Excessive fuel delivery	Overhaul injection pump and injectors

DISASSEMBLY AND REPAIR


Dismantle the engine by referring to the following removal procedure. Refer to the “Specifications” section as necessary.

NOTE: *All gaskets, seals, and O rings must be replaced with new ones upon reassembly. Where new sealant is to be applied, refer to “Specifications.”*

If the engine is to be removed as an assembly, the hood will need to be removed. Refer to Section 90, Chapter 2. For engine removal refer to Section 21, Chapter 2.

NOTE: *The cylinder head can be removed with the engine installed in the tractor.*

To remove the cylinder head only, remove the hood and engine upper frame as a complete assembly. For this procedure, refer to Section 90, Chapter 2.




15

CYLINDER HEAD


Removal

1. Close the engine coolant shutoff valves, 1, then disconnect and plug the heater hoses (where fitted).




16

2. Drain the coolant from the radiator using the drain tap, 1, on the bottom of the radiator. Remove radiator top hose.




17

3. Drain the coolant from the block using the drain plug, 1, on the left-hand side of the engine.




18

4. Disconnect and remove injector lines, 1, and leak-off lines, 2, from the fuel injectors and injection pump (cap all exposed openings).




19

5. Disconnect and remove the rocker cover ventilation tube.
6. Remove the fan belt, 1.



20


7. Remove the turbocharger oil pressure and return lines, turbocharger hardware, and turbocharger assembly. Ensure all openings are capped to prevent dirt ingress.



21

8. Remove the thermostat housing, 1, and water pump housing, 2.


NOTE: *Remove the water pump connector from the engine cylinder head.*



22


NOTE: *70 Series art shown in Figure 23.*

9. Remove the fuel filter assembly and fuel shutoff solenoid, 1.



23


10. Loosen and remove the inlet and exhaust manifold bolts, and remove manifolds, 1, and 2, and gaskets, 3.



24


NOTE: *Any tractor with the crankcase ventilation kit, or any tractor with the crankcase ventilation kit installed, must have the filter removed from the valve cover and never to be used.*

11. Remove the crankcase ventilation kit by removing the oil return tube, 1, removing the clamp and hose, 2, and removing the 2 bolts holding the oil separator housing, 3.



25

12. Remove the rocker cover and gasket.




26

13. Loosen the rocker shaft retaining bolts (which also serve as head bolts) evenly and alternately, and remove the rocker shaft assembly.

NOTE: *Leave bolts in the rocker shaft supports during removal, as they retain the support on the shaft.*


Remove pushrods in turn, and place in a numbered rack to maintain the same position for reassembly.




27

14. Remove the remaining cylinder head bolts, working inwards from the end of the cylinder head, alternately to the center of the cylinder head.

Remove the cylinder head.



28




29

1. Keepers
2. Spring retainer
3. Seal
4. Spring
5. Inlet valve
6. Exhaust valve
7. Spring
8. Seal
9. Spring retainer
10. Spring rotator
11. Keepers

Disassembly

1. Using a valve spring compressor, 1, remove the valve keepers, 2, springs, 3, seals and rotators, and place in a numbered rack.
2. Clean the cylinder head, and remove carbon deposits from around the valve heads.



30

Inspection and repair, cylinder head

1. Cylinder head core plugs if discolored (rusty) or leaking require changing. Before fitting new plugs, remove all old sealer from the cylinder head. Apply sealant G, see “Specifications,” to the new plug mating faces, and drive the new plugs into location.

   Core plugs required:
   6 off, in the top, and 1 off, in the rear of the cylinder head.
   5 off, in the intake face.

   Scrape all gasket surfaces, clean and wash cylinder head in a suitable solvent, also cleaning valve guide bores.

NOTE: *Be sure all fuel injector washers have been removed prior to cleaning.*

2. Inspect cylinder head for nicks and burrs on mating face. Remove them using a suitable abrasive, and ensure faces are clean after repair.


3. Using a straightedge, 1, and feeler gauges, 2, check that flatness of the cylinder head in all directions does not exceed:

   0.03 mm (0.001″) in any 25.4 mm (1″), or 0.127 mm (0.005″), overall limit.


   If the cylinder head has been resurfaced, determine if all head bolt faces will seat by placing the cylinder head, less gasket, on the cylinder block, and installing bolts finger tight.

   Ensure rocker shaft supports are fitted with long bolts. Using a feeler gauge, check clearance between the underside of bolt heads and cylinder head or rocker shaft support.

   If a 0.25 mm (0.010″) or more feeler gauge can be inserted under the bolt head, the bolt has bottomed; therefore, the cylinder block thread must be increased using a 9/16-13 UNC-2A thread tap. Identify the bolt heads, and be sure they are reinstalled in the bolt holes they were checked in.



31



32

Valve Inserts

NOTE: *Refacing the valve seat should always be coordinated with refacing the valve to ensure a compression tight fit.*

1. Examine the valve seat inserts and reface if pitted, renew if loose, or damaged.
2. To install a new valve insert, the cylinder head must be counter bored, as described in the following chart. The new insert must be chilled in dry ice prior to installation.

   Valve Seat Specifications.


   1, Valve seat angle:
   Intake = 30.0 - 30.30°
   Exhaust = 45.0 - 45.30°

   2, Valve seat width:
   Intake = 1.9 - 2.4 mm (0.078 - 0.098″)
   Exhaust = 1.8 - 2.3 mm (0.072 - 0.092″)

   3, Valve Head Face to Cylinder Head Face Depth:
   Intake = 0.86 - 1.32 mm (0.034 - 0.052″)
   Exhaust = 1.2 - 1.6 mm (0.047 - 0.065″)

NOTE: *Valve inserts of 0.25 mm (0.010″) and 0.5 mm (0.020″) oversize on diameter are sometimes installed during manufacture. Cylinder heads with oversize inserts are stamped so10/os, so20/os, on the exhaust manifold side in line with the valve seat concerned.*


3. Check the width of the valve seat inserts, and as required, reface by grinding to dimensions.



33


Insert Oversize	Counterbore Diameter in Cylinder Head	
	Exhaust Valve Insert	Intake Valve Seat Insert
0.254 mm (0.010″)	44.17 - 44.20 mm (1.739 - 1.740″)	50.01 - 50.04 mm (1.969 - 1.970″)
0.508 mm (0.020″)	44.42 - 44.45 mm (1.749 - 1.750″)	50.27 - 50.29 mm (1.979 - 1.980″)
0.762 mm (0.030″)	44.68 - 44.70 mm (1.759 - 1.760″)	50.52 - 50.55 mm (1.989 - 1.990″)

4. Measure the concentricity of valve seats, 2, using a dial indicator, 1, and measure concentricity of seat to the valve guide bore. Total Indicator Reading should not exceed 0.051 mm (0.002″).
5. Use a seat cutter to correct any seat eccentricity or clean up any pits and grooves. Be sure after any rework that seat width is within specified limits.



34


6. Rotate a new or refaced valve in the seat using engineering blue; ensure all the blue is transferred to the valve head protrusion. If any blue remains below or around the seat, raise or lower the seat accordingly in the following manner:
   1. Lower the valve seats by removing material from the top of the seat, 1, using a 30° grinding wheel for exhaust valves and a 15° grinding wheel for intake valves.
   2. Raise the valve seats by removing material from the bottom of the seat, 2, using a 60° grinding wheel for exhaust valves, and a 45° grinding wheel for intake valves.



35

Valve Identification

1) Valve land edge
2) Valve head
3) Valve face angle
4) Valve face
5) Valve stem
6) Valve tip/foot




36

Valve Guides

1. Using a telescopic gauge, 1, and micrometer, 2, measure the valve guide bore clearance and ensure it does not exceed:

   0.023 - 0.069 mm (0.0009 - 0.0027″),
   on the intake valve stem,
   0.048 - 0.094 mm (0.0019 - 0.0037″),
   on the exhaust valve stem.

NOTE: *Production cylinder heads may have one or more machined, oversize valve guide bores, or valves installed, 0.38 mm (0.015″). Such cylinder heads have 15 or VO15OS stamped on the cylinder head exhaust manifold side, adjacent to the valve concerned.*



37

2. Using a suitable reamer, ream out the valve stem guide with three reamer and pilot combinations as follows:

   0.076 mm (0.003″) oversize reamer, and standard diameter pilot.

   0.38 mm (0.015″) oversize reamer, and 0.076 mm (0.003″) oversize pilot.

   0.76 mm (0.030″) oversize reamer, and 0.38 mm (0.015″) oversize pilot.

NOTE: *When going from a standard valve stem to an oversize, always use reamers in sequence.*

Valve Springs

1. Checked on a flat surface, squareness should not exceed 1.52 mm (0.060″) between the square and the spring at the top edge.

   Check the length of valve springs on both free length and loaded length.


   Free length = 60.7 mm (2.39″)

   Installed length = 47 - 49.6 mm (1.86 - 1.95″)

   Loaded length = 48.26 mm (1.9″) using a weight of 28.31 kg (61.96 lbs)

   Loaded length = 35.69 mm (1.4″) using a weight of 61 - 69 kg (135 - 153 lbs)


   Be sure the valve spring retainer locks are in good condition, and replace if worn or damaged.



38


Valve Stem Seals Rework

1. Remove and disassemble the cylinder head.
2. Clean the cylinder head, and remove any carbon deposits from the valves.
3. Lubricate the valve guide bores with penetrating oil.




39

4. Adjust the valve stem cutting tool #CNH297669 to allow 113.5 mm (4.46″) of guide to protrude from the inner cutting edge to the tip of the guide.




40

5. Place the cylinder head on to a clean, flat piece of steel approximately the size of the cylinder head. Position the cylinder head squarely onto the bed of a pillar drill and adjust to allow the valve stem cutting guide to enter the valve guide bore. Securely clamp the cylinder head to the pillar drill bed.



41

6. Select a drill speed of 180 - 200 RPM.
7. Start the drill and slowly lower the cutting tool into the valve guide bore.
8. Continue cutting until the tool “bottoms out” on the steel plate below the cylinder head. The cutting tool will only cut the required amount to allow fitment of the valve stem seal.
9. Wash the cylinder head to remove all debris.




42

CYLINDER HEAD REASSEMBLY

1. Insert the valves into the guide bores from which they were removed, and lap with a suitable paste, ensure all traces of paste are removed after lapping. Remove any sharp edges from the end of the valve stems and the collet retaining areas. Lubricate components with clean engine oil on reassembly.
2. Put protective sheath over the valve stem. Push the new seal down over the valve stem and into position.
3. Use a spring compressor to reassemble the valves, valve springs, retainers, rotators and keepers.

Rocker Shaft Reassembly

1. Check the rocker shaft for signs of wear or damage on internal and external diameters respectively. If not to specification, replace with new. If reused, before reassembly, clean thoroughly in solvent making sure all oil passages are clear.
2. Position the shaft identification groove forwards and upwards. This ensures oil grooves and holes face downwards.
3. Assemble rocker shaft support with long head bolts, ensuring springs and spacers are reassembled.




43

Rocker Shaft Installation

1. Inspect rocker arm adjusting screws, 1, and pushrod ends of the rocker arm, 1, including the ball end of the screws for nicks, damage, or excessive wear.
2. Also inspect the inside diameter of the rocker arm for damage or wear. If any of these characteristics are not to specification, replace with new parts.
3. Check the ends of the pushrods, 3, for damage or wear. If not to specification, or pushrods were found not to be straight during dismantling, install new rods.
4. Coat all components with clean engine oil prior to assembly, and insert each pushrod, 3, into its original position, ensuring each ball end is seated in its cam follower, 2.

NOTE: *Do not attempt to straighten bent pushrods, replace with new ones.*




44

Installation

Installation of the cylinder head assembly and components is the reverse of the removal procedure, observing the following:

NOTE: *A new design head gasket has been introduced in production and is available through service parts. The laminated steel gasket can easily be identified by the small hollow rivets as shown. This gasket combined with new head bolts and new torque angle tightening process, explained in this bulletin, will extend the long-term durability of this component seal. Effective from engine serial #846528.*



45

The new laminated head gasket REPLACES the previous level and must be used in conjunction with the revised cylinder head bolts and the torque angle tightening process. The new bolts can be identified by the longer threaded section, although their overall length remains unchanged.

NOTE: *When fitting the new gasket on 7.5 liter engines, prior to engine serial #846528, the new cylinder head bolts must be used.*

IMPORTANT: *Do not attempt to apply the torque angle tightening procedure to previous level cylinder head bolts, as this may result in damage to the threads of the cylinder block.*

PARTS

Prev. #	Qty.	Description	Qty.	Current #	Comments
82850515	1	Gasket, head	1	87801753	Turbo-charged engine
83982127	1	Gasket, head	1	87801752	Non turbo-charged engines
87801209	19	Bolt, short	19	87802206	All
87801208	7	Bolt, long	7	87802207	All


NOTE: *87801209 was replaced by 87801691 and then by 87802206.*

87801208 was replaced by 87801690 and then by 87802207.

1. Install the new head gasket and lower the cylinder head into place, while ensuring the gasket remains in position.


NOTE: *Lubricate bolts prior to assembly.*

2. Torque the cylinder head bolts according to steps 3 to 6 below in the numbered sequence shown.




46

3. Tighten all bolts in sequence to a torque of 55 N·m (40 ft lbs).




47

4. Tighten all bolts in sequence to a new torque of 95 N·m (70 ft lbs).




48

5. Using a torque angle indicator, special tool OEM #7415 or equivalent, tighten ALL bolts in sequence by 90° IN A SINGLE STROKE.



49

6. Further tighten the long bolts which secure the rocker shaft, by a further 45° IN A SINGLE STROKE, in the bolt number sequence 1, 2, 3, 4, 5, 6, 7, 8.




50

ADDITIONAL INFORMATION

IMPORTANT: *Head bolts #87802206 and #87802207 are fully interchangeable with the previous 9/16″ design 3-cylinder, 4-cylinder, and pre-genesis 6-cylinder engines. Continue to torque the new headbolts to the old method in these engines with older conventional style head gaskets.*

7. Install the intake gasket and intake manifold. The intake manifold bolts are to be refitted and torqued to 38 N·m (28 ft lbs).



51

8. Adjust valve lash setting with each piston in turn at Top Dead Center and rockers free to move.

   Intake Valve Lash:
   0.36 - 0.46 mm (0.014 - 0.018″)

   Exhaust Valve Lash:
   0.43 - 0.53 mm (0.017 - 0.021″)

NOTE: *Valve lash is to be set only when the engine is cold.*


9. Install the injectors with new seat washers, cork seals, and torque to 23 N·m (17 ft lbs).
10. Install the injector and leak-off lines with new washers, and torque the leak-off banjo bolts to 10 N·m (8 ft lbs).

NOTE: *Hold the leak-off plastic tubing when tightening to prevent the pipes from pivoting during torque up.*

11. Install the exhaust manifold gasket and exhaust manifold.

NOTE: *Ensure exhaust manifold gaskets are fitted correctly to suit profile of exhaust ports.*

NOTE: *The exhaust manifold bolts are to be refitted and torqued to 38 N·m (28 ft lbs).*




52

CRANKCASE FRONT CASSETTE SEAL

To improve the durability of the front crankshaft seal, a cassette type seal has been introduced.

Effective at engine serial #901908, the new cassette seal was incorporated into production.

The new cassette seal is fully interchangeable with the prior level seals.




53

PARTS AFFECTED

Previous Part #	Qty	Description	Current
87800695	1	Front Crankshaft Seal	87802236

ADDITIONAL INFORMATION


The cassette seal can ONLY be fitted with the aid of the new special tool NH01417, 1, following the revised installation instructions. This new tool will be shipped automatically from OTC to Service Excellence Dealers. Non-Service Excellence Dealers who want to order this new tool may call OTC at 1-800-533-0492 to place an order.



54


REMOVAL OF OLD STYLE SEAL AND INSTALLATION OF THE NEW CASSETTE SEAL

1. Remove the crankshaft pulley using the Tool FNH09539 or suitable equivalent.



55


2. Remove the drive key, 1.



56


3. Withdraw the wear sleeve, 1, seal, 2, and O ring, 3.

NOTE: *When removing oil seal, protect the flange of the crankshaft with a cloth. Use a long screwdriver to pry out the seal.*



57


4. Clean all the parts and install a new O ring, 1.



58


5. Carefully remove the dust shield from the cassette seal.

NOTE: *It is important that the shield is removed.*




59

Cassette Seal, 1, separated from dust shield, 2.




60

6. Using fingers push the inner section of cassette seal forward.




61

7. Position the cassette seal, 1, on the installation Tool NH 01417, 2.



62


8. Locate tool onto end of crankshaft.



63


9. Tighten bolt to press seal into end cover.

IMPORTANT: *Only tighten the bolt sufficiently to ensure face of tool touches face of end cover.*



64


10. Re-install shield, 1, onto the seal.



65


11. Install the wear sleeve. Gently push the sleeve, 1, over the crankshaft and into the seal.

NOTE: *Do not coat the wear sleeve or seal with oil.*




66

12. Install the drive key, 1.



67

13. Install the front crankshaft pulley using the T-bar Tool FNH09506, 1, or suitable equivalent.
14. Refill the engine with oil as specified.




68

FRONT CASSETTE SEAL REMOVAL


NOTE: *Removal can be with the engine in the frame with the seal remover tool #380000212, 1.*

1. Raise the hood of the tractor.




69

2. Remove the two bolts,1, holding the fan guard on the right side of the engine. Remove the fan guard. Repeat this step for the left side fan guard.




70

3. Remove the injector pump return spring,1, on the right side of the engine. Remove the two bolts, 2, holding the lower front side shield on the right side of the tractor. Remove the side shield.




71

4. Remove the bolt, 1. Remove the two bolts, 2, holding the lower front side shield on the left side of the tractor. Remove the side shield.




72

5. Remove the fan, 1.




73

6. Remove the fan belt, 1.




74

7. Remove the fan shroud.




75

8. Remove the bracket, 1, holding the hydraulic oil cooler hoses in front of the radiator.



76


9. Remove the smaller bracket, 1, holding the hydraulic oil cooler hoses behind the radiator. Push the hydraulic oil hoses towards the right frame rail.



77


10. Remove the crankshaft pulley bolt and washer. Thread the crankshaft pulley bolt back into the crankshaft without the washer.

11. Remove the crankshaft pulley using tool #FNH09506 or a suitable tool.




78

12. Remove the dust shield, 1, from the seal using a blade screwdriver working it around the edge.




79

13. Remove the drive key, 1.



80

14. Remove the wear sleeve, 1.




81

15. Install the foam ring #380000401, 1, onto the crankshaft and then install the seal remover tool #380000212, 2, by inserting the thin edge of the three legs into the outer seal housing. Turn the center screw to make the tool snug.

NOTE: *Be sure the legs of the tool are all the way out against the seal housing.*

16. Remove the cassette seal from the engine block by turning the center screw.
17. For installation of the cassette seal see Crankshaft Front Cassette Seal on page 48 beginning with step 4.



82


ENGINE FRONT COVER AND TIMING GEAR

Removal


1. Remove the fan belt and tensioner, and withdraw the bolt and washer from the crankshaft pulley.
2. Using puller 9539 or FHN09539 and shaft protector 9212 or FHN09212, remove the pulley, spacer, and O ring from the shaft.
3. Drain the engine oil, and remove the oil pan.
4. Withdraw the retaining bolts, and remove the front cover and gasket.

NOTE: *The crankshaft timing gear, 1, should not be removed. The gear is heat shrunk onto the crankshaft and aligned to the crankshaft no. 1 pin to 0.10 mm (0.004″).*

5. Before removing the timing gears, use a dial indicator or feeler gauge to measure the backlash between each set of gears.



83




84

6. Rotate the gears and check the backlash using a feeler gauge, 1, or dial indicator at four equal points on the gears. Renew if the backlash exceeds the following:

   Backlash to crankshaft gear:
   0.15 - 0.46 mm (0.006 - 0.018″)

   Backlash to camshaft gear:
   0.15 - 0.46 mm (0.006 - 0.018″)


   Backlash to fuel injection pump gear:
   0.10 - 0.53 mm (0.004 - 0.021″)



85

Camshaft Drive Gear

1. Pry the camshaft gear, 3, using a lever, 1, away from the thrust plate. Using a dial indicator, 4, or feeler gauge, check the clearance to 0.076 - 0.35 mm (0.002 - 0.007″); if outside of limits, fit a new camshaft thrust plate, 2.
2. Remove the camshaft idler gear retaining bolt, gear, and adaptor from the block, then remove the camshaft gear bolt and disassemble.




86

Inspection and Repair of Gears

1. Wash the gears using a suitable solvent, and examine gear teeth for wear, burrs, or scratches. Minor marks can be removed using a fine abrasive; thoroughly clean before reassembly.
2. Be sure the camshaft idler gear adaptor is free from obstruction and the bushing is not damaged. The camshaft key and keyway should be checked for damage and repaired as required.

Installation

1. Position piston no. 1 at Top Dead Center, install the spacer, key, and camshaft gear, 1, and tighten to 69 N·m (51 ft lbs).
2. Install the camshaft idler gear, 2, to the block, align timing marks and torque to 237 N·m (175 ft lbs).
3. The front oil seal should be replaced every time the front cover is removed. Drive out the old seal using a punch, taking care not to damage the front cover.
4. Apply a new seal using a suitable lubricant, and drive the seal into the rear of the front cover using tool #630-16, alternatively use tool #T87T-6019-A, and drive the seal into position from the front of the cover.
5. Position gasket on the front cover plate.




87

6. Install the front cover, ensuring alignment with dowel pins. Use the retaining bolt sequence and torque the bolts to:

   5/16″-18 UNC bolts tighten to 18 - 24 N·m (13 - 18 ft lbs).

   3/8″-16 UNC bolts tighten to 34 - 41 N·m (25 - 30 ft lbs).
7. Lubricate the crankshaft, fitting a new O ring first, slide the pulley spacer over the key. Place the pulley onto the crankshaft and push fully home, tightening the securing bolt to 284 N·m (210 ft lbs).
8. Apply sealer D or J (see “Specifications”) to the front and rear housing joints, fitting a new gasket to the oil pan, and torque the bolts to 38 N·m (28 ft lbs).
9. Replace the engine coolant and oil; fill to the correct levels using fluids specified in the “Specifications” section.



88

OIL PAN

Removal

1. Drain engine oil through the oil pan plug and remove the dipstick.
2. Remove the oil pan bolts, then lower to the ground.

Inspection and repair


Clean gasket material from the sump face, clean the sump in a suitable solvent, inspect the sump for cracks, damage, or damaged sump face.

Installation

Installation is the reverse of removal, but with the following requirements:

1. Be sure the block face is clean and free of gasket material. Install a new gasket on the front cover and oil pan. Be sure that sealer is applied to the front plate and rear oil seal return joints.
2. Position the oil pan, and install a bolt at each corner finger tight to hold in position. Install the remaining bolts and torque to 33 N·m (25 ft lbs).

CONNECTING RODS, BEARINGS, PISTONS AND RINGS



89


Removal

NOTE: *The connecting rods and pistons can be removed with the engine installed after removal of the cylinder head and oil pan sump.*

1. With the cylinder head removed, clean off any ridge from the top of the cylinder bores with a ridge remover to enable removal of the pistons. This is essential if old pistons are to be reused, as failure to do so could result in ring land damage.
2. With the piston at the bottom of the stroke, remove the end cap bolts, cap, and bearing liner. Using the handle end of a hammer, push the piston assembly out through the top of the block and remove the liner from the connecting rod.
3. Turn the crankshaft again, and repeat the process for the remaining pistons.


NOTE: *Bearing caps and liners must be kept with their respective connecting rods.*

4. Remove piston pin snap rings from each side of the piston and remove the pin. Using an expander, remove the piston rings.



90

5. Ensure each piston and rod assembly remains matched together for reassembly into the cylinder block.



91

Inspection and Repair

1. Clean the piston and connecting rod assembly in a suitable solvent, and inspect for damage to ring lands, skirts, or pin bosses.
2. Check the connecting rod components for damage, and place in an alignment fixture to check for distortion, and ensure that any distortion is within specification as follows.

   Maximum Twist 0.30 mm (0.012″)

   Maximum Bend 0.10 mm (0.004″)
3. Check the piston pin bushing for damage or wear in the following manner:

   Measure the outside diameter of the piston pin, and inside diameter of the connecting rod bushing, to the following:

   Piston Pin Outside Diameter

   Turbocharged:
   44.442 - 44.447 mm (1.7497 - 1.7499″)


   Connecting Rod Bushing Internal Diameter

   Turbocharged:
   44.460 - 44.467 mm (1.7504 - 1.7507″)

Connecting Rod Bushing Replacement


1. Use tool, 1, #FNH00035, and press out the old bushing, 2, using the removal fixture. Press fit a new bushing through the fixture using the installation detail and into the connecting rod, 3. After fitting a new bushing, be sure all sharp edges and burrs are removed.

NOTE: *Be sure the split, 4, in the small end bushing is at right angles to the centerline of the connecting rod. Connecting rods should only be changed as matched sets.*



92

2. Where special tooling is not available for the removal or fitment of the connecting rod bushing, a standard bushing can be fitted in the following manner.
3. Place the connecting rod securely in a bench press. From suitable bar stock, manufacture a press tool with the end face ground at an angle to suit the connecting rod bushing side face. Position the tool on the bushing, and gently drive the bushing from its position. Manufacture a guide to assist alignment of the bar stock during this operation.



93

Connecting Rod Bushing Installation


1. Washer
2. Collar
3. Installation Insert 1
4. Bushing
5. Installation Insert 2
6. Pins
7. Fixture
8. Connecting Rod Facing Up
9. Remover Insert 1
10. Remover Insert 2
11. Remover Insert 3
12. Connecting Rod Location
13. Washer
14. Location Plate

4. A new bushing can then be fitted in a similar manner, by using a suitable piece of bar stock, with an end face machined flat to suit the standard parallel bushing. Use a guide as described, and gently drive in the new bushing into the connecting rod.


5. After installation, grind the side faces of the new bushing to match the side faces of the connecting rod. Be sure all sharp edges are removed and loose chippings are cleaned from the connecting rod before reassembly into the engine.

6. Drill an oil hole through the new bushing with a 4.6 mm (0.187″) drill bit. Use the existing oil hole of the connecting rod as a guide.

7. Use an expanding reamer to obtain the correct bushing to piston pin clearance (refer to “Specifications.” Remove burrs and chippings before refitting.



94



95

CYLINDER BLOCK OVERHAUL

1. Cylinder block plugs and senders must be replaced if leaking or rusty. Clean the old sealant off the block and fit new plugs with sealer. The above diagram refers to the front and left-hand side of the cylinder block.

NOTE: *New part mating faces and threads should be coated in sealant, refer to "Specifications" in this chapter. Assemble in the following manner:*

Plug, 1, torque to 8 - 14 N·m (6 - 10 ft lbs). Use sealant, C.


Switch, 2, torque to 24 - 34 N·m (18 - 25 ft lbs). Use sealant, E.

Plug, 3, torque to 68 - 95 N·m (50 - 70 ft lbs). Use sealant, F.

Plug, 4, drive in to block.

Plug, 5, torque to 24 - 34 N·m (18 - 25 ft lbs). Use sealant, E.

Plug, 6, torque to 27 - 47 N·m (20 - 35 ft lbs). Use sealant, E.



96

2. The above diagram refers to the rear and right-hand side of the block.

Plug, 1, torque to 24 - 34 N·m (18 - 25 ft lbs). Use sealant E.

Plug, 2, torque to 8 - 14 N·m (6 - 10 ft lbs). Use sealant, E.

Oil jets, 3, replace with new if damaged, apply engine oil only on reassembly – Do not use sealant.

Plug, 4, torque to 54 - 81 N·m (40 - 60 ft lbs).

Plug, 5, drive into block. Use sealant, G.

Plug, 6, drive into block. Use sealant, G.

Cylinder Bore

1. Check the cylinder bore for scuffing or rings around the ring travel area. Irregularities can be felt by running a finger over the surface. To check out-of-roundness, wear, or taper, use a telescopic gauge.

   Measure lengthwise:
   A to B and C to D and compare dimensions, variances between the readings will indicate "taper."

   Measure crosswise:
   C to D and compare dimensions lengthwise. A to B variances will indicate an out-of-round condition.

   Specifications:

   Taper of cylinder bore:
   repair limit - 0.025 mm (0.001″)
   wear limit - 0.127 mm (0.005″)

   Cylinder bore out of round:
   repair limit - 0.03 mm (0.0015″)
   wear limit - 0.127 mm (0.005″)

   Cylinder bore diameter:
   111.778 - 111.841 mm (4.4007- 4.4032″)

2. Where only minor imperfections exist and bores are to specification, hone the bores prior to installing new piston rings, provided piston to bore clearance does not exceed 0.165 mm (0.0065″).

3. If cylinder bores are outside the specification, they should be bored or honed to fit the next oversize piston. The finished bore size can be determined by measuring piston diameter at right angles to the piston pin and adding the appropriate piston to bore clearance.


4. Oversize pistons available:
   0.10 mm (0.004″)
   0.51 mm (0.020″)
   0.76 mm (0.030″)
   1.0 mm (0.040″)

5. Bores to take 0.10 mm (0.004″) oversize pistons need only be honed using a rigid hone with a grit size of 150 - 220. Clean thoroughly after boring and honing.

6. Sleeving of the cylinder bores becomes expedient when:

   - Oil consumption is high due to porosity.
   - Replacing sleeves, installed in service.
   - Cylinder bore is damaged beyond reboring limits.

NOTE: *When reconditioning engines equipped with sleeves, use only standard or 0.1016 mm (0.004″) oversize pistons.*



97

Sleeving - Boring and Honing

1. Measure the outside diameter, 1, of the sleeve in several places, and average the dimension. Counterbore the cylinder block (see step 2) using the average dimension to obtain a press fit between bore and sleeve. Interference of sleeve to the cylinder bore is to be 0.025 - 0.076 mm (0.001 - 0.003″).
2. Counterbore to a depth of 209 mm (8.26″), from the block face, surface finish of the bore is not to exceed (80 microns). Leave a step at the bottom of the bore a minimum of 4.572 - 5.080 mm (0.180 - 0.200″), allowing for runout of chamfers.
3. Bore through diameter to the diameter of 114.3 - 116.0 mm (4.454 - 4.456″).
4. Clean the cylinder bores and dry thoroughly.
5. Grease the sleeve with ESA-MIC75-B or similar, and press the sleeve home to the lip in the bore. The top of the sleeve should protrude through the top of the block: 0.127 - 1.0 mm (0.005 - 0.040″).
6. Bore the sleeve to 110.00 - 111.76 mm (4.3985 - 4.400″).
7. Skim the block face and top of sleeves to achieve the specified flatness of:


   0.08 mm (0.003″) in any 152 mm (6″)
   0.03 mm (0.001″) in any 25.4 mm (1″)

   A chamfer in the internal diameter at the top of the sleeve of 45° x 0.5 mm (0.020″) should be maintained to prevent piston damage on reassembly.
8. Break the sharp edge at the bottom of the sleeve prior to honing.
9. Hone the cylinder bore to:
   Grade A, 111.77 - 111.98 mm
   (4.4007 - 4.4015″)
   Grade B, 111.98 - 112.19 mm
   (4.4015 - 4.4023″)

NOTE: *Surface finish to be an average of 20 to 30 microns, crosshatched at 35 - 55°.*

Maximum Taper:
0.025 mm (0.001″) through to bottom of the bore.

Maximum Ovality:
0.038 mm (0.0015″)



98

Reassembly


NOTE: *Replaced pistons must be of the same type that were removed and have the same identification letters and numbers as embossed on the underside of the old piston.*

1. Upon reassembly with the piston at Top Dead Center, ensure the piston to block height is correct using a dial indicator. Deck height should be 0.00 - 0.30 mm (0.000 - 0.012″) above.
2. Check the piston to bore clearance in the following manner:
   a. Measure the cylinder bore diameter cross-wise, then measure piston diameter at right angles to the piston pin.
   b. Subtract piston diameter from the bore diameter and the resultant figure should be 0.152 - 0.178 mm (0.006 - 0.007″).


NOTE: *Pistons are available as standard and oversize; new pistons should always be fitted if the clearance exceeds specification.*

   c. If clearance is “greater,” try a similar new piston; if limit is still exceeded, measure remaining cylinder bores and pistons and establish greatest clearance.

      Based on the highest figure, rebore to take the next oversize piston.
   d. If the clearance is “less,” hone bore to obtain desired clearance.
3. Lubricate all of the components with engine oil, and assemble the connecting rod and piston with the letter or grade mark, 1, on the piston, aligned to the pip, 2, on the connecting rod. Install the piston pin and retainers.



99




100

4. Using a feeler gauge in the vertical position, check the piston ring gap width at the top, middle, and bottom of the bore:

   0.36 - 0.66 mm (0.014 - 0.026″), Top compression ring.


   0.36 - 0.66 mm (0.014 - 0.026″), 2nd compression ring.

   0.36 - 0.66 mm (0.014 - 0.026″), Oil control ring.



101

5. Ensure the correct expander, 1, is used to remove or install rings, 2.



102

6. Use gauge #FNH00180 to check Keystone ring lands for wear.


   Using a new piston ring, 1, check with a feeler gauge, 2, the gap between the ring and groove on pistons:

   0.102 - 0.152 mm (0.0040 - 0.0060″), 2nd compression ring - Models 8670 and 8770

   0.061 - 0.112 mm (0.0024 - 0.0044″), Oil control ring - All Models

7. Install the piston rings, but note the following.


NOTE: *Before installing new pistons and rings into a used cylinder bore, remove the high polish from the cylinder walls by honing, as previously described.*



103

8. Install top, 1, and second compression rings, 2, with the word “top” towards the top of the piston. Ensure the ring gaps are staggered a minimum of 120° from each other on the diameter, and with no gap on the thrust side of the piston.


NOTE: *The 170 and 190 horsepower engines use an iron insert for the top Keystone ring, 1. The 210 and 240 horsepower engines use an iron insert on the top two Keystone rings, 2.*




104

PISTON ASSEMBLY INSTALLATION

1. Select the correct bearing liners as in the following crankshaft section, and install in the rod and cap. Be sure the liner tang locates in the slots of the rod and cap.
2. Turn the crankshaft to position no. 1 crankpin at the bottom of the stroke, and lubricate all parts with new engine oil. Using a ring compressor, 2, and a soft drive, 1, slide pistons into bores, ensuring grade letter on pistons is towards the front of the engine.
3. Be sure the connecting rod bearing liner seats on the crankpin with the bearing cap fitted to the connecting rod as a matched assembly. Fit new bolts lubricated with oil, and tighten to a torque value of 149 N·m (110 ft lbs).
4. Using feeler gauges, check the side clearance of each connecting rod to crankshaft, 0.13 - 0.33 mm (0.005 - 0.013″) and continue for remaining assemblies.
5. Refit the oil pump tube/screen and oil pan as previously described, refill engine oil and coolant, run the engine and check for leaks.



105



106

MAIN BEARINGS, FLYWHEEL AND CRANKSHAFT


NOTE: *Replaceable bearing liners are installed in production to ensure correct crankshaft journal to bearing clearance is maintained in service. The main bearings can be overhauled with the engine in the tractor. The crankshaft can only be serviced after removal from the tractor.*

Main Bearing Removal

1. Remove the oil pan to gain access to the crankshaft. Remove the main bearing cap from the journal to be repaired and install only one set at a time. Leave the remainder securely in place.

NOTE: *A liner removal tool can be fabricated from a 25 mm (1″) x 1/8″ split pin; flatten and bend the head to conform to the angle of the oil passage in the crankshaft.*

2. Install the bearing liner removal tool in the crankshaft journal oil passage. Turn the crankshaft counterclockwise until the tool forces the bearing out of the cylinder block.



107

Inspection and Repair


Thoroughly clean bearing liners, journals, and caps; inspect for wear, scores, or damage; replace as required**.**

Installation

1. Coat all parts in new engine with oil, prior to assembly. Position the bearing cap with locking tang towards the camshaft side of the engine, and fit the bolts; tighten evenly to 190 - 203 N·m (140 - 150 ft lbs).
2. If a new thrust bearing liner is installed, bearing must be aligned as described in the crankshaft portion of this chapter.

Flywheel Removal

1. To gain access to the flywheel, separate the engine to transmission. Refer to Section 21, Chapter 2, “Separating the Engine From the Transmission.”
2. Prior to removal, using a dial indicator, 1, rotate the flywheel, 2, and measure to specification 0.127 mm (0.005″) Total Indicator Reading. If not to specification, check crankshaft to flywheel seating.



108

Inspection and Repair

1. Inspect the flywheel ring gear; if damaged, repair in the following manner:
   a. Cut old ring gear free from the flywheel.
   b. Clean the mating surfaces of the new ring gear and flywheel.
2. Use temperature indicating crayons to mark the side face of the ring gear in six equal places, mark with a 204° C (400° F) crayon at a point 13 mm (0.5″) below the root of the teeth, and mark with a 212° C (450° F) crayon at a point just below root of the teeth.
3. Use an oxyacetylene torch with a tip size of no. 2 maximum, and direct the flame against the internal face of the gear.
4. Quickly place the hot gear on the flywheel with flat face against the shoulder on the flywheel. The gear to flywheel runout should be checked using a dial indicator, and should not exceed a Total Indicator Reading of 0.63 mm (0.025″).

Installation


Clean the crankshaft rear flange and mating surface of the flywheel, and install the flywheel. Torque the bolts to 244 N·m (180 ft lbs).

REAR COVER PLATE

NOTE: *To improve sealing at the rear of the engine, an improved crankshaft rear seal carrier and seal carrier gasket has been introduced.*

Effective from engine serial number: 783958, date code 8D08, a revised seal carrier was introduced into production with a slotted hole, 2, to enable the alignment of the seal carrier with the oil pan.


Effective from serial #806633, date code 8J10, an improved gasket was introduced into production.



109

Improved sealing and gasket positioning is achieved using a rubber-coated metal gasket, 1. Further improvement to the sealing at the base of the seal carrier has been achieved by the encapsulated sealer on the open ends of the gasket, 2.

The seal carrier and gasket are fully interchangeable with the previous level and should be changed as a set.




110

Part #	Qty.	Description	Current Part #
81876599	1	Seal Carrier Crankshaft Rear Oil Seal (stamped steel oil pan)	87801619
81865591	1	Gasket Crankshaft Rear Oil Seal Retainer	87801610

Removal

1. To gain access to the engine oil pump, camshaft gear, or end of crankshaft, remove the oil pan as previously described, and the rear cover.

   Split the tractor - see Section 21, Chapter 2, “Separating the Engine From the Transmission.”
2. With the rear of the engine exposed, loosen and remove the 12 attaching bolts, 1, and gently pry off the cover plate.
3. Remove the crankshaft oil seal, and check for damage, or distortion around the sealing faces.




111

Installation
Turn the engine upside down.

1. Ensure the rear block face is clean and free of the old sealer.
2. Install the new gasket to the seal carrier and align with the bolt holes. Use grease to retain the gasket.

NOTE: *Do not apply sealer to this gasket.*


3. Install the seal carrier and loosely install all the bolts.
4. Apply a liberal coating of clean engine oil on a new oil seal, 1; position the rear seal over the end of the crankshaft. Locate tool, 2, #FNH 01301 on the end of the crankshaft using the three attaching bolts. Tighten evenly and squarely until the seal is fully seated.



112

As an alternative, the rear crankshaft oil seal can be installed using the following installation tool:


- Apply a liberal coating of clean engine oil to the rear seal, retainer seal, and journal. Mount a new seal on the crankshaft, then bolt tool #FT6212, 2, to the crankshaft end, and install the new seal squarely.
- Secure the center stock of the tool to the crankshaft flange with two screws. Assemble the cylinder end plate to the center stock, and secure with nut and washer. Tighten the nut until the outer diameter of the tool abuts the retainer. The tool must not be over tightened, as stress and distortion could be imposed on the retainer.
- Remove the tool after assembly and check the crankshaft seal runout.




113

NOTE: *The first seal replacement should be pushed into the retainer with the plain end of the tool, and subsequent seals with the stepped end of the tool, which will reposition seal 1.52 mm (0.060″) further in.*

5. Place a straight edge along the rear of the engine block above the seal carrier, 1.
6. Use the bolt in the slotted hole, 2, to orient the seal carrier to ensure correct alignment with the base of the block, 3. The seal carrier must be parallel to the base of the block. Hand tighten this bolt.
7. Hand tighten the remaining bolts, ensuring the seal carrier is still correctly aligned, parallel to the base of the block.
8. Fully tighten the twelve bolts, in sequence 16 - 23 N·m (12 - 17 ft lbs).




114



115

9. With the new crankshaft seal installed, place a dial indicator, 1, on the end of the crankshaft, and ensure seal runout is within 0.51 mm (0.020″) Total Indicator Reading.




116

OIL PUMP

Removal

NOTE: *The oil pump can only be removed with the engine split from the transmission, and the flywheel, back plate, engine oil pan, and oil pump tube removed.*


1. Prior to pump removal, be sure pump gear to camshaft gear backlash does not exceed 0.40 - 0.56 mm (0.016 - 0.022″).
2. Loosen and remove the camshaft gear to expose the oil pump, detach the three pump mounting bolts, and withdraw the pump from the block.



117

Disassembly


Loosen and remove the pump face plate to body bolts. Disassemble the pump and discard the O rings, 1 and 2.



118

Inspection and Repair


1. Wash all parts in a suitable solvent, and inspect the inside of the pump plate and body for excessive wear or damage. If visually okay, check in the following manner.
2. Invert pump plate/rotor assembly, 1, and place outer rotor over inner rotor, 2. Placing a ruler, 3, across the top of both, slide a feeler gauge, 4, between the ruler and inner rotor to 0.025 - 0.089 mm (0.001 - 0.0035″).



119

3. Place outer rotor, 1, in pump body, 2, and check clearance by inserting a feeler gauge, 3, between the rotor and body. Check to a maximum of 0.55 mm (0.022″). If exceeded, a new pump is required.

NOTE: *If not to specification, replace the oil pump as reduced pump pressure through wear could result in reduced engine life.*




120

Installation

1. Clean and coat parts in new engine oil. Place the outer rotor in the pump body, and ensure free rotation. Insert the inner rotor and pump plate assembly into the body, and be sure the shaft is fully seated into the bushing.
2. Assemble the front plate to the body using three or four bolts, and torque to 23.0 - 28.4 N·m (17 - 21 ft lbs).

NOTE: *After tightening, ensure the drive gear rotates freely by hand at least 5 revolutions; if not, disassemble and repeat the exercise.*

3. Fit a new O ring, 1, to the output tube. Lubricate and insert the pump, 3, into the block tightening the bolts, 2, to 23.0 - 28.4 N·m (17 - 21 ft lbs).




121

4. Fit a new O ring into the suction port. Lubricate and insert tube/screen assembly, 2, into pump, 1, through the bottom of the engine. Fit a new gasket if originally installed and torque the attaching bolts, 3, to 2 - 34 N·m (20 - 25 ft lbs).

NOTE: *Plug, 5, is factory installed to facilitate machining and should not be removed during the life of the engine.*

5. Refit gears as previously described, along with the rear plate and flywheel.



122


OIL FILTER SUPPORT ASSEMBLY

Removal

1. Unscrew and discard the old filter, loosen the attaching bolts and oil connections, and remove the filter support assembly from the block. Discarding the three O rings.
2. Clean the filter support, 1, in a suitable solvent.
3. Remove pressure relief valve plug, 4, removing valve, 2, and spring, 3. To ensure correct operation of the pressure relief valve, check the spring length:

   Free length = 55.9 mm (2.20″).


   Compressed length = 44.2 mm (1.74″) using a weight of 13.6 kg (30 lbs).
4. Clean the assembly in a suitable solvent and ensure all ports are free of dirt.
5. Check the parts for damage or wear; replace as necessary. Failure to do so could result in premature wear to the engine, due to oil bypassing the filter and returning back to the system.



123

Installation

Lubricate the pressure relief valve and spring, and insert into the housing, ensuring free movement. Fit new O rings and torque hardware to 42 N·m (31 ft lbs). Fit tubes to connectors and torque to 41 N·m (30 ft lbs).



124

CRANKSHAFT

Removal

1. When removing the engine from the tractor, refer to Section 21, Chapter 2, "Separating the Engine From the Transmission" and place the engine on an engine stand.
2. Remove the flywheel, rear cover plate, crankshaft pulley and engine front cover, as previously described.

NOTE: *If the crankshaft is removed with the cylinder head in position, be sure all timing marks are realigned prior to reassembly. This action will prevent possible interference between valves and pistons during reassembly.*

3. Remove the oil pan and oil pump tube as previously described.
4. Remove the connecting rod caps, main bearing caps and liners, and identify to facilitate reassembly.
5. Carefully remove the crankshaft from the cylinder block.

Inspection and Repair

NOTE: *Current production engines may have a crankshaft with main or crankpin journals ground 0.25 mm (0.010″) undersize. These are identified with the letters 010 MUS and/or 010 PUS respectively, letters being stamped on one of the crankshaft counterbalance weights.*

1. If the crankshaft timing gear teeth are worn or damaged, replace as described.

2. Wash the crankshaft and drilled passages in a suitable solvent. Dress minor imperfections using an oil stone, but for severely marked journals, machine to the next undersize bearing size.
3. Measure the diameter of each journal in four places to determine out-of-round, taper, or wear:

   Measuring A compared with B indicates vertical taper.

   Measuring C compared with D indicates horizontal taper.

   Measuring A and B compared with C and D indicates journal out-of-round.

   Journal Ovality: compare A/C and B/D

   Maximum Ovality: 0.005 mm (0.002″)

   Journal Taper: compare A/B and C/D

   Maximum Ovality: 0.005 mm (0.002″)
4. If the journal exceeds specified limits, refer to “Specifications” and refinish the journal to the next undersize bearing.

   Bearing inserts are available in the following sizes:

   Standard dimensions (each journal coded red or blue)

   Main Bearing Journal Diameter:


   85.631 - 85.644 mm (3.3713 - 3.3718″) blue

   85.644 - 85.656 mm (3.3718 - 3.3723″) red

   Crankpin Diameters:

   69.840 - 69.850 mm (2.749 - 2.7500″) blue


   69.850 - 69.860 mm (2.750 - 2.7504″) red
5. Examine the rear oil seal journal for score marks, remove minor imperfections with fine emery cloth, and if severely damaged renew the crankshaft.



125

Crankshaft Reassembly

1. Check the crankshaft bearing clearance using a plasti-gauge as follows:
   a. Position a piece of correct size plasti-gauge across the full width of the bearing cap, approximately 6.35 mm (0.25″) off center.
   b. Install the main bearing cap and tighten bolts to 197 N·m (145 ft lbs).
   c. Remove the cap and use the scale to check the width of the flattened plasti-gauge.



126


d. The widest point of the gauge establishes the minimum clearance**.**

e. The narrowest point of the gauge establishes maximum clearance**.** The difference between the two readings is the taper.

NOTE: *Normally main bearing journals wear evenly and will not be out-of-round, but if a liner which is to specification is fitted to an out-of round journal, ensure that the liner suits the maximum diameter of the journal.*

2. If these combinations of liners do not produce specified clearance, refinish the crankshaft and fit undersize bearings.


3. Be sure to align bearing liners, 1, correctly to line up with oil galleries, 3, and integral oil jets, 2. Position the bearing liners and caps in the block, and coat with oil. If the crankshaft has been refinished, fit the correct undersize bearing liners.



127


4. Ensure the bearing surfaces are clean and bearing liner tangs align with slots in the block and cap.

5. Align the timing mark on the crankshaft gear with that of the camshaft idler gear, and install the crankshaft. Install a thrust bearing cap with flange-type bearing liner first, installing remaining bearing caps to their original location.



128


6. Tighten all bearing caps (except thrust bearing cap, leave finger tight) to a torque of 197 N·m (145 ft lbs).
7. Pry the crankshaft forward against the thrust surface of the bearing, hold the crankshaft forward and pry the bearing cap rearwards, taking care not to pry against the flange of the bearing liner. This will align the thrust surfaces of both halves of the bearing. Hold forward pressure on the crankshaft, and tighten the bearing cap bolts to a torque of 197 N·m (145 ft lbs).



129

8. Check crankshaft end play with a dial indicator gauge. Pry the crankshaft towards the front of the engine, and set the dial indicator to zero. Pry the crankshaft towards the rear of the engine, and note the reading on the dial. If end play exceeds 0.10 - 0.36 mm (0.004 - 0.014″), fit a new thrust bearing liner.
9. If the end play is less than specification, check the thrust bearing for burrs, scratches, or dirt and realign the thrust bearing as in operation 7.
10. Install rear crankshaft oil seal as previously described in back plate removal.

NOTE: *Do not reinstall seal into retainer. To ensure seal concentricity, it must be assembled with the rear plate and installation tool when fitted to the crankshaft.*




130

CAMSHAFT

Removal

NOTE: *The camshaft bearings and tappets can only be serviced with the engine removed from the tractor, see Section 21, Chapter 2, "Separating the Engine From the Transmission."*

1. Remove the engine front cover and cylinder head.
2. Check the camshaft end play (see "Timing Gears") and remove the gear. Install a new thrust plate prior to reassembly.
3. After removal of the flywheel and rear cover, remove the camshaft oil pump drive gear.
4. Invert the engine on the stand if camshaft bearings are to be replaced, and remove the oil pan.
5. Carefully withdraw the camshaft from the engine.
6. Lift out the cam follower, 1, and place in a numbered rack for reassembly.



131

Inspection and Repair

1. Inspect the camshaft journals and lobes for damage, pitting, or heat discoloration. If any of these conditions exist, install a new camshaft.
2. Inspect the oil pump drive gear on the camshaft and the mating gear on the oil pump for broken or worn teeth; if any wear or damage is apparent, fit new gears.
3. Check each tappet for wear or damage and check diameters; if not to specification, repair:

   25.15 - 25.17 mm (0.9900 - 0.9910″).
4. Measure the diameter and out-of-round condition of the bearing journals; if exceeded, fit a new camshaft:

   60.693 - 60.719 mm (2.389 - 2.390″).


Camshaft Bearings

1. Inspect the camshaft bearings for wear or damage. Measure the clearance between the internal diameter of the bearing and outside diameter of the respective journal:

   0.076 - 0.01220 mm (0.003 - 0.005″).

2. If the specification is exceeded, install new bearings using Remover/Replacer tool #FT 6203 or 1255 and handle tool #N 6261-A or #1442.
3. To remove, position the tool against the bearing to be removed and attach the handle, driving the bearing from the bore.
4. To install, align the oil holes of the new bearing with the holes in the block, and drive the bearing into the bore using tools as described.


NOTE: *A positive alignment check can only be made with the crankshaft removed when an 0.018″ (4.6 mm) rod can be passed down the oil passage from the crankshaft main bearing. The liner is correctly positioned when the end of the rod passes through the oil hole in the liner.*



132

Installation


1. Apply petroleum jelly to each tappet foot, and coat the tappet body with oil. Install tappets in the bores from which they were removed.
2. Oil the camshaft journals, and apply petroleum jelly to the cam lobes. Install the camshaft into the engine.
3. Install new spacer and keyway on the end of the camshaft.
4. Apply sealant ESE-M2G-114A to the sealing flange of the front cover plate on reassembly.
5. Install the camshaft gear, and align the camshaft gear timing mark, then recheck end play.



133

ENGINE TIMING GEARS

No. 1 piston is at the top dead center when the crankshaft gear keyway is positioned as shown.



134

1 Camshaft gear
2 Crankshaft gear
3 Camshaft idler gear
4 Injection pump gear

The timing marks should be aligned in this position.

NOTE: *There are no timing marks on the injection pump gear. The injection pump gear must only be installed once the injection pump is timed to the engine. Refer to timing the injection pump to the engine.*

ENGINE COMPRESSION TEST

TEST PROCEDURE

1. Be sure battery performance meets specifications.
2. Warm up the engine by operating for a minimum of half an hour at 1200 rev/min.
3. Stop the engine and remove the injector and seat washer from No.1 cylinder.
4. Clean the injector bore and crank the engine to blow out any loose carbon particles.
5. Install a proprietary engine compression test gauge into the injector bore, using the injector mounting bolts and a new seat washer.
6. Connect the gauge and hose to the adaptor, Tool Number FNH 00882.
7. Crank the engine at 200 rev/min with the engine stop cable pulled out where fitted, or the electric fuel shut off wire disconnected to prevent engine start up.
8. Observe the gauge reading and repeat the compression test, steps 5 - 7, for each cylinder.

   Typical cranking compression at 200 rev/min should be 25.5 bar (375 PSI).

TEST READING

1. All cylinder compressions should be uniformly within 1.7 bar (25 PSI) of each other.
2. A reading of more than the 1.7 bar (25 PSI) below the other cylinders indicates leakage at the cylinder head gasket, piston rings or valves.
3. A reading or more than 1.7 bar (25 PSI) above the other cylinders indicates excessive carbon deposits on the piston and cylinder head.
4. A low even compression in two adjacent cylinders indicates a cylinder head gasket leak. Check this item before considering the rings or valves.

TEST CONCLUSION

To determine whether the rings or the valves are at fault, squirt the equivalent of a table spoon of heavy oil into the combustion chamber. Crank the engine to distribute the oil and repeat the compression test.

The oil will temporarily seal any leakage past the rings. If approximately the same reading is obtained, the rings are satisfactory but the valves are leaking.

If compression has increased over the original reading, there is leakage past the rings.

During a compression test, if the pressure fails to climb steadily and remains the same during the first two successive strokes, but climbs higher on the succeeding strokes, or fails to climb during the entire test, suspect a sticking valve.

SECTION 10 – ENGINE

Chapter 2 – Cooling System

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	4
	Cooling System	4
	Troubleshooting	6
	Disassembly and Repair	7
	Radiator	7
	Thermostat	9
	Temperature Warning Sender	10
	Fan Blade	10
	Viscous Clutch Assembly	10
	Fan Belt Tensioner	11
	Idler Pulley	11
	Water Pump	12

SPECIFICATIONS

TIGHTENING TORQUES

Description	N·m	Ft Lbs
Thermostat housing	24	18
Temperature senders	20	15
Tensioner pulley bolt	54	40
Tensioner front cover	54	40
Idler pulleys	54	40
Pump connector to block	24	18
Water pump to block	65	48
Fan blade to support body	23	17
Fan blade to clutch support body	105	78

THERMOSTAT

Opening temperature	79° C - 83° C (174° F - 181° F)
Fully open	93° C - 96° C (199° F - 205° F)

RADIATOR CAP

Opening pressure	0.9 bar (13 PSI)

WATER PUMP

Type	Centrifugal	Poly V-belt drive

FAN BELT

Belt tension	Maintained by tensioner

COOLING CAPACITIES

Total	25 L (6.6 gal) - Models 8670 and 8770 26.5 L (7 gal) - Models 8870 and 8970

COOLANT FLOW

Coolant flow at rated engine speed	291.4 L/min (77 GPM)

COOLING FLUID

The 70 Series and 70A Series before serial number #D423202, antifreeze ESEM97B-18C/D or SSM-97B-9101A (green in color) was used. Mix with an equal amount of clean water and change every 2400 hours or 24 months (whichever occurs first). Change the coolant filter at the same time.

The 70A Series after serial number #D423202, the anti-freeze is purple in color. The anti-freeze meets or exceeds the ASTM 06210/6211 and TMC RP 329 standards. If can be mixed with the old anti-freeze but is not recommended because it would dilute the effects of the additives plus create a murky color.

Clean water only (only applicable to hot countries where antifreeze is not available).

Change coolant and coolant filter every 1200 hours or 24 months (whichever occurs first).

IMPORTANT: *The new filter contains a measured amount of chemical inhibitor in paste form. The amount of conditioner and the size of the filter element are matched to the cooling capacity of the tractor. It is important that this filter is changed every 1200 hours if total protection of the engine cooling system is to be maintained. The use of a non-approved filter may jeopardize this protection.*

IMPORTANT: *Install a new filter/conditioner in the event of a large coolant loss such as a failed coolant hose.*

IMPORTANT: *Do not replace the filter/conditioner more frequently than specified unless a large coolant loss occurs.*

IMPORTANT: *Anti-leak additives should not be used. The clogging properties of these additives could affect the performance of the filter and conditioner.*

IMPORTANT: *If it becomes necessary to replace the filter before the 1,200 hour change interval, or if less than one-half of the coolant is lost, a filter without a conditioner should be installed.*

NOTE: *In order to reduce deposits and corrosion, water used in the cooling system should not exceed the following limits:*


Total hardness	*300 parts per million*
Chlorides	*100 parts per million*
Sulfates	*100 parts per million*

DESCRIPTION OF OPERATION

COOLING SYSTEM

The function of the water pump mounted at the front of the engine is to maintain a continuous flow of water around the cooling system. This is essential to ensure correct engine temperature and performance during vehicle operation.


The water pump, 1, is driven by a poly V-belt, 2, from the crankshaft pulley when the engine is running. The fan belt tension is maintained by a spring-loaded belt tensioner, 3, bolted to the front cover.



1

The cooling system is of the recirculating bypass type with full-length water jackets for each cylinder. The coolant is drawn from the bottom of the radiator by the water pump which passes the coolant to the cylinder block. The coolant then flows through cored passages to cool the cylinder walls.


Passages in the cylinder head gasket allow coolant to flow from the cylinder block into the cylinder head. Cored passages also conduct the coolant to the fuel injector nozzle locations before entering the thermostat housing; dependent upon water temperature, water either reenters the water pump or is circulated through the radiator for cooling.



2


The thermostats are located in the top of the housing above the water pump body and control the flow of the water as required by temperature changes.

NOTE: *A faulty thermostat may cause the engine to operate at a too hot or too cold operating temperature. If not replaced, this could result in damage to the engine or impaired engine performance.*



3

When the thermostat is closed, a recirculating bypass, 1, is provided to allow the coolant to recirculate from the head to the block, to effect faster warm-up.




4

Once the engine has reached its normal operating temperature, the thermostat will open and allow water to be drawn through the radiator by the pump action. Cooled water then returns to the engine system.

Cooling occurs as the coolant passes down through the radiator cores (which are exposed to the air) as it is drawn through the radiator by the fan.

NOTE: *Do not operate an engine without a thermostat.*



5

TROUBLESHOOTING

IMPORTANT: *Whenever effecting a repair, the cause of the problem must be identified and corrected to avoid repeat failures. The following table lists problems and their possible causes with recommended remedial action.*


PROBLEM	POSSIBLE CAUSE	CORRECTION
Engine overheats	Hose connection leaking or collapsed	Tighten hose connection Replace hose if damaged
	Radiator cap defective or not sealing	Replace radiator cap
	Radiator leakage	Repair/replace radiator
	Improper fan belt adjustment	Check tensioner Check belt
	Radiator fins restricted	Clean with compressed air
	Faulty thermostat	Replace thermostat
	Internal engine leakage	Check for source of leakage, replace gasket or defective parts
	Water pump faulty	Overhaul water pump
	Exhaust gas leakage into cooling system	Replace cylinder head gasket, check head for damage or distortion
	Coolant aeration	Tighten all connections and check coolant level is correct. Ensure cylinder head gasket is not blown
	Cylinder head gasket improperly installed	Replace cylinder head gasket
	Hot spot due to rust and scale or clogged water jackets	Reverse flush the entire cooling system
	Obstruction to radiator air flow	Remove the obstruction
	Extended engine idling	Do not allow the engine to idle for too long a period
	Oil cooler tube blocked	Clean
	Radiator core tubes blocked	Check free flow
Water temperature gauge fails to reach normal operating temperature	Faulty temperature sender	Replace sender switch
	Incorrect or faulty thermostat	Replace thermostat
	Faulty water temperature gauge	Replace temperature gauge

DISASSEMBLY AND REPAIR

RADIATOR


Removal

1. Raise the engine hood.
2. Close the heater hose taps, 1, located on the right-hand side of the engine.




6

3. Loosen and remove the left- and right-hand side fan guards.




7

4. Loosen the drain plug, 1, at the base of the radiator and drain the coolant. Remove the radiator cap to speed up the draining. Use caution if the system is hot. Remove the lower radiator hose after the coolant has drained.



8

5. Disconnect the radiator top hose, 1.
6. Loosen the fan shroud screws and place the shroud behind the fan blade.




9

7. Ensure that all pipes are disconnected and harnesses are unclipped and away from the radiator assembly.
8. Remove all remaining hardware, attaching the condenser and oil cooler to the radiator, and remove the radiator.

Inspection and Repair

1. Inspect the fins for damage and leaks and repair as required. Ensure they are free from any obstruction.



10


Installation

Installation is the reverse of removal.

1. Ensure that the correct grade and quantity of antifreeze is added to the coolant. The recommended mixture is 50% water with 50% Antifreeze, Specification ESE-M97B-18C/D or SSM-97B-9101A.

NOTE: *Do not add conditioner to this mixture. Coolant conditioner is contained in the coolant filter in the form of a slow release paste.*

2. Refill the system through the radiator pressure cap until completely full, then continue to fill through the expansion tank until the coolant is at the correct level.
3. Run the engine for several minutes checking for leaks, topping up any fluid levels that may have settled during testing.




11

THERMOSTAT


Removal

1. Drain the coolant system below that of the level of the thermostat housing.
2. Remove the thermostat retaining bolts and remove the housing.




12

3. Withdraw the thermostat from the housing along with the gasket.




13

4. To remove the lower housing, loosen the hose clamps, 1, between the thermostat housing and the water pump.
5. Remove the four retaining bolts, and remove the housing.



14

Inspection and repair
Place the thermostat in a container of water and raise the temperature to 100° C (212° F). If the thermostat fails to open when hot, or close properly when cooled, it must be replaced.



15

Installation
Installation of the thermostats is the reverse of the removal procedure, but observe the following:


1. Coat the new gasket with sealer and position in the recess on the thermostat housing, prior to installing the thermostat.
2. Coat the edge of the thermostat with grease and install, with the heat element located in the cylinder head.
3. Refit the thermostat housing and torque the bolts to 20 - 28 N·m (15 - 21 ft lbs).

TEMPERATURE WARNING SENDER

The temperature warning gauge, 1, is located on the dash.

The temperature sender for the gauge is located by the thermostat housing.

If a new sender is to be fitted, apply sealant to the threaded portion of the new sender body, 2, and torque the senders to 16 - 24 N·m (12 - 18 ft lbs).



16

FAN BLADE

Removal
Remove the viscous fan by holding the fan blade in a fixed position and removing the attaching bolts. Torque the bolts to 20 - 25 N·m (15 - 18 ft lbs).

VISCOUS CLUTCH ASSEMBLY


Removal
To remove the fan and clutch assembly (where fitted), hold the pump pulley in the fixed position. Placing an open-ended wrench on the nut to the rear of the clutch assembly spacer, loosen the nut in the clockwise direction.

On reassembly of the fan assembly, tighten the attaching nut in the counterclockwise direction, and torque to 65.5 N·m (48.0 ft lbs).

FAN BELT TENSIONER

To remove the fan belt, 1, place a lever with socket attachment onto the tensioner, 2, and gently lever the tensioner up. Remove the fan belt from the alternator pulley, and gently allow the tensioner to return to its untensioned position once the belt has been removed.

Remove the tensioner from the front cover by loosening and removing the center attaching bolt.



17

Inspection and Repair


Checking of the tensioner assembly operation should be done while the assembly is still attached to the front cover. To check the spring load, place a break back torque bar preset to 70 - 85 N·m (52 - 63 ft lbs) onto the pulley housing. Raise the lever up through an arc of 20° maximum. If the torque arm does not “break” within the range, a new tensioner assembly is required.

Ensure the tensioner pulley rotates freely by hand. If it does not, replace with new parts.

Fit a new pulley assembly if required and torque the attaching bolt to 54.5 N·m (40 ft lbs).

To reassemble the arm assembly, position the tensioner on the front cover. Fit the mounting bolt through the assembly and torque to 54.5 N·m (40 ft lbs).

Fitting the fan is the reverse of the removal procedure, but ensure the poly V-belt is positioned correctly onto all of the pulleys.



18


IDLER PULLEY

Two idler pulleys are fitted to the vehicle - one to the right-hand side of the engine front cover, the other where the air conditioning is fitted on the left-hand side of the front cover close to the crankshaft.

Check and be sure the idler pulleys rotate freely; if tight or worn, replace with new. Removal and replacement is by the attaching bolts through the center of the bodies. Torque the bolts to 54.5 N·m (40 ft lbs).


WATER PUMP

The water pump front view shows the inlet from the thermostat housing, 1, outlet to the rear of the engine, via the oil cooler, 2, the water pump pulley, 3, and the inlet from the radiator, 4.



19


The water pump rear view shows the outlet to the front of the engine, 1.



20


Removal

1. Drain the cooling system.
2. Remove the radiator.
3. Loosen or lever the fan belt tensioner, 2, to ease the tension and remove the fan belt, 1, from the vehicle.




21

4. Loosen the hose clamps to the hoses connecting the water pump to the thermostat housing and the water pump to oil cooler.




22

5. Withdraw the three bolts which pass through the water pump and into the block. Slide the pump forward away from the its rear connector and remove the sealing O ring.



23




70-140-1945

24

1. Seat and seal assembly
2. Impeller
3. Bearing
4. Pulley
5. Pulley shaft mating surface


Disassembly
With the water pump removed, lay the pump on a bench (pulley down).

1. Undo and remove the securing bolts from the adaptor cover on the rear of the pump body. Carefully ease out the backplate. Remove and discard the O ring.




25

2. With the adapter cover removed, pry the backplate off.




26

3. Place the pump body between the two supports, 3, and by gently pressing on the shaft, push the shaft and pulley, 4, away from the impeller, 2, and out of the pump body, 1.




27

4. With the impeller/shaft assembly removed from the pump, place the pulley, 1, on supports, 2, and press out the shaft assembly, 3, from the pulley.
5. The seal assembly attached to the bearing shaft is not removable or serviceable. During the manufacturing process, the seal is pressed onto the shaft and destroyed on removal. This is to meet pre-load conditions and maintain an effective wear seal.



28



29

1. Adapter cover
2. Backplate
3. Impeller
4. Seal and bearing assembly
5. Pulley
6. Bearing
7. Pump body


Inspection and repair

1. Check the bearing shaft and seal assembly for signs of wear or leaks, If evident, the assembly must be replaced with new parts.
2. Check the impeller for worn or damaged vanes and replace if not to an acceptable standard.
3. Clean and check the pump body for signs of cracks, erosion or leaks. If any of these faults are evident and likely to cause pump failure at a later date, the pump body must be repaired or replaced with a new one.

Reassembly


1. To install the bearing, 1, into the pump body, 3, place the body rear face down onto a flat surface. Install the bearing with the longer stepped end of the shaft in the body and using a sleeve, 4, that contacts the bearing outer race only. Use a press, 5, to press the bearing into the body. Once installed in the body, the bearing case end face must be flush with the pump front face to within 0.00 - 0.076 mm (0.000 - 0.006″), 6.

NOTE: *Use Loctite 609 around the pulley bore chamfer and press the pulley onto the shaft.*




30

2. With the water pump, 4, placed front face down and the shaft, 6, supported with suitable blocks, 5, place the seal assembly, 3, on the end of the shaft with its smallest diameter uppermost. To insert the seal assembly, place tool, 2, over the seal and use a press, 1, to press until the lip on the seal body seats on the pump body.




31

3. With the seal installed correctly, the seal working height should be maintained at 10.9 - 11.7 mm (0.430 - 0.460″), 1.




32

4. With the water pump rear, 1, face up, and the shaft supported, place the impeller, 2, over the shaft, 3, and press the impeller into the water pump body. Installed correctly the face of the impeller fins to the operating face of the water pump should be 0.25 - 0.88 mm (0.010 - 0.035″).
5. To achieve this, check the dimension from the rear face of the impeller to the rear face of the pump. The dimension should be maintained at 28.07 - 28.58 mm (1.105 - 1.125″), 5.




33

6. With the pump rear face down and the shaft supported, press the pulley onto the shaft ensuring the pulley front face to the rear face of the pump dimension is 157.10 - 157.86 mm (6.185 - 6.215″).



34


7. Ensure a new O ring is fitted and place the water pump backplate in position. Make sure the water pump pulley/impeller assembly rotates freely by hand prior to reassembly. If not, disassemble and recheck the dimensions.



35

Installation

1. Installation of water pump, 1, to the engine is the reverse of disassembly.
2. Ensure the fan belt tensioner pulley, 2, rotates freely and the swinging arm, 3, of the tensioner returns to rest freely. Gently lever the arm up, to enable the fan belt to be seated in the grooves on the pulleys. Refit the fan blade assembly.
3. After installation of the radiator, refill the cooling system as previously described and run the engine checking for leaks.



36

SECTION 10 – ENGINE

Chapter 3 – Induction System

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	4
	Air Cleaner	4
	Turbocharger	6
	Intercooler	9
	Troubleshooting	10
	Intercooler Leak Test	12
	Disassembly and Repair	13
	Air Cleaner	13
	Turbocharger	15
	Intercooler	21

SPECIFICATIONS

AIR CLEANER
Dry Element

Service interval	Whenever the light glows (outer element)
Change interval	600 hrs. - outer element 1200 hrs. - inner element

Torques:	**N·m**	**Ft Lbs**
Air cleaner tube to manifold clamps	2.0	1.5
Air cleaner tube to turbocharger clamps	2.0	1.5
Aspirator tube to muffler clamps	2.0	1.5
Cleaner to manifold bolts	23.0	17.0

TURBOCHARGER

General Torques:	**N·m**	**Ft Lbs**
Turbine housing bolts	16 - 19	12 - 14
Turbocharger to manifold	47 - 54	35 - 40
Oil feed tube to turbocharger (banjo bolt)	30 - 40	22 - 30
Oil feed tube to filter head connector	18 - 20	13 - 15
Connector to filter head	54 - 81	60 - 90
Oil return tube bolts from turbocharger	20 - 25	15 - 18.5
Oil return tube to block connector	34 - 37	20 - 35
	N·m	**In. Lbs**
Inlet hose clamps	1.7-2.3	15-20
Turbocharger oil feed line connector to engine block	Snug fit	Snug fit

INTERCOOLER

General Torques:	**N·m**	**Ft Lbs**
All hose clamps	65	5.7

Center Shaft:		**mm**	**In.**
Radial clearance	Maximum	0.127	0.0051
	Minimum	0.056	0.0022
Axial clearance	Maximum	0.084	0.0039
	Minimum	0.025	0.001

SEALERS

Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595, or 596 LOCTITE ULTRA BLUE 587 DOW CORNING SILASTIC 732 GENERAL ELECTRIC RTV 103 or 108
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)


DESCRIPTION OF OPERATION

AIR CLEANER

The function of the air cleaner is to remove impurities from the air, but at the same time allow a sufficient volume of air to enter the engine and ensure complete combustion of the fuel.

Air is drawn through screens, 1, mounted at the front of the radiator which prevents large particles of chaff and dirt from being sucked into the engine.


The air then passes into the air cleaner system that consists of an inner and an outer element within a metal casing located under the hood.



1

NOTE: *70 Series art shown in Figure 2.*

As air enters the cleaner, 1, the heavier particles of dirt are thrown to the outside of the container and drawn through an aspirator tube connected to the muffler. This allows the heavier particles to be expelled through the exhaust pipe. The lighter particles are then collected on the primary element and will be suspended until cleaned off during servicing. The inner secondary element is located within the outer element and protects the engine in the event of dust passing through the outer element if damaged.




2

A restriction indicator switch, 2, is mounted in the outlet tube of the air cleaner. If the element becomes blocked, the vacuum in the air cleaner outlet pipe will increase and actuate the vacuum switch. When the switch is actuated, a warning light will illuminate in the vehicle's instrument panel.

If the air filter restriction warning lamp, 1, illuminates when the engine is running, stop the engine as soon as possible or within at least one hour and investigate the cause.

NOTE: *It is important that the outer element only be cleaned when the restriction light illuminates. Cleaning the element more frequently may cause dust to be allowed into the intake manifold.*




3


Inner Element

The inner element, 1, should not be disturbed unless damaged, or contaminated with dirt by failure of the outer element, 2. If contaminated, a new inner element should be installed.

If the inner element is clean, leave it assembled in the cleaner body and change annually or every 1200 hours, whichever occurs first.



4




5

TURBOCHARGER

The output of most engines is usually limited by the engine's ability to breathe, i.e., to get a volume of air into the engine quickly enough for combustion and then to expel exhaust gas to get ready for the next cycle.

This problem is overcome with the use of a turbocharger. Unlike normally aspirated engines, turbocharged engines are unaffected by the reduced density of air found at higher altitudes.

Forcing more air into the engine means more fuel can be burnt, and so more power developed. Because of the constant air to fuel ratio, turbocharged engines are also very fuel economic.




6


Turbocharger, 1, is pressure lubricated directly from the engine lubrication system, 2.

IMPORTANT: *To ensure adequate lubrication of the turbocharger, allow the engine to idle for approximately one minute after starting the engine.*

Before stopping the engine, allow the turbocharger and exhaust manifold to cool down by idling the engine for approximately one minute. This will prevent the distortion of any components.



7



8

1. Center housing
2. Retaining ring
3. Bearing
4. Wheel shroud
5. Split ring seal
6. Turbine wheel
7. Bolt
8. Thrust bearing
9. Back plate assembly
10. Split ring seal
11. Compressor wheel
12. Nut
13. Thrust collar
14. Seal ring

A turbine wheel is driven inside the turbocharger by the exhaust gas before it is expelled to the atmosphere. The turbine is connected via a shaft to the compressor wheel which draws air in from the air cleaner and forces it as compressed air into the inlet manifold. The harder the engine is loaded, the faster the turbo runs and more power is developed.

Split ring seals are installed at each end of the shaft between the bearing and the adjacent turbine or compressor wheel to prevent lubricating oil from entering the turbine and the compressor area.

INTERCOOLER


An intercooler, 1, is used on Models 8870 and 8970 tractors. The intercooler cools air from the turbocharger, 2, before it enters the intake manifold, 3. Cooling the air increases the density and provides a greater air mass. This permits increased fuel delivery to the engine and a corresponding increase in engine horsepower.

NOTE: *Special clamps and hoses are used to withstand the high operating temperatures and pressure. Do not substitute any other type of material.*

Intake air from the air cleaner is compressed by the turbocharger and forced under pressure towards the intake manifold. The high-pressure air is directed towards the intercooler where it is forced through the intercooler matrix and cooled by the air being drawn in by the engine fan. After passing through the cooler, the pressurized intake air has a greater density as a result of cooling and a higher volume of fuel can be burnt in the correct air/fuel ratio to give increased power.

⚠ WARNING ⚠

Air temperature within the intercooler system can easily reach 93 - 149°C (200 - 300°F) which can burn the skin. Do not touch these parts while tractor is in operation.



9

TROUBLESHOOTING

AIR CLEANER

PROBLEM	POSSIBLE CAUSE	CORRECTION
Air cleaner warning light illuminates	Clogged air cleaner	Clean or replace outer element
Air cleaner warning light illuminates after filter service	Vacuum switch faulty	Replace switch
Air cleaner warning light illuminates, before service intervals	Aspirator tube not working, debris in filter body	Clean aspirator tube, check muffler, clean element

TURBOCHARGER

When trying to diagnose a suspected turbocharger malfunction, the turbocharger cannot compensate for incorrect engine operation, deficiencies of the engine air intake and fuel system, or for damaged engine components, such as valves, pistons, rings, liners, etc.

Consequently, a systematic fault-finding procedure is essential to accurately find the concern and ensure that subsequent failure does not occur.

Turbocharger failures are usually a result of dirt ingress into the intake manifold, which damages the fins, or through lack of lubrication which destroys the bearing surfaces, and the turbocharger seizes.

In general, fault-finding procedures that can be performed with the least amount of effort should be performed first. It is important to perform all troubleshooting procedures before attempting any disassembly.

PROBLEM	POSSIBLE CAUSE	CORRECTION
Engine lacks power or emits black smoke	Dirty air cleaner	Service air cleaner
	Loose compressor to intercooler to intake manifold clamps	Tighten intake manifold clamps
	Leak at the engine intake at turbocharger mounting flange	Repair leak
	Turbocharger rotating assembly binding	Rebuild turbocharger
	Air cleaner to turbocharger duct restricted	Clean air cleaner to turbocharger duct
	Compressor to intake manifold duct restricted	Clean compressor to manifold duct
	Engine exhaust system restricted	Clean engine exhaust system
	Engine malfunction (rings, pistons, valves)	Rebuild the enigne
	Turbocharger damaged due to engine debris passing through it after a catastrophic engine failure	Rebuild turbocharger

TURBOCHARGER (continued)

PROBLEM	POSSIBLE CAUSE	CORRECTION
Seal leaks at compressor end of turbocharger	Dirty air cleaner	Service air cleaner
	Restricted duct between air cleaner and turbocharger	Clean air cleaner and turbocharger duct
	Loose compressor to intake manifold dust connections	Tighten compressor to intake manifold duct connectors
	Leaks at the engine manifold	Repair leak
	Restricted turbocharger oil drain line	Clean turbocharger oil drain line
	Plugged engine crankcase breather	Clean engine crankcase breather
	Worn or damaged compressor wheel (worn bearings, bores or journals)	Rebuild turbocharger
	Excessive piston blow-by or high internal crankcase pressure	Rebuild engine
Seal leaks at turbine end of turbocharger	Excessive pre-oiling	Reset pre-oiling system
	Plugged engine crankcase breather	Clean engine crankcase breather
	Restricted turbocharger oil drain line	Clean turbocharger oil drain
	Sludged or coked center housing	Clean center housing
	Worn turbocharger bearings, bearing bores, or shaft journals	Rebuild turbocharger
Turbocharger rotating assembly binding or dragging	Damaged compressor wheel	Rebuild turbocharger
	Damaged turbine wheel	Rebuild turbocharger
	Compressor or turbine wheel rubbing on housing due to worn bearings	Rebuild turbocharger
	Excessive dirt buildup in compressor (housing or wheel)	Rebuild turbocharger
	Excessive carbon buildup behind turbine wheel	Rebuild turbocharger
	Sludged or coked center housing (check engine lubrication system)	Rebuild turbocharger

INTERCOOLER

PROBLEM	POSSIBLE CAUSE	CORRECTION
Loss of engine power Low turbocharger boost pressure Higher than normal exhaust temperature	Leak or crack in intercooler	Replace intercooler

NOTE: *Do not disassemble. The intercooler is serviced as a complete unit.*

INTERCOOLER LEAK TEST

NOTE: *To ensure proper performance, the intercooler must be leak tested and pressure checked.*

Connect an air gauge in one port of the unit and a stop/air supply in the other port.

Apply 3.45 bar (50 PSI) air pressure to the unit. Reduce the air pressure to 2.1 bar (30 PSI) and plug the unit.

Let the unit sit for a couple of minutes and note any loss of air pressure.

Loss of air pressure should not be more than 0.1 bar (1.5 PSI) per minute. If it is, the cooler should be checked, repaired and tested again until it passes the test.

There should be no permanent distortion of the unit. If there is, replace the cooler.


DISASSEMBLY AND REPAIR

AIR CLEANER

NOTE: *70 Series art shown in Figure 10.*

To service the filter (outer element):

1. Unscrew the wing nut, 1, which is attached to the cover and remove the outer cover, 2.




10

2. Unscrew the wing nut, 1, and remove the outer element, 2.

IMPORTANT: *Do not remove the inner element, 3.*

3. Examine the inside of the outer element, 2. If dust is present, the outer element is defective and must be replaced.
4. If the element is dusty, lightly tap the ends of the element against the palm of your hand.


IMPORTANT: *Do not tap the element against a hard surface as this may damage the element.*



11

With large buildups of dust, use compressed air not exceeding 2.1 bar (30 PSI). Insert an air line inside the element. With the nozzle approximately 152 mm (6″) from the element, blow air from the inside to the outside of the element to remove dust. If the element is oily or heavily contaminated, the element may be washed by immersing it in warm water containing a small amount of non-sudsing detergent. Allow to soak for 15 minutes keeping the end of the element above the water line.


IMPORTANT: *Never use fuel oils, gasoline, solvent or boiling water, as the filter element may be damaged.*



12

After soaking, agitate the element in the water, taking care not to allow dirty water outside the element to splash over to the inside. Rinse the element with clean running water from the inside out not exceeding 2.1 bar (30 PSI). Shake the excess water from the element and allow it to dry naturally.

IMPORTANT: *Do not attempt to dry the element with heat or compressed air, and do not install the element until thoroughly dry as it may rupture. It is recommended that a new, or previously cleaned element be installed, and the washed element put aside for the next service.*




13

NOTE: *It usually takes from one to three days for a filter element to dry.*

The outer element may be washed up to six times.

5. Inspect the element for holes and ruptures with a light. Check the casing and rubber seal for distortion and discard if damaged.




14

6. Clean the inside of the air cleaner housing using a damp lint-free cloth and install a cleaned or new outer element. Tighten the wing nut.

NOTE: *Replace the wing nut seal if it is damaged.*

NOTE: *70 Series art shown in Figure 15.*

Install the air cleaner cover, 2, and wing nut, 1. If the indicator light continues to illuminate after cleaning the element, replace the element.




15

TURBOCHARGER


Removal

1. Raise the hood of the tractor, 1.
2. Remove the protective heat shield from the exhaust side of the turbocharger, 2.



16

3. Loosen and disconnect the air cleaner to turbocharger and turbocharger intake and intercooler hoses as required, 1.
4. Disconnect the turbocharger to muffler tube.




17

5. Disconnect the oil supply and return tubes from the turbocharger. Cap the ends of the tubes and oil ports of the turbocharger to prevent entry of foreign material, therefore preventing future bearing failures.

NOTE: *Before removing and cleaning the unit, look for signs of oil and/or gas leakage, also wheel damage may not be evident after cleaning.*

6. Remove the turbocharger and gasket from the exhaust manifold. Cover the opening in the exhaust manifold to prevent the entry of dirt which could cause damage to the turbine wheel blades after installation and start-up.



18


Disassembly

1. Clean the old gasket material from the oil line flanges and the center housing flange mating surfaces.
2. Clean the exterior of the turbocharger using a non-caustic cleaning solvent to remove accumulated surface matter before disassembly.


   Mark the compressor housing, turbine housing and center housing with a punch or scribe to facilitate orientation of the housing during reassembly.
3. Loosen the bolts that hold the compressor and turbine housings to the center housing so the housings can be rotated.
4. Loosen and remove the bolts/lock plates from the turbine housing exhaust side and from the center housing intake side.

NOTE: *Exercise care when removing the compressor housing to avoid damaging the compressor wheel blades. Tap the turbine housing with a soft-faced hammer if force is needed to remove.*

NOTE: *Service on the turbocharger is limited to replacement of the center housing rotating assembly, compressor housing, and/or turbine housing, due to the precise balancing requirements of the core assembly. Do not disassemble the center housing rotating assembly.*



19



20

TURBOCHARGER EXPLODED VIEW

1. Intake housing
2. Center housing and rotating assembly
3. Turbine housing

Cleaning

Before cleaning, inspect all parts for burning rubbing or impact damage that may not be evident after cleaning. Clean all parts in a non- caustic solution using a soft bristle brush, a plastic blade scraper, and dry compressed air to remove residue.

DO NOT - use abrasive cleaning methods which might damage or destroy machined surfaces.

DO NOT - immerse center housing and relating assembly in solvent.

DO NOT - blow under compressor wheel with compressed air.

DO NOT - permit wheel/shaft assembly to spin when blowing off solvent or residue.

Inspection

1. Inspect the compressor housing assembly for the following defects:

   Wheel rub damage in the contour area that cannot be polished out with 80 grit silicon carbide abrasive cloth.

   Nicks, dents or distortion that could prevent proper sealing between the compressor housing and the center housing and rotating assembly.

NOTE: *Replace the compressor housing if any of the above defects are found.*

2. Inspect the turbine housing assembly for the following defects:

   Wheel hub damage in the contour area that cannot be polished out with 80 grit silicon carbide abrasive cloth.

   Nicks, dents or distortion that could prevent proper sealing between the turbine housing and the center housing and rotating assembly.

NOTE: *If there is any compressor or turbine wheel blade damage, the center housing and rotating assembly must be replaced. Operating the turbo-charger with damaged blades will result in further damage to component parts or the engine.*

   Blades cannot be straightened in service.

IMPORTANT: *The center housing rotating assembly has been balanced as an assembly at the factory, under precision conditions, and must not be disassembled in any way. Disassembly will destroy the balance, and a new center housing and rotating assembly and a new housing will have to be installed.*

Center shaft radial check


Check the journal bearing radial clearance whenever there is reason to suspect that the bearings are worn enough to allow either the wheel or the turbine wheel to rub on its housing. This may be heard as a high-pitched whine.

1. With the turbocharger removed, attach a dial indicator with a dogleg probe to the center housing. The indicator plunger should extend through the oil outlet port and contact the shaft of the turbine wheel assembly.
2. Manually apply equal and simultaneous pressure to the wheels to move the shaft as far as it will go away from the dial indicator probe.
3. Set the dial to zero.
4. Manually apply equal and simultaneous pressure to the wheels to move the shaft as far as it will go toward the plunger. Make a note of the shaft movement shown on the indicator dial.

NOTE: *Make sure the dial reading indicated is the maximum possible; roll the wheels slightly in both directions while applying pressure.*

5. Manually apply equal and simultaneous pressure to the wheels to move the shaft away from the plunger again. Note that the indicator pointer returns exactly to zero.
6. Repeat steps 2 to 5 several times to ensure that maximum radial clearance, as indicated by maximum shaft movement, has been measured.
7. If the maximum clearance is less than 0.056 mm (0.0022″) or greater than 0.127 mm (0.0050″), replace the center housing and rotating assembly.


   Troubleshoot the engine to find the cause of bearing failure and correct the problem before resuming operations.



21

Axle Clearance Check
Check the thrust bearing axial clearance:

1. Place a dial indicator, 1, with the probe on the compressor end of the turbocharger shaft assembly.
2. Manually move the compressor turbine wheel assembly as far as it will go away from the plunger.
3. Set the dial indicator, 1, to zero.
4. Manually move the compressor turbine wheel assembly as far as it will go toward the dial indicator plunger. Make a note of the shaft movement shown on the indicator dial.
5. Manually move the compressor/turbine wheel assembly as far as it will go away from the plunger; note that the indicator plunger returns to zero.
6. Repeat steps 2 through 5 several times to make sure the maximum axial clearance, as indicated by maximum shaft movement, has been measured.
7. If the maximum clearance is less than 0.0254 mm (0.0010″) or greater than 0.084 mm (0.0039″), replace the center housing rotating assembly.



22

⚠ CAUTION ⚠

Continued operation of a turbocharger having an excessive amount of thrust bearing axial clearance will result in irreparable damage to the compressor wheel and housing or to the turbine wheel assembly.

Reassembly

1. It is recommended the following be replaced with factory authorized parts only, at each overhaul, or whenever parts are removed:


   Compressor housing retainer O ring seal, compressor housing retainer plates, turbine housing bolts, turbine housing retainers.
2. Parts that require changing if faulty or damaged:

   Center housing rotating assembly, turbine assembly, compressor housing, turbine housing.
3. Inspect all mating surfaces to insure they are free of burrs, foreign matter, and corrosion deposits.

4. Install an O ring, 1, on the center housing compressor end flange and place the compressor housing assembly in position. Be careful not to damage the compressor wheel blades.
5. Carefully rotate the compressor housing onto the center housing rotating assembly to line up scribe marks.
6. Reinstall bolts and lock tabs to secure the center housing to the compressor housing. Torque to 16 - 18 N·m (12 - 13 ft lbs).

NOTE: *When installing a new center housing rotating assembly or turbine housing, transfer scribe alignment marks from old to new parts.*

7. Position the turbine housing discharge side down on a flat, level surface. Place the center housing rotating assembly turbine wheel end into the housing, using special care to avoid damaging the wheel blades. Check visually for proper alignment.
8. Carefully rotate the center housing rotating assembly in the turbine housing to line up the scribe marks. Recheck for proper alignment and position the locking plates.
9. Coat the bolts with a suitable non-seize compound and torque to 16 - 19 N·m (12 - 14 ft lbs).



23

Installation

1. Prior to installation, fill the turbocharger center housing with new clean oil, and rotate the main shaft to lubricate the bearings.
2. Installation of the turbocharger follows the removal procedure in reverse. Install a new manifold gasket, and tighten to 47 - 54 N·m (35 - 40 ft lbs).
3. Replace the washers and reconnect the oil feed tube banjo bolt and torque to 20 - 27 N·m (15 - 20 ft lbs).
4. The oil feed tube connector if disturbed should be refitted. Apply sealer to the connector and torque to 54 - 81 N·m (4 - 60 ft lbs).
5. Apply sealer (see "Specifications"), assemble the oil feed tube to the oil filter head connector and tighten to 18 - 20 N·m (13 - 15 ft lbs).
6. Place a suitable receptacle below the oil outlet port and, **with the electrical solenoid wire disconnected at the fuel injection pump,** crank the engine until oil flows from the outlet port.
7. Reconnect the oil outlet tube using a new gasket and tighten the retaining bolts at the turbocharger to 20 - 25 N·m (15 - 18.5 ft lbs).
8. Tighten the oil return tube to cylinder block connector using new rubber hose and hose clamps if required.
9. If disturbed, the oil return tube connector should have sealer applied (see "Specifications") and torque to 34 - 47 N·m (25 - 35 ft lbs).
10. Reconnect the air inlet and outlet tubes with the hose clamps and torque to 1.7 - 2.3 N·m (15 - 20 in lbs).
11. Reconnect the fuel injection pump solenoid wire.
12. Check the engine oil level and add oil if required. Idle the engine and check all tubes and gaskets for leaks.
13. Run the engine at rated speed and listen for sounds of metallic contact from the turbocharger. If any noise is apparent, stop the engine immediately and correct the cause.

NOTE: *After the unit has attained operating temperatures, the rotating assembly should coast freely to a stop after the engine is stopped. If the rotating assembly jerks to a sudden stop, correct the cause immediately.*

Leak Diagnosis

1. Feel, or listen, for air leaking while the engine is revved to engage the turbocharger.
2. Mark, then correct, any leak locations.

INTERCOOLER

Removal

To remove the intercooler, disconnect the supply hose from the turbocharger and the feed hose to inlet manifold. Loosen and remove the hardware retaining the cooler.

1. Do not damage the cooler fins or tubes.
2. Cover the cooler inlet and outlet to prevent any foreign matter from entering the cooler or engine.
3. Inspect the cooler to determine the extent of damage.
4. Look for two types of cracks: tube cracks and/or tank weld cracks. Tube cracks will usually occur first in the corners of the core and will be seen where the tube goes into the tank. Visual inspection will usually find most tube cracks; however, a better way is to pressurize the cooler to 2.1 bar (30 PSI) and apply a liquid soap film to all the tank joints. If bubbles form, there is a tube crack present.

   For additional information, refer to "Intercooler Leak Test" in the "Troubleshooting" portion of this chapter.
5. If tube cracks are found, replace the cooler.
6. Installation is the reverse of removal.

SECTION 10 – ENGINE

Chapter 4 – Fuel System

CONTENTS

Section	Description	Page
10 000	Specifications	3
	Fuel System Torque Chart	4
	Special Tools	4
	Description of Operation	5
	Testing and Diagnosis	19
	Low Pressure Fuel System	20
	Fuel Tank Valves	20
	Filter Inlet and Outlet Pressure Tests	20
	High Pressure Fuel System	25
	Injection Timing Check	25
	Fuel Injector Nozzle Check	28
	Injector Assembly Bench Testing	28
	Preliminary Setup Procedure	29
	Perform Opening Pressure Test	29
	Perform Nozzle Seat Leakage Test	30
	Perform Chatter and Spray Pattern Test	31
	Surging	31
	Fuel Shutoff Diagnosis	32
	Shutoff Solenoid Specifications	32
	Preliminary Checks	32
	Checking Electrical Feed	32
	Adjustments	34
	Bleeding the Fuel System	34
	Adjustment of Foot and Hand Throttle Cables	35
	Adjustment of High Idle Speed	35
	Adjustment of Low Idle and Antisurge	36
	Removal and Installation	37

Fuel Lift Pump 37
Fuel Shutoff Solenoid 38
Fuel Injection Pump 39
Fuel Injection Lines 47
Low-pressure Fuel Injection Lines 47
High-pressure Fuel Lines 48
Injector Leak-off Line 50
Fuel Filter 51
Fuel Filter Manifold 52
Injection Nozzles 53

SPECIFICATIONS

	8670/8670A	8770/8770A	8870/8870A	8970/8970A
Fuel tank capacity	Lower (main) Upper (auxiliary) Total -	246 L (65 U.S. gal) 170 L (45 U.S. gal) 416 L (110 U.S. gal)		
Injection pump	Bosch A2000	Bosch P3000		
Timing static deg. BTDC (non-emissionized)	24	21	16	16
Timing static deg. BTDC (emissionized)	18	18	16	16
Injectors - type	Bosch, 5 Hole, Type - Differential Needle			
Injector opening pressure (new)	241 bar (3500 PSI)	241 bar (3500 PSI)	255 bar (3700 PSI)	255 bar (3700 PSI)
Injector opening pressure (used)	213 bar (3100 PSI)	213 bar (3100 PSI)	227 bar (3300 PSI)	227 bar (3300 PSI)
Recommended injector service	2400 Hours			
Governor type	Bosch “RSV”/All Speed			
Governed range (RPM)	750-2310			
Low idle speed (RPM) 8670/8670A, 8770/8770A	900 ± 25			
Low idle speed (RPM) 8870/8870A, 8970/8970A	815 ± 25			
High idle speed (RPM)	2305 ± 25			
Rated engine speed (RPM)	2100			
Fuel filter	Sedimenter and Micronic Filter			
Water separator	Integral with Filter			
Recommended fuel filter service	600 Hours			


FUEL SYSTEM TORQUE CHART

	N·m	Ft Lbs
Injector attachment bolts	23	17
Injector line nuts	24	18
Injection pump drive gear	38	28
Injection pump rear mounting bolts	38	28
Injection pump-to-front adaptor plate	38	28
Injection pump-to-gear drive bolts	67	50
Injection timing gear access cover	38	28
Leak-off tube banjo fitting bolts	9	7
Lift pump mounting to main junction pump, nuts (3)	8	6

SPECIAL TOOLS

Tool Number	Description
FNH00536	Timing pin kit - Contains rigid and spring-loaded
FTC213312	Universal Pressure Test Kit
FNH01721	Injection Nozzle Tester
FNH00041	Nozzle Tester Adapter

DESCRIPTION OF OPERATION



1


Tanks
Low pressure to pump
Return circuit
Low pressure supply
High pressure to injectors

The fuel system consists of:

1. Fuel injector assemblies
2. Injector return lines
3. High-pressure pumping elements
4. Overflow valve which regulates fuel gallery pressure
5. Supply pump
6. Injection pump assembly
7. All-speed mechanical governor
8. Combination filter/ water separator /primer pump
9. Low-pressure supply
10. Finger screen
11. Drain valve
12. Return line
13. Lower supply tank
14. Upper supply tank
15. Fuel tank venting
16. Filler neck
17. High-pressure injection lines
18. Aneroid, or boost-control, assembly

Supply Tanks

Two fuel tanks are standard equipment. The lower, or main, tank, 4, having a capacity of 246 L (65 U.S. gallons), is located along the left side of the center axle housing. The upper, or auxiliary, tank, 2, having a capacity of 170 L (45 U.S. gallons), is located below the cab toward the rear of the tractor. Fuel tank filling, 8, as well as the engine supply and return, are accomplished through the lower tank. A large, diameter tube, 3, connects the upper and lower tanks. There is no valve on this tube, so it is not possible to isolate the upper and lower tanks. The tanks are vented through a tube attached to the upper tank. The vent tube, 1, extends up the right rear cab post. Both the supply, 6, and return fittings, 7, on the lower tank contain shutoff valves to ease service. The supply fitting threads into a 24 mesh inlet screen, 5, approximately 76 mm (3″) long, which in turn threads into the fuel tank. The return fitting contains a drain cock.




2

NOTE: *Figure 3 is 70 Series art.*


NOTE: *Figure 4 is 70A Series art.*

Fuel Filter/Water Separator/Primer Pump

The primary purpose of this assembly is to remove water and solid contaminants from the fuel before the fuel enters the gallery of the injection pump. The plunger and barrel assemblies (pumping elements) of the injection pump are matched to each other with an accuracy of a few ten thousandths of an inch. Impurities of this size can cause severe damage, or excessive wear, to the injection pump and injector assemblies. The fuel filter assembly consists of a manifold, or base, containing the primer pump, 3, along with a bleed port. For the 70A Series tractor, the primer pump, 3, is now on the top of the supply pan. The primer and bleeder (70 Series only) are used when the engine has run out of fuel or a new filter element has been installed. Threaded onto the manifold is the filter element. The water separator, 1, is in turn threaded onto the filter element. The separator bowl contains a drain, 2, that can be used if water or sediment are observed.




3



4

NOTE: *70 Series art shown in Figures 5 and 6.*


Fuel Injection Pump
Models 8670/8670A and 8770/8770A are equipped with the Bosch Type “A2000” pump.




5

Models 8870/8870A and 8970/8970A are equipped with the Bosch Type “P3000” pump.

NOTE: *Operation of both pump types is very similar.*



6




7

COMPARISON OF IN-LINE INJECTION PUMPS

1. Deliver valve holder
2. Filler Piece
3. Delivery Valve
4. Pump Barrel
5. Flange
6. Pump Plunger
7. Gear Segment
8. Control Sleeve
9. Lever Arm With Ball Head
10. Control Rod
11. Plunger Control Arm
12. Plunger return Spring
13. Adjusting screw
14. Spring Seat
15. Roller Tappet
16. Camshaft
17. Spring-Chamber Cover


NOTE: *70 Series art shown in Figures 8, 9 and 10.*

The fuel injection pump, the heart of the fuel system, consists of a number of subassemblies.



8


The supply pump is the entry point into the engine fuel system from the tanks. The supply pump is mechanically driven by the injection pump camshaft. The purpose of the supply pump is to draw fuel from the tank, and pressurize the fuel to a minimum of 1.4 bar (20 PSI) in order to cause fuel to flow through the filter, and to provide sufficient pressure for pumping element filling. The supply pump housing also contains a sedimenter assembly consisting of a clear bowl, 1, and strainer screen, 2. The clear bowl should be inspected for sediment every 50 hours and cleaned every 300 hours.




9

The rear portion of the injection pump assembly houses the all-speed “RSV” mechanical governor. The governor receives inputs from the following:

- Throttle control lever, 1
- Intake manifold pressure, 3
- Injection pump camshaft speed, 4
- Engine oil pressure, 2
- Mechanical fuel shutoff lever, engine side of pump (not shown), which is, in turn, controlled by the fuel shutoff solenoid



10



11


1. Governor housing
2. Starting spring
3. Throttle control lever
4. Governor housing
5. Shutoff idle stop
6. Tensioning lever
7. Guide lever
8. Governor spring
9. Auxiliary idle speed spring
10. Torque control & idle speed helical compression spring
11. Full load stop (fuel delivery)
12. Fulcrum lever
13. Guide bushing
14. Flyweight
15. Swiveling lever
16. Rocker
17. Strap
18. Control rod

Receiving these inputs, the governor, by moving the pumping element control rack, 18, controls engine-off, excess fuel for starting, minimum and maximum idle speeds, and any midrange speeds independent of load. A pair of flyweights, 14, are attached to the pump camshaft. The force of the flyweights increases with engine speed. The force of the weights operates against that of the governor spring, 8. The tension on the governor spring is varied by the position of the throttle lever, 3. Also contained within the governor housing is the starting spring, 2. This lightweight spring pulls the fuel control rack fully forward to the excess fuel position whenever the engine is not running. As soon as the engine starts and the flyweights begin to generate force, the starting spring is overcome and the rack returns to normal fuel delivery.

Aneroid assembly

The aneroid assembly prevents excessive smoke under load by limiting maximum fuel delivery until the turbocharger is providing sufficient air to effect clean combustion. An example of this operation would be starting a load out onto a roadway, when the engine is idling, and throttle position and load are increased simultaneously.


1 Headless setscrew
2 Plate washer
3 Governor cover
4 Strap
5 Fulcrum lever
6 Starting spring
7 Governor housing
8 Control rod
9 Bell crank
10 Control shaft
11 Guide bushing
12 Helical compression spring
13 Diaphragm
14 Charge air pressure



12

The aneroid also contains a hydraulic activator, 1, which is controlled by engine oil pressure, A. When there is no oil pressure, B, the activator allows the control rack full travel to the excess fuel position. Without this feature, during starting, fuel delivery would be extremely limited due to lack of turbocharger boost pressure.

1 Hydraulic activator
2 Bell crank
3 Strap




13

NOTE: *70 Series art shown in Figure 14.*

Overflow Valve Assembly

The supply pump has a capacity of about twice that of the requirements of the high-pressure pumping elements. This excess flow provides cooling and lubrication for the injection pump. Flow from the supply pump travels through the filter element and then to the fuel gallery of injection pump, where it is available to fill the pumping elements. The fuel must be pressurized in order to properly fill the pumping elements. The job of the overflow valve, 1, is to maintain a pressure of approximately 1.5 bar (22 PSI) in the fuel gallery. Once that pressure is reached, the overflow valve opens and allows the excess fuel to return to the tank.




14

High-Pressure Pumping Elements

The high-pressure pumping elements, one for each engine cylinder, supply fuel at a pressure of approximately 240 bar (3500 PSI) to the injectors. The pumping elements must provide the fuel in a precisely measured amount at the proper time.

Operation of the individual element is as follows:



15

Fuel Delivery Cycle

Reference (A) – Bottom dead center / Fuel in

Reference (B) – Spill port closure / Fuel Pressurized

Reference (C) – Spill port opening / Fuel delivery ends


(A) With the plunger, 1, at the bottom of the stroke, fuel flows into the barrel through the spill port, 2, and fills the space above the plunger.

(B) As the plunger, 1, rises, the spill port in the barrel, 3, is covered and the fuel is trapped. This is the point of port closure. The continued upward movement of the plunger pressurizes the trapped fuel until the delivery valve (at the base of each high-pressure injection line) is lifted from its seat. High- pressure fuel is transmitted through the line to the injector and injection takes place through the injector nozzle.


(C) Injection stops when the upper edge of the helix, 4, uncovers the lower edge of the spill port. Pressure escapes to the fuel gallery. The drop in pressure causes the injector to close and injection to stop. After fuel delivery ceases, the plunger continues to the top of the stroke and is returned by a spring for the next cycle.

Because the end of delivery is reached when the helix on the plunger uncovers the spill port, 1, the amount of fuel delivered is varied by turning the pump plunger as shown at D. If the plunger is turned until the vertical groove completely uncovers the spill port as shown at E, during the entire lift of the plunger, there will be no fuel delivered to the engine. This is because injection pressure cannot be reached, thereby shutting off the engine.

The plungers are rotated by a control rack splined to each plunger. Rack movement is determined by the control rod, actuated by the governor.




16



17

Fuel Delivery and Timing During Starting

The plungers, 1, are equipped with starting grooves, 2, on their crown. The purpose of this groove is to assist in starting the engine by providing both excess fuel and slightly retarded timing. When the key switch is turned on, the fuel shutoff solenoid retracts, moving the mechanical shutoff lever to the “RUN” position. The starting spring in the governor housing pulls the control rack fully forward, beyond the normal maximum fuel position. This aligns the starting groove with the spill port. With the starting groove aligned with the spill port, there is a delay in spill port closure which, in turn, delays the start of injection. Note also that there is no helix in this region of the plunger, so once injection begins, it is not cut off until the plunger reaches the end of its stroke. This provides a very large amount of fuel to aid starting.




18

Delivery Valves

A delivery valve is located above each plunger. The delivery valve serves as a one-way valve which allows fuel under injection pressure to move into the high pressure tubes and prevents fuel from coming back. The valve also serves to rapidly reduce pressure in the injection line once pressure from the plunger has ceased. Rapid pressure reduction is required to ensure the injector valve snaps shut to prevent fuel “dribble,” a condition which can cause carbon formation on the injector tip.

(a) Valve closed

(b) Valve open during fuel delivery



19

Components are identified as follows:

1 Delivery valve holder
2 Spring
3 Valve
4 Valve seat
5 Valve holder


Fuel Injector Assemblies

The job of the injector assembly is to atomize the fuel in order to facilitate proper combustion. The injector must cleanly deliver the fuel into the combustion chamber with a good spray pattern. There must also be a “crisp” start, and end of, injection with no drips either before or after the injection cycle.

The nozzle is housed within a nozzle holder. In order to properly place the fuel charge into the combustion chamber, dowel pins orient the nozzle within the holder, and a clamp ring orients the holder within the engine cylinder head.

Operation of the injection nozzle is as follows:

1 High pressure inlet line
2 Edge-type filter
3 Pressure channel
4 Intermediate disc
5 Nozzle-retaining nut
6 Union nut for fuel-injection tubing
7 Holder body
8 Leak-off port
9 Pressure-adjusting shims
10 Pressure spring
11 Pressure spindle
12 Locating pins (locating the nozzle)
13 Injection nozzle



20


The high-pressure line delivers the fuel charge from the injection pump. Fuel enters the inlet and passes through the edge-type filter. Coarse foreign particles are retained by the filter.

A passage routes fuel through the nozzle holder to the nozzle valve. The nozzle valve is lifted off its seat by the high-pressure inlet fuel, 1, acting on the annulus in the valve.

When the nozzle valve opens, a definite quantity of fuel (determined by the injection pump output for each plunger stroke) is forced out through the orifices. The fuel becomes finely atomized as it is sprayed into the combustion chamber at high velocity. Once fuel flow from the pump ceases, the spring pressure forces the needle valve back onto its seat via the spindle and needle valve stem. Fuel dribble should not occur, as might happen if the nozzle showed excessive wear.

The nozzle assembly is lubricated by a small amount of fuel which seeps between the lapped surfaces of the nozzle and valve which accumulates around the spring.

The leakage fuel, 2, is routed out the nozzle holder through a leak-off connector and returned back to the fuel tank.




21

NOTE: *70 Series art shown in Figure 22.*

Fuel Shutoff Solenoid

The purpose of the fuel shutoff solenoid, 1, is to move the mechanical fuel shutoff lever to the “RUN” position when the key switch is turned on, and to keep the lever in that position while the key switch remains in the “RUN” position. When the key switch is turned “OFF,” the solenoid is de-energized, and allows spring force within the governor housing to move the mechanical shutoff lever to the “FUEL-OFF” position.




22

NOTE: *70 Series art shown in Figures 23 and 24.*

The fuel shutoff solenoid is connected to the tractor electrical system with a 3-wire connector. Wire colors (noted on the TRACTOR harness, NOT the fuel solenoid) are as follows:

Ref	Color	Function	Maximum Current Draw (Amps)
1	Black	Ground	N/A
2	Orange	Pull	60
3	Purple	Hold	0.87



23

When the key switch is first turned to the “RUN” position, power is supplied to both the “pull” and “hold” circuits. After approximately 2 seconds, power to the “pull” circuit is removed, and only the “hold” circuit continues to be powered.


See the Electrical System - Section 55 for further information on electrical operation of the fuel shutoff solenoid.

The solenoid linkage must be free to travel fully. If the mechanical shutoff lever is not moved fully to the “RUN” position, difficult starting or failure to develop full power may occur.

Plumbing

Low-Pressure Fuel Lines
The purpose of the low-pressure fuel lines, 1, is to carry fuel from the tank to the injection pump gallery and to return excess fuel from the pump and injectors to the tank.

High-Pressure Fuel Lines
The purpose of the high-pressure fuel lines, 2, is to carry fuel, under high pressure, from the injection pump to the injector assemblies. These lines are a precise length to provide proper fuel delivery. For this reason, always use the correct line if replacement is required.



24


TESTING AND DIAGNOSIS

The fuel system can be divided into 4 basic components. See the “Description of Operation” section for details on each of these components.

- The low-pressure system consists of the fuel supply tanks, supply (lift) pump, filter assembly, overflow valve, injector leak-off lines, and the associated plumbing. The job of the low-pressure system is to present to the high-pressure pumping elements a supply of clean fuel, with very little entrained air, at a regulated pressure of approximately 1.52 bar (22 PSI). An unrestricted return of excess fuel to tank also must be provided. The low-pressure system also must prevent or “check” the flow of fuel out of the injection pump gallery when the engine is not operating.
- The high-pressure system consists of the pumping elements, delivery valves, fuel injector assemblies, and the lines connecting the pump to the injectors. The job of the high-pressure system is to delivery a measured, atomized charge of fuel into the combustion chamber at the proper time.
- The governor controls high and low idle speeds and attempts to maintain constant engine speed at the various throttle lever positions selected by the operator.
- The fuel shutoff solenoid, by controlling the mechanical shutoff lever on the pump, causes the injection pump to deliver fuel with the key switch in the “run” position and to cease delivery when the key switch is turned to “off.”

LOW-PRESSURE FUEL SYSTEM

NOTE: *70 Series art shown in Figures 25 and 26.*



25

Initial Test

Conduct the following test FIRST. If the system passes this test, along with the leakback test, then the problem is not with the low- pressure fuel system.

Check the system for air ingress, and correct pressure. Required gauges and fittings will be found in Pressure Test Kits FTC213312 and FTC61682.

Install a clear line, with tee, between the filter manifold and the pump gallery inlet. This also will be referred to as the Filter Outlet Pressure Test below. With the engine operating under load, such as on a dynamometer, the fuel stream should be clear, and under a pressure of approximately 1.52 bar (22 PSI).

If insufficient pressure is found, check the following:

FUEL TANK VALVE(S)

Ensure that both the supply and return valves at the lower fuel tank are open.

FILTER INLET AND OUTLET PRESSURE TESTS

Leave the gauge and clear line installed between the filter and pump gallery inlet. Install a second gauge between the supply pump and filter.


Operate the engine at full load. Monitor filter inlet and outlet pressures. Specifications are as follows:

Filter Outlet Pressure . . . . . 1 - 2 bar (15-28 PSI)

Filter Inlet Pressure . . . . . 1 - 2.1 bar (15-30 PSI)

Difference Between Inlet
and Outlet Pressures . . . . . 0.5 bar max. (7 PSI)

If pressure drop across the filter is excessive, first replace the filter element. If pressure drop continues to be excessive, replace the filter base.



26

NOTE: *70 Series art shown in Figure 27.*

Supply Pump Sedimenter

Clean, or replace, the screen in the sedimenter. Be sure that the bowl is sealing well against the housing.


IMPORTANT: *Before loosening or disconnecting any part of the fuel injection system, thoroughly clean the area to be worked on.*

To clean the sedimenter:

1. Remove the sedimenter bowl, 1, from the lift pump, 2. Catch the fuel in a suitable container and dispose of properly.
2. Inspect the O ring, 3, and replace if damaged.
3. Remove the screen, 4, and spring, 5.
4. Clean screen and bowl.
5. Inspect screen and replace if damaged.
6. Install the spring and screen in the bowl.
7. Fill the bowl with clean, fresh fuel.
8. Install the bowl. Hand tighten only.
9. Depress the hand primer on the fuel filter manifold repeatedly until resistance is felt and the sedimenter bowl is full.
10. Start the engine and check for leaks.

NOTE: *A partially plugged filter screen can cause reduced fuel supply to engine. This can cause low power performance.*

IMPORTANT: *If the engine does not start after cranking for 20 seconds, the fuel system must be purged of air.*




27

Supply Pump - Perform Pump Output Test

1. Connect a 0 - 60 PSI gauge to one end of a pressure hose 10 - 12″ long. Connect the other end of the hose to the pump outlet. All air must be out of the system.
2. Crank the engine for 10 seconds with the starter motor (approximately 200 RPM). Supply pump minimum pressure should be 2.0 bar (29 PSI).

IMPORTANT: *The starter motor must crank the engine at normal cranking speed. Use booster batteries if necessary.*


3. If pressure is below the minimum specified above, check the in-tank strainer and supply line from the tank to pump. If no obstruction is found, replace the pump.



28


NOTE: *70 Series art shown in Figure 29.*

Overflow Valve
Temporarily replace the valve with a known good valve. If the overflow valve is at fault, it must be replaced as an assembly.




29

In-Tank Strainer
The strainer can be accessed by removing the inlet fitting. It will be necessary to first drain the fuel tanks. Both tanks drain through the cock at the return fitting.



30

NOTE: *70 Series art shown in Figure 32.*




31

Test for Air Ingress
If air ingress is indicated by foam and bubbles during the initial test, conduct the following test:

1. Disconnect the fuel supply line, 1, and return line, 2, at the fuel tank.
2. Direct the return line to a drain pan.
3. Using an air source regulated to not more the 2.75 bar (40 PSI), pressurize the fuel system at the fuel supply line. Most of the fuel will be forced out of the system and into the drain pan.

NOTE: *This procedure is necessary since air is less viscous (is thinner) than diesel fuel, and air will leak both in and out of a system component where fuel will not.*

4. Once the fuel is purged from the system, shut off the air source.
5. Reinstall the return line to the tank fitting and ensure that the return valve is closed.
6. Using an air source regulated to not more the1.4 bar (20 PSI), pressurize the fuel system at the fuel supply line.
7. Apply liquid soap and water solution to all joints and connections in the fuel system and inspect for leaks.
8. If any leaks are found, take the necessary steps to repair.
9. Reconnect the supply and return lines and prime the system.
10. Start the engine and run it for approximately 10 minutes.



32

NOTE: *70 Series art shown in Figure 33.*

Leakback to Tank with Engine Off
When the engine is shut off, it is important that the injection pump fuel gallery remain full of fuel. If fuel trapped in the gallery is allowed to drain back to the tank, a void develops in the gallery. This void must be refilled with fuel before the engine will start. This situation can cause very difficult cold starting.

The fuel is trapped in the gallery by a one-way check valve in the supply pump and by the overflow valve.

To Test Leakback
Install a clear line several feet long to the supply pump inlet port.

Install a clear line several feet long to the return port on the pump.

Place a container of CLEAN fuel onto the floor, and insert both clear lines into the container.

Start the engine.

You will observe the fuel being drawn out of the container through the supply line and returned through the return line.

Continue to operate the engine until all air is cleared from the system.


Shut off the engine.

Leave the engine shut off for a period of at least 4 hours. Overnight is better.


Using the same principal as the finger over the straw, the clear lines should remain nearly full of fuel.

If the fuel leaks out of the supply line, the problem is with the supply pump which should be replaced.

If the fuel leaks out of the return line, the problem is with the overflow valve which should be replaced.



33



34

HIGH-PRESSURE FUEL SYSTEM

The job of the high-pressure system is to deliver a measured, atomized charge of fuel into the combustion chamber at the proper time.

The high-pressure pumping elements are housed within the injection pump.


IMPORTANT: *Internal repairs to the fuel injection pump* ***must*** *be accomplished through a Bosch authorized Diesel Service Dealer (DSD). The only adjustment that can be accomplished to the pump on-vehicle is low speed idle adjustment.*

Should symptoms arise that indicate a problem with the high-pressure portion of the fuel system, the following procedures should be used.

INJECTION TIMING CHECK


The spring-loaded go/no-go pin, tool number FNH00536-2, 1, can be used to verify correct timing.

The rigid pin, 2, should be used during injection pump installation.




35

1. Remove the fan belt.




36

2. Remove the injection pump timing gear cover.



37


3. Locate the timing pin hole on the front of the injection pump.



38


4. Using a 29 mm (1-1/8″) socket on the bolt at the front of the crankshaft, rotate the engine clockwise, viewed from the front of the tractor, until the timing pin hole is near the 8 o'clock position.

NOTE: *This assures that #1 cylinder is coming up near TDC on the compression stroke.*



39

5. Continue to rotate the engine clockwise until the timing marks on the front pulley align with the pointer according to the following text and chart.



40

NOTE: *All the 70A Series have emissionized static timing.*

The static timing for the 170 hp (North American specification only) and 190 hp emissionized engines is different to the earlier, non-emissionized versions.

Model Type	HP	Non-Emissionized Static Timing (deg. BTDC)	Emissionized Static Timing (deg. BTDC)
8670*	170	24	18
8770	190	21	18
8870	210	16	16
8970	240	16	16

***** North American specification only.

The emissionized engines were introduced into production on the following tractor serial numbers. The emissionized 8670 and 8770 models can be visually identified by the fitment of an inter-cooler:

8670 – D411682

8770 – D408877

8870 – D409270


8970 – D409255

6. Thread the go/no-go timing pin (spring-loaded) FNH00536-2 into the pump hub.

CAUTION

The engine must never be rotated while the timing pin is installed. Engine rotation, even carefully by hand, will both destroy the timing pin and make removal difficult.


NOTE: *The hole should be in the area of 8 to 10 o'clock position. If the pin is inserted at any other location it can catch on the pump timing plate.*



41

7. If the pin anvil engages the hole in the pump timing plate, then the injection pump is in time and the engine can be reassembled. If the pin anvil will not engage the pump timing plate, then the pump drive gear must be removed and the rigid pin used.


   Use of the rigid pin can be found in the “Disassembly and Reassembly” section, under “Injection Pump Installation.”



42

FUEL INJECTOR NOZZLE CHECK, ENGINE RUNNING

1. Operate engine at intermediate speed and no load.
2. Slowly loosen the fuel pressure line at one of the nozzles, 1, until fuel escapes at the connection (fuel not opening the nozzle).
3. If engine speed changes, the injection nozzle is probably working satisfactorily.
4. If engine speed does not change, a nozzle is faulty and must be checked and repaired (or replaced).



43

INJECTOR ASSEMBLY BENCH TESTING

Remove the injector assemblies. Removal and reinstallation information is found later in this chapter. All tests are accomplished using Tester Tool No. FNH01721, Adapter Tool No. FNH00041, and a container, such as a glass beaker.

⚠ WARNING ⚠

The spray from an injector tester can pierce human skin, with fatal results. When an injector is spraying, the nozzle holder should be turned away from the operator and any other persons.


The spray is flammable. Ensure that no exposed light bulbs or ignition sources are in the area. Do not generate excessive vapor.

NOTE: *If the injector assembly fails to pass any of the following tests, the assembly must be taken to an authorized Bosch Diesel Service Dealer for repairs and adjustment.*

PRELIMINARY SETUP PROCEDURE

1. Fill the injector tester with a calibrating type fuel oil. Do not use diesel fuel, as gummy deposits can form over a period of time. Also vaporized diesel fuel is more flammable than calibrating fluid.
2. Prime the tester until oil is emitted from the tester line, then connect the injector.
3. Ensure the knob, 1, on the tester is screwed in to prevent the gauge being over pressurized if the nozzle is seized.
4. Pump the tester and check that the nozzle is free to open (i.e., not seized shut). Open the pressure gauge valve, 1, and commence injector testing. If the nozzle is blocked or the needle jammed, take the injector assembly to an authorized Bosch Diesel Service Dealer for repairs, or replace the injector assembly.

IMPORTANT: *Nozzle tester should be checked periodically for accuracy.*



44

PERFORM OPENING PRESSURE TEST

1. Slowly increase the pressure until the nozzle opens, and fuel sprays from the tip. Opening specifications follow.

   A new nozzle, or a used nozzle with a new spring should open at approximately the following pressures. A used nozzle that has been rebuilt with a new spring and/or valve should be reset to same pressures as a new nozzle. New nozzle opening pressures are:


Tractor Model	Opening Pressure
8670/8670A	241 bar (3500 PSI)
8770/8770A	241 bar (3500 PSI)
8870/8870A	255 bar (3700 PSI)
8970/8970A	255 bar (3700 PSI)

On nozzles which have been in service, the spring and spring seat will have taken a normal set. In this case, opening pressure is satisfactory if it meets or exceeds the used nozzle minimum opening pressure given below, but does not exceed the new opening pressure given previously. Used nozzle minimum opening pressures are:

Tractor Model	Opening Pressure
8670/8670A	213 bar (3100 PSI)
8770/8770A	213 bar (3100 PSI)
8870/8870A	227 bar (3300 PSI)
8970/8970A	227 bar (3300 PSI)

The difference in nozzle opening pressures between cylinders in an engine should not exceed 3.5 bar (50 PSI).


Spray pattern should be uniform and well-adjusted, 1. A stringy non-uniform or split stream, 2, is unacceptable.



45

PERFORM NOZZLE SEAT LEAKAGE TEST

1. Wipe nozzle dry.
2. Apply a pressure of 20 bar (285 PSI) BELOW the opening pressure.
3. Hold the pressure for ten seconds. Ideally the tip should remain dry. However, if a drop forms but DOES NOT fall, the nozzle passes the test.




46

PERFORM CHATTER AND SPRAY PATTERN TEST

1. The injection nozzle should chatter very softly and only when hand lever movement is very rapid (four to six downward movements per second). Failure to chatter may be caused by a binding or bent nozzle valve.
2. Until the chattering range is reached, the test oil emerges as non-atomized streams. When lever movement is accelerated, sprays should be very broad and finely atomized.

   If the injector passes the tests, reinstall in the engine. If the injector fails any of the tests, take the injector to an authorized Bosch Diesel Service Dealer for repair.




47

SURGING

If surging occurs:

1. Adjust the low speed idle with the low idle screw, 1, and the low idle auxiliary adjustment screw, 2, as described in “Adjustments” (later in this chapter).
2. Check the low-pressure fuel system pressure, and for air ingress, as previously described.




48

NOTE: *70 Series art shown in Figures 49 and 50.*

FUEL SHUTOFF DIAGNOSIS

In cases where the proper function of the fuel shutoff solenoid is suspect, the following steps will diagnose both the solenoid and the electrical feed to the pull coil terminal, hold coil terminal, and common ground terminal.

Ref	Color	Function
1	Black	Ground
2	Orange	Pull
3	Purple	Hold




49

SHUTOFF SOLENOID SPECIFICATIONS

Specifications:	@ Rated voltage 12V and rated temp. 20° C (68° F)
Pull current:	60 amps
Hold current:	0.87 amps
Pull rating:	93.4 N (21 lbs) @ 1″ stroke
Hold rating:	178 N (40 lbs)
Plunger stroke:	25.4 mm (1″) maximum

PRELIMINARY CHECKS

1. Place the transmission in NEUTRAL and set the parking brake.
2. Check the battery voltage. Must be 12 volts or higher.
3. Turn the key switch to the “run” position.
4. Verify that the solenoid plunger and pump control lever, 1, move freely the full range, with no evidence of binding or sticking.
5. With key switch in the “off” position, the control lever will be in the down position, 2.
6. Check the fuel shutoff solenoid linkage adjustment as described later. If readjusted, try restarting the engine while observing the solenoid for proper function.
7. Inspect the electrical connections between the solenoid and harness to ensure good positive contacts, and not sign of rust or corrosion.



50


NOTE: *70 Series art shown in Figures 51 and 52.*

CHECKING ELECTRICAL FEED

Ref	Color	Function
1	Black	Ground
2	Orange	Pull
3	Purple	Hold

1. Attach the positive lead of the voltmeter to the “hold coil terminal” of the solenoid. Attach the negative lead of the voltmeter to the “common ground terminal” of the solenoid. Turn the ignition switch to the “RUN” position. The voltmeter should read a minimum of 9 volts. Less than 9 volts indicates a bad circuit. Also, there should be a 0.87 amp current draw.
2. Attach the positive lead of the voltmeter to the “pull coil terminal” of the solenoid. Attach the negative lead of the voltmeter to the “common ground terminal” of the solenoid.


   Turn the key switch to the “RUN” position. A voltage of at least 9 volts should be present for approximately two seconds, and the solenoid plunger should retract. Also there should be a 60.3 amp draw.
3. Attach the voltmeter leads between the solenoid “common ground” terminal and a good ground on the frame. While the solenoid is in the “PULL” and “HOLD” positions, the voltmeter should read 0 volts. If there is voltage, the ground circuit needs to be checked.



51

Verify Linkage Adjustments

1. Turn the key switch to the “RUN” position. The solenoid should fully retract.
2. Remove the solenoid rod from the mechanical fuel shutoff lever.
3. Pull the mechanical fuel shutoff lever to the full “RUN” position.
4. It should now be possible to insert the fuel shutoff solenoid ball joint over the mechanical shutoff lever pin.
5. If necessary, adjust the fuel shutoff solenoid rod in order to accomplish step 4.



52

ADJUSTMENTS

NOTE: *70 Series art shown in Figure 53.*

NOTE: *70A Series art shown in Figure 54.*

BLEEDING THE FUEL SYSTEM

To bleed the system, use the following procedure:

NOTE: *There must be a minimum of 19 L (5 gal) of fuel in the tank to ensure that priming can be achieved.*

1. Open the bleed screw, 1, on the fuel filter manifold. (70 Series only)
2. Pump the hand primer, 2, until fuel free of air bubbles escapes from the bleed screw. (70 Series only)
3. Close the bleed screw. (70 Series only)
4. Pump the hand primer, 2, 30 pumps.
5. Crank the engine for a a maximum of 30 seconds. While cranking, depress the foot accelerator to the floor.

IMPORTANT: *Do not crank the starter continually for more than 30 seconds at a time. Let the starter cool for two minutes between attempts.*


NOTE: *Keep the accelerator to the floor during rough running until the engine is running smoothly, then throttle back to idle.*

6. Repeat steps 4 and 5 if the engine starts then stalls.


NOTE: *Repeat steps 1 through 6 and bleed the fuel system if the engine does not start.*

⚠ CAUTION ⚠

Check the bleed screw after the engine starts to ensure there are no fuel leaks.



53




54

NOTE: *70 Series art shown in Figures 55 and 56.*

ADJUSTMENT OF FOOT AND HAND THROTTLE CABLES


Set the foot throttle cable jam nuts, 1, at the throttle bracket bulkhead so that the throttle lever contacts the high-idle stop, 2, when the foot throttle is fully depressed.



55

Set the hand throttle cable jam nuts, 1, at the throttle bracket bulkhead so that the throttle lever contacts the high-idle stops, 2, when the hand throttle lever is moved to the wide-open position.


Recheck the foot throttle cable and correct, if necessary, by repeating the step above.



56

ADJUSTMENT OF HIGH IDLE SPEED

High idle speed adjustment is sealed. High idle can be adjusted only by an authorized Bosch Diesel Service Dealer.




57

ADJUSTMENT OF LOW IDLE AND ANTISURGE

NOTE: *Before proceeding, make certain that the foot and hand throttle cables are properly adjusted, as previously described.*

NOTE: *This is the only adjustment that can be done to the fuel injection pump by a technician NOT authorized by Bosch.*

1. Release any operator pressure on the foot throttle pedal, and ensure that the hand throttle lever is pulled fully rearward to the low idle position.
2. Back off the low idle auxiliary adjustment screw, 2.
3. Adjust the low idle screw, 1, so that the engine speed is 870 ± 10 RPM.
4. Thread the low idle auxiliary screw in until low idle speed reaches 880 ± 10 RPM.
5. If surging still exists, repeat steps 2, 3, and 4, EXCEPT that in step 3, adjust the low idle screw to 850 ±10 RPM instead of 870 RPM.
6. Run the throttle up to high idle and then back down to the low idle position to confirm correct speed settings.




58

REMOVAL AND INSTALLATION

FUEL LIFT PUMP

NOTE: *70 Series art shown in Figure 59.*



59

Removal

1. Remove the fuel inlet and outlet lines from the lift pump.
2. Remove the three nuts which mount the lift to the fuel injection pump.
3. Remove the lift pump.
4. Clean all old gasket material from the lift pump and the fuel injection pump mating surfaces.
5. If required, remove the fuel inlet tube fitting. Discard the seal ring.

Installation


1. If needed, rotate the crankshaft so the low side of the fuel injector pump camshaft lobe is facing out.
2. Install the lift pump gasket onto the fuel injection pump. Make sure the gasket mating surfaces are clean.
3. Install the lift pump onto the fuel injection pump.
4. Place the mounting nuts on the studs and tighten to 7 - 9 N·m (5 - 7 ft lbs).
5. Start and stop the engine to check proper operation of the solenoid.
6. Install the inlet and outlet lines on the fuel lift pump. Tighten until the coupling contacts the body shoulder 7 N·m (5 ft lbs).
7. Loosen the inlet line to the fuel injection pump. Operate the hand primer on the lift pump to displace any air that might be in the fuel lines. Tighten the connection.
8. Start the engine and run it for approximately two minutes. Observe all connections for fuel leaks.
9. Stop the engine and check for oil leakage from the lift pump gasket.

NOTE: *70 Series art shown in Figures 60 and 61.*

FUEL SHUTOFF SOLENOID

Removal


1. Disconnect the wire connector from the fuel shutoff solenoid.
2. Remove the solenoid plunger linkage from the pump run/stop lever, 1.
3. Remove the two cap screws which hold the fuel shutoff solenoid to the engine block.



60

Installation

1. Attach the fuel shutoff solenoid to the engine block with two cap screws.
2. Torque cap screw to 5 - 7 N·m (42 - 60 in. lbs).
3. Attach the solenoid plunger linkage to the pump run/stop lever, 1.
4. Connect the wire connector to the fuel shutoff solenoid, 1.
5. Check the fuel shutoff solenoid for proper adjustment.
6. Start and stop the engine to check for proper operation of the solenoid.



61


FUEL INJECTION PUMP

NOTE: *Before removing any fuel lines, clean the exterior of the fuel injection pump with clean fuel oil or solvent to help prevent the entry of dirt or other contamination. The area can be steam cleaned (which is probably the best method of getting the area clean), but it can only be done when the engine is cold and shut off.*

ATTENTION: *Do not wash or steam clean the engine while it is running or still hot from running. Serious damage to the injection pump could occur.*


Removal

1. Disconnect the negative battery cables from the battery and/or batteries.
2. Remove the fan guard and belt.




62

3. Remove the injection pump timing gear cover.



63


4. Locate the timing pin hole on the front of the injection pump.



64


5. Using a 29 mm (1-1/8″) socket on the bolt at the front of the crankshaft, rotate the engine clockwise, viewed from the front of the tractor, until the timing pin hole is near the 8 o'clock position.

NOTE: *If the injection timing is correct initially, the timing pin hole will be in the 8 to 9 o'clock position when the #1 cylinder is at approaching TDC on the compression stroke.*



65

6. Continue to rotate the engine clockwise until the timing marks on the front pulley align with the pointer according to the following chart.



66

NOTE: *All the 70A Series have emissionized static timing.*

The static timing for the 170 hp (North American specification only) and 190 hp emissionized engines is different to the earlier, non-emissionized versions.

Model Type	HP	Non-Emissionized Static Timing (deg. BTDC)	Emissionized Static Timing (deg. BTDC)
8670*	170	24	18
8770	190	21	18
8870	210	16	16
8970	240	16	16

* North American specification only.

The emissionized engines were introduced into production on the following tractor serial numbers. The emissionized 8670 and 8770 models can be visually identified by the fitment of an inter-cooler:

8670 – D411682


8770 – D408877

8870 – D409270

8970 – D409255

NOTE: *70 Series art shown in Figures 67 and 68.*

7. Remove the four cap screws, 1, retaining plate, 2, and drive gear, 3, from the front of the injection pump.




67

8. Remove the oil feed, 1, and fuel lines, 2. Cap all the lines and openings to prevent the entry of dirt or contaminants.

CAUTION

Use two wrenches on these high pressure lines to prevent distorting or rotating the pumping element.


9. Remove the tube assembly from the boost control.
10. Disconnect the throttle and fuel shutoff linkage, 4.



68

NOTE: *70 Series art shown in Figure 69.*


11. Remove the pump support bracket from both the fuel injection pump and the engine mounting bracket. This will allow for easier turning of the pump when it is loosened.
12. Remove the five bolts from the rear of the adapter plate.
13. Slide the pump toward the rear of the engine and remove it from the machine.



69

Installation


1. With the pump on the bench, rotate the injection pump clockwise, viewed from the front, until the threaded hole in the pump drive flange aligns with the pump timing plate.




70

2. Thread in the rigid pin, Tool No. FNH00536, 1, until it bottoms.

   Install new O ring, 2, on pump mounting flange.



71




72

1. A Type Fuel Injection Pump
2. Pump Retaining Nuts
3. Pump Retaining Bolts
4. Cylinder Block Bracket
5. Cylinder Block Bolts
6. Bracket Bolts
7. Pump Support Bracket
8. Pump Crankcase Oil Fill Plug

Models 8670/8670A and 8770/8770A

NOTE: *Initially tighten hardware finger tight during fuel injection pump installation*

3. Locate A type pump, 1, into position on the engine.
4. Install the four nuts, 2, from the rear of the injector pump adapter plate.
5. Install the two hex bolts, 3, that retain the injection pump to the pump support bracket, 7.
6. Install cylinder block bracket, 4, with two bolts, 5.
7. Install two bolts, 6, securing the two brackets together.



73

1. B Type Fuel Injection Pump
2. Pump Retaining Nuts
3. Pump Retaining Bolts
4. Cylinder Block Bracket
5. Cylinder Block Bolts
6. Bracket Bolts
7. Pump Support Bracket
8. Pump Crankcase Oil Fill Plug

Models 8870/8870A and 8970/8970A

NOTE: *Initially tighten hardware finger tight during fuel injection pump installation.*

3. Locate B type pump, 1, into position on the engine.

4. Install four nuts, 2, from the rear of the injector pump adaptor plate.

5. Install the two hex bolts, 3, that retain the injection pump to the pump support bracket, 7.

6. Install cylinder block bracket, 4, with two bolts, 5.

7. Install two bolts, 6, securing the two brackets together.

8. Tighten the following bolts previously installed in the installation procedure:
   a. Four nuts, 2, in rear of injection pump adaptor plate 27 - 34 N·m (20 - 25 ft lbs).
   b. Two hex-head bolts, 3, retaining the injection pump to the pump support bracket, 47 - 61 N·m (35 - 40 ft lbs), see step 9.
   c. Bolts for injection pump support and engine mounting bracket, 5 and 6, 27 - 35 N·m (20 - 26 ft lbs).
9. Add 450 ml (1.0 pt) of crankcase oil to the pump assembly through the fill plug, 8. Tighten the plug to 10 - 12 N·m (7 - 9 ft lbs).


NOTE: *Premature pump failure may result if the pump is not pre-lubricated.*

10. Reconnect the fuel shutoff solenoid.
11. Attach the throttle linkage and adjust if necessary.
12. Install the oil feed and fuel lines. Do not remove caps from the lines until just before they are to be installed. Observe the torque specifications.
13. Install the boost control tube assembly to the boost control.
14. Install all the fuel lines. Use two wrenches on the fuel lines to prevent accidental rotation of the pumping element.
15. Make sure all connections are complete and tightened to specification.

NOTE: *It may be necessary to bleed the fuel system if the engine fails to start.*

16. Connect the battery cables.
17. Then start the engine and check for leaks.
18. Replace fan belt, guard and hood trim panel.

NOTE: *70 Series art shown in Figure 74.*



74

FUEL INJECTION LINES

In the case of damage to a single fuel injection line, do not attempt to remove it by itself. Always remove the fuel injection lines as a set, 2, it is much easier to get them off the engine, and it helps to prevent damaging the injection lines that are still good.

LOW-PRESSURE FUEL INJECTION LINES


Removal

NOTE: *Before removing any fuel lines, clean the exterior of the fuel lines with fuel oil or solvent to prevent the entry of dirt into the fuel system when the fuel lines are removed. Blow dry with compressed air.*

1. Disconnect the battery ground cables from all batteries.
2. Disconnect and remove the low-pressure fuel line assembly, 1, including the filter. Cap the lines as they are removed. Inspect the rubber spacers at the ends of the lines for distortion. Replace as required.
3. If required, remove the overflow valve from the pump return tube. Remove and discard the overflow valve seal.
4. If required, remove the inlet fitting and seal from the pump. Discard the seal.

Installation

1. Install the low-pressure fuel lines, 1, and filter assembly back on the engine. Make sure the tubes have fully seated into their correct fittings before tightening the retaining nuts to specification.
2. If removed, install the overflow valve with a new seal to the pump return tube. Tighten the valve to 30 - 40 N·m (22 - 30 ft lbs).
3. If removed, install the fuel inlet fitting with a new seal to the pump. Tighten to 30 - 40 N·m (22 - 30 ft lbs).
4. Connect the battery ground cable to both batteries.
5. Run the engine and check for leaks.



75

HIGH-PRESSURE FUEL LINES

NOTE: *70 Series art shown in Figure 75.*

Removal

1. Remove the low-pressure fuel lines following the procedures described in this chapter.
2. Disconnect the fuel injection lines at the injectors. As the line is removed, use a plastic cap to prevent the entry of dirt into the system.
3. Disconnect the fuel lines at the fuel injection pump, 1. Cap each line and pumping element as the line is removed to prevent the entry of dirt into the system. Use two wrenches on the lines to prevent accidental rotation of the pumping element.
4. Detach the bracket, 1, holding the fuel injection line assembly to the intake manifold.
5. Carefully wiggle the fuel injection lines, 2, out from under the intake manifold and remove them from the engine. Start from the back and move toward the front of the engine.

Once removed from the engine, individual fuel lines can be removed from the assembly for replacement. Keep in mind when ordering parts that each line is different and cannot be interchanged; therefore, order lines individually for the particular cylinder the line goes to.

Installation

1. Make sure the clamps, 4, holding lines together are tight.

NOTE: *High-pressure fuel lines must be installed as a set. It is much easier than installing them individually.*

2. Wiggle the high-pressure fuel injection lines into position on the engine. Start from the back and go toward the front of the engine.
3. Install the injection lines, 2, onto the injection pump, 3, and tighten the nuts to 22 - 27 N·m (16 - 20 ft lbs). Tighten the bracket, 1, holding the high-pressure fuel lines to the intake manifold. Use two wrenches to tighten the lines to prevent accidental rotation of the pumping element.


4. Connect the high fuel injection lines to the fuel injectors one at a time starting with cylinder No. 1.

NOTE: *Do not remove the caps from the fuel lines or components until they are to be connected. This will help prevent the entry of dirt into the system.*

5. Tighten the fuel injection line to injector nuts, 1, to 22 - 27 N·m (16 - 20 ft lbs).
6. Install the low-pressure fuel lines and filter assembly back on the engine. Tighten the nuts to specification.
7. Connect the battery ground cables to both batteries.
8. Run the engine and check for leaks.
9. If necessary, purge the high-pressure fuel lines of air by loosening the connector one-half to one turn and cranking the engine until solid fuel, free from bubbles, sprays from the connection.

⚠ WARNING ⚠


Wear safety glasses or a protective face shield when working with high-pressure fuel. Keep eyes and hands away from nozzle spray. Fuel spraying from the nozzle under high pressure can penetrate the skin and cause blood poisoning. Medical attention should be provided immediately in the event of skin penetration.



70-150-2232

76

INJECTOR LEAK-OFF LINE




77

Removal

1. Remove the fuel injector line, 1. Remove banjo bolts, 3, holding leak-off line, 4, to the fuel injector, 2. Start at No. 1 injector and work back.

2. Store banjo bolts in a clean place to avoid contamination. Discard washers, 5, 8 and 9. New washers, 5, 8 and 9, must be used for reassembly.



78

Installation

1. Position the leak-off line on the engine at the injectors.
2. Insert the banjo bolt, 3, into the No. 1 injector, 2, first. Make sure there is a washer, 5, on both sides of the banjo fitting; otherwise, the connection will leak. Start the banjo bolt, 3, into the injector. Do not tighten it at this time.

ATTENTION: *Be careful to avoid cross threading the banjo bolt into the nozzle body.*

3. Install the rest of the banjo bolts and new washers working from front to back.
4. Beginning at injector No. 1, tighten the banjo bolts to 5.6 - 6.8 N·m (50 - 60 in. lbs). Tighten the support bracket, 7, using the existing manifold attaching bolt, 6, to 31 - 38 N·m (23 - 28 ft lbs).
5. Install the fuel injector lines.
6. Start the engine and check the connection for fuel leaks.


NOTE: *70 Series art shown in Figures 79 and 80.*

FUEL FILTER


Removal and Installation

A single fuel filter/water separator is located on the side of the engine. The filter is a spin-on type and is replaced as part of the scheduled maintenance.

1. Hold the filter, 1, so it cannot turn.
2. Unscrew the plastic water separator bowl, 2, from the filter. Do not damage the bowl or lose the O ring, 3. Catch the fuel in a suitable container and dispose of properly.
3. Remove the filter, 1. Dispose of filter properly.
4. Clean the filter mount surface, 2.
5. Install the O ring and plastic water separator bowl on the new filter. Hand tighten only.
6. Fill the filter with clean, fresh, diesel fuel.
7. Coat the filter seal, 3, with diesel fuel.
8. Install the filter until the seal contacts the mount, then tighten an additional 1/2 turn.
9. Depress and release the hand primer, 4, until resistance is felt indicating the filter is full.
10. Start the engine and check for fuel leaks.



79




80

NOTE: *70 Series art shown in Figure 81.*

FUEL FILTER MANIFOLD

Removal

1. Remove the filter, 1, from the fuel filter manifold with a suitable oil filter wrench.
2. Disconnect the low-pressure inlet and return lines, 2, from the ports on the rear of the fuel filter manifold, 3, and inspect the rubber spacers, 4, for distortion or cracks and replace as required.
3. Remove the two bolts, 5, retaining the fuel filter manifold to the intake manifold, and remove the fuel filter manifold.



81

Installation

1. Position the fuel filter manifold on the intake manifold and install hardware. Tighten to 27 - 34 N·m (20 - 25 ft lbs).
2. Install the lines in their respective ports in the fuel filter manifold.
3. Install new fuel filter. Refer to “Fuel Filter Removal and Installation” earlier in this chapter.
4. Bleed the system as required. Refer to “Bleeding the Fuel System” earlier in this chapter.

INJECTION NOZZLES

Removal and Reinstallation

⚠ WARNING ⚠

Diesel fuel escaping under pressure can penetrate the skin causing serious injury.

Do not use your hand to check for leaks. Use a piece of cardboard or paper to search for leaks. Wear eye protection.

Stop the engine and relieve pressure before connecting or disconnecting lines.

Tighten all connections before starting the engine or pressurizing lines.


If any fluid is injected into the skin, obtain medical attention immediately or gangrene may result.

IMPORTANT: *Before loosening or disconnecting any part of the fuel injection system, thoroughly clean the area to be worked on.*

IMPORTANT: *Remove and replace one injector at a time. This will reduce the chance of dirt entering the engine through the injector opening.*

IMPORTANT: *Place caps on all open lines or injector openings to prevent the entry of dirt.*

1. Disconnect the high pressure injector line, 1, from the injector, 2.
2. Remove the leak-off line retaining bolt, 3.
3. Remove the leak-off line, 4, and discard the two copper washers (one on either side of the banjo fitting).



82

4. Remove the injector retaining bolts and washers, 1, and hold-down clamp, 2.
5. Turn the injector, 3, clockwise to loosen it, then remove from the head.
6. Remove the copper sealing washer, 4, from the injector. If the washer is not on the injector it has remained in the head and must be extracted. Discard the copper washers.

   Make sure the injector cavity is clean of carbon before installing new copper washer.
7. Remove the cork dust seal, 5, from the injector.
8. Install a new cork dust seal on the replacement injector.
9. Install a new copper washer on the end of the injector.
10. Install the injector.
11. Install the hold-down clamp.

NOTE: *Be sure to install the clamp with the raised side facing up.*


12. Install the retaining bolts and washers. Torque the bolts evenly to 22 N·m (17 ft lbs).
13. Install the leak-off line using new copper washers, 6, on either side of the banjo fitting.
14. Torque the leak-off line retaining bolt, 7, to 4.5 N·m (40 in. lbs).
15. Install the high pressure line and tighten the connector to 24 N·m (18 ft lbs).
16. Repeat the process on the remaining injectors.
17. Bleed the fuel system as detailed earlier in this chapter.
18. Start the engine and visually inspect for leaks.

    The injectors which were removed should be serviced by an authorized dealer and retained for use at the next service interval.

NOTE: *Unauthorized modification or adjustment of fuel injection equipment outside specification will invalidate the warranty.*

⚠ WARNING ⚠

Wear safety glasses or a protective face shield when working with high-pressure fuel. Keep eyes and hands away from nozzle spray. Fuel spraying from the nozzle under high pressure can penetrate the skin and cause blood poisoning. Medical attention should be provided immediately in the event of skin penetration.



83

SECTION 10 – ENGINE

Chapter 5 – Engine Removal

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Engine Removal	4
	Engine Installation	8

SPECIFICATIONS

Engine size	7.5 L (456 in.^{3})
Engine weight	738 kg (1625 lbs)
Cylinders, bore x stroke	6, 112 mm x 127 mm (4.4″ x 5″)

Coolant capacity:	8670, 8770	8670/8670A, 8770/8770A	25 L (6.6 U.S. gal.)
	8870, 8970	8870/8870A, 8970/8970A	26.4 L (7 U.S. gal.)

Torques

Starter mount retainers	55 N·m (41 ft lbs)
Engine to transmission bolts (top)	488 N·m (360 ft lbs)
Engine to transmission bolts (center)	240 N·m (177 ft lbs)
Engine to transmission bolts (bottom)	55 N·m (41 ft lbs)
Fan mount bolts to pulley	55 N·m (41 ft lbs)
Air-conditioner compressor	54 N·m (40 ft lbs)
Side rail bolts	528 N·m (390 ft lbs)

DESCRIPTION OF OPERATION

The tractor engine is mounted to the front surface of the transmission. The engine is not attached or supported at the front bolster. The axle and front bolster are connected to the transmission by the use of side rails.


The engine can be removed for major service without separating the transmission from the front axle. A central engine lift point is provided to remove the engine with a suitable hoist. Enough clearance is provided to remove the engine without removing the radiator.

DISASSEMBLY AND REPAIR

ENGINE REMOVAL


If major engine repair is required, the engine assembly can be removed from the tractor as follows:

1. Park the tractor on a level surface and apply the parking brake. Ensure that there is a clear area to use a lifting hoist to lift the engine from the tractor.
2. Remove the battery cover and the negative battery cables, 1.
3. Remove the engine hood as described in this section, Section 90, Chapter 2, “Hood Removal.”
4. Remove the left hood access door and hinge mount.




1

5. Remove the exhaust pipe, 1, from the right side of the tractor and the hood access door, 2, and hinge mount.




2

6. Drain the engine coolant into a suitable container using the drain tap at the bottom of the radiator.
7. Remove the fan shields, 1, and the fan assembly, 2.
8. Remove all hoses, 3, from the front of the engine to the radiator.



3


9. Turn the cab heater valves, 1, off and disconnect the hoses from the front and rear of the intake manifold.



4


NOTE: *70 Series art shown in Figure 5.*

10. Remove the starter, 1, from the right rear of the engine. A 16 mm curved obstacle wrench is required to remove the inner retaining nut. The fuel filter, 2, may have to be removed for better access to the starter.
11. Remove the throttle cables, 3, from the injection pump on the right side of the engine.
12. Remove the fuel supply and return lines, 4, from the right side of the engine.




5

13. Remove the cab doorsill plates, then the front floor mats and the center floor cover to gain access to the two transmission to engine retaining bolts.




6

14. Remove the intercooler supply, 1, and return tube, 2.




7



8

15. Remove the air-conditioner compressor and hoses from the engine.

NOTE: *DO NOT disconnect the hoses or discharge the system.*




9

NOTE: *70 Series art shown in Figure 10.*

16. If additional air-conditioner hose clearance is required to clear the engine, remove the air-conditioner condenser, 1.


NOTE: *DO NOT disconnect the hoses or discharge the system.*

17. Remove the air cleaner inlet horn, 2.



10


18. Disconnect the front main harness from the rear main harness (C008 connector), 1, above the batteries.



11


19. Attach a suitable lift to the center attaching point in the upper engine frame.

NOTE: *Removal of the transmission and rear axle oil cooler lines may be required for additional clearance.*




12

20. Remove the two top transmission to engine bolts, 1, from inside the cab.
21. With the engine weight supported with a hoist, carefully remove the two lower bolts, 3, and the four center engine to transmission retaining bolts, 2.



13


22. Pull the engine forward and up to clear the transmission and side frame rails.
23. Place the engine in a stand or on suitable blocks to allow further disassemble and repair of the engine.



14

ENGINE INSTALLATION

1. Installation of the engine is the reverse of removal.
2. Ensure that the engine is properly aligned without damage to wiring, lines and fittings during installation.
3. Torque all retaining bolts as indicated in the “Specifications” portion of this chapter.



15

SECTION 10 – ENGINE

Chapter 6 – Fuel Tank Removal

CONTENTS

Section	Description	Page
10 000	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Lower Tank Removal	4
	Lower Tank Installation	5
	Top Tank Removal	6
	Top Tank Installation	6

SPECIFICATIONS

Tank material	Plastic with steel frame
Tank capacity	Lower - 246 L (65 U.S. gal.) Upper - 170 L (45 U.S. gal.)

Torques

Tank mount to transmission bolts		115 N·m (85 ft lbs)
Lower tank retaining strap bolts:	large	115 N·m (85 ft lbs)
	small	64 N·m (47 ft lbs)
Top tank retaining strap bolts		64 N·m (47 ft lbs)
Cab step bolts		64 N·m (47 ft lbs)

DESCRIPTION OF OPERATION


The tractor fuel system is supplied by two fuel tanks. The lower tank is mounted on the left side of the transmission at the left steps, and the top tank is mounted to the bottom rear of the cab.

To make repairs to the components on the left side of the rear axle, removal of the lower fuel tank is required. The tank must also be removed prior to removing the cab.

DISASSEMBLY AND REPAIR


LOWER TANK REMOVAL

1. Remove the left cab step assembly.




1

2. Close the supply, 2, and return, 1, valves.
3. Open the drain valve, 3, and drain the fuel into an approved container.
4. Disconnect the fuel lines at the shutoff valves.




2

5. Remove the fuel tank front, 2, and rear, 1, lower support pins.




3

6. Disconnect the top to lower fuel tank hose at the top rear of the lower tank.




4

7. Support the fuel tank on a floor jack. Raise and disconnect the tank from the upper support pins.
8. Carefully lower the tank assembly 10 mm (3″).



5

9. Disconnect the fuel sender, 1, (white) and work light, 2, (black) connectors located at the top front of the fuel tank and lower the tank from the tractor.
10. Remove the mount brackets from the tank by removing the retaining straps. Note the large center bolt and spacer.
11. Cap all tank openings and store the tank in a suitable location.




6

LOWER TANK INSTALLATION

1. The tank is installed in the reverse order of disassembly. Torque the retaining straps to 64 N·m (47 ft lbs). The center bolt and spacer is torqued to 115 N·m (85 ft lbs).

TOP TANK REMOVAL

1. The top tank can only be removed after the cab has been removed. See Section 90, Chapter 3 - “Cab Removal” in this manual for details.
2. With the cab removed and supported, remove the tank vent connection, 1, from the right rear corner of the tank.




7

3. Carefully loosen the four tank attaching straps and lower the tank from the bottom of the cab.

TOP TANK INSTALLATION

The tank is installed in the reverse order of disassembly. Torque the retaining straps to 64 N·m (47 ft lbs).



8

SECTION 21 - TRANSMISSION

Chapter 1 - Operation and Overview

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Powershift Transmission	2
	Gear Ratios	2
	Ground Speed	3
	Electrical System	5
	Description of Operation	6
	Transmission Housing	7
	Powershift Transmission Controls	8
	Digital Display	8
	Inching Pedal	9
	Starting the Engine and Moving Forward	10
	Starting the Engine and Moving in Reverse	11
	Shuttle Operations	12
	Speed Matching	13
	Auto Shift	14
	Creeper Gears (optional)	15
	Programmable Upshift - Downshift	15
	Transmission Components	17
	Clutches	17
	Speed Clutches	17
	Directional Clutches	21
	Clutch Engagement	22
	Troubleshooting and Diagnosis	33

SPECIFICATIONS

POWERSHIFT TRANSMISSION

Type ..... 16 forward and 9 reverse speed, using helical cut gears and multi-plate wet clutches.

Control System ..... Electrohydraulic with single lever and inching pedal and Electronic Management System

GEAR RATIOS

(F=Forward R=Reverse)
U=Upshift ratio, D=Downshift ratio for F8 and F9

F1	9.144		F9-U	2.564		R3	6.773
F2	7.737		F9-D	2.566		R4	5.731
F3	6.612		F10	2.193		R5	4.898
F4	5.772		F11	1.914		R6	4.275
F5	4.884		F12	1.620		R7	3.618
F6	4.174		F13	1.384		R8	3.091
F7	3.546		F14	1.176		R9	2.626
F8-U	3.000		F15	0.995		R10	2.222
F8-D	3.033		F16	0.850		R11	1.899

GROUND SPEED - 8670/8670A WITH 16X9 POWERSHIFT TRANSMISSION (18.4 - 42 TIRES)

FORWARD GEARS

Gear Ratio	1500 engine RPM		1900 engine RPM		2100 engine RPM	
	MPH	(KPH)	MPH	(KPH)	MPH	(KPH)
F1	1.23	(1.98)	1.56	(2.51)	1.72	(2.77)
F2	1.46	(2.34)	1.85	(2.97)	2.04	(3.28)
F3	1.70	(2.74)	2.16	(3.48)	2.39	(3.84)
F4	1.95	(3.14)	2.48	(3.98)	2.73	(4.40)
F5	2.30	(3.71)	2.93	(4.71)	3.23	(5.20)
F6	2.71	(4.35)	3.43	(5.51)	3.78	(6.08)
F7	3.18	(5.11)	4.03	(6.49)	4.45	(7.16)
F8	3.76	(6.04)	4.77	(7.67)	5.26	(8.46)
F9	4.40	(7.07)	5.58	(8.97)	6.16	(9.90)
F10	5.14	(8.27)	6.52	(10.49)	7.20	(11.58)
F11	5.89	(9.47)	7.47	(12.01)	8.24	(13.26)
F12	6.96	(11.19)	8.82	(14.19)	9.74	(15.67)
F13	8.14	(13.10)	10.33	(16.62)	11.40	(18.34)
F14	9.59	(15.91)	12.16	(19.56)	13.42	(21.59)
F15	11.33	(18.22)	14.37	(23.11)	15.86	(25.51)
F16	13.25	(21.32)	16.81	(27.04)	18.55	(29.85)

REVERSE GEARS

R3	1.66	(2.68)	2.11	(3.40)	2.33	(3.75)
R4	1.97	(3.16)	2.49	(4.01)	2.75	(4.43)
R5	2.30	(3.70)	2.92	(4.70)	3.22	(5.18)
R6	2.64	(4.24)	3.34	(5.38)	3.69	(5.94)
R7	3.11	(5.01)	3.95	(6.36)	4.36	(7.02)
R8	3.65	(5.87)	4.62	(7.44)	5.10	(8.21)
R9	4.29	(6.90)	5.44	(8.75)	6.01	(9.67)
R10	5.07	(8.16)	6.43	(10.34)	7.10	(11.42)
R11	5.93	(9.55)	7.53	(12.11)	8.31	(13.37)

Based on rear tire 18.4 - 42

GROUND SPEED - 8770/8770A, 8870/8870A AND 8970/8970A WITH 16X9 POWERSHIFT TRANSMISSION
(18.4 - 42 TIRES)

FORWARD GEARS

Gear Ratio	1500 engine RPM		1900 engine RPM		2100 engine RPM	
	MPH	(KPH)	MPH	(KPH)	MPH	(KPH)
F1	1.25	(2.01)	1.58	(2.54)	1.75	(2.81)
F2	1.47	(2.37)	1.87	(3.01)	2.06	(3.32)
F3	1.72	(2.77)	2.19	(3.52)	2.41	(3.88)
F4	1.97	(3.18)	2.50	(4.03)	2.76	(4.45)
F5	2.33	(3.75)	2.96	(4.76)	3.27	(5.26)
F6	2.73	(4.39)	3.46	(5.57)	3.82	(6.15)
F7	3.21	(5.17)	4.08	(6.56)	4.50	(7.24)
F8	3.80	(6.12)	4.82	(7.76)	5.32	(8.57)
F9	4.44	(7.15)	5.64	(9.07)	6.22	(10.00)
F10	5.20	(8.36)	6.59	(10.60)	7.27	(11.70)
F11	5.95	(9.58)	7.55	(12.15)	8.33	(13.41)
F12	7.03	(11.31)	8.92	(14.33)	9.85	(15.84)
F13	8.23	(13.24)	10.44	(16.80)	11.52	(18.54)
F14	9.69	(15.59)	12.29	(19.78)	13.56	(21.83)
F15	11.45	(18.42)	14.52	(23.37)	16.03	(25.79)
F16	13.40	(21.56)	16.99	(27.34)	18.76	(30.18)

REVERSE GEARS


R3	1.68	(2.71)	2.13	(3.43)	2.36	(3.79)
R4	1.99	(3.20)	2.52	(4.06)	2.78	(4.48)
R5	2.33	(3.74)	2.95	(4.75)	3.26	(5.24)
R6	2.67	(4.29)	3.38	(5.44)	3.73	(6.00)
R7	3.15	(5.07)	4.00	(6.43)	4.41	(7.10)
R8	3.69	(5.93)	4.67	(7.52)	5.16	(8.30)
R9	4.34	(6.98)	5.50	(8.85)	6.07	(9.77)
R10	5.13	(8.25)	6.50	(10.46)	7.18	(11.55)
R11	6.00	(9.66)	7.61	(12.25)	8.40	(13.52)

Based on rear tire 18.4 - 42

ELECTRICAL SYSTEM

COMPONENT	LOCATION	FUNCTION
Fuses	Main fuse panel (MFP) right side of floor	MFP #3 - 40 AMP main trans. power
	Main distribution panel (MDP) right “B” post	MDP #18 - 20 AMP trans. shift control
		MDP #19 - 20 AMP trans. shift control
		MDP #20 - 15 AMP trans. f/r control
Relays	Main distribution panel (MDP) right “B” post	MDP #6 dir. interrupt relay
		MDP #11 Trans. power relay
Electronic transmission control (ETC)	Part of chassis control module (CCM)	16 BIT micro-controller with application memory and non-volatile calibration memory
Speed sensors	Engine speed front trans. housing	2500 OHMS resistance digital eng. speed
	Ground speed center trans. housing	2500 OHMS resistance digital grnd. speed
Switches	Inching pedal	Normally closed opens at full stroke
	Transmission pressure transmission valve	Operates pressure lamp closes at 125 PSI
Potentiometer	Inching pedal	Variable resistance feathers MC1 and MC2
Solenoids	Transmission valve	9-direct acting 1.79 OHMS operate at 100 Hz
		2-modulating 1.79 OHMS MC1 & MC2 operate at 100 Hz

DESCRIPTION OF OPERATION



70-220-787


1

The powershift transmission is a 16 forward speed and 9 reverse speed hydromechanical transmission with electronic management. The term “powershift” refers to the feature of the transmission that allows gear changing, or shifting, to be performed without interruption of the power delivery to the wheels.

Forward and reverse speeds are achieved by using a constant mesh system of high quality carburized helical cut gears. Power flow selection is made possible by multi-plate wet clutches engaged hydraulically using an electronic control system. A cutaway view of the mechanical aspect of the transmission is shown.

TRANSMISSION HOUSING


The housing is cast in three major parts - a front housing, 1; a center section, 2; and a rear housing, 3. Access to the internal components is only possible by separating the rear housing from the center section, and then removing the center section from the front housing. The transmission must be completely removed from the tractor for all disassembly procedures involving the internal components.



2

The front housing contains the primary speed components, 1, that provide the first 9 speeds in their initial stages. In addition, it provides support on its forward face for the front bearings of these components. The center section provides support for the rear bearings of these components and has attached to it the main hydraulic control valve housing. This center section also acts as the oil circuit distributor. All circuits are drilled and routed to the various components through this item. Additionally, the forward bearings of the components in the rear housing are supported by this center section. The rear housing contains the components providing two forward range and reverse speeds, 2. This housing also provides support for the rear bearings of these components.

The transmission housing together with the rear axle center housing form a common oil reservoir.



3

POWERSHIFT TRANSMISSION CONTROLS

NOTE: *70 Series art shown in Figure 4.*

The powershift transmission is operated by a single control lever, 1. Because the transmission has only one control lever, it is extremely easy to use.

NOTE: *The control lever is equipped with a neutral lock button, 2. The control lever may only be moved to the forward or reverse position if the neutral lock button on the control lever knob is depressed. Neutral may be selected without depressing the neutral lock button.*


In place of the usual clutch pedal is an inching pedal.

The powershift transmission control lever is used to select forward or reverse travel and to change transmission speeds. Move the lever forward for forward travel and rearward for reverse travel.

The powershift transmission control lever is also used to make instantaneous upward or downward gear ratio changes. Nudge the lever to the right for upward changes and to the left for downward changes. In this context, “nudge” means move the lever and then release.

Consecutive gear ratio changes may be made, either by nudging the lever several times or by holding the lever to the left or right and allowing the transmission to shift through the gear ratios automatically.


IMPORTANT: *The powershift transmission should not be towed other than to remove it from the field or onto a transporter. Do not attempt to tow-start the tractor. See “Starting the Tractor with Jumper Leads” in this section of the manual.*



4

DIGITAL DISPLAY


The function of the LCD display, 1, indicates which gear is selected and whether the transmission is in forward (F), neutral (N), or reverse (R).



5

INCHING PEDAL


The inching pedal, 1, is installed in place of the clutch pedal found on tractors with a conventional transmission. The inching pedal operates like a clutch for safe, accurate positioning of the tractor when hitching up implements or operating in confined spaces.



6

Optimum inching control, particularly with heavy loads, is achieved in the lowest ratios (F1 and R3). The degree of inching control gradually diminishes as higher gear ratios are selected up to 10th speed. At gear ratios higher than 10th, the electronic management system takes over to protect the system from abuse.

IMPORTANT: *To ensure maximum transmission life, avoid using the inching pedal as a footrest or "riding" the pedal. Use of the inching pedal is only necessary if the low gears are not slow enough at moderate/low engine speeds to give precise control for operations such as implement attachment.*



7

When using the inching pedal, particularly at high engine speeds, avoid stalling the engine. Lubrication of the transmission ceases under stall conditions and is detrimental to the transmission.

The inching pedal may also be used to automatically select a gear ratio to match load, engine speed, and road conditions. See "Speed Matching" later in this section.

To stop the tractor in an emergency, depress the inching pedal and apply both foot brakes together.

The inching pedal is not required for normal gear changes.

STARTING THE ENGINE AND MOVING FORWARD

There are two methods:


1. Preselect A Forward Gear Ratio Before Moving

Start the engine with the speed control lever in neutral (the digital display will show “N5”).


Nudge or hold the control lever to the right and allow the transmission to select any speed ratio between 5th and 10th as shown in the display (10th speed is the highest available speed for moving from a standstill).

To start in a speed ratio below 5th, nudge or hold the control lever to the left and allow the display to change sequentially from 5th down to 1st.

After the desired gear ratio is selected, increase engine speed, as required, by means of the throttle. Depress the neutral lock button and move the control lever forward. To increase tractor speed, open the throttle further and/or continue to nudge or hold the control lever to the right to select a higher speed ratio. To decrease speed, close the throttle and/or move the control lever to the left to select a lower gear ratio.



8




9

2. Powershift Forward Gear Ratios While Moving

With the engine running, depress the neutral lock button and move the control lever forward (the digital display will show “F5” and the tractor will start to move forward).

Increase engine speed and/or move the control lever to the right and allow the transmission to run through the gear ratios until the desired operating speed is achieved.

To further increase tractor speed, open the throttle more and/or continue to hold the control lever to the right to select a higher ratio. To decrease speed, close the throttle and/or hold the control lever to the left to select a lower ratio.



10

STARTING THE ENGINE AND MOVING IN REVERSE

As with forward travel, there are two methods:

1. Preselect a Reverse Gear Ratio Before Moving


Start the engine with the control lever in neutral (the digital display will show “N5”).

Nudge or hold the control lever to the right and allow the transmission to select any gear ratio between 5th and 10th as shown in the display. Nudge the lever to the left to select 4th and 3rd.

NOTE: *There are nine reverse gears, the lowest shown as R3 in the digital display, the highest shown as R11. They are numbered R3 to R11 since the ground speeds correspond to the forward speeds F3 to F11.*

After the desired gear ratio is selected, depress the neutral lock button and move the control lever rearward. To increase speed, open the throttle further and/or hold the control lever to the right to select a higher gear ratio. To decrease speed, close the throttle and/or hold the control lever to the left to select a lower gear ratio.

NOTE: *If the transmission has been preprogrammed to select a different reverse from forward gear, the neutral gear selected may change when reverse gear is selected - see “Programming Reverse Gear Ratios” later in this section.*




11

2. Powershift Reverse Gear Ratios While Moving

With the engine running, depress the neutral lock button and move the control lever rearward. The digital display will show “R5,” provided the transmission has not been preprogrammed (see “Programming Reverse Gear Ratios” later in this section). Nudge or hold the lever to the right and allow the transmission to run through the gear ratios until the desired operating speed is achieved.

To further increase tractor speed, open the throttle more and/or hold the control lever to the right to select a higher ratio. To decrease speed, close the throttle and/or move the control lever to the left to select a lower ratio.



12

SHUTTLE OPERATIONS

To change from forward to reverse travel, simply depress the neutral lock button and move the control lever fully rearward. This may be done at any engine speed and with any gear ratio selected.

⚠ WARNING ⚠

Gear ratios 1, 2 and 12-16 inclusive are not available in reverse.


SPEED MATCHING

When traveling on the road in 10th gear or higher, the transmission will automatically select a ratio to match the engine speed to the road speed if the following is performed:

Upshift

Momentarily depress the inching pedal, then decrease engine speed with the foot throttle. Release the inching pedal, then increase engine speed. The transmission will automatically select a higher ratio (provided 16th speed is not already selected) to match the lower engine speed and so maintain approximately the same road speed.

NOTE: *It is recommended that the hand throttle is set to maintain a minimum engine speed of 1000 RPM and the foot throttle is used when higher engine speeds are required.*




70-550-379

13

Downshift

Decrease engine speed, then depress the inching pedal, simultaneously increasing engine speed by pressing the foot throttle further down, then release the inching pedal. The transmission will automatically select a lower gear (provided 10th gear is not already selected) to match the higher engine speed.



70-550-380


14

AUTO SHIFT

NOTE: *70 Series art shown in Figure 15. 70A Series art shown in Figure 16.*

AUTO shift controls automatic speed shifting through forward gears 10 - 16.


AUTO shift can be engaged by depressing, then releasing, the AUTO switch, 1, on the right-hand console while traveling in forward gear ratios of 10th and above at engine speeds of 1600 RPM or more.



15

When AUTO shift is engaged, the LCD digital display on the dash will display an “A” for AUTO, 2, and show the gear selected, 3.


When in AUTO shift, the tractor will automatically select higher gears whenever the engine speed exceeds a predetermined speed. It will select lower gears when the engine speed drops below a predetermined speed as shown.



16

To disengage AUTO shift and return to normal shifting, depress the AUTO switch, upshift, or downshift with the shift control lever.

Depressing the inching pedal or selecting neutral in any gear other than 10th will also disengage AUTO shift.



17

CREEPER GEARS (OPTIONAL)


Tractors can be equipped with a 10.609:1 creeper gear for extra low ground speeds. Creeper gear provides an additional 16 forward and 9 reverse gears.

When in creeper gear, the transmission display on the dash will show "C" for creep, 1, and the gear ratio, 2, selected.

To engage creeper gears, place the transmission in neutral, stop the tractor and depress the inching pedal. Depress the top of the creeper switch, 3, engage a gear and release the inching pedal and operate normally.

To disengage the creeper gear, stop the tractor, depress the inching pedal, return the shift lever to neutral, and depress the bottom of the creeper switch.

IMPORTANT: *The creeper gear offers very low ground speeds. Do not use the low gearing to apply excessive draft loads to the tractor.*




18

PROGRAMMABLE UPSHIFT - DOWNSHIFT

NOTE: *70 Series art shown in Figure 19. 70A Series art shown in Figure 20.*


For field use, the transmission can be programmed to upshift 1, 2, or 3 gears or downshift 1, 2, or 3 gears when switch, 1, is activated. This feature allows the operator to upshift or downshift a predetermined number of gears on row ends then return to the original gear when returning to work.



19

The programmable downshift should be used to reduce speeds in the field for crossing rough terrain or climbing steep inclines.

The UPSHIFT, DOWNSHIFT rocker switch, 1, is located beside the 3-point hitch FAST RAISE/WORK switch, 2. See "3-Point Hitch Hydraulic Controls." The use of these features together allows quick turnaround at the end of the field.



20

Upshift
Up shift is activated by depressing then releasing the front of the switch. The transmission will automatically upshift the preprogrammed number of gears. The EIC dash Up-Shift lamp, 1, will illuminate and the new gear ratio will be displayed as shifts are completed.


To return to the original gear ratio, depress then release the rear of the switch. The Up-Shift lamp will go out, and the tractor will downshift to the original gear.

Downshift
Downshift is activated by depressing then releasing the rear of the switch. The transmission will automatically downshift the predetermined number of gears. The EIC Down-Shift lamp, 2, will illuminate and the new gear ratio will be displayed as shifts are completed.

To return to the original gear ratio, depress then release the front of the switch. The Down-Shift lamp will go out and the transmission will upshift to the original gear.

NOTE: *The programmable upshift, downshift feature only functions in forward gears.*

The programmed change in gear ratios will occur whenever the front or the rear of the rocker switch is depressed.



21


TRANSMISSION COMPONENTS

CLUTCHES

Nine multi-plate clutches are used in conjunction with twenty-two gears. The clutches can be divided into two groups. The first group consists of six speed clutches, 1, positioned in the transmission front housing; the second group of three directional clutches, 2, are positioned in the transmission rear housing.


SPEED CLUTCHES

The “speed” clutches control the selection of the first nine ratios. The clutches provide the early stages of engine speed reduction. The “directional” clutches work with the speed clutches, provide a further two stages of engine speed reduction to the required final output level and additionally provide reverse direction.



70-210-790

22



23

1. Front tapered roller bearing
2. End gear bearing set (6 pieces)
3. End gear for “3” clutch
4. Retainer plate and snap ring
5. Clutch piston and seals
6. Center gear and shaft assembly
7. Friction and separator plates (9)
8. End gear carrier ball bearings (Tapered set in A clutch)
9. End gear for “B” clutch
10. Rear tapered roller bearing
11. Center housing oil supply sleeve
12. Sealing rings
13. Snap ring and retainer
14. Belleville washers (6)
15. Lube blocker washer
16. Clutch apply oil passage (“B” clutch)
17. Clutch apply oil passage (“3” clutch)
18. Lube oil passage
19. End gear snap ring


Illustrated is a sectional view of the 3/B speed clutch assembly. Two speed clutches share a common center shaft, 6. This illustration is representative of all six speed clutches in that they are all paired and share common shafts. The only differences in these three pairs of speed clutches are the center shaft, 6, of one of them and the number of gear teeth and hub shape of the end gears, 3 and 9.

The main shaft has a central gear that is precision welded to it. This weldment also provides the housings for the two multi-plate clutches. At each end of the main shaft are two free-running gears, supported by two tapered roller ball bearings, 2, or ball bearings, 8. The complete assembly is carried by a tapered roller bearing at each end, 1 and 10.

All of the six speed clutches are identical. Nine internally splined, composition friction plates, 7, are carried on the hub of the end gears, and nine polished steel plates are externally splined and carried by the central housing. The clutches are hydraulically applied and spring released. The spring medium is provided by six belleville washers, 14, in each clutch. As the clutches are hydraulically applied there is automatic compensation for normal wear, eliminating any need for adjustment.


When a clutch, 2, is applied, the respective end gear, 1, is locked to the shaft, 3, and power can be transmitted from the end gear to the center gear, or vice versa. When both clutches are actuated, power can be transmitted from end gear to end gear.

The speed clutch assemblies each receive three separate oil supplies - a supply for each of the two clutch actuation circuits, 4, and one common supply, 5, for lubrication and cooling of the two clutch assemblies, the bearings of the two main gears, 6, and the two support shaft bearings, 7.



24


The three oil supplies are controlled by an electronically managed hydraulic control valve, 1, mounted externally on the right-hand side of the center section, 2, of the three-piece main casing. Details of the hydraulic control valve and the electronic management system are covered in Chapters 3 and 4 respectively. Internal drillings, 3, in the housing center section route the oil supplies to the ends of the three pairs of speed clutches.



25

Bronze impregnated Teflon sealing rings, 2, are positioned in annular grooves on the shaft ends. Oil for clutch actuation is fed between the sealed grooves from the drilled passages, 1, in the center section. The center section carries serviceable steel sleeves, 3, should wear occur in this oil transfer area. The third oil supply for lubrication and cooling enters the end of the shaft from a similar drilling, 4, in the center section.

Oil is transferred along the center of the shaft through axial drillings and meets cross drillings connecting with the clutch piston chambers.




26


Oil entering the piston chamber, 6, acts on the surface area of the piston, 3, which is sealed to the central housing, 4, and the shaft by sealing rings, 5, and moves the piston against the lube blocker washer, 7, and the six belleville washers, 8. The polished steel plates, 2, that are externally splined to the central housing, are then compressed against the composite friction plates, 9, which are internally splined to the end gears, 1. Power can be transmitted between the central gear, 4, to the end gear, 1, or vice-versa, depending on which speed is selected.

Note that for some speeds both clutches within a speed clutch assembly may be engaged transferring power from one end gear to the other end gear.

When the electronically managed control valve signals release of a clutch, the belleville springs, 8, return the piston, 3, to its original position, sending the exhausted oil back to the control valve and releasing the friction between the two sets of plates, 2 and 9.




27



28

The rate and amount of pressure supplied to and released from the clutch is controlled by the electronic management system and provides smooth, progressive, and timely clutch engagements. Lubrication and cooling oil, entering the shaft at its end face, 3, is allowed to exit the shaft at various lateral drillings, 1, positioned to ensure all components are thoroughly lubricated and cooled.

The lube blocker washers, 2, limits lube oil flow to the non-applied clutches to reduce drag and increase efficiency. As the piston, 4, moves, the lube blocker washer uncovers the lube port, 1, to maximize lube flow to the clutch.



29

1. Front tapered roller bearing
2. F2 gear and output shaft
3. Clutch piston
4. Lube blocker washer
5. Belleville washers (8)
6. F2 drive gear
7. F2 drive gear ball bearings (small bearing has shield or seal)
8. Rear tapered roller bearing
9. Lube oil passage
10. Bearing spacer
11. Snap ring and retainer
12. Clutch retaining plate
13. Snap ring
14. Clutch friction and separator plates (11)
15. Clutch apply oil pressure
16. Center housing oil sleeve
17. Sealing rings
18. O Ring (Directional clutches only)

DIRECTIONAL CLUTCHES

The directional clutches F1 and F2 for forward speeds and R for reverse speeds are much heavier in construction compared with the speed clutches. The directional clutches are operating at slower revolutions and are carrying higher torque loads.

All three directional clutches are similar to each other but differ from the speed clutches in that there is only one clutch system in each directional clutch assembly.

The directional clutch assemblies each have a gear precision welded to the center shaft, 2, and a second free-running gear, 6, which can be connected to the shaft and its gear by the clutch. The second gear is supported by two ball bearings, 7, mounted on the common shaft. Each directional clutch is similar, only the number of teeth on the respective gears and the hub design differ.

Like the speed clutches, the directional clutches receive oil supplies from the electronically managed control valve, but they only receive two supplies, one supply for the actual clutch operation, 15, and the second for lubrication and cooling, 9.

Application of the clutch and oil routing in principle is identical to the speed clutches, oil being channelled from the control valve through the transmission housing center section to the end, 1, of the directional clutch assemblies. The F1 and R directional clutches, because of their heavier duty, feature fourteen composition internally splined friction plates and fourteen polished steel externally splined plates. The plates, pistons, snap rings, and seals are all common between both speed clutches and directional clutches, although the number of plates is increased to fourteen, and the number of belleville spring washers increased to eight.

The F2 clutch and shaft assembly, 2, has larger diameter friction, 4, and steel drive plates, 5, than the F1 and reverse clutches. The F2 clutch also has a larger piston, 7, and belleville washers, 6.


The F1 and Reverse directional clutches are supported between the center and rear housing on roller bearings. The F2 clutch has tapered roller bearings, 8, which are shim adjustable.

The center shaft, 2, of the F2 directional clutch is utilized as the main output shaft for all forward and reverse speeds. However, the clutch is only engaged for hi range forward speeds.

CLUTCH ENGAGEMENT


All clutch engagement is accomplished by the solenoid operated low-pressure hydraulic valves controlled by Electronic Transmission Control module (ETC) as follows.

Note the overlap of the F8 and F9 gears. The speed and directional clutch application varies for these gears depending on the operator upshifting or downshifting the tractor.



30


UP					DOWN		
SHIFT GEARS					SHIFT GEARS		
GEAR	SPEED		DIR		SPEED		DIR
F1	1	A	F1		1	A	F1
F2	2	A	F1		2	A	F1
F3	3	A	F1		3	A	F1
F4	1	B	F1		1	B	F1
F5	2	B	F1		2	B	F1
F6	3	B	F1		3	B	F1
F7	1	C	F1		1	C	F1
F8	2	C	F1		1	A	F2
F9	3	C	F1		2	A	F2
F10	3	A	F2		3	A	F2
F11	1	B	F2		1	B	F2
F12	2	B	F2		2	B	F2
F13	3	B	F2		3	B	F2
F14	1	C	F2		1	C	F2
F15	2	C	F2		2	C	F2
F16	3	C	F2		3	C	F2
R3	1	A	R				
R4	2	A	R				
R5	3	A	R				
R6	1	B	R				
R7	2	B	R				
R8	3	B	R				
R9	1	C	R				
R10	2	C	R				
R11	3	C	R				



31

First Gear Forward


1. With1st speed selected, clutch 1 and clutch A are hydraulically applied.
2. Clutch 1 locks the adjacent end gear to its center shaft gear assembly, and clutch A locks the adjacent end gear to its center shaft.



32

Second Gear Forward


1. With 2nd speed selected, clutch 2 and clutch A are applied locking both end gears to the center shaft gear assembly.
2. Power flows are as shown.



33

Third Gear Forward


1. With 3rd speed selected, clutch 3 and clutch A are applied locking their end gears to their respective shaft gear assemblies.
2. Power flows are as shown.
3. Power is transmitted to the rear housing by the two gear cluster and transfer shaft.



34

Fifth Speed Selected


1. With speeds 4, 5 or 6 selected, clutch B is hydraulically engaged locking the adjacent end gear to the center shaft gear assembly.
2. Application of clutches 1, 2 and 3 with clutch B engaged provides speeds 4, 5 and 6 respectively.
3. Power flow in 5th speed is illustrated.
4. The power flow through clutch B end gear to the two gear cluster decreases the drive reduction compared to the power flow through clutch A. Therefore, the speeds using clutch B are increased compared to the speeds using clutch A.
5. Power is transmitted to the rear housing by the two gear cluster and transfer shaft.



35

Seventh Speed Selected


1. With speeds 7, 8 and 9 selected during upshifts, clutch C is hydraulically engaged locking the adjacent end gear to the center shaft gear assembly.
2. Application of clutches 1, 2 and 3 with clutch C engaged provides speeds 7, 8 and 9 respectively.
3. Power flow in 8th speed is illustrated.
4. The power flow through clutch C and its end gear direct to the two gear cluster decreases the drive reduction compared to the power flow through clutch B. Therefore, the speeds using clutch C are increased compared to speeds using clutch B.
5. Power is transmitted to the rear housing by the two gear cluster and transfer shaft.



36

Engagement of Gears F1-F9


1. The F1 directional clutch is engaged for upshift speeds 1-9 and downshift gears 7-1.
2. With the clutch engaged, the shaft gear assembly is locked to the end gear.
3. Power flows are as indicated; low speed range is achieved by the three stages of reduction between the transfer gear and output shaft gear.



37

Engagement of Gears F8-F16

1. The F2 directional clutch is engaged for upshift speeds 10-16 and downshift gears 16-8.
2. With the clutch engaged, the end gear is locked to the output shaft and gear.
3. Power flows as shown from the transfer gear directly to the locked F2 clutch end gear and output shaft.
4. The higher speed range is achieved by only one stage of reduction between the transfer gear and output shaft.



38


Engagement of Gears R3-R11

1. The reverse directional clutch is engaged for reverse speeds (R3-R11).
2. With the clutch engaged, the end gear is locked to the shaft gear assembly.
3. Power flows are as indicated.
4. The reverse speed range is achieved by two stages of reduction between the transfer gear and output shaft; the output shaft rotation is also reversed.
5. The reverse speeds (R3-R11) are matched to forward speeds F3-F11.

All gear teeth and speed ratios are detailed as follows:

F=Forward
R=Reverse
U=Upshift ratio
D=Downshift ratio for F8 and F9

F1	9.144
F2	7.737
F3	6.612
F4	5.772
F5	4.884
F6	4.174
F7	3.546
F8-U	3.000
F8-D	3.033
F9-U	2.564
F9-D	2.566
F10	2.193
F11	1.914
F12	1.620
F13	1.384
F14	1.176
F15	0.995
F16	0.850
R3	6.773
R4	5.731
R5	4.898
R6	4.275
R7	3.618
R8	3.091
R9	2.626
R10	2.222
R11	1.899




39

Torque Limiting Clutch

The torque limiting clutch provides protection to the engine and transmission driveline components in the event of shock loading or transmission malfunction causing a lockup condition.

The clutch “disc” consists of a friction lining attached to spring damper hub. The disc is clamped inside the pressure plate and bolted to the flywheel.

Drive is transmitted from the torque limiting clutch to the transmission input gear by the input shaft.




40

PTO Drive

The power take-off driveline is driven directly from the engine.

Drive from the engine is transmitted through the torque limiting clutch to the input gear, 1, in the front housing.

The PTO drive shaft, 2, is splined into the input gear, 1, which transmits live power to the hydraulic gear drive splines, 3, and on to the PTO clutch pack located in the rear axle housing.



41

TROUBLESHOOTING AND DIAGNOSIS

PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor won't move after starting	Flashing "F" "R" "P" "U" or "d" Transmission operation performed out of sequence	Return shift control lever to neutral and release parking brake. See "Operator Prompts."
Poor inching control when using inching pedal	Transmission clutches out of calibration	Recalibrate transmission clutches F1, F2 and R. See "Hydraulic Components," Chapter 5.
	Clutch potentiometer	Replace the clutch potentiometer.
	Clutch spring	Replace the clutch spring.
Transmission will not operate	Fault code displayed indicating malfunction	See "Fault Codes" Electrical System, Section 55, Chapter 2.
Low transmission oil pressure warning lamp on	Low oil supply	Fill system with oil. See "Hydraulic Components," Chapter 5.
Transmission filter lamp on	Clogged transmission oil filter	Replace filter.
Tractor drives in limited gears	One or more solenoids in operation	Compare working gears to clutch apply chart (Chapter 5) to determine faulty solenoid.
Tractor stalls in limited gears	More than 3 clutches engaged at one time	Compare non-working gears to clutch apply chart (Chapter 5) to determine faulty clutch.

SECTION 21 - TRANSMISSION

Chapter 2 - Separating the Engine and Front Axle from the Transmission

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Engine and Side Rail Separation from the Transmission	4
	Four-wheel Drive Shaft Removal (if equipped)	8
	Engine and Side Rail Reassembly	10

SPECIFICATIONS

Engine size	7.5 L (456 cu. in.)
Engine weight	738 kg (1625 lbs.)
Cylinders, bore x stroke	6, 112 mm x 127 mm (4.4″ x 5″)
Coolant capacity: 8670/8670A, 8770/8770A	25 L (6.6 U.S. gal.)
8870/8870A, 8970/8970A	26.4 L (7 U.S. gal.)

Torques

Starter mount retainers	64 N·m (47 ft. lbs.)
Engine to transmission bolts (top)	488 N·m (360 ft. lbs.)
Engine to transmission bolts (center)	240 N·m (177 ft. lbs.)
Engine to transmission bolts (bottom)	55 N·m (41 ft. lbs.)
Air-conditioner compressor	54 N·m (40 ft. lbs.)
Side rail bolts	576 N·m (425 ft. lbs.)

SPECIAL TOOLS

Engine support brackets	FNH00526
Tractor splitting stands	FTC201387
Splitting stand adapter	FNH00530

DESCRIPTION OF OPERATION


The tractor engine is mounted to the front surface of the transmission with no supports at the front bolster. The axle and front bolster are connected to the transmission by the use of side rails. The engine, front axle and side rails can be separated from the transmission. Special tools are provided to attach the side rails to the engine and allow the assembly to be rolled away from the transmission. This procedure should be completed if the transmission requires repair or if a leak is diagnosed between the engine and transmission.

DISASSEMBLY AND REPAIR

ENGINE AND SIDE RAIL SEPARATION FROM THE TRANSMISSION


The engine and side rails can be rolled away from the transmission assembly as follows:

1. Park the tractor on a level surface and apply the parking brake. Be sure there is a clear area to use a lifting hoist to lift the engine from the tractor.
2. Remove the battery cover and the negative battery cables, 1.




1

3. Removal of the front weights will aid in the proper balance of the engine and front axle. Use a suitable hoist to lift the weights from the tractor.
4. Remove the left hood access door and hinge mount.
5. Remove the lower fuel tank, as outlined in this section, Chapter 2, “Fuel Tank Removal.”




2

6. Remove the exhaust pipe, 1, from the right side of the tractor and the hood access door, 2, and hinge mount. (Hood removed for clarity.)



3


7. Turn the cab heater valves, 1, off at both ends of the intake manifold. Disconnect the hoses and plug them to prevent coolant loss.



4


NOTE: *70 Series art shown in Figure 5.*

8. Remove the starter, 1, from the right rear of the engine. A 16-mm curved obstacle wrench is required to remove the inner retaining nut. The fuel filter, 2, may have to be removed for better access to the starter.
9. Remove the throttle cables, 3, from the injection pump on the right side of the engine.
10. Remove the fuel supply and return lines, 4, from the right side of the engine.




5

11. Remove the cab doorsill plates, then the front floor mats and the center floor cover.
12. Remove the two transmission to engine retaining bolts.



6


13. Disconnect and cap the two steering axle supply lines at the cab floor opening.
    1 Left-hand steering line
    2 Right-hand steering line



7

14. Remove the air-conditioner compressor and hoses from the engine.

NOTE: *Do not disconnect lines or discharge the system.*




8

NOTE: *70 Series art shown in Figure 9.*


15. Remove the air-conditioner condenser, 1. Remove the receiver/drier.

NOTE: *Do not disconnect lines or discharge the system.*




9

16. Store the air-conditioner compressor, 1, and condenser, 2, in the cab. Attach the receiver/drier, 3, to the cab rail.




10

17. Disconnect the front main harness from the rear main harness (C008 connector), 1, above the batteries.



11

18. Remove the cooler bypass valve to cooler lines, 1, at the transmission.




12

FOUR-WHEEL DRIVE SHAFT REMOVAL (IF EQUIPPED)

If not equipped, proceed to step 23.

The four-wheel drive shaft is comprised of two shafts splined together in the middle.


19. Remove the drive shaft and shields.
20. Unscrew the dust seal retainer, 1, from the rear section, 2. This will allow the front section, 3, to slide from the rear section.



13


21. Disconnect the front section, 2, from the front axle by removing the retainer caps, 1 and 3.

    Carefully lower and remove the front drive shaft from the tractor.



14


22. Disconnect the drive shaft support bearing, 1, and pull the rear section, 2, from the rear axle pinion shaft.



15

23. Install the four engine to side rail brackets FNH00526 inside the rails. The brackets attach to the engine oil pan bolts in four locations.


NOTE: *The two hole bracket is used at the left rear corner of the engine.*



16

24. Install the adapter FNH00530, 1, to the side rails and attach it to the engine section of the splitting stands FTC201387, 3.


NOTE: *The location of the engine to side rail brackets, 2.*



17


25. Install the transmission section of the tractor splitting stands FTC201387, 1, securely under the transmission.

NOTE: *The splitting stand transmission adapter plate (front), 2, part #42148-BL2, will have to be drilled to fit the transmission case. Use the dimensions from the case for proper spacing.*




18

26. With the engine and transmission supported, carefully remove the remaining engine to transmission retaining bolts and rail to transmission bolts.



19


27. Roll the engine, side rails and front axle forward to clear the transmission. Ensure that all electrical harnesses, fuel and hydraulic lines are clear to prevent damage.



20

ENGINE AND SIDE RAIL REASSEMBLY

1. Reassembly of the engine and side rails is the reverse of removal.
2. Ensure that the engine is properly aligned to prevent damage to wiring, lines and fittings during installation.
3. Torque all retaining bolts as indicated in the “Specifications” portion of this chapter.



21

SECTION 21 – TRANSMISSION

Chapter 3 – Separating the Rear Axle from the Transmission

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Rear Axle to Transmission Separation	4
	Reassembly	8
	MInimum Hardware Tightening Torques	9

SPECIFICATIONS

General

Transmission	16 x 9 powershift
Rear axle	Double reduction
Axles	Bar

Sealers


Anaerobic sealer	Loctite Gasket Eliminator 518
RTV silicone sealer	Loctite Superflex 593, 595, or 596 Loctite Ultra Blue 587 Dow Corning Silastic 732 General Electric RTV 103 or 108
Pipe sealant	PST 592 Pipe Sealant with Teflon
Thread-locking compound	Loctite 271 Threadlocker/Sealant (red)

Torques

1 Four rear axle to transmission (large) - 668 N·m (495 ft. lbs.)

2 Sixteen rear axle to transmission (medium) - 135 N·m (100 ft. lbs.)

3 Four rear axle to transmission - 344 N·m (255 ft. lbs.)



1

SPECIAL TOOLS

Splitting stands	FTC201387
Stand adapter	FNH00530
Engine supports	FNH00526
Cab lifting fixture	FTC213997B

DESCRIPTION OF OPERATION

If major internal rear axle service is required, the tractor must be separated at the rear axle to transmission connection.


If internal transmission repair is required, the tractor must be separated at the rear axle and at the engine.

To service either component, the tractor cab must be removed. See Section 90, Chapter 3 - “Cab Removal,” Chapter 2 - “Fuel Tank Removal,” and Section 21, Chapter 2 - “Engine and Side rail Separation” before completing this chapter.

DISASSEMBLY AND REPAIR

REAR AXLE TO TRANSMISSION SEPARATION


1. Remove the cab as described in Section 90, Chapter 3.
2. Remove the fuel tank as described in Section 90, Chapter 2.
3. Remove the rear axle drain plug, 1, and drain the oil into a suitable container capable of holding 140 L (37 U.S. gal.).



2

4. Remove 4WD shield assembly.
5. The four-wheel drive shaft is comprised of two sections splined together in the middle.


   Unscrew the dust seal retainer, 1, which protects the splined joint from ingress of dirt between the rear section, 2, and the front section, 3, of the drive shaft.



3


6. Disconnect the drive shaft, 2, from the front axle by removing the retaining caps, 1 and 3.

   Carefully lower and remove the front drive shaft from the tractor.




4

7. Disconnect drive shaft support bearing, 1, and pull rear section, 2, of the drive shaft from the rear axle pinion shaft.




5

8. Remove hydraulic hoses:
   1 Charge filter to variable displacement hydraulic pump
   2 Charge pump to charge filter
   3 Transmission pump to transmission filter




6

9. Remove the power steering flow divider valve, 1, and mounting bracket.




7

10. Disconnect the low-pressure supply line, 1, and the PTO lubrication line, 2, from the transmission control valve.




8

11. Disconnect and fold back the rear main harness, 1.
12. Remove the brake valve return to sump hose, 2.




9

13. Install wooden chocks, 1, and 2, to prevent the axle from oscillating.



10



11


14. Position the tractor transmission splitting stand beneath the tractor.

NOTE: *The splitting stand transmission adapter plate (front), 3, part #42148-BL2, will have to be drilled to fit the transmission case. Use the dimensions from the case for proper spacing.*

15. Using the two 1/2″ threaded holes provided in the bottom of the transmission casing to secure the FWD shaft pillow block and two long 1/2″ bolts, secure the transmission section of the splitting stand, 1, to the transmission.


16. Ensure the rear axle section of the splitting stands, 2, is securely located beneath the rear axle immediately in front of the axle pinion.

NOTE: *Make sure the tractor is evenly supported on the splitting stands.*



12

17. Remove the twenty-four buckle-up bolts securing the rear axle to the transmission and roll the engine and transmission assembly away from the rear axle.



13

REASSEMBLY

1. Reassembly follows the separation procedure in reverse.
2. Clean the mating surfaces thoroughly and apply a bead of specified anaerobic sealer, 4, as shown.
3. During reassembly, ensure all bolts are tightened to:

   1 668 N·m (495 ft. lbs.)

   2 344 N·m (255 ft. lbs.)

   3 135 N·m (100 ft. lbs.)
4. Make sure the transmission/rear axle is replenished with the correct quantity of specified oil.

MINIMUM HARDWARE TIGHTENING TORQUES

IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

INCH HARDWARE AND LOCKNUTS

NOMINAL SIZE	SAE GRADE 2		SAE GRADE 5		SAE GRADE 8		LOCKNUTS		NOMINAL SIZE
	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	GR.B w/GR5 BOLT	GR.C w/GR8 BOLT	
1/4	55* (6.2)	72* (8.1)	86* (9.7)	112* (13)	121* (14)	157* (18)	61* (6.9)	86* (9.8)	1/4
5/16	115* (13)	149* (17)	178* (20)	229* (26)	250* (28)	324* (37)	125* (14)	176* (20)	5/16
3/8	17 (23)	22 (30)	26 (35)	34 (46)	37 (50)	48 (65)	19 (26)	26 (35)	3/8
7/16	27 (37)	35 (47)	42 (57)	54 (73)	59 (80)	77 (104)	30 (41)	42 (57)	7/16
1/2	42 (57)	54 (73)	64 (87)	83 (113)	91 (123)	117 (159)	45 (61)	64 (88)	1/2
9/16	60 (81)	77 (104)	92 (125)	120 (163)	130 (176)	169 (229)	65 (88)	92 (125)	9/16
5/8	83 (112)	107 (145)	128 (174)	165 (224)	180 (244)	233 (316)	90 (122)	127 (172)	5/8
3/4	146 (198)	189 (256)	226 (306)	293 (397)	319 (432)	413 (560)	160 (217)	226 (306)	3/4
7/8	142 (193)	183 (248)	365 (495)	473 (641)	515 (698)	667 (904)	258 (350)	364 (494)	7/8
1	213 (289)	275 (373)	547 (742)	708 (960)	773 (1048)	1000 (1356)	386 (523)	545 (739)	1

NOTE: Torque values shown with * are inch pounds.

IDENTIFICATION
CAP SCREWS AND CARRIAGE BOLTS




SAE GRADE 2




SAE GRADE 5



SAE GRADE 8



REGULAR NUTS




SAE GRADE 5 HEX NUTS



SAE GRADE 8 HEX NUTS

LOCKNUTS



GRADE IDENTIFICATION

GRADE A NO NOTCHES

GRADE B ONE CIRCUMFERENTIAL NOTCH

GRADE C TWO CIRCUMFERENTIAL NOTCHES




GRADE IDENTIFICATION

GRADE A NO MARKS

GRADE B THREE MARKS

GRADE C SIX MARKS

MARKS NEED NOT BE LOCATED AT CORNERS



GRADE A NO MARK
GRADE B LETTER B
GRADE C LETTER C

GRADE IDENTIFICATION

MINIMUM HARDWARE TIGHTENING TORQUES


IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

METRIC HARDWARE AND LOCKNUTS


NOMINAL SIZE	CLASS 5.8		CLASS 8.8		CLASS 10.9		LOCKNUT CL.8 W/CL8.8 BOLT
	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	
M4	15* (1.7)	19* (2.2)	23* (2.6)	30* (3.4)	33* (3.7)	42* (4.8)	16* (1.8)
M6	51* (5.8)	67* (7.6)	79* (8.9)	102* (12)	115* (13)	150* (17)	56* (6.3)
M8	124* (14)	159* (18)	195* (22)	248* (28)	274* (31)	354* (40)	133* (15)
M10	21 (28)	27 (36)	32 (43)	41 (56)	45 (61)	58 (79)	22 (30)
M12	36 (49)	46 (63)	55 (75)	72 (97)	79 (107)	102 (138)	39 (53)
M16	89 (121)	117 (158)	137 (186)	177 (240)	196 (266)	254 (344)	97 (131)
M20	175 (237)	226 (307)	277 (375)	358 (485)	383 (519)	495 (671)	195 (265)
M24	303 (411)	392 (531)	478 (648)	619 (839)	662 (897)	855 (1160)	338 (458)

NOTE: Torque values shown with * are inch pounds.

IDENTIFICATION
HEX CAP SCREW AND CARRRIAGE BOLTS
CLASSES 5.6 AND UP



HEX NUTS AND LOCKNUTS
CLASSES 05 AND UP



SECTION 21 – TRANSMISSION

Chapter 4 – Mechanical System

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Torque Specifications	3
	Special Tools	4
	Description of Operation	5
	Troubleshooting and Diagnosis	6
	Disassembly and Repair	7
	Removal and Disassembly	7
	Rear Housing and Directional Clutches - Removal	8
	Front Housing and Speed Clutches - Removal	12
	Main Input Gear Assembly - Removal	14
	Speed Clutches - Disassembly	16
	Speed Clutches - Inspection	21
	Directional Clutches - Disassembly	23
	Directional Clutches - Inspection and Overhaul	26
	Speed/Directional Clutch - Reassembly	27
	Main Input Gear and Oil Seal - Disassembly Inspection, Overhaul and Reassemble	29
	Two Gear Clusters in Front and Rear Housing - Disassembly, Inspection and Reassembly	30
	Front and Rear Housings and Center Section - Inspection and Overhaul	30
	Torque Limiting Clutch and Sprung Damper Hub Drive Assembly - Removal, Inspection and Replacement	32
	Reassembly	33
	Speed Clutches and Front Housing	33
	Directional Clutches and Rear Housing	34
	Transmission Shimming	36
	Front Housing Shimming	36
	Rear Housing Shimming	37
	Shimming the Output Shaft	38
	Creeper Gear	39
	Creeper Gear Repair	41
	Installation	44

SPECIFICATIONS

Transmission Housing	3 section, cast iron
Transmission Gears	22, helical cut, carbonized precision cut gears
Creeper Gear (optional)	10.609:1 - Addition 16 x 9 speeds Double planetary gear set

Multi-Plate Wet Clutches

No. and type of clutches	6 speed clutches, A,B,C, and 1,2,3 3 directional clutches Rev, F1 and F2
Type	Constant running, pressure lubricated, pressure applied and spring released.

Speed Clutches

No. of friction plates	9 in each of 6 clutches
No. of separator plates	9 in each of 6 clutches
No. of belleville springs	6 in each of 6 clutches
*Maximum clutch piston travel	5.38 mm (0.212″)
*Minimum clutch piston travel	3.38 mm (0.133″)

Directional Clutches

No. of friction plates	14 in F1 and R clutches, 11 in the F2 clutch
No. of separator plates	14 in F1, 15 in R clutches, 11 in the F2 clutch
No. of belleville springs	8 in each of 3 clutches
*Maximum clutch piston travel	14 plates - 8.2 mm (0.323″) F1
*Minimum clutch piston travel	14 plates - 5.13 mm (0.202″) F1
*Maximum clutch piston travel	14 plates - 4.57 mm (0.180″) Reverse
*Minimum clutch piston travel	14 plates - 2.54 mm (0.100″) Reverse
*Maximum clutch piston travel	11 plates - 5.76 mm (0.247″)
*Minimum clutch piston travel	11 plates - 3.76 mm (0.148″)


Friction and separator plates, pistons and belleville springs in all clutches are identical except the F2 clutch.

*Maximum and minimum clutch travel is measured with clutch fully assembled

Bearings

Type	High quality, high performance and durability roller and tapered roller. (substitution with claimed equivalents is not recommended)
Weight (dry)	886 kg (1950 lbs.) approximately

TORQUE SPECIFICATIONS



1


SPECIAL TOOLS

DESCRIPTION	PART NUMBER	USAGE
Clutch gear/bearing puller	*FNH 00101	Clamp and pull gears/bearings
Speed clutch lifting tool	*FNH 00102	Speed clutch lifting device
Clutch spring compressor	*FNH 00103	Allow clutch piston removal
Aligning dowel set (2)	*FNH 00104	Aligns housing assemblies
Wear sleeve remover	*FNH 00105	Remove clutch supply sleeve
Housing lifting eyes (3)	*FNH 00106	Lift housing sections
Housing lifting eyes (3)	*FNH 00107	Lift housing sections
Clutch lifting eye	*FNH 00108	Lift clutch packs
Limp home harness	FNH00539	Troubleshoot transmission
Clutch lifting eye	**FNH 00546	F2 clutch removal/shimming
Bearing installer - short	**FNH 00543	Press bearings in place
Bearing installer - long	**FNH 00544	Press bearings in place
Transmission rotation tool	**FNH 00545	Rotate trans while shimming
* All items part of kit	FNH 00100	Powershift Service kit
**All items part of kit	FNH 00542	

DESCRIPTION OF OPERATION

The mechanical components of the powershift transmission consist of a front, center and rear housing. Six speed clutch packs are located in the front housing, and three directional clutch packs are located in the rear housing. The transmission is controlled by an electrohydraulic valve on the right side and oil is supplied by the tandem gear pump mounted on the rear axle housing.

This chapter deals with the disassembly and repair procedures for the transmission. For additional operation on transmission controls and operation see Chapter 1, “Operation/Overview.”



70-220-701

2

TROUBLESHOOTING AND DIAGNOSIS


PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor won't move after starting	Flashing "F" "R" "P" "U" or "d" Transmission operation performed out of sequence	Return shift control lever to neutral and release parking brake. See "Operator Prompts."
Poor inching control when using inching pedal	Transmission clutches out of calibration	Recalibrate transmission clutches F1, F2 and R. See "Hydraulic Components" Chapter 5.
	Clutch potentiometer	Replace the clutch potentiometer.
	Clutch spring	Replace the clutch spring.
Transmission will not operate	Fault code displayed indicating malfunction	See "Fault Codes" Electrical System, Section 55, Chapter 2.
Low transmission oil pressure warning lamp on	Low oil supply	Fill system with oil. See "Hydraulic Components" Chapter 5.
Transmission filter lamp on	Clogged transmission oil filter	Replace filter.
Tractor drives in limited gears	One or more solenoids inoperative.	Compare working gears to Clutch Apply Pressure Chart - Chapter 5 to determine faulty solenoid/ clutch.
Tractor stalls in limited gears	More than 3 clutches engaged at one time.	Compare non-working gears to Clutch Apply Pressure Chart - Chapter 5 to determine faulty clutch.

DISASSEMBLY AND REPAIR

Disassembly of the transmission for access to the speed and directional clutches can only be performed with the transmission completely removed from the tractor and with the housing in a vertical position resting on its front buckle-up face. If the main input seal, or the torque limiting, cushioned damper drive shaft assembly between the engine flywheel and the transmission assembly require attention, these items may be disassembled by separating the engine from the transmission. Refer to Section 21, Chapter 2 - Separating the Tractor for details of transmission separation and removal.


REMOVAL AND DISASSEMBLY

To aid in disassembly and repair of the transmission, special tool kit FNH00100 will be required. An additional transmission rotation tool FNH00545, 1, and bearing installers FNH00544, 2, and FNH00543, 3, will also be required along with an additional lifting eye FNH00546, 4.



3


Additional shop tools including a dial indicator with extension, 1, good quality bearing splitters, 3, and pullers, 2, along with a Porta-Power with a 6″ ram.



4

1. Remove the transmission as described in Section 21, Chapter 2 - Separating the Tractor.
2. Place the transmission, 1, vertically on its front buckle-up face, resting it on a wooden sheet, 2,to protect the front face. If a trolley or cart can be made that incorporates wheels, this will aid in disassembly.
3. Remove the input and output speed sensors, 3.


NOTE: *The transmission weighs approximately 886 kg (1950 lbs.). Make sure an adequate hoist is available and note that a hoist will be necessary during disassembly; therefore, a smooth floor space will be required.*



5


REAR HOUSING AND DIRECTIONAL CLUTCHES - REMOVAL

1. Remove the 5 bolts, 1, retaining the lube cooler valve.




6

2. Carefully remove the valve, 1, and O rings.




7

3. Remove the 22 bolts retaining the main hydraulic control valve assembly in the numbered sequence shown. Start with bolt 22 and end with bolt 1.
4. Remove the valve and gasket.




8

5. Remove the snap ring, 1, securing the PTO shaft, 2, to the rear housing, 3, and by grasping the PTO shaft withdraw it from the transmission.



9

6. Remove the 19 bolts that retain the rear housing, 1, and center section to the front housing. Attach a suitable lifting sling, 2, to the rear housing, with lifting eyes FNH00107, 3, and place two threaded aligning dowels, FNH00104, 4, at opposite sides of the housing (guide rods may be suitably threaded bolts with the heads cut off).
7. With the aid of a suitable hoist, carefully lift off the rear housing. Do not allow the front housing to separate from the center section. Remove the gasket, 5.




10

8. Remove the two bolts, 1, retaining the F2 directional clutch/output shaft oil splash shield, 2, and remove it.

CAUTION

All helical cut gears are very sharp. Use gloves to handle gears.



11

9. Mark all gears with a paint pen to aid in inspection and reassembly.


   Reverse, 1.

   Transfer gear, 2.

   Two gear cluster, 3.


   F1 directional clutch, 4.

   F2 directional clutch, 5.




12

10. Install the transmission rotation tool FNH 00545, 1, into the rear transmission transfer gear. Remove the transfer gear and spacer, 2, using the transmission rotation tool to aid in removal.




13

11. Remove reverse clutch pack, 1.




14

12. With a hoist and FNH 00108 eyebolt, 1, installed, lift F1 clutch, 2, slightly.
13. Remove F1 transfer gear, 3, then remove F1 clutch.




15

14. Remove F2 clutch, 1, with hoist and FNH 00546 lifting eye, 2.



16


Disassembly of the rear housing components (directional clutches) is now complete. If repair of the removed assemblies is now necessary, refer to the following headings covering overhaul of these items. If further disassembly is required, it is recommended that complete transmission disassembly is completed before overhauling sub-assemblies.



17


FRONT HOUSING AND SPEED CLUTCHES - REMOVAL

1. Screw in three lifting eyes, FNH 00106, 1, into the threaded holes provided in the center section, 2, (thread size 3/4-10 U.N.C.) Using a suitable lifting sling, 3, carefully lift the center section away from the front housing.
2. Remove the gasket.




18

3. Using a paint pen, 1, mark the speed clutches and case to aid in inspection and reassembly.




19

4. In order to remove speed clutches 1/C, 1, and 3/B, 2,it will be necessary to use lifting tool, FNH 00102, 3.
5. Position the tool over the ends of the speed clutch shafts and install the locking bar, 4, by rotating in place.




20

6. Using the hoist, slightly raise the two speed clutches, 1, and at the same time slightly raise the two gear cluster, 2. By applying a lever or pry bar to the hole in the lifting eye, 3, the angle of the clutches may be altered to assist in removal, if necessary.
7. Grasp the two gear cluster, 2, and lift it away from the speed clutches. It may be necessary to alter the angle of the suspended speed clutches and to lift them further.



21


8. With the two gear cluster removed, carefully raise the two speed clutches 1/C, 1, and 3/B, 2, and remove them from the housing, 3.



22


9. The remaining speed clutch 2/A, 1, may now be lifted and removed from the housing, 2.

NOTE: *Installing the lifting tool, 3, on this clutch to use as a handle will aid in removal.*



23


10. Inspect the bearing races, 1, in the front housing, 2, for damage.



24


MAIN INPUT GEAR ASSEMBLY - REMOVAL

1. With the front housing now resting on its rear face, remove the 8 bolts, 1, retaining the input gear cover, 2, to the front housing.




25

2. Remove the front cover, 1, and shims, 2. Note the location of the lube inlet hole, 3, at the 12 o'clock position on the front cover.




26

3. Pull out the input gear and bearing assembly, 1.




27

4. The front housing center bearing races, 1, can now be removed.
5. Use a 3-jaw puller and slide hammer or soft punch to remove both races, one from each side.
6. Remove the 2 snap ring retainers, 2, one from each side.
7. Remove the internal snap rings, 3.
8. After inspection, replace the snap rings, retainers and bearing races in the reverse order of removal.



28




29

1. Front tapered roller bearing
2. End gear bearing set (6 pieces)
3. End gear for “3” clutch
4. Retainer plate and snap ring
5. Clutch piston and seals
6. Center gear and shaft assembly
7. Friction and separator plates (9)
8. End gear carrier ball bearings (tapered set in A clutch)
9. End gear for “B” clutch
10. Rear tapered roller bearing
11. Center housing oil supply sleeve
12. Sealing rings
13. Snap ring and retainer
14. Belleville washers (6)
15. Lube blocker washer
16. Clutch apply oil passage (“B” clutch)
17. Clutch apply oil passage (“3” clutch)
18. Lube oil passage
19. End gear snap ring

SPEED CLUTCHES - DISASSEMBLY


The speed clutch assemblies are all identical with respect to the actual clutch components - all pistons, belleville springs, plates and retainers being common. End gears are of differing size and hub shape, and bearings vary in size and type. However the disassembly, inspection and overhaul procedure is identical. The following illustrations depict the 3/B speed clutch assembly, but the principles apply to all speed clutches.

1. Position the speed clutch assembly, 1, on suitable blocks, 2, or a support that will allow the assembly to sit securely in a vertical plane.




30

2. Pull off the front shaft support bearing, 1, and gear assembly, 2, using tool FNH 00101, 3, and a suitable shaft protector.




31

3. Note that the inner bearing, 1, of the end gears, 2, may remain on the shaft, 3. The bearing will be removed in a following step.




32

4. Invert the assembly and remove the rear end gear and carrier bearing assembly, 1, by repeating steps 1 and 2. Protect the oil passage with a suitable shaft protector, 2.




33

5. The clutch assembly, 1, may now be disassembled. Remove the clutch plate retainer snap ring, 2.



34


6. Invert the assembly, 1, and allow the clutch plate retainer, 4; clutch friction, 2; and separator plates, 3, to fall out.



35

7. If not previously removed, pull off the end gear inner bearing, 1, from the main shaft as follows:


   Using a 2-jaw puller, 2, and a suitable shaft protector, 3, pull the bearing from the shaft. Ensure that the cage is not damaged by the puller. A C-clamp, 4, may be required to hold the jaws securely when removing the taper roller bearings (4 places).



36


8. To release the belleville washers, it will be necessary to compress them to release the retaining snap ring, 1. Use the clutch spring compressor tool, FNH 00103, 2, in a press as follows:

   Position the clutch assembly in a suitable press. Using the FNH 00103 tool, compress the washers sufficiently to allow removal of the snap ring, 1. Remove the snap ring and the retainer ring, 3.



37


9. Remove the 6 belleville washers, 1, and the lube blocker washer, 2.
10. Repeat steps 8 and 9 on the opposite clutch.



38

11. Using an air supply, not exceeding 3 bar (50 PSI), apply the air gun, 1, to each of the two annular groove cross drillings, 3, to expel the two clutch pistons, 2.


IMPORTANT: *For safety, position the clutch assembly on a bench so the piston cannot cause injury when expelled.*



39

12. An exploded view of a complete speed clutch assembly is shown.
    1. Tapered roller carrier bearing
    2. Tapered bearing set, (7 parts)
    3. Input end gear (“1” clutch)
    4. Retainer snap ring
    5. Clutch plate retainer
    6. Friction and separator plates (9 each)
    7. Piston retainer snap ring
    8. Snap ring retainer
    9. Belleville washers (6 each)
    10. Lube blocker washer
    11. Piston and sealing rings
    12. Shaft assembly, 1/C clutch
    13. Roller bearing for end gear
    14. Output end gear (“C” clutch)
    15. Roller bearing for end gear
    16. Tapered roller carrier bearing
    17. Clutch apply sealing rings (3 each)

The 1/C clutch and the 3/B speed clutches use ball bearings, 13 and, 15, in the end gear, 14. All other speed clutches have a matched bearing set, 2, consisting of 7 pieces in the end gear.




40

SPEED CLUTCHES - INSPECTION


Before inspection of the transmission, consider the history of the transmission. If disassembly and overhaul has been dictated by a specific failure at relatively low service hours, a thorough examination of components will identify salvageable bearing, seals and other such items. If, however, the transmission has operated considerable service hours, then replacement of all bearings and seals is recommended.

1. Clean all parts in a suitable solvent and dry thoroughly using a clean, lint free cloth or compressed air.
2. Remove and discard the three annular groove sealing rings, 1.
3. Remove the inner, 2, and outer, 3, seals from the pistons and inspect both pistons for scoring or damage. Install new seals.




41

4. Check the clutch assembly shaft, 1, carefully, the center gear, 2, the two contained clutch housings, 3, for scratches, scores, excessive wear and piston scuffing. Any damage caused to the shaft during bearing removal should be carefully dressed using a suitable abrasive. Be sure to remove all traces of abrasive upon completion.



42

5. Check the clutch friction and separator plates, 1, for excessive wear; measure a new friction disc and separator plate. Measure the friction discs and separator plates from the transmission. If more than .10 mm (.004 in.) of wear is present, replace the friction discs or plates. All plates should be flat without warping, and there should not be excessive discoloration.
6. Inspect the two end gears, 2, examining the teeth for wear or pitting, and the clutch friction plate hub splines for wear or damage.
7. Make sure the snap ring, 3, separating the bearings in the front end gear and the “A” clutch end gear is in place and secure.



43


8. Inspect all bearings for wear, looseness and free running if these are to be reused. Consider the economic value of reinstalling new bearings versus the possibility of a further transmission removal and overhaul.

NOTE: *The A, 3, 2, and 1 speed clutches are all assembled with a matched bearing set consisting of two bearings, 3; two races, 4; an inner spacer, 5, and an outer spacer/snap ring retainer, 2. This assembly is only serviced as a set. The inner bearing race, 6, goes against the snap ring, 1; and the outer race goes against the snap ring retainer.*


9. Install new sealing rings to the shaft annular grooves. Make sure these rings are allowed to "resize" themselves to the grooves before reassembly to the center section.

10. Inspect the lube blocker washer, 1, and Belleville washers, 2, for deformation or damage. If necessary, compare these parts with a new part, using the new part as an example.


NOTE: *If any doubt exists as to the further service life of any component, assess the economic factor involved of a further transmission removal and disassembly cost versus the replacement cost of that particular part.*



44



45




46

1. Front tapered roller bearing
2. F2 gear and output shaft
3. Clutch piston
4. Lube blocker washer - (reverse clutch washer is drilled)
5. Belleville washers (8)
6. F2 drive gear
7. F2 drive gear ball bearings (the small bearing is shielded or sealed on one side)
8. Rear tapered roller bearing
9. Lube oil passage
10. Bearing spacer
11. Snap ring and retainer
12. Clutch retaining plate
13. Snap ring
14. Clutch friction and separator plates (11, 14 for F1 and Rev. clutch)
15. Clutch apply oil pressure gallery
16. Center housing oil sleeve
17. Sealing rings
18. O Ring (Directional clutches only)

DIRECTIONAL CLUTCHES - DISASSEMBLY

The directional clutches are similar to the speed clutches except that each of the assemblies houses just one clutch. The pistons and plates in F1 and reverse are identical to the speed clutches except that there are 14 friction plates and 14 separator plates. The reverse clutch has 15 separator plates. Piston seals and snap rings are also identical. In addition, note that directional clutches, F1 and R, are identical, including number of gear teeth and bearings. However, the 8th stage (Rev) shaft has a larger drilling lube orifice than the 6th stage (F1) shaft. the part numbers are not interchangeable. Directional clutch F2 has 11 larger friction and separator plates, a larger piston, retainer and belleville washer and has different gears and bearings. It also serves as the main output shaft.


1. Position the directional clutch, 3, on a suitable block or support that will allow the assembly to sit in a vertical plane. Pull off the shaft support bearings using a suitable puller, 1, making sure a suitable shaft protector, 2, is used.



47


2. Remove the snap ring, 1, retaining the end gear and bearing, 2.

NOTE: *F2 clutch does not have a snap ring at this location.*




48

3. Using the puller assembly, 1, positioned around the end gear, pull off the gear, 2. Note that similar to the speed clutches, the gear hub forms the carrier for the internally splined clutch friction plates.




49

4. Remove the clutch plate retainer snap ring, 1.
5. Invert the assembly, 2, and allow the clutch plate retainer and clutch friction and separator plates to fall out.




50

6. Pull the inner ball bearing, 1, using a two-jaw puller, 2.



51

7. Using the clutch spring compressor tool, FNH00103, 1, compress the belleville washers sufficiently to allow removal of the snap ring, 2. Remove the snap ring and the locking retainer ring, 3.
8. Invert the assembly and remove the 8 belleville washers and the lube blocker washer.




52


9. Using an air supply not exceeding 3 bar (50 PSI), apply the air gun, 1, to the annular groove cross drilling, 2, to expel the clutch piston, 3.

IMPORTANT: *For safety, position the clutch assembly on a bench so the piston cannot cause injury when expelled.*

An exploded view of a complete F1 or Reverse directional clutch assembly is shown in Figure 54.



53



54

1. Sealing rings (2)
2. End gear roller bearing (tapered on F2 clutch)
3. Snap ring (not used on F2 clutch)
4. End gear outer roller bearing
5. End gear
6. End gear inner roller bearing (with shield or seal on one side)
7. Snap ring and retainer
8. Clutch friction and separator plates (14) (11 for F2)
9. Piston snap ring and ring retainer
10. Belleville washers (8)
11. Lube blocker washer
12. Piston and seal rings
13. F1 or Reverse shaft assembly
14. End roller bearing
15. O Ring (Directional clutches only)

DIRECTIONAL CLUTCHES - INSPECTION AND OVERHAUL

As the directional clutches are very similar to the speed clutches, the inspection and overhaul procedure listed for these also applies to the directional clutches.

SPEED CLUTCHES AND DIRECTIONAL CLUTCHES - REASSEMBLY


Reassembly of the speed and directional clutches in general follow the disassembly procedure in reverse. However, note the following points:

1. Lubricate the piston seals and the clutch housing before assembling the piston into the housing.
2. Assemble the belleville washers in the pattern as shown in the assembly view, noting that the speed clutches use 6 washers and the directional clutches use 8 washers.
3. If new clutch friction plates are to be installed, lubricate the plates with transmission oil prior to assembly. If used plates are to be reinstalled, do not lubricate until plate stack height has been checked. This is not necessary if all new plates have been installed.


   Check the height as follows:

   a. Place a dial indicator with a long extension, 1, against the piston.
   b. Apply an air gun, 2, with at least 7 bar (100 PSI) pressure, to the piston oil supply port. With the air pressure applied, energizing the clutch, record the distance the piston moved. This measurement is the total piston movement and equal to the wear of the clutch plates and separator plates.
   c. If the measurement exceeds that specified (see Specifications), then the clutch plates and/or separator plates are not fit for further service and should be replaced.
   d. If the pack is within specified limits, remove the snap ring and retainer plate, 3. Remove the clutch plates and lubricate with transmission oil prior to assembly.
4. Install the clutch plates into the clutch housing starting with an externally splined separator plate. Install the clutch plate retainer and the snap ring, making sure the snap ring is fully seated.
5. Press the end rear inner bearing, 1, on the shaft using the bearing installer tool, FNH00544, 2, pushing on the bearing inner track.

NOTE: *Use the smaller OD end of the bearing installer tool on the tapered roller bearings to prevent damage to the bearing cage.*




55




56

6. Install O ring, 3, then, assemble the gear and its splined hub, 1, to the shaft over the installed inner bearing, 2. Ensure that the splined hub engages with each friction plate. Do this by lightly supporting, by hand, some of the weight of the gear and its hub while allowing it to rest slightly on the next spline to be engaged. Swift rotational backward and forward movement of the hub within the plates will engage each of the internally splined friction plates and allow the gear and hub to drop one by one through the plates until all plates are positioned on the gear hub. Under no circumstances should the gear and hub be forced through the plates.



57


7. Press the remaining bearings in a similar fashion and install the snap ring, 1, on the F1 and Reverse clutches as identified in the sectional views.



58

8. Press the large speed clutch end bearing, 1, in place using bearing installer FNH00543, 2.

   Tapered roller end bearings are installed on all speed clutches and the F2 directional clutch only.




59

MAIN INPUT GEAR AND OIL SEAL - DISASSEMBLY INSPECTION, OVERHAUL AND REASSEMBLE


Disassembly of the main input gear and oil seal is limited to removal of the oil seal, outer O ring seal, and the bearings.

1. Remove the oil seal, 1, by carefully prying it from the housing, 2.



60

2. Inspect both front and rear bearings, 4, for looseness and wear. If necessary, pull off the bearings using bearing splitters and two jaw pullers with a suitable shaft protector.
3. Inspect the gear, 5, for wear or pitting and the shaft spline for fretting.
4. Press on new bearings, if required, using a suitable installer pushing on the inner track.
5. Inspect the front cover O ring groove, 2, for any nicks or burrs; remove any using an abrasive stone.
6. Press the bearing race into the carrier.
7. Install a new O ring, 3, on the front cover outer diameter.
8. Gently press a new oil seal, 1, into the center of the front cover, making sure the oil seal lip is facing inward towards the oil.




61

TWO GEAR CLUSTERS IN FRONT AND REAR HOUSING - DISASSEMBLY, INSPECTION AND REASSEMBLY

Overhaul of the three two gear cluster assemblies is confined to inspection of the gear teeth, the bearings and splines.


1. Inspect the gear teeth, 2, on each of the three clusters for excessive wear and pitting.
2. Inspect the splines, 3, of the two mating assemblies, one internal, one external, for excessive wear and looseness.
3. Inspect each bearing assembly, 1, for wear and looseness; if necessary, pull off the bearings from the shaft using bearing splitters and two-jaw pullers.
4. Install new bearings using a press and the FNH00543/FNH00544 bearing installers or a suitable diameter installer pressing on the inner track.



62


FRONT AND REAR HOUSINGS AND CENTER SECTION - INSPECTION AND OVERHAUL

1. The three main housings are doweled together at two opposing points on each face joint. Make sure all four dowels, 2, are undamaged and in place.
2. Inspect all three housings for damage including each bearing bore, 1. If bearings have been found excessively worn, make sure the respective bore is undamaged.
3. A split or “jiggle” pin is located in the lower part of the front housing. Check that this pin is present and free to “jiggle.” This pin allows any engine or transmission oil leakage to escape from the front housing and be identified.




63

4. Each of the speed and directional clutches have oil for control of the clutch actuating pack fed to the ends of the clutch shaft. Located in the center section, 1, forward face, for the speed clutches, are three removable sleeves, 2, and in the rear side three removable sleeves for the directional clutches. Inspect these sleeves for wear and damage. If necessary, extract the sleeves using a slide hammer and puller, FNH00105, 3. It is important during removal that the bore in the center section is not damaged.



64

5. Install new sleeves using a suitable step plate adapter. Ensure that the correct sleeve is installed in the center section before driving in the sleeves. Directional sleeves, 1, have two holes and speed sleeves, 2, have four.




65

TORQUE LIMITING CLUTCH AND SPRUNG DAMPER HUB DRIVE ASSEMBLY - REMOVAL, INSPECTION AND REPLACEMENT


The torque limiting clutch and sprung damper hub assembly, 1, bolted to the engine flywheel, 2, should be removed and inspected.

1. Remove the damper assembly from the engine flywheel by removing the eight retaining bolts, 3.
2. Inspect the input shaft spline for wear and fretting, and inspect for any looseness between it and the damper assembly.




66

3. Remove the sixteen inner damper bolts, 1.



67

4. Inspect the lining face, 1, and the sprung hub, 2, for wear of the lining face and looseness of the springs, 4, in the spring pocket area.
5. Inspect the splines, 3, in the sprung hub for excessive wear.
6. Reassembly of the torque limiting clutch and sprung hub assembly follows the disassembly procedure in reverse.
7. Tighten the pressure plate retaining bolts to 46 N·m (34 ft. lbs.).



68


REASSEMBLY

SPEED CLUTCHES AND FRONT HOUSING

1. Install the main input shaft and gear assembly, 1, into the front housing. Use alignment studs, 2, to install the front cover, 4, and shims, 3.


NOTE: *The front cover notch, 5, should be installed at the 9 o'clock position.*

2. Tighten the eight retaining bolts to 27 N·m (20 ft. lbs.). Rotate the front housing onto a flat surface with the center housing mating surface up.




69

3. Reassembly of the speed clutches into the front housing is as follows:
   - 1/C clutch first, 1.
   - 3/B and 2/A clutch assemblies using FNH00102 lifting tool, 2.
   - Raise 3/B and 2/A clutch slightly.
   - Insert front two gear cluster, 4.
   - Lower 3/B and 2/A clutch, 2.



70


4. Make sure the sequence of disassembly is exactly reversed when installing each assembly.
5. Liberally lubricate each assembly with transmission/rear axle oil, making sure each bearing and each of the annular groove areas and sealing rings is fully coated.
6. Make sure the aligning dowels, 1, are threaded into the front housing and a new gasket is used before installing the center section, 2. With the lifting eyes, FNH00106, 3,installed, use a sling, 4, to lower the center housing onto the front housing. During this operation it is essential that the center section is lowered or parallel to the front section. The annular grooves and seals of the speed clutch shafts and the shaft bearings must enter the housing without damage.



71


DIRECTIONAL CLUTCHES AND REAR HOUSING

1. Reassembly of the three directional clutches, the transfer gear and the two gear cluster again follows the disassembly procedure in reverse.
2. Thoroughly lubricate the annular grooves and seals on the front end of the clutch shafts and the bearings.
3. As with the speed clutches, make sure the sequence of disassembly is exactly reversed during assembly as follows:
   - F2 clutch first, 1.
   - F1 and 2 gear cluster, 2.
   - Reverse clutch, 3.
   - Output transfer gear last, 4.




72

4. Install the F2 clutch oil splash shield, tightening the two retaining bolts to 27 N·m (20 ft lbs).
5. Install a new gasket, 4, on the center section, 3. Using the lifting eyes, FNH 00107, 1, and a sling, raise the rear housing, 2. Make sure the rear housing is perfectly aligned to allow the bearings to enter the bores cleanly. Slight bumping of the rear housing may be necessary to fully seat the housing.
6. Remove the guide bolts, 5, and install the nineteen housing retaining bolts.




73

7. Check the clutch apply circuits for leaks by pressurizing the ports as shown. If large amounts of escaping air can be heard, investigate the cause.




74

8. The nine clutch apply ports can be identified on the valve mount with a paint pen.



75


9. Install the control valve assembly with a new gasket, tightening the retaining bolts in the sequence shown starting with bolt, 1. Tighten bolts progressively to 27 N·m (20 ft. lbs.).



76

TRANSMISSION SHIMMING

Both ends of the transmission require shimming to prevent internal damage. The front housing has four shimmable shafts and the back housing has two. To begin shimming, rotate the transmission, 1, in a horizontal position and install the transmission arbor tool, 2.




77

FRONT HOUSING SHIMMING

The input shaft must be rotated using the transmission arbor tool, then shimmed to 0.025 - 0.125 mm (0.001 - 0.005″) end play as follows:


1. Install a dial indicator, 2, to measure input shaft movement.
2. Grasp the shaft, 1, then push and pull. Record the dial indicator reading.
3. If end play exceeds 0.125 mm (0.005″), remove the cover, 3, and remove shims to achieve proper end play.
4. If no end play is recorded, remove cover and add shims to achieve proper clearance.



78

The three speed clutches must be rotated using the transmission arbor tool, then shimmed to 0.025 - 0.125 mm (0.001 - 0.005″) as follows:

1. Make sure caps, 1, are properly torqued.
2. Remove both plugs in each cap.
3. Install a 5/16″ x 4″ cap screw into the center of a speed clutch shaft (a “T” handle, 2, can be made by welding a piece of round stock to the bolt).
4. Push and pull on the “T” handle to check end play.
5. If the shaft has end play, install a dial indicator, 3, through the outer hole to contact the end of the shaft.
6. Push and pull the T handle and record the shaft end play. If in excess of 0.125 mm (0.005″), remove the end cover and remove shims to achieve proper clearance.




79

7. If end play is less than 0.050 mm (0.002″) or no movement, remove end cover, 1, and add shims, 2, to achieve the proper end play.

NOTE: *Check end play only with end cover properly torqued and after transmission is rotated using the transmission rotation arbor.*

8. Reinstall end cover plugs, 3, with sealer.

   Check the two remaining speed clutch shafts for proper end play. Adjust following the previous procedure.




80


REAR HOUSING SHIMMING

The rear housing has two shafts that must be shimmed; the main output shaft and the transfer shaft that is retained by the PTO carrier cap. The PTO cap is shimmed to 0.150 - 0.250 mm (0.006 - 0.010″) and the output shaft to 0.025 - 0.075 mm (0.001 - 0.003″) as follows:

1. Rotate the transmission gears using the transmission rotating arbor, FNH00545, 1, installed in the transfer shaft.
2. Push and pull on the tool to make sure the shaft has some end play. If there is no end play, remove the end cap, 3, pull the race, and remove a shim.
3. Reinstall and torque the end cap retaining bolts. Make sure the shaft has end play.
4. Install a dial indicator with a long extension, 2, down the bore of the end cap, 3.
5. Push and pull the shaft using the rotation tool and measure the end play.
6. If the shaft has too little end play, remove the end cap, 1, and bearing race, 2, and remove a shim, 3. If the shaft has too much end play,add a shim.
7. Reinstall the end cap and torque the bolts. Recheck the end play until 0.150 - 0.250 mm (0.006 - 0.010″) is achieved.



81




82

SHIMMING THE OUTPUT SHAFT


1. Rotate the output shaft by turning the transmission arbor tool.
2. Push and pull the output shaft, 2, to ensure it has end play.
3. Install a dial indicator, 4, and check for 0.075 - 0.175 mm (0.003 - 0.007″) end play by pushing and pulling the shaft, 2.

NOTE: *Using the FNH 00546 eye, 3, in the end of the shaft will aid in pushing and pulling the shaft.*




83

4. If there is no end play, remove the end cap, 1, and remove a shim, 2, from under the bearing race.
5. Reinstall the end cap, retorque the bolts and recheck for end play.
6. Add or remove shims as with the previous shaft to adjust end play to achieve the proper clearance.



84


7. Reinstall the PTO shaft, 1, bearing and snap ring.



85


CREEPER GEAR

The optional factory-installed creeper reduction gear consists of a double set of planetary gears that provide an additional 10.609:1 reduction of all forward and reverse gear speeds. The reduction gears, 1, are mounted on the output shaft.




86

Creep is engaged by a rocker switch, 3, on the front operator's console. The operator knows that creep is engaged by the letter "C," 1, and the gear, 2, selected being displayed in the EIC on the dash.



87


The switch operates as electrohydraulic solenoid, 1, mounted on the top rear transmission housing. A pressure test port, 2, is provided on the left side of the transmission housing.



88

Direct Drive


In direct drive, the outer ring gear moves rearward due to spring-loaded pistons, 1, in the transmission housing. This causes the ring gear to engage the drive gear, 2, on the output shaft, 3. The entire planetary set rotates at output speed.




89

Creep (Reduction) Drive

When creep is engaged, low-pressure hydraulic oil is provided to the pistons which forces them into the housing and the ring gear, 2, moves forward. The ring gear engages a stationary gear, 3, on the rear housing and prevents rotation. The first planetary set, 4, begins to rotate inside the ring gear and its output drives the second planetary set, 1, to its output which is attached to the rear axle. The double reduction reduces the transmission output speed from 10.609 to 1.



90




91

CREEPER GEAR REPAIR


Solenoid Valve Disassembly

1. Disconnect the supply tube to the creep solenoid valve, 1.
2. Remove the two retaining bolts, 2, and remove the valve assembly.



92

3. Remove the solenoid retaining nut and remove the solenoid.
4. Remove the core and valve assembly, 2, from the holder, 1.
5. Clean the assembly with a suitable solvent and inspect all parts of the valve for wear and damage.




93

Solenoid Valve Reassembly

1. Reassemble the valve in reverse order. Use new seals and gaskets, 3. Torque the valve retaining bolts to 27 N·m (20 ft. lbs.).


Creep Gear Disassembly

1. Remove the output shaft retaining bolt, 1.
2. Remove the piston disc snap rings and washers, 2.




94

3. After removing the retaining bolt, 3, pull the planetary gear set, 2, and ring gear, 4, from the transmission output shaft.
4. Remove the two piston retaining nuts and the pistons assemblies, 1, from the transmission housing.
5. Remove the creep stationary gear from the transmission housing by removing the sixteen bolts.



95




96

6. On a clean bench, disassemble the planetary gear set by sliding the components apart. One snap ring must be removed from the rear planetary gear set to allow the thrust washer and bearing to be removed. Lay all parts out in order to aid in reassembly.

Reassembly


1. Inspect all parts for damage and wear. If wear is noticed, inspect the lubrication orifice in the transmission output shaft.
2. Reassemble the planetary assembly, 1, in reverse order of disassembly.

NOTE: *Washers, 3 and 5, must be installed with chamfer away from thrust bearing, 4, on spacer, 2.*




97

3. Install the creep stationary gear, 1, on the transmission and torque the bolts to 54 N·m (40 ft. lbs.).
4. Install the pistons, 2, into the transmission housing. **DO NOT** install the discs on the pistons.



98


5. Slide the assembled planetary gear set, 1, on the output shaft while at the same time engaging the discs, 2 and 3, for the pistons into the grooves on the side of the ring gear.
6. Install washers and snap rings on each piston.
7. Install the output shaft retaining bolt and torque to 76 N·m (56 ft. lbs.).



99

INSTALLATION

1. Install the transmission as described in Section 21, Chapter 2 - Separating the Tractor.
2. Make sure all electrical components are correctly installed.
3. Fill the hydraulic system with fresh oil to the quantity and type described in Section 35, Chapter 1 - Specifications.
4. Pressure test and calibrate the transmission assembly as detailed in Chapter 5 - Hydraulic Components.


70-220-786

100

SECTION 21 - TRANSMISSION

Chapter 5 - Hydraulic System

CONTENTS

Section	Description	Page
21 000	Specifications	3
	Low-pressure Hydraulic System	3
	Special Tools	4
	Description of Operation	5
	Regulator Valve Operation	7
	Clutch Valve Operation	7
	Modulator Valve Operation	8
	Electro-hydraulic Pilot Line	9
	Troubleshooting and Diagnosis	10
	70/70A Series Transmission Test Sheet	11
	Electrical/Electronic System Checks	11
	Hydraulic System Checks	13
	Clutch Apply Pressure Chart	14
	Pressure Testing and Adjustments	15
	Clutch Apply Circuit Pressure Testing	17
	Transmission Pressure Checklist	19
	Transmission Programming	21
	Programming the Programmable Upshift, Downshift	21
	Programming Reverse Gear Ratios	23
	Transmission Calibration	25
	Check Powershift Transmission Clutch Calibration	25
	Calibration Review	26
	Calibrate F1 Directional Clutch	26
	Calibrate F2 Directional Clutch	27
	Calibrate Reverse Directional Clutch	27
	Exit Calibration Mode	28

Calibration of Shift Constant 28
Disassembly and Repair 31
Removal and Disassembly 31
Removal of the Complete Valve Assembly from the Tractor 31
Disassembly 33
Solenoid and Valve Assembly 34
Speed and Directional Clutch Circuit Valves 34
Modulator Valves 35
Regulator Valve 37
Lubrication and Cooling Circuit Relief Valve 39
Removal 39
Installation 39
Inspection 40
Reassembly 40
Installation 41

SPECIFICATIONS

LOW-PRESSURE HYDRAULIC SYSTEM

Pump

Type	Positive displacement spur gear, mounted on right side of the rear axle housing.
Capacity	Minimum of 117 L/min (31 GPM) @ 57° C (135° F) and 2100 ERPM

Lubrication

Source	Pressure and flow from low-pressure pump, oil from rear axle and transmission.
Lube relief setting	6.2 - 9.3 bar (90 - 135 PSI) factory set, non-adjustable.

Cooler

Type	Oil to air mounted in front of engine radiator
Capacity	Minimum of 92 L/min (22 GPM) @ 57° C (135° F) and 2100 ERPM

Filtration

Type	Spin-on 10-micron high capacity with electrical restriction warning light and bypass facility.
Filter bypass	Differential pressure 2.0 bar (30 PSI)
Warning light	Differential pressure 1.7 bar (23 PSI)

Transmission Control Valve

Type	Separate casting, Multi-spool with internal cast-in galleries
Control	Electrically operated solenoid coils signalled by the ETC module
Regulated pressure	16.5 - 18.9 bar (240 - 275 PSI) @ 57° C (135° F) and 2200 ERPM Shim adjustable
Modulating valve pressure	Factory set, non-adjustable

Torques


Valve body retaining bolts	27 N·m (20 ft. lbs.)
Valve body spool plugs (large)	74 N·m (55 ft. lbs.)
Valve body plugs (small)	23 N·m (17 ft. lbs.)
Solenoid retaining nuts	8 N·m (6 ft. lbs.)

SPECIAL TOOLS

DESCRIPTION	TOOL NUMBER	USAGE
PD male quick coupler	FNH 00533	Pressure checks
PD female quick coupler	FNH 00535	Pressure checks
Adapter	FNH 00035	Connects test hose to PD coupler
Hose, test	FNH 07099	High-pressure hose with fittings
Gauge, pressure	FNH 02027	600 PSI mechanical gauge
Gauge, pressure	FNH 02026	100 PSI mechanical gauge
Adapter	FNH 00110	Low-pressure pump flow
Adapter	FNH 00538	Low-pressure pump flow
Hydraulic flowmeter	FNH02760	Low-pressure pump /cooler flow
Gauge set	FNH02990A	12-gauge bar and hose set

DESCRIPTION OF OPERATION

The electrohydraulic transmission control valve assembly is mounted externally on the right-hand side of the transmission housing center section. The valve functions to perform the actual application and release of the speed clutches and the directional clutches.



1


The main control valve contains twelve separate hydraulic valves - the regulating valve and eleven valves which are actuated by electronically energized coils. Of these eleven electronically actuated valves, nine control the application of the six speed and three directional clutches, while the two remaining valves control modulating circuits - one for the F1 (forward 1) directional clutch and the other for the F2 (forward 2) and REV (reverse) directional clutches.

The two modulation valves, MC1 and MC2, control the apply pressure of the directional clutches:


1. Whenever they are first energized.
2. When the transmission is shuttled to change direction.
3. In all upshifts using the F2 clutch pack.
4. Anytime the inching pedal is used.

The energization of the valve, 1, and modulator circuits is controlled by the electronic management system, 3, which in turn is signaled by the in-cab control lever, 2, and the foot operated inching pedal, 4.

A regulating valve within the main control valve assembly, set at 16.5 - 18.9 bar (240 - 275 PSI), maintains a constant oil pressure for the tractor low-pressure circuit which controls the power brake valve, the PTO clutch, Diff-lock and four-wheel-drive engagement clutch.



2




3

1. Speed clutch assemblies (6)
2. Cooler assembly
3. Direct acting solenoids (9)
4. Pressure regulating valve
5. Transmission filter
6. Tandem gear pump
7. Modulator solenoids (2)
8. Lube relief valve
9. Directional clutches (3)

The low-pressure hydraulic circuit provides oil to the control valve by the tandem gear pump, 6, via the external filter, 5. The main regulator valve, 4, maintains a pressurized oil supply to each of the nine clutch circuits, 3, the modulator valves, 7, and a supply for the tractor low-pressure circuit. The oil flow from the hydraulic pump continues past the regulator valve to the lubrication and cooling circuit, passing a lube and cooling circuit relief valve, 8, and the cooler assembly, 2, mounted in front of the engine radiator, and an internal bypass port cast into the main control valve housing. The external cooler handles only a proportion of the total lubrication and cooling oil flow. All excess flow is passed through the internal bypass port directly to the transmission lubrication and cooling circuit. The main purpose of the control valve is to supply oil to apply the speed clutches, 1, in the front of the transmission and to modulate the apply pressure to the directional clutches, 9, in the rear of the transmission.

REGULATOR VALVE OPERATION

Pump oil, present in gallery A, of the control valve assembly, 2, which is also linked to the clutch circuits at gallery B, cannot escape until the regulator spool, 5, has moved to the right. Oil enters the hollow spool through an opening and via a removable orifice plate, 1, incorporated for cushioning purposes, which acts on the left side of the spool. This oil pressure moves it to the right, against the opposing force of the two springs, 3, and the pressure adjustment shims, 4. As the spool moves, pump oil, surplus to that required for operating the speed clutches, directional clutches and modulating valves, moves on to the lubrication and cooling circuits via gallery C.




4

CLUTCH VALVE OPERATION

Each of the nine clutch circuit valves operates in an identical manner. However, the directional clutch application circuits are modulated or proportionally controlled, allowing their application and release to be cushioned and feathered when required.

The nine clutch circuits operate on a simple open or shut basis. Oil from the now regulated pressure gallery A is not allowed to pass to the clutch supply port, S, by the position of the clutch circuit valve spool, 1. The coil spring, 2, holds the valve in the closed position.




5

With the coil, 1, energized, the core of the valve, 2, is magnetically drawn into the surrounding tube, 3, allowing the clutch circuit to open to the regulated oil supply.

The coil spring, positioned in the hollowed end of the valve core acts as a shock absorber when the valve is energized, and a return device when the electrical signal is removed to close the valve.

Any oil leaking past the valve from the regulated pressure supply will exhaust to the peripheral gallery R connected to sump. When the valve closes, oil within the clutch pack can return to sump from gallery S to R.



6


MODULATOR VALVE OPERATION

The modulator valve, 3, controlled by the Electronic Transmission Controller (ETC), proportionally varies the pressure being sent to the directional clutches - the variation being determined by the degree of movement of the valve, 10, controlled by the strength of the electrical signal from the electronic management system.

Oil from the regulated oil pressure gallery, A, passes around the waisted section of the modulating spool, 10, to gallery, D, which in turn, is connected to the directional clutch circuit valves. As the solenoid coil, 4, in this situation, is not energized, oil passing into the center of the spool from passage A to D cannot overcome the same oil pressure which is present in chamber E, and assisted by the force of the spring, 9.

The solenoid coil, 4, has now been energized and the pilot valve spool, 7, is drawn off its seat, 8,inside the solenoid housing, 6. This allows oil to flow from chamber E, over the pilot seat to sump at R. The degree of flow is controlled by the removable orifice, 2, (which is protected by a filter screen, 1) and the amount the pilot valve is drawn off its seat.


The degree of pilot valve movement is dictated by the strength of the current supplied to the coil, 4.When the current is turned off, return spring, 5, reseats the pilot valve, 7, on its seat, 8.



7

As the oil flows across the pilot valve seat, the pressure in chamber E reduces, dependent on the rate of flow, and unbalances the modulating spool, 10, causing it to move to the right. This allows pressure at gallery D to be regulated by the throttling action of the spool as it opens the gallery, R, to sump.

Depending on the strength or degree of electrical current supplied to the proportional valve solenoid and the timing of the opening of the clutch circuit valve, speed of application and release of the directional clutches will be controlled. All signals to the solenoids are controlled by the ETC. Refer to Chapter 4 for additional information on the ETC and electrical system.




8

ELECTRO-HYDRAULIC PILOT LINE

NOTE: *70A Series tractor only.*

The electro-hydraulic pilot line, 1, supplies transmission regulated pressure to the remotes as pilot oil to assist up to 10 electro-hydraulic solenoids (depending upon how the tractor is equipped), in shifting the remote valve main spools and EDC spool. The pilot line connects from the transmission main pressure port, 2, to the remote assembly top cap, Figure 9. An inline screen helps protect the EHR pilot valves from contaminants.



9

TROUBLESHOOTING AND DIAGNOSIS

PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor won't move after starting	Flashing "F" "R" "P" "U" or "d" Transmission operation performed out of sequence	Return shift control lever to neutral and release parking brake. See "Operator Prompts."
Poor inching control when using inching pedal	Transmission clutches out of calibration	Re-calibrate transmission clutches F1, F2 and R. See "Hydraulic Components" - Chapter 5.
	Clutch potentiometer	Replace the clutch potentiometer.
	Clutch spring	Replace the clutch spring.
Transmission will not operate	Fault code displayed indicating malfunction	See "Fault Codes" Electrical System - Section 55, Chapter 2.
Low transmission oil pressure warning lamp on	Low oil supply	Fill system with oil. See "Hydraulic Components" - Chapter 5.
Transmission filter lamp on	Clogged transmission oil filter	Replace filter.
Tractor drives in limited gears	One or more solenoids inoperative	Compare working gears to Clutch Apply Pressure Chart (Chapter 5) to determine faulty solenoid.
Tractor stalls in limited gears	More than 3 clutches engaged at one time	Compare non-working gears to Clutch Apply Pressure Chart (Chapter 5) to determine faulty clutch.

70/70A SERIES TRANSMISSION TEST SHEET

1. Date: _____ Dealer Code: _____ Dealer Contact: _____
2. Phone Number: _____ Dealership Name: _____
3. Model: _____ Tractor Serial Number: _____ Hours: _____
4. Transmission Serial Number: _____
5. Description of Concern: Be Specific (Won't move, erratic operation, harsh shifting, intermittent problems, inability to calibrate, noisy…). What is the actual customer Complaint?

_____

_____

_____

_____

If tractor will not move, was Limp Home harness tried with what results? _____

6. Check the condition of the inching pedal return spring? _____

ELECTRICAL/ELECTRONIC SYSTEM CHECKS

NOTE: *Refer to Section 3 - Electrical system for detailed information on accessing and using the various EIC Modes identified or the 70 Series Portable Diagnostic Tool Instruction manual (FNH00507) for information on using PDT.*

7. Record stored Clutch Calibration Values (Mode 10 or PDT): F1 _____ F2 _____ R _____
8. Record Hardware and Software Versions (Mode 9 or PDT):

	Hardware	Software		Hardware	Software
EIC	_____	_____	RHC	_____	_____
ETC	_____	_____	EDC	_____	_____

9. Record system status of each module (with key switch on). Circle one in each row.

EIC Status Light:	FLASHING	STEADY	OFF
RHC Status Light:	FLASHING	STEADY	OFF
CCM Status Light 1:	FLASHING	STEADY	OFF
CCM Status Light 2:	FLASHING	STEADY	OFF

10. Record fault codes: (Mode 2 or PDT)

Fault Code	Description	Hour of last occurrence	Number of occurrences	Current	Stored

70/70A SERIES TRANSMISSION TEST SHEET

11. Check condition of Fuses (Pull and Examine):
    MFP-2 _____ MFP-3 _____ MDP-F25 _____ MDP-F21 _____
    MDP-F18 _____ MDP-F19 _____ MDP-F20 _____

12. Check condition of Relays: _____ MDP-R11_____ MDP-R6 _____ (Install known good relay.)

13. Check condition of Grounds: Remove, clean, re-install (Repair manual page ????).
    Cab Main Rear _____ Rear Main _____ Cab to Chassis _____ Battery _____
    Cab Main Front _____ Front Main _____ Cab to Chassis Ground Strap _____

14. Check condition of Connectors (corrosion, damaged, loose…) Disconnect, inspect, install.
    C001 _____ C002 _____ C003 _____
    C005 _____ C006 _____ C007 _____

15. Perform Module Input Checks (Mode 3 or PDT): All switches must indicate a "HI" (single tone) and "LOW" (pulse tone) response. Correct any defects.

	HI	LOW		HI	LOW
Neutral switch P108	_____	_____	Inching pedal potentiometer P215 (range)	_____	_____
Downshift P109	_____	_____	Transmission enable P107	_____	_____
Up-shift P110	_____	_____	Reverse P111	_____	_____
Forward P112	_____	_____	Programmable downshift P113	_____	_____
Auto-shift P115	_____	_____	Programmable up-shift P114	_____	_____
Park brake P203	_____	_____	Creeper P110 (if equipped)	_____	_____

    Was the inching pedal transition smooth? _____

16. Perform ETC Module Output Checks (Mode 7 or PDT): Check each parameter for a "HI" (single tone) and "LOW" (pulse tone). A "HI" indicates the ETC has sent voltage to the solenoid and "LOW" indicates the ETC has turned the solenoid off. Verify the operation of each solenoid by checking for voltage at the solenoid when turned on and off.

		Parameter Test			
Solenoid	Parameter	**LOW**	**Sol Volt**	**HI**	**Sol Volt**
F1	P350*				
F2	P351*				
R	P352*				
1	P353				
2	P354				
3	P355				
A	P356				
B	P357				
C	P358				
Creeper	P359				
MC1	P360**				
MC2	P361**				

    * Parameter Will only work when shift lever is in forward position.
    ** Did voltage start high and modulate to low? _____

17. Calibrate and record new Clutch Calibration Values: F1 _____ F2 _____ R _____

70/70A SERIES TRANSMISSION TEST SHEET
HYDRAULIC SYSTEM CHECKS

18. Perform low pressure circuit relief pressure check (transmission main regulator valve).
    Pressure _____ 1724 - 1896 kPa (240 - 275 PSI)

19. Check MC1 and MC2 filter screens.

	Damaged		Clogged	
MC1 filter screen	Yes	No	Yes	No
MC2 filter screen	Yes	No	Yes	No

20. Check hydraulic system for evidence of contamination.

Check	Contamination		Description
Suction Screen	Yes	No	_____
Transmission Filter	Yes	No	_____
Hydraulic Filter	Yes	No	_____

21. Verify operation of solenoid valve assemblies. Swap solenoid/valve assemblies. All solenoid assemblies are interchangeable with each other except MC1 and MC2. MC1 and MC2 can only be interchanged with each other. Did the problem move from one gear to another? NO /YES (if yes replace solenoid assembly).

22. Verify operation of solenoid valve assemblies. Swap solenoid/valve assemblies. All solenoid assemblies are interchangeable with each other except MC1 and MC2. MC1 and MC2 can only be interchanged with each other. Did the problem move from one gear to another? NO /YES (if yes replace solenoid assembly).

23. Install Limp Home Harness in the following sequences to verify operation of clutch packs (F1, F2, 1, 2, 3, A, B, & C). ***NOTE:*** *Disconnect all wires to transmission solenoids, including MC1 and MC2 when connecting limp home switch.*

	Limp home Connectors				**Tractor Moves**			
	F1	**R**	**2**	**B**	**Forward**		**Reverse**	
Gear					YES	NO	YES	NO
F1	F1	R	1	A				
F2	F1	R	2	A				
F3	F1	R	3	A				
F4	F1	R	1	B				
F7	F1	R	1	C				
F8 DOWN	F2	R	1	A				

WARNING

When using the limp home harness there is no transmission modulation. The tractor will lunge in the direction of travel when the limp home switch is pressed.

24. Other Comments: Explain any condition or additional troubleshooting procedure not covered.

_____

_____

_____

_____

70/70A SERIES TRANSMISSION TEST SHEET

25. Perform Clutch Apply Pressure Check using the following chart.1

CLUTCH APPLY PRESSURE CHART

GEAR	PORT	PSI	PORT	PSI	PORT	PSI	COMMENTS
F1	1		A		F1		
F2	2		A		F1		
F3	3		A		F1		
F4	1		B		F1		
F5	2		B		F1		
F6	3		B		F1		
F7	1		C		F1		
F8-UP	2		C		F1		
F8-DOWN	1		A		F2		*
F9-UP	3		C		F1		
F9-DOWN	2		A		F2		*
F10	3		A		F2		*
F11	1		B		F2		*
F12	2		B		F2		*
F13	3		B		F2		*
F14	1		C		F2		*
F15	2		C		F2		*
F16	3		C		F2		*
R3	1		A		R		*
R4	2		A		R		
R5	3		A		R		
R6	1		B		R		
R7	2		B		R		
R8	3		B		R		
R9	1		C		R		
R10	2		C		R		
R11	3		C		R		

Shaded areas is the transmission gear overlap.

Record F8-UP and F9-UP when checking up-shifts.

Record F8-Down and F9-Down when checking downshifts.

***NOTE:** Does modulation in the designated F port when shifting from N to R, N to F, F to R, R to F and all F2 up-shifts? Comments* _____

PRESSURE TESTING AND ADJUSTMENTS


This section will be divided into two parts.

1. Pressure Testing and Adjustment
2. Transmission Calibration

Insure the system is working electrically before proceeding with pressure testing and adjustments. See Chapter 6 for additional information.

PRESSURE TESTING AND ADJUSTMENT

If the operator complains of a hesitation during shifts or notices the transmission pressure lamp, 1, on during tractor operation, the low-pressure circuit relief should be checked.




10

To check the low pressure circuit relief pressure:


NOTE: *70 Series art shown in Figure 11. 70A Series art shown in Figure 12.*

1. Operate the transmission and or hydraulic system until the oil reaches an operating temperature of 57° C (135° F).
2. Park the tractor an a level surface, stop the engine and apply the parking brake.




11

3. Install a 40 bar (600 PSI) gauge FNH02027 and a PD female quick coupler FNH00535 to the PD male test port, 2, at the bottom right corner of the transmission control valve, 1.
4. With the parking brake applied, start and run the tractor at 1200 RPM.
5. The pressure reading should be 16.5 -18.9 bar (240 - 275 PSI).
6. If the pressure is lower or higher than specified, stop the engine and re-shim the pressure regulating valve as follows.



12

7. Carefully remove the spring retainer cap, 3. The springs, 2 and 7, are loaded and may escape when the cap is removed.
8. On the cap will be a large washer, 6, and adjustment shims, 5. Add shims to increase or remove shims to decrease pressure as required.
9. Reinstall the spring retaining cap with all items, 1 through 7, in place and retest system pressure.




13

CLUTCH APPLY CIRCUIT PRESSURE TESTING

To test the individual clutch apply circuits, it is imperative the pressures be logged in sequence of the Clutch Apply Pressure Chart. Only three clutches should be engaged at one time - a lettered speed clutch, a numbered speed clutch and one of the directional clutches. The use of a transmission pressure checklist will assist in locating a transmission fault.


To test the clutch apply circuits, proceed as follows:

1. Operate the transmission and/or hydraulic system until the oil reaches an operating temperature of 57° C (135° F).
2. Park the tractor on a level surface, stop the engine and apply the parking brake.



14

3. Connect a 40 bar (600 PSI) gauge FNH02990A, 1, and a PD female quick coupler FNH 00533 to the PD male quick coupler FNH 00535 installed in the “A” test port, 2, at the top right corner of the transmission control valve.
4. Connect a 40 bar (600 PSI) gauge FNH02990A in the “1” test port, 3, at the top right corner of the transmission control valve.




15

5. Install a 40 bar (600 PSI) gauge FNH02990A in the “F1” test port, 4, at the bottom left corner of the transmission control valve.
6. Start the tractor and select Forward, first gear and record pressures at the three gauges.

⚠ WARNING ⚠

Use long hoses to allow the gauges to be viewed from the operator’s seat. do not view the gauges while in the area of the tires. If required, place the tractor on suitable stands at all four corners to pressure test the transmission.




16

NOTE: *If three gauges are not available, pressures can be checked at each location one at a time.*

If a multi-gauge set, FNH02990A, 1, is available, nine gauges can be used to check the entire valve stack at one time. This is the preferred method.


7. If the number of gauges are limited, repeat steps 2 through 6, installing the fittings and gauges as required to check all nine clutches.
8. Record all tractor information and pressures on a photocopy of the following pages.



17

9. After pressure checks have been completed, compare the reading between the applied clutches. All readings should be within 10% of each other. If one or more clutches are extremely low, a stuck valve or major leak may be indicated. If no pressure reading is recorded, make sure the clutch is electrically engaged. If pressure is indicated when a clutch is turned off, an internal leak could be bleeding oil across a clutch pack or a sealing ring failure could have occurred.


NOTE: *Transmission and cooler flow testing is covered in Section 35, "Hydraulics."*



18

TRANSMISSION PRESSURE CHECKLIST

Locate transmission identification plate, 1.




19

1. Tractor model number _____
2. Tractor serial number _____
3. Transmission serial # _____
4. Hours of operation _____

NOTE: *70 Series art shown in Figure 20.*


5. Main transmission, 1, pressure_____ using PD coupler, 2. Pressure will normally be 16.5 - 18.9 bar (240 - 275 PSI) at 1200 RPM.



20

6. Enter the calibration mode (see "Transmission Calibration" later in this section) and review the current calibration numbers. (With "CC" flashing, move shift lever to reverse downshift).

   F1_____
   F2_____
   R _____




21

7. Operate tractor until oil temperature is 57° C (135° F).
8. Enter the calibration mode and calibrate.


   Record the new numbers.

   F1_____
   F2_____
   R _____




22

9. Install 40 bar (600 PSI) pressure gauges FNH02990A, 1, in test ports shown, 2. Use the PD male test couplers FNH part #00533.
10. Test ports are 7/16-20 inch SAE O ring.
11. Drive the tractor with the engine at 1200 RPM, and record the pressures in the Clutch Apply Pressure Chart next to the clutch location for the respective gear. (Clutch pressure will be about 16.5 - 18.9 bar (240 - 275 PSI).



23



24

TRANSMISSION PROGRAMMING


PROGRAMMING THE PROGRAMMABLE UPSHIFT, DOWNSHIFT

The tractor transmission will shift 1, 2 or 3 gears higher when the upshift switch is activated. It will downshift 1, 2, or 3 gears when the downshift switch is activated. The number of upshift and downshift gears is programmable.

NOTE: *See also Section 55 - Electrical System, Chapter 1 - EIC and System Overview, Mode 10 - Transmission Calibration Review and Programming.*

To change the number of gears increased or decreased when selecting the programmable upshift or downshift, proceed as follows:

- Turn the “KEY-START” switch off.
- Move the shift lever to the reverse speed position, then hold the lever to the left.
- While holding the shift lever to the left, turn on the “KEY-START” switch (but do not start the engine). After three seconds, the digital display should show “U-d” indicating the up/downshift programming mode is engaged.
- Return the shift lever to the “REVERSE” position.



25

To program the upshift:


- With the shift lever still in reverse, move the lever to the right and hold for three seconds. The digital display will show an up arrow and the upshift number currently stored in memory.
- Nudge the shift lever to the right one, two or three times, as required. The display will show “1”, “2” or “3.” This indicates that when the UPSHIFT switch is depressed, the transmission will upshift one, two or three gear ratios higher than the gear currently being used. To cancel the upshift program, nudge the shift lever to the left until “0” appears.
- Return the shift lever to neutral after selecting the desired upshift to store the program.

To program the downshift:

- To change the number of gears that will be downshifted when Downshift is selected, position the shift lever in neutral. The display should show “U-d.” Move the shift lever to “REVERSE” position then to the left and hold for three seconds. The display will show a down arrow and the downshift number currently stored in memory.
- Nudge the shift lever to the right one, two, or three times and the display will show “1”, “2” or “3.” This indicates the number of gear ratios that will be downshifted from the current gear when the DOWNSHIFT switch is activated. To cancel the downshift program, nudge the shift lever to the left until “0” appears.
- Return the shift lever to neutral after selecting the desired downshift to store the program.

To exit the program:

- Turn the key-switch to the “OFF” position to exit the upshift and downshift program mode.



26


PROGRAMMING REVERSE GEAR RATIOS

When changing from forward to reverse, the transmission will normally select the same ratio in reverse as was selected for forward travel (when operating in gears between 3rd and 11th). For special shuttle shift applications, the powershift offers the advantage of automatically changing the reverse gear ratio up to three ratios higher or lower than the engaged forward gear ratio. The transmission may also be programmed to always select the lowest reverse gear (R3).

NOTE: *See also Section 55 - Electrical System, Chapter 1 - EIC and System Overview, Mode 10 - Transmission Calibration Review and Programming.*

To program an alternative reverse gear, proceed as follows:

- Turn the “KEY-START” switch off.
- Move the shift lever to the “REVERSE” position, then hold the lever to the right.
- While holding the shift lever to the right, turn on the “KEY-START” switch (but do not start the engine). Release the shift lever after five seconds. The digital display should show “0” (unless the transmission has previously been programmed to select a higher or lower reverse gear).



27

To program a higher ratio:

- From the “REVERSE” position, nudge the shift lever to the right one, two, or three times, as required. The display will show “1”, “2” or “3.” This indicates that when reverse is selected the gear will be one, two or three ratios higher than the forward gear ratio.

To program a lower ratio:

- From the “REVERSE” position, nudge the shift lever to the left one, two or three times, the display will show “-1”, “-2” or “-3.” This indicates that when reverse is selected the gear will be one, two or three ratios lower than the forward gear.

To program the lowest gear:

- Nudge the shift lever to the left a fourth time, an “L” will be displayed. This means whichever forward ratio is engaged when the lever is moved rearward, the lowest reverse ratio (3rd) will always be selected, regardless of forward gear ratio.


To cancel the program:

- From the “REVERSE” position, nudge the shift lever to the right until “0” is displayed.

NOTE: *Remember, only reverse gears between 3rd and 11th are available.*


To exit the program:

- Turn the “KEY-START” switch off. The transmission is now programmed.



28

TRANSMISSION CALIBRATION



29

CHECK POWERSHIFT TRANSMISSION CLUTCH CALIBRATION

NOTE: *The powershift transmission has three directional clutches. Calibrate the clutches periodically to compensate for wear. This service should be performed every 1200 hours or more frequently if a deterioration in shift quality is noted.*

WARNING

Before carrying out the calibration procedure, firmly apply the park brake and block the wheels, front and rear.

IMPORTANT: *During the calibration procedure, the electronic management system detects precisely the point at which the clutches start to engage. This engagement is detected by a very small reduction in engine speed. During calibration, it is essential that no action is taken to cause the engine speed to vary. Be sure the air conditioner and all electrical equipment is switched off. Do not operate the PTO or any hydraulic lever or move the hand or foot throttle.*

Preparing the Tractor for Calibration

NOTE: *The clutches should be adjusted when the oil is at normal operating temperatures.*

Prior to calibrating the directional clutches, carry out the following:

1. Park the tractor on level ground away from any obstacles in case of unexpected tractor movement. Stop the engine and place remote hydraulic controls in the “NEUTRAL” position.
2. Engage the park brake and block the wheels, front and rear.
3. Turn off the air conditioning.
4. Move the shift lever to the “NEUTRAL DOWNSHIFT” position (to the left) and hold in position. While holding it there, turn the key-start switch to the start position.
5. Start the engine. The full LCD will be displayed.
6. Release the shift lever three to five seconds after the engine starts.
7. Verify the digital display is showing a steady “CC” indicating the electronic management system is in the clutch calibration mode.

NOTE: *Repeat steps 1 through 7 if “CC” is not present.*


8. Adjust engine speed to 1200 ± 30 RPM.
9. Push the shift lever forward and “CC” should begin flashing.
10. Proceed to calibrate the clutches if “CC” is flashing.

CALIBRATION REVIEW

NOTE: *See also Section 55 - Electrical System, Chapter 1 - EIC and System Overview, Mode 10 - Transmission Calibration Review and Programming.*

Before calibrating the transmission, it is important to record the current calibration numbers to know if changes have occurred in the new calibration numbers:

1. Move the shift lever to the “REVERSE” position.
2. Verify the digital display shown is flashing “CC.”
3. Move the shift lever to the left and hold it there.
4. Observe the digital display. The current calibration numbers will display in this order “F1”, “F2” and “Reverse.” Record the numbers.
5. Return the shift lever to the “NEUTRAL” position.
6. Verify the digital display shown is flashing “CC.”




30

CALIBRATE F1 DIRECTIONAL CLUTCH

To calibrate the low range directional clutch (F1):

1. Move the shift lever to the “FORWARD” position.
2. Verify the display shows a flashing “CC.”
3. Move the shift lever to the left and hold it there.
4. Observe the digital display. It will flash “20” for approximately 4 seconds, then the number displayed will increase by one digit every second until the reading becomes steady. A steady reading indicates that clutch F1 is calibrated.
5. Return the shift lever to the “NEUTRAL” position after the clutch is calibrated.
6. Verify the digital display shown is flashing “CC.”

NOTE: *During F1 calibration, speed clutches B and 1 are engaged, and the F1 pressure ramps up.*




31

CALIBRATE F2 DIRECTIONAL CLUTCH

To calibrate the high range directional clutch (F2):

1. Move the shift lever to the “FORWARD” position.
2. Verify the display shows a flashing “CC.”
3. Move the shift lever to the right and hold it there.
4. Observe the digital display. It will flash “20” for approximately 4 seconds, then the number displayed will increase by one digit every second until the reading becomes steady. A steady reading indicates that clutch F2 is calibrated.
5. Return the shift lever to the “NEUTRAL” position after the clutch is calibrated.
6. Verify the digital display shown is flashing “CC.”

NOTE: *During F2 calibration, speed clutches A and 1 are engaged, and F2 pressure ramps up.*




32

CALIBRATE REVERSE DIRECTIONAL CLUTCH

To calibrate the reverse range directional clutch:

1. Move the shift lever to the “REVERSE” position.
2. Verify the display shows a flashing “CC.”
3. Move the shift lever to the right and hold it there.
4. Observe the digital display. It will flash “20” for approximately 4 seconds, then the number displayed will increase by one digit for every second until the reading becomes steady. A steady reading indicates the reverse range clutch is calibrated.
5. Return the shift lever to the “NEUTRAL” position after the clutch is calibrated.
6. Verify the digital display shown is flashing “CC.”

NOTE: *During reverse clutch calibration, speed clutches A and 2 are engaged, and reverse pressure ramps up.*



33

EXIT CALIBRATION MODE

To exit the calibration mode:

1. Stop the engine and wait ten seconds before proceeding.
2. Start the engine in the normal manner.
3. Verify that with the shift lever in the “NEUTRAL” position, the digital display indicates “N5.”

The tractor is now ready for normal operation.

CALIBRATION OF SHIFT CONSTANT


The F9 to F10 upshift and F8 to F7 downshift constants can be adjusted to improve shift quality. The factory setting of 10 can be increased to a maximum of 19 or decreased to a minimum of 2.

NOTE: *See also Section 55 - Electrical System, Chapter 1 - EIC and System Overview, Mode 10 - Transmission Calibration Review and Programming.*

Always adjust the number by three or more digits to insure the shift quality is better or worse than the previous number. The tractor must be operated after every adjustment to evaluate the shift quality. If the tractor shift is better, the digits may be adjusted one at a time to further fine tune the shift. If the shift is worse, change the number by six digits in the opposite direction to improve the shift. Make sure the new number is saved after every adjustment.


NOTE: *Cold oil, improper ballast and tire pressure will adversely affect the transmission shift.*

1. To adjust shift constant, move the speed lever to the “NEUTRAL DOWNSHIFT” position (to the left), and hold in position. While holding it there, turn the key-start switch to the run position.
2. Release the shift lever five to seven seconds after the key-switch is turned to run.
3. Verify the digital display is showing a steady ”CC”, indicating the electronic management system is in the clutch calibration mode.




34

4. Next you must select to either adjust the F9 to F10 shift constant, or the F8 to F7 shift constant. To select F9 to F10 calibration, move the shift lever to the “NEUTRAL UPSHIFT” position (to the right) and hold it there until the display shows an up arrow and a 10.




35

5. Adjust the F9 to F10 shift constant by nudging the shift lever to the right to increase, or to the left to decrease.




36

6. Exit F9 to F10 calibration by nudging the shift lever into the “FORWARD” position. The display will then return to a steady “CC.”
7. To select the F8 to F7 shift constant, move the shift lever to the “NEUTRAL DOWNSHIFT” position (to the left), and hold it there until the display shows a down arrow and a 10.



37

8. Adjust the F8 to F7 shift constant by nudging the shift lever to the right to increase, or to the left to decrease.
9. Shift constants can be saved at any time by turning the key-start switch to the “OFF” position.



70-220-1373

38

DISASSEMBLY AND REPAIR


REMOVAL AND DISASSEMBLY

If the transmission is already removed from the tractor, remove the control valve assembly as described in Chapter 2 - Mechanical System. If the control valve is to be removed from the tractor, proceed as detailed in the following paragraphs.

NOTE: *It is possible to remove certain valving elements from the main valve assembly without removing the whole assembly from the tractor. Refer to the relevant step as required.*


REMOVAL OF THE COMPLETE VALVE ASSEMBLY FROM THE TRACTOR

1. Position the tractor on a hard level surface and apply the parking brake.
2. Remove the battery cover, 2, and disconnect the batteries. Note that in removing the main control valve the sump passages will be opened to the atmosphere.
3. Unbolt the right cabstep assembly, 1, to provide access to the control valve assembly.




39

4. Disconnect and release the 12 separate harnesses connecting the solenoids and pressure sender to the main harness.



40

5. Disconnect the pump oil tube, 1, to the transmission filter and remove the tube.




41

6. Disconnect the low-pressure circuit supply tubes leading to the tractor PTO, 1; brake, 2; four-wheel-drive engagement clutch, and lubrication circuits, 3.


   If necessary, disconnect these tubes at the opposite ends or tie them out of the way to provide access and clearance during valve assembly removal.

7. Disconnect the cooler lines, 4, from the valve. If necessary, loosen or remove the tube to provide access.




42

8. Remove the five retaining bolts that hold the cooler bypass valve, 1, in place and remove the valve.




43

9. Following the numbered sequence shown, loosen each of the 22 retaining bolts, start with bolt number 22, and progressively loosen in decreasing order. Remove all but two bolts.



44

10. With the help of an assistant, support the valve assembly, 1, and remove the last two bolts. The use of two dowels, 2, made from spare bolts will aid in removal and installation. Carefully remove the control valve making sure the solenoid harnesses are not snagged or caught.




45

DISASSEMBLY

Disassembly of the control valve requires removal of the six speed clutch circuit valves and the three directional clutch circuit valves. All nine valves are identical in the disassembly procedure. In addition, the two modulator valves for directional clutch control are similar and the same procedure applies to both. The remaining regulating valve is unique in its removal procedure.

Before beginning disassembly, consider if the whole assembly requires inspection or overhaul. If it is required or suspected that this is the case, then remove all solenoids to avoid accidental damage. If only one or two circuits are suspect, then individual solenoids may be removed.




46

1. Speed Clutch B Solenoid
2. Speed Clutch C Solenoid
3. Speed Clutch A Solenoid
4. F1 Directional Clutch Modulator Solenoid
5. Reverse Clutch Directional Solenoid
6. F2 and REV Directional Clutch Modulator Solenoid
7. F2 Directional Clutch Solenoid
8. F1 Directional Clutch Solenoid
9. Speed Clutch 2 Solenoid
10. Speed Clutch 1 Solenoid
11. Speed Clutch 3 Solenoid

SOLENOID AND VALVE ASSEMBLY


1. Identify each of the eleven solenoids, 1, to its respective valve by marking each with a suitable marker pen, using the same coding that is cast into the valve body, i.e., 1,2,3, and A,B,C, for the speed clutch circuit valves, F1, F2 and REV for the directional clutches, and MC1 and MC2 for the modulator valves.
2. Identify the valve core to its port as described in the previous paragraph. It is desirable that valves are reassembled into the mating valve bore and not intermixed. However, each circuit valve is serviced separately and may be replaced without replacing the valve body.



47

SPEED AND DIRECTIONAL CLUTCH CIRCUIT VALVES


1. Remove the solenoid retaining locknut, 2, and slide the solenoid, 1, from the valve core, 3. Repeat for each solenoid.



48


2. Unscrew the valve core, 2, and extract the valve spool, 3, and the spring, 1. Insert the spool in the valve core in order to prevent intermixing with other clutch circuit valves.

   Repeat the procedure for each speed and directional clutch circuit valve.



49

NOTE: *The speed clutch circuit valves differ from the directional clutch valves in that the waisted section of speed clutch valves, 1, is shorter than that of directional clutch, 2, circuit valves.*




50

MODULATOR VALVES

1. Identify the valve core to its port as described under "Solenoids and Valve Assembly" in this chapter. Unscrew the valve core, 3, and pilot valve assembly, 4. Inspect the O rings, 1 and 2, for damage.

NOTE: *Also remove the screen assembly from the bore.*




51

2. Lightly grip the core hexagon head, 2, in a vise, and unscrew the pilot valve seat, 3, and remove the pilot valve, 4, and spring, 1.


NOTE: *The modulator valve is serviceable only as an assembly. Individual components are not available.*

The service assembly kits include a "new" coil. This particular coil was used when the valve was adjusted prior to shipment.



52


3. From the opposite side of the valve body, unscrew the port plug, 1, and remove the main spool, 2, and spring, 3, from the bore.



53

4. Using a 3/16″ hexagonal allen wrench, remove the small blanking plug, 3, situated above the MC1 modulating valve bore.
5. Using a 1/8″ hexagonal wrench, unscrew and remove the in-line metal filter, 2.
6. Using a 3/32″ hexagonal wrench, unscrew and remove the threaded orifice, 1.
7. Repeat the above steps for removal of the MC2 modulator valve, filter and orifice.

NOTE: *A male PD test fitting is used in place of the blanking plug #3 in the MC 2 valve.*



54


REGULATOR VALVE

1. Unscrew the large headed plug, 1, on the front side of the control valve body, and collect the regulating valve springs, washers and shims.

⚠ CAUTION ⚠


The regulating valve springs are highly loaded. take care when unscrewing the plug that these springs are not lost, or ejected, which could cause physical injury.

2. Rotate the valve body and collect the spring seat washer from the spring bore.




55

3. From the opposite side of the valve body, unscrew the regulating valve spool plug, 1, and, using a soft probe inserted through the spring bore, push out the spool, 3.
4. Inspect the outer end of the spool, checking that the orifice in the removable inner plate, 2, is not restricted. If necessary, the retaining snap ring may be removed and the plate extracted for cleaning.



56



57

CONTROL VALVE ASSEMBLY


1. Circuit Valve Core 3
2. Circuit Valve Spool Spring
3. Circuit Valve Spool (speed)
4. Valve Body
5. Clutch Circuit Valve B
6. Clutch Circuit Valve C
7. Clutch Circuit Valve A
8. Reg. Valve Outer Spring
9. Reg. Valve Inner Spring
10. Reg. Valve Washer and Shims
11. Reg. Valve Plug and Seal
12. Mod. Valve F1 (MC1)
13. Clutch Circuit Valve REV
14. Mod. Valve Spool Spring
15. Mod. Valve F2 and REV (MC2)
16. Mod. Valve Spool
17. Pilot Valve Seat and Seal
18. Mod Valve Screen
19. Mod. Valve Spool Spring
20. Mod. Valve Spool
21. Mod. Valve Plug and Seal
22. Mod. Plug, Pilot Filter, & Orifice
23. Clutch Circuit Valve F2
24. Clutch Circuit Valve F1
25. Directional Spool Spring
26. Directional Spool
27. Reg. Valve Plug and Seal
28. Reg. Valve Spool & Orifice Plate
29. Clutch Circuit Valve 2
30. Clutch Circuit Valve 1

LUBRICATION AND COOLING CIRCUIT RELIEF VALVE

A relief valve protecting the lubrication and cooler circuit is positioned in the center section of the transmission housing. Should the function of this valve be suspect, it will be necessary to destroy the valve in order to remove it. Make sure before removal that a replacement valve is available.


REMOVAL

1. Using a 3/8-16 UNC bottom tap, cut a thread in the relief valve plug, 1, in order to allow extraction.



58

2. Fabricate an adaptor that will allow a slide hammer to be connected to a threaded bolt screwed into the relief valve plug.
3. Using the adaptor and slide hammer, extract the plug, valve and spring.



59

INSTALLATION

Install a new valve, spring and plug in the center section, gently driving the plug into its bore.


INSPECTION

NOTE: *It is important to keep all components identified to their respective areas and bores.*


1. Clean all parts in a suitable solvent and dry thoroughly using a clean, lint-free cloth or compressed air.
2. Inspect all spool and valve components, 3, for wear and damage; ensure each spool and valve component moves freely in its respective bore, 2, without sticking or binding.
3. Make sure each clutch circuit valve, 3, has its end piece securely retained to the spool end.
4. Remove each valve core and blanking plug O ring seal and replace with new parts.
5. Inspect the valve return/damper springs, 1, for breakage or deformation, comparing these parts with a new spring.

NOTE: *All nine clutch circuit valve return/damper springs are identical.*

6. Inspect the modulator valve main spool, 1, seat and return spring, 2, for damage and deformation.
7. Inspect the modulator valve pilot line filter screens and orifice plug. Either clean or replace.
8. Inspect the valve body for internal cracks and external damage.



60




61

REASSEMBLY

1. Reassembly of the control valve follows the disassembly procedure in reverse.
2. Refer to “Specifications” in this chapter for tightening values of valve cores, plugs, solenoid retainers, and other components.


INSTALLATION

1. Installation of the control valve follows the removal procedure in reverse.
2. Make sure a new gasket is used.
3. To aid repositioning of the valve on to the transmission center section, make up two suitably threaded guide studs long enough to be gripped and removed, and loosely screw these into the center section.
4. With the help of an assistant, carefully lift the control valve onto the two studs, install the retaining bolts and remove the two guide studs.
5. Tighten the twenty-two retaining bolts in the sequence shown to the torque value stated in "Specifications."



62

6. Reinstall the cooler bypass valve assembly, 1, with new O rings, 2.
7. Reconnect all tubes and fittings and refill the transmission and rear axle with oil, to specifications, as stated in the Operator's Manual.




63

8. Ensure that each solenoid is connected to the correct harness end, 1. Each end is identical.

Pressure test and adjust the regulator valve, as detailed in "Adjustments and Pressure Testing" in this section.

Recalibrate (see "Transmission Calibration") the directional clutches with oil at operation temperature.



64

SECTION 21 - TRANSMISSION

Chapter 6 - Electrical System

CONTENTS

Section	Description	Page
21 000	Specifications	2
	Electrical System	2
	Description of Operation	3
	Clutch Apply Circuits	4
	Modulation Solenoids	4
	Shift Control Lever	5
	Inching Pedal	6
	Speed Sensors	6, 10
	Display Module	6
	Troubleshooting and Diagnosis	7
	Transmission Solenoid and Pressure Testing	8
	Disassembly and Repair	9
	Control Valve Solenoids	9
	Chassis Control Module	11
	Inching Pedal Switches	12
	Transmission Shift Control	14


SPECIFICATIONS

ELECTRICAL SYSTEM

COMPONENT	LOCATION	FUNCTION
Fuses	Main fuse panel(MFP) right side of floor	MFP #3 - 40 AMP main trans. power
	Main distribution panel (MDP) right “B” post	MDP #18 - 20 AMP trans. shift control
		MDP #19 - 20 AMP trans. shift control
		MDP #20 - 15 AMP trans. f/r control
Relays	Main distribution panel (MDP) right “B” post	MDP #6 dir. interrupt relay
		MDP #11 Trans power relay
Electronic transmission control (ETC)	Part of chassis control module (CCM)	16 BIT micro-controller with application memory and non-volatile calibration memory
Speed sensors	Engine speed front trans. housing	2500 OHMS resistance digital eng. speed
	Ground speed center trans housing	2500 OHMS resistance digital grnd. speed
Switches	Inching pedal	Normally closed opens at full stroke
	Transmission pressure transmission valve	Operates pressure lamp closes at 125 PSI
Potentiometer	Inching pedal	Variable resistance feathers MC1 and MC2
Solenoids	Transmission valve	9-direct acting 1.79 OHMS Operate at 100 Hz
		2-modulating 1.79 OHMS MC1 & MC2 Operate at 400 Hz

DESCRIPTION OF OPERATION

The transmission control system consists of an electrohydraulic control valve, 2, attached to the transmission; a single lever control, 3, mounted in the right-hand console which reports signals to the Right-Hand Controls (RHC) module, 4; a digital transmission display in the Electronic Instrument Cluster (EIC), 1; an inching pedal, 6, left of the brake pedals; and the Electronic Transmission Control (ETC) module located in the Chassis Control Module (CCM), 5, which is attached to the floor behind the operator's seat.



1

The ETC is a microprocessor which is programmed with instructions to control and manage the transmission. A fail-safe mode instantly allows the transmission to go to neutral in the unlikely event that a malfunction should occur. The ETC can be calibrated by the technician or owner to modify shift quality and match the electronics to the transmission hardware.

The ETC has a built-in program to provide self-diagnostics of faults which can be displayed in the Tractor Performance Monitor (TPM) while operating or stored for review while servicing.

Fault codes will either allow normal operation or automatically return the transmission to neutral depending on the severity of the fault. Fault codes are discussed in "Troubleshooting."

There are no mechanical components serviced in the ETC so it should not be opened or disassembled to service.

CLUTCH APPLY CIRCUITS

The eleven solenoids located on the electrohydraulic control valve are activated with a pulse width modulator (PWM) positive voltage from the ETC, 1.


Pulse Width Modulation (PWM) is a term used to describe the control function of the electrical output from the ETC.

Of the eleven solenoids, 2, all are direct operating except the two modulator valves, MC1 and MC2, 3. The direct operating solenoids receive a 100 Hz PWM signal of 5-6 volts.

MC1 modulates oil supplied to the F1 clutch and MC2 modulates the supply to the F2 and Reverse clutches.

The six speed clutch direct operating valves are supplied with regulated oil pressure and, when the solenoid is energized, oil is supplied to the clutch pack. The clutches fill quickly and little or no slippage will occur.

The directional clutches are also direct operating but, when they are activated, the oil supply is interrupted by the modulator solenoids, MC1 and MC2. These clutches are much more tolerant to slippage due to their construction.




2

MODULATION SOLENOIDS

The modulator solenoids, MC1 and MC2, are pulse width modulated at 400 Hz. The modulation PWM solenoids allow regulation of the hydraulic pressure to the appropriate clutch, to be inversely proportional to the average DC electrical current in the solenoid coil. The lower the solenoid current, the higher the pressure applied to the clutch. The MC1 and MC2 voltage range is from 5 to 0 volts.

When the solenoid, 3, is not electrically energized, a needle valve, 2, is spring loaded in the closed position causing pilot pressure on the spring, 4, end of the control spool, 1, to be equal to regulated system pressure. This pilot pressure and spring pressure controls the position of the spool, 1, to control clutch pressure.



3


When current is applied to the solenoid, 4, in the form of a pulse width modulation signal, the needle valve, 3, is moved open to the extent dictated by the average DC current on the solenoid. This causes an oil flow across the needle valve; the pilot pressure is dictated by the oil flow through the fixed orifice, 2.

As the needle valve opens, the pressure drops in the valve spool cavity and the spool, 1, moves to the right, dumping oil pressure to the clutch port, 5.

As the current drops, the needle valve closes which builds pressure in the valve spool cavity forcing the spool to the left which increases pressure to the clutch port, 5. The clutch application pressure is, essentially, equal to the pilot pressure regardless of the amount of oil flow in the clutch cavity.

PWM is best understood by imagining a switch attached to a 12-volt source. If the switch is turned on and off very rapidly, the voltage is reduced depending on the amount of time the switch is off. If the switch is off 50% of the time, six volts are available. If the switch is off 75% of the time, three volts are available. The ratio of “on” versus “off” is referred to as Pulse Width Modulation.

The ETC has the ability to adjust the pulse width or voltage to vary the speed that the directional clutches apply depending on load, engine speed and ground speed.




4

SHIFT CONTROL LEVER

The shift control lever, 1, uses nine halifax switches, 2, activated by a magnet, 3, attached to the shift control lever. When the magnet passes over a switch, a signal is transmitted to the ETC via the RHC to select a higher or lower speed or a direction change.

One switch is dedicated to the neutral start circuit, and the tractor will not start if the lever is in any position but neutral.

This switch also controls a directional clutch interrupt relay. This relay prevents operation of the directional solenoids while in neutral.




5

INCHING PEDAL

The inching pedal, 1, has two sensors associated with it - a position sensor, 2, and a sense switch, 3. The position sensor is a potentiometer that is powered from the ETC. The potentiometer indicates the position of the pedal and varies the PWM signal to MC1 and MC2 to engage and disengage the transmission.

The sense switch is used to break the circuit to the directional interrupt relay when the pedal is fully depressed. This removes power from the directional clutch and puts the transmission in neutral. This switch is also used for other transmission functions such as speed matching and automatic transport.




6

SPEED SENSORS

Two reluctance sensors are used to measure engine speed and axle speed. The engine speed sensor, 1, is located in the front section of the transmission and measures input shaft speed. The axle speed sensor, 2, is located in the lower center section of the transmission and measures output shaft speed.

Both sensors are threaded into the transmission housing and are positioned next to gears to induce a pulse signal which is converted and displayed in the EIC as engine and ground speed. The information produced is also used by the ETC for speed matching and automatic shift functions along with other speed related functions.




7

DISPLAY MODULE

The display module for the transmission is part of the EIC. The top center LCD, 1, is dedicated to transmission information. The display shows tractor gear selection and direction. The letter A will be displayed when in Automatic shift, C for creeper gear, F for forward, N for neutral and R for reverse.

A flashing letter indicates an Operator Prompt, which means the shift control was not in neutral when starting, etc. A flashing P indicates that the transmission was engaged with the parking brake applied. The transmission is disabled when the parking brake is applied.

The speed sensors supply outputs for the engine speed, 2, and the ground speed, 3.



8

TROUBLESHOOTING AND DIAGNOSIS

PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor won't move after starting	Flashing "F" "R" "P" "U" or "d" Transmission operation performed out of sequence	Return shift control lever to neutral and release parking brake. See "Operator Prompts."
Poor inching control when using inching pedal	Transmission clutches out of calibration	Re-calibrate transmission clutches F1, F2 and R. See "Hydraulic Components" - Chapter 5.
	Clutch potentiometer	Replace the clutch potentiometer.
	Clutch spring	Replace the clutch spring.
Transmission will not operate	Fault code displayed indicating malfunction	See "Fault Codes" Electrical System - Section 55, Chapter 2.
Low transmission oil pressure warning lamp on	Low oil supply	Fill system with oil. See "Hydraulic Components" - Chapter 5.
Transmission filter lamp on	Clogged transmission oil filter	Replace filter.
Tractor drives in limited gears	One or more solenoids inoperative*	Compare working gears to Clutch Apply Pressure Chart (Chapter 5) to determine faulty solenoid.
Tractor stalls in limited gears	More than 3 clutches engaged at one time	Compare non-working gears to Clutch Apply Pressure Chart (Chapter 5) to determine faulty clutch.


*See "Transmission Solenoid & Pressure Testing."

TRANSMISSION SOLENOID AND PRESSURE TESTING

NOTE: *70 Series art shown in Figure 9.*

If a limited number of transmission gears are not available, one or more solenoids may have failed. To test for proper solenoid operation:

1. Park tractor on level surface and apply parking brake.
2. 2. Turn the key switch to the run position. Do not start the tractor. The display will show N5.
3. Move the shift lever to the left and select N1.
4. Move the transmission shift control lever to forward and check that the display shows F5.
5. Check that “ON” solenoids are on and “OFF” solenoids are off by touching the end of the solenoids, 1, with a non-magnetized screwdriver. The screwdriver will be pulled towards solenoids that are on.
6. Refer to the following chart for solenoid engagement.
7. Pressures can also be recorded in the gears selected in the appropriate locations. Normal apply pressures are 16.5 - 18.9 bar (240 - 275 PSI).



9


DISASSEMBLY AND REPAIR

The electrical components that can be serviced consist of the control valve solenoids, speed sensors, the CCM which houses the Electronic Transmission Control (ETC) module, the inching pedal switches and the shift control lever.

CONTROL VALVE SOLENOIDS

NOTE: *70 Series art shown in Figure 12.*


1. Position the tractor on a hard level surface and apply the parking brake.
2. Remove the battery cover, 2, and the negative battery cables.
3. Remove the right step assembly, 1, to gain access to the valve assembly
4. Clean the valve area to ensure that all connections can be identified.



10

5. To remove a solenoid, remove the connector, then remove the retaining nut, 2.
6. Slide the solenoid, 1, from the stem, 3.
7. Inspect the solenoid for damage and for proper resistance of 1.79 ohms.
8. Replace the solenoid in the reverse order. Torque the retaining nut to 8 N·m (6 ft. lbs.)


NOTE: *Do not over torque retaining nuts as the spool stems can be distorted and bind the spool.*



11

9. Ensure the proper connector is attached to the solenoid. Each connector is embossed with the identification of the solenoid it attaches to. If the connector is damaged, inspect the wire and locate the wire identification number. Use the wiring diagram in Section 55, Chapter 6, to match the harness to the proper solenoid.

NOTE: *The clearance required to remove the F1 and F2 solenoids from the valve is limited on MegaFlow™ ready and MegaFlow equipped tractors due to the larger charge pump. To replace these solenoids, the transmission valve assembly will have to be removed.*



12


SPEED SENSORS

Both the input, engine RPM and output, axle speed sensor are serviced from the right side of the transmission.

Input Sensor

The input speed sensor is located on the top right side of the front transmission housing.

1. To remove the sensor, 1, park the tractor on a level surface and apply the parking brake.
2. Locate the sensor in the front housing, 2, and disconnect the electrical connector. The sensor can be checked for resistance of 2500 ohms at this time.
3. To remove the sensor, clean the area around the housing opening and thread the sensor out of the transmission.
4. Inspect the sensor for damage and replace as required.




13

Output Sensor

The output sensor is located in the center housing just below the transmission valve.

1. To remove the sensor, 1, park the tractor on a level surface and apply the parking brake.
2. Locate the sensor in the center housing, 2, and disconnect the electrical connector. The sensor can be checked for resistance of 2500 ohms at this time.
3. To remove the sensor, clean the area around the sensor. The sensor is above the rear axle oil level but a drain pan should be placed under the opening to catch any additional oil. Thread the sensor out of the transmission.
4. Inspect the sensor for damage and replace as required in the reverse order of removal.




14

CHASSIS CONTROL MODULE (CCM)


The ETC is located behind the operator's seat on the left side of the floor. It is part of the Chassis Control Module (CCM). No parts in the control module can be serviced, so it must be replaced as an assembly.

1. To remove the CCM, park the tractor on a hard level surface and apply the parking brake.
2. Remove the battery cover and the negative battery cables, 1.



15

3. From the outside rear of the tractor, remove the two connectors, 1, at the bottom of the CCM module.




16

NOTE: *70 Series art shown in Figure 17.*


4. From inside the cab, pull the left rear corner of the floor mat, 2, up and block it up with a short block, 1, between the mat and the rear wall.

NOTE: *For 70 Series tractors, proceed to step 7.*




17

5. Remove the connectors, 1, from the EHR module and remove the retaining hardware, 2.
6. Remove the EHR module.



18

7. Remove the connector, 1, from the right side of the CCM and remove the retaining hardware, 2.
8. Remove the CCM.
9. Replace the CCM in the reverse order. Ensure that all connectors are clean and that dielectric grease is applied to the connectors before attaching to the module.
10. After the CCM has been installed, it must be reconfigured to communicate with the other modules on the tractor. See Section 55, Electric System, Chapter 1, EIC, Mode 12 Tractor Features Configuration for more details.




19

INCHING PEDAL SWITCHES


The switch and potentiometer for the inching pedal can be serviced from the left side of the cab as follows:

1. Remove the four left side cover retaining screws and the side cover, 1.




20

2. The switch, 1, is mounted at the top of the inching pedal mount. Remove the connector and the two retaining screws, 2, to change the switch. The switch is a normally closed switch and it opens when the clutch pedal is fully depressed.



21


3. Reinstall in the reverse order. Adjust the switch by first depressing the inching pedal. Insert a 3.0 mm (0.120″) feeler gauge, 1, between the switch and the inching pedal tab. Rotating the mount bracket, 2, towards the pedal until the switch bottoms internally. Tighten the retaining hardware and remove the feeler gauge.



22

4. The potentiometer is serviced by first removing the adjusting nut, 3.
5. Remove the three pin connector, 4, and the clevis connection and arm, 2, at the pedal.
6. Remove the through bolt, 1, and nut. The potentiometer, 5, and control arm can now be separated.
7. Inspect the potentiometer for damage.
8. Replace the parts in the reverse order of disassembly. To adjust the switch, see Section 55, Electrical, Chapter 1, EIC and enter Mode 3.
9. With the pedal fully depressed, the TPM display should show P215, and the 3-point hitch area display should show 15-20.


   With the pedal up, the display should read 75.
10. Adjust the arm with nut, 3, to obtain these readings.



23

Inching Pedal Removal

1. With both the switch and potentiometer removed, the inching pedal can be disassembled by removing the snap ring, 2, from the right end of the pivot pin.
2. With a suitable punch, drive the pivot pin, 1, from the inching pedal, 3. Separate the inching pedal and return spring, 4, from the pivot bracket.
3. Inspect all parts for wear and damage and replace as necessary. To ensure smooth operation of the pedal, the plastic bushings, 5, must be replaced.
4. After repairs, the transmission must be recalibrated due to new positioning of the switch and potentiometer. See Chapter 5, “Transmission Calibration” for more details.




24

TRANSMISSION SHIFT CONTROL

The transmission shift control assembly is located in the right-hand control panel.

The shift control has an electronic circuit board than can be serviced in the tractor. If a problem with the neutral latch, return spring, or lever is experienced, the assembly must be removed for service.




25

Shift Control Circuit Board Assembly


NOTE: *70 Series art shown in Figure 26.*

1. To replace the shift control circuit board, position the tractor on a hard level surface and apply the parking brake.
2. With the right-hand control console in the full forward position, remove the battery cover and disconnect the negative battery cables.
3. Remove the four retaining screws and the right-hand control console lower shield, 1.




26

4. Remove the hand throttle stop bar, 2, and disconnect the circuit board electric connector.
5. The circuit board is retained by two screws, 1, on the side of the control box, 3. Remove the screws and carefully pull the board from the bottom of the control box.



27


6. Inspect the circuit board, 1, for damage and replace as required. Inspect the nine halifax switches, 2, for damage or cracks. Reassemble in the reverse order of disassembly. Ensure that dielectric grease is used at the connector.



28

Shift Control Assembly


1. To remove the shift control assembly, complete steps 1 - 3 under “Shift Control Circuit Board Assembly” heading earlier in this chapter.
2. Remove the hand throttle control cable, 3, by disconnecting the cable end from the pivot.
3. Remove the hand throttle knob, 1.
4. Disconnect the circuit board electrical connector.
5. Remove the six shift control retaining bolts, 2, and lower the control assembly, 4, from the right-hand console.



29


Shift Control Disassembly

1. With the shift control on a workbench, remove the hand throttle and throttle stop bar, 1, and throttle control lever.



30

2. The circuit board is retained by two screws, 1, on the side of the control box. Remove the screws and carefully pull the board, 2, from the bottom of the control box.




31

3. Remove the lower pivot stop bolts, 1, from the front and rear of the control box assembly.


CAUTION

The coil spring, 2, on the rear pivot is tightly wound. Remove the rear pivot bolt carefully.




32

4. Remove the four retaining screws, 1, from the top shift gate plate, 2, and remove the plate.




33

5. Remove the locknut from the front of the center pivot bolt. The bolt, 2, is threaded into the front housing. Remove the bolt; spring, 3; and spacer, 1.



34


6. The shift assembly, 1, can now be pulled from the top of the shift tower, 2.



35


Handle Disassembly

1. Remove the shift lever, 1, from the pivot assembly by removing the lock screw, 2. Pull the handle from the pivot, 3.



36


2. The handle houses the neutral latch. Compress the lower spring, 2, by pushing the latch pin, 3, in flush with the end of the lever, 1.
3. Carefully pull the neutral latch, 4, from the shift knob, 6. The neutral latch is notched to fit around the neutral center pin wire, 5.



37

4. With the latch removed, loosen the setscrew at the base of the knob, 2, and pull the knob from the lever. The setscrew can now be removed in the neutral wire retainer.
5. All parts can now be pulled from the handle tube and inspected. Replace worn or damaged handle parts as required.
6. Reassemble in the reverse order of disassembly.


NOTE: *For the neutral latch to have enough travel to allow the shift lever to move, it is important to set the wire length properly.*



38


Neutral Latch Adjustment

1. Assemble the lower spring, 4, the neutral pin and wire assembly, 5, into the shift lever, 3.
2. Install the top spring, 2, and the wire retainer, 1.
3. Compress the lower spring by pushing the neutral pin inside the shift lever.
4. With the pin flush with the bottom of the lever, adjust the wire retainer to 1/2″ clearance, 6, between top of the lever, 3, and the base of the retainer, 1.



39


5. Install the shift knob, 1, over the retainer, 2.
6. The neutral latch, 4, can now be installed into the knob, with the neutral pin pushed into the handle. Install the latch between the bottom of the retainer, 2, and the top spring, 3.
7. Tighten the knob setscrew.
8. Insure the latch works freely after it is assembled.



40


Shifter Pivot Assembly

1. Remove the forward, reverse detent retainer assembly, 2.
2. Remove the snap rings, 4, and forward reverse pivot pin, 3. The pivot bracket, 1, can now be removed.



41


3. Remove the flanged pivot pin bushings, 1.
4. Remove the lower neutral stop plate, 3.
5. Inspect all pivot parts for wear and damage. Ensure that the magnet, 2, is secure and not damaged. Replace parts as required.



42

Reassembly


1. Reassemble in reverse order of disassembly. Ensure that the neutral latch works properly. If it doesn't shift or the latch doesn't engage, review "Neutral Latch Adjustment" earlier in this chapter.
2. After the shifter is assembled, adjust the forward to reverse detent screw, 2. It will require 6 N (4 lbs.) of force to return the lever, 1, to neutral from forward or reverse. To adjust the detent, rotate the screw in to increase pressure and out to decrease pressure.



43

Installing Shift Control Assembly

1. To install the shift control assembly, position the control assembly, 4, in the right-hand console.
2. Install the six shift control retaining bolts, 2.
3. Attach the hand throttle control cable, 3, by connecting the cable end to the pivot.
4. Install the hand throttle knob, 1.
5. Connect the circuit board electrical connector coated with dielectric grease.
6. Reconnect the battery cables and reinstall the cover.
7. Check the shift control for proper function. Gears F1-F10 and Rev 3-10 are selectable with the key on and the engine off.
8. Reinstall the right-hand control console lower shield.



44

SECTION 23 - DRIVE LINES

Chapter 1 - Four-wheel Drive Clutch


CONTENTS

Section	Description	Page
23 202	Description of Operation	2
	70 Series FWD Electronic Control Operation	4
	70A Series FWD Electronic Control Operation	5
	Engaging and Disengaging Four Wheel Drive	5
	FWD Operating Precautions	5
	Disassembly and Repair	8
	Removal	8
	Disassembly	12
	Inspection	13
	Reassembly	15
	Installation	18
	Pressure Testing	23


DESCRIPTION OF OPERATION

INTRODUCTION

The four-wheel drive wet clutch, 2, transmits power from the pinion rear shaft, 1, to the output shaft, 3, which drives the four-wheel drive axle.



1




2

This clutch is located in the front end of the rear axle center section. The clutch is spring applied and is hydraulically disengaged.


Clutch engagement is controlled by an electric solenoid mounted on the rear of the tractor. Oil is directed to the clutch via an internal tube in the rear axle center section.

Oil to disengage the clutch enters the clutch through connector, 3, through passage, 2, in the shaft to hole, 1.



3

The oil pressure that disengages the clutch is directed internally through the cross drilling, 1, to the piston cavity, 2. The oil pressure forces the piston against the spring washer to disengage the clutch. When the pressure is removed, the spring reapplies the clutch.




4

70 SERIES FWD ELECTRIC CONTROL OPERATION

Four-wheel drive is controlled by an electrical solenoid activated by a three-position rocker switch. The rocker switch also contains an internal lamp which indicates the operating position of the switch.

NOTE: *The park brake lever must be released and the engine must be running to allow the FWD electric circuit to disengage the clutch. The FWD clutch is always engaged whenever the park brake lever is applied.*



5

FWD Auto
From off, press the front of the switch to engage the automatic control mode of operation.

The chassis control module (CCM) will automatically disengage the FWD when either brake pedal is applied as in turning the tractor. When the brake pedal is released, the controller will automatically reengage the FWD.

NOTE: *The electric solenoid is off and no oil pressure is directed to the clutch whenever the clutch is engaged.*

FWD On
Press the switch to the third position to engage FWD on. This engages the operator-controlled mode which keeps the FWD engaged all the time.

NOTE: *Both FWD Auto and FWD On will automatically disengage at speeds above 24 KPH (15 MPH) and reengage at lower speeds.*

If both brake pedals are depressed at the same time, the FWD circuit will engage to aid in braking.

A lamp in the electronic instrument cluster (EIC) will be illuminated to indicate which mode is selected.

When the electric circuit is activated (FWD off), the electric solenoid is energized and the clutch is disengaged. This allows the clutch to default to the applied position should an electric or hydraulic malfunction occur.

70A SERIES FWD ELECTRIC CONTROL OPERATION

INTRODUCTION

The four wheel drive (FWD) axle comes in either limited slip differential with Automatic Traction Management or fully locking differential with TerraLock Traction Management. Use FWD Automatic or TerraLock when operating to obtain maximum efficiency and traction under any field conditions.

ENGAGING AND DISENGAGING FOUR WHEEL DRIVE

Four wheel drive can be engaged and disengaged in all gears (forward and reverse) during operation and under full load.

Switch, 1, has three operating positions: Off, Automatic or Terralock and Full-time On.

Fully depress the rear of switch, 1, to disengage FWD, 2.

Depress the front of the switch one notch to the Automatic or Terralock position, 3. The AUTO FWD indicator lamp on the instrument console will illuminate to indicate engagement of either Automatic or Terralock.

When the tractor is in Automatic or Terralock mode, FWD will automatically disengage when either brake pedal is used to assist in turning or at transport speeds above 24.2 km/h (15 MPH) which reduces tire wear. The FWD will automatically reengage when transport speed drops below 24.2 KPH (15 MPH) and when the applied foot brake is released.

TerraLock will also disengage and reengage under the following conditions:


At speeds of 0-10 kph (0-6 MPH) disengage at turn angles of 30 degrees or higher and reengage at angles less than 30 degrees.

Or between 10–20 kph (6–13 MPH) disengage at turn angles of 25 degrees or higher and reengage at angles less than 25 degrees.

Fully depress the front of the switch to the ON position, 4, to engage full-time FWD. The indicator lamp in the switch will illuminate to indicate that the FWD is engaged.

In this mode FWD automatically disengages when transport speed is above 24.2 KPH (15 MPH) which will reduce tire wear. FWD will automatically reengage when speeds drop below 24.2 KPH (15 MPH).

NOTE: *FWD will automatically engage to improve braking any time that both brake pedals are depressed.*



6

FWD OPERATING PRECAUTIONS

CAUTION


Four wheel drive greatly increases traction. Extra caution is needed on slopes. Compared to two-wheel drive, a fwd tractor maintains traction on steeper slopes, increasing the possibility of overturning.

When driving on icy, wet, or graveled surfaces, reduce speed and make sure the tractor is correctly ballasted to avoid skidding and loss of steering control. For best control, engage four wheel drive by using full-time on mode, rather than auto mode for four wheel braking.

IMPORTANT: *To increase front tire life, disengage four wheel drive when transporting the tractor. Disengagement is automatic at transport speeds above 24.2 KPH (15 MPH). Always use front/rear tire combinations specified to ensure acceptable tire wear.*

IMPORTANT: *Disengage FWD when making extremely tight turns. This action will increase front tire life, decrease stress on the FWD axle and allow tractor to achieve minimum turn diameters.*

The 12-volt solenoid, 1, that supplies oil for clutch disengagement is located on a manifold at the rear of the tractor.




7

Solenoid Schematic without Steering Sensor

The electric circuit for the FWD switch is supplied by the RHC 5-amp fuse in the main fuse panel located in the right side cab “B” post.


The FWD switch sends a signal to the Right-Hand Console module (RHC) which communicates with the Chassis Control Module (CCM). The CCM sends power to operate the solenoid at the rear of the tractor.



8

Solenoid Schematic with Steering Sensor

When the tractor has a steering sensor and the FWD switch is in the auto position, the steering angle pot may send a signal to the CCM, depending on the angle of the front wheels. The CCM then will activate or deactivate the FWD solenoid at the rear of the tractor.




50021982

9

DISASSEMBLY AND REPAIR


REMOVAL

1. Park the tractor in a safe, clean location with the park brake applied.
2. Remove drain plug, 1, and drain oil from the rear axle center section approximately 136 L (36 gallons, US).




10

3. Drain the fuel tank.
4. Remove the left side step, work light, and fuel tank support.
5. Remove the fuel tank.




11

6. Remove drive shaft shield, 2.
7. Remove drive shaft, 1, by separating at the front flange and special shouldered bolts from the bearing hanger.



12

8. Remove setscrews, 2, and rear coupler, 1.




13

9. Remove cap screws, 2, that retain side cover, 1.


⚠ WARNING ⚠

Make sure oil was drained.




14

10. The drive gear, 1, driven gear and clutch spider assembly, 3, can be seen after the cover is removed.
11. Install a wood block, 2, to support the clutch assembly.



15

12. Remove the snap ring using a pair of locking snap ring pliers.




16

13. Pry seal retainer, 2, and shaft, 1, out as an assembly.

CAUTION


The clutch assembly must be supported as shown to prevent it from falling out of the counterbore.

NOTE: *If the seal retainer is the only part that must be removed as in replacing the seal, the shaft must be held securely to the rear of the tractor to prevent loss of the thrust bearings.*




17

14. Remove the output shaft assembly.



18

15. Roll the clutch assembly out to the opening. Make sure that the thrust bearing and washer are captured.




19

16. Remove the clutch assembly from the housing.

⚠ WARNING ⚠

Always wear gloves and use both hands to handle this assembly. This assembly weighs more than 60 pounds.




20

DISASSEMBLY

The FWD clutch assembly consists of:


1 Output shaft
2 Seal and bearing retainer
3 Piston, hub and disc assembly
4 Clutch spider and driven gear
5 Thrust bearing
6 Thrust washer



21

1. The clutch spring can be compressed by using special tool, 1, FNH 00103.
2. After the spring is compressed, loosen the adjusting nut, 2, with spanner wrench.
3. After removing the nut and spring, the piston can be removed.
4. Remove the snap ring from the other end of the hub and remove the clutch plates.


NOTE: *The adjusting nut may be hard to turn due to the lock tab on the nut and interference thread fit.*



22

The piston hub and disc assembly consist of:


1 Adjusting locknut
2 Spring washer
3 Piston
4 Hub with two seals
5 Pressure plate
6 Snap ring
7 Separator plate (7)
8 Friction plate (8)



23


INSPECTION

1. Check the separator plates for warpage, scoring, circular gouging, and wear. Replace if worn. New thickness is 2.06 mm - 2.16 mm (0.081″ - 0.085″). Replace if worn thinner than 1.96 mm (0.077″).




24

2. Check friction plate for warpage, scoring evidence of overheating, circular gouging, and wear. New thickness is 2.42 mm - 2.62 mm (0.095″ - 0.103″). Replace if worn thinner than 2.32 mm (0.091″).




25

3. Replace the seals, 1, in the hub. Coat them with petroleum jelly prior to installation.



26

4. Press the old bearing, 1, off the shaft and install a new bearing.



27


5. Examine the gear teeth for wear. Prior to November 1998, two different gear and hub assemblies were used, depending upon tire combinations (all 70 Series models).

   1 38-tooth gear, or

   2 40-tooth gear

   Effective November 1998, Serial #D415637, only one clutch driven gear tooth is offered.


   - 8670/8670A - 40 tooth gear
   - 8770/8770A - 39 tooth gear
   - 8870/8870A - 39 tooth gear
   - 8970/8970A - 39 tooth gear



28


REASSEMBLY

1. Inspect bearings, 1, and replace if required. Press new bearings in until edge is flush. Always press on the numbered side.




29

2. Inspect the clutch spider slots, 1, for wear. Replace the clutch spider if wear is deep enough to cause a plate to hang up.




30




31

3. Reassemble the clutch by installing the eight friction plates, 4, and seven separator plates, 5, in alternating order on the hub, 3.
4. Install the backplate, 6, and snap ring, 7.
5. Install the piston, 2, and spring washer, 1.
6. Temporarily install the clutch drum and output shaft to make sure that the clutch plate tabs are all aligned correctly and the plates are centered in the hub so that the shaft will slide through the assembly.



32


7. Compress the spring washer, 2, with special tool, 1, FNH 00103.




33

8. Turn the adjusting nut down until there is 1.30 mm - 1.70 mm (0.054″ - 0.066″) clearance between the nut and the washer.
9. Relax the press and recheck the clearance between the underside of the washer and the piston as shown.

   THIS MUST BE DONE TO ENSURE THAT THE CLUTCH HAS THE PROPER PRELOAD SO THAT IT WILL DRIVE CORRECTLY.



34




35

INSTALLATION

1. Prior to installation, check the condition of needle bearing; connector seal; thrust bearing, 1; and washer, 2. Replace worn or damaged components.

NOTE: *If the needle bearing requires replacement, pull out the old bearing using a slide hammer and press a new bearing in place. Install with the bearing writing facing out.*


2. Install thrust bearing, 1, and washer, 2, on the clutch as shown. Use petroleum jelly to hold in place during installation.
3. Install the clutch and drum assembly back into the case.



36


4. Install the clutch and drum assembly in the needle bearing. Support the assembly with a block of wood, 1, as shown.

NOTE: *Be sure that the thrust bearing and washer are properly installed after installation.*




37

5. Insert the output shaft through the front opening. Make sure that the O rings are coated with petroleum jelly.




38

6. Tap the shaft in place until the front bearing is seated. A rubber hammer may be required. The O rings passing through the hub are tight.




39

7. Install a new shaft seal, 1, in the front seal retainer, 2. Be sure to install with the seal spring lip towards the clutch assembly.




40

8. Install a new O ring, 1, on the retainer and insert it on the shaft. Protect the seal from the shaft spline, 2, with some tape.




41

9. Tap the seal retainer, 2, into place using a suitable driver, 1.




42

10. Install the snap ring in the groove.




43

11. Apply a gasket eliminator sealing compound, 1, around the opening as shown. Make sure the sealing compound surrounds the bolt holes as shown.




44

12. Reinstall the cover plate, 1, and torque all the hardware, 2, to 78 N·m (58 ft lbs).




45

13. Reinstall the drive shaft, 1, coupler, and shield, 2, previously removed.



46

14. Reinstall the fuel tank, step, and light assembly which was previously removed.
15. Refill the rear axle reservoir with ESN-M2C134-D hydraulic oil.




47

PRESSURE TESTING

1. Install a pressure gauge, 1, in the test port, 2, as shown on the top of the rear axle and operate the tractor to determine that the FWD disengagement pressure is correct.

NOTE: *The park brake must be released to allow the FWD clutch to be disengaged.*

2. Pressure should be 16.5 bar - 18.9 bar (240 PSI - 275 PSI) when the clutch is disengaged and 0 bar (0 PSI) when the clutch is engaged.



48

SECTION 25 – FRONT MECHANICAL DRIVE

Chapter 1 – Four-Wheel Drive Dana Axle

CONTENTS

Section	Description	Page
25 000	Specifications	2
	Special Tools	4
25 100	Description of Operation	6
	Troubleshooting	15
41 106	Adjustments	16
41 106	Wheel Toe-in	16
25 108	FWD Steering Stop	17
25 108	Hub Bearing Preload Adjustment	18
25 102	Check for Correct Pinion to Ring Gear Tooth Contact	21
25 102	Wrong Tooth Contact Pattern	21
25 108	Swivel Pin Bearing Adjustment	23
25 104	FWD Ratios	23
25 104	FWD Tire vs Gear Ratios	24
	Four Wheel Drive Lead Factor	28
	Front Axle Serviceability	30
00 400	Lubrication	30
	Disassembly and Repair	35
25 100	Front Axle	35
41 216	Steering Cylinders	38
25 108	Planetary Reduction	40
25 108	Hub	44
25 108	Swivel Housing	47
25 108	Center Housing Swivel Bearing	50
25 108	Drive Shaft	51
25 108	Outer Yoke	54
25 102	Differential	56
25 102	Crown Wheel to Backlash Adjustment	69

⚠ WARNING ⚠

When overhauling the axle, always ensure the tractor and axle is fully supported on axle stands, and the rear wheels are blocked to prevent any movement of the tractor.

SPECIFICATIONS

TYPE:	Dana heavy-duty, center driven, double reduction (ring gear and pinion plus planetary hubs).
STEERING TURN ANGLE (Dependent on track setting)	50° max (standard FWD axle) 65° max (SuperSteer FWD axle)
AXLE OSCILLATION ANGLE	12°
OVERALL WIDTH (Wheel Mounting Flange)	1910 mm (75.2″)

CLEARANCES AND ADJUSTMENTS

Front Wheel Toe-In	0.0 - 6.0 mm (0 - 0.25″)
Axle Hub Bearing Rolling Resistance*	6 N·m -10 N·m (50 in. lbs. - 90 in. lbs.) Adjustable by shims 0.05/0.075/0.125/0.25/0.5/0.75 mm (0.002/0.003/0.005/0.010/0.020/0.030″)
Swivel Housing Turning Torque*	11 N·m - 20 N·m (8 ft lbs - 15 ft lbs) Adjustable by Shims 0.05/0.15/0.25/0.375/0.75 mm (0.002/0.006/0.010/0.015/0.030″)
Pinion to Ring Gear Bevel Tooth Engagement	Adjustable by shims 0.075/0.125/0.25 mm (0.003/0.005/0.010″)
Pinion Bearing Rolling Resistance	2.5 N·m - 4.5 N·m (20 in. lbs. - 40 in. lbs.)
Pinion to Ring Gear Backlash	0.125 N·m - 0.255 N·m (0.005″ - 0.009″)
Differential Bearing Rolling Resistance	0.5 N·m -1.1 N·m (5 in. lbs. - 10 in. lbs.) Greater than pinion bearing rolling resistance and adjusted by tightening/loosening bearing rings.
FWD Clutch Preload Air Gap	1.5 ± 0.2 mm (0.060″)
FWD Clutch Release Operating Pressure	16.6 bar - 18.0 bar (240 PSI - 260 PSI)

*Measured w/o seals installed.

TIGHTENING TORQUES

	N·m	Ft Lbs
Differential Bearing Cap Bolts	240 - 270	180 - 200
Differential Bearing Adjusting Ring Lock Tab Retaining Bolts	47 - 54	35 - 40
Pinion Nut	325 - 410	240 - 300
Crown Wheel Retaining Bolts	165 - 190	120 - 140
Differential Housing Bolts	130 - 150	95 - 110
Differential to Axle Housing Bolts	190 - 217	140 - 160
Drive Shaft Retainer Bolts	47 - 61	35 - 45
Swivel Pin Retaining Bolts	108 - 122	80 - 90
Ring Gear Retaining Bolts	88 - 102	65 - 75
Cylinder/Track Rod Ball End Nut	190 Min.*	140 Min.*
Cylinder/Track Rod Clamp Nuts	82 - 95	60 - 70
* Tighten further to fit split pin if required.		
Hub Rolling Resistance	6 - 10	50 - 90 in. lbs.

SEALERS

Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595, OR 596 LOCTITE ULTRA BLUE 587
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)

LUBRICANT SPECIFICATIONS

80-90W GL5	
Hub Oil Capacity	
3 pinion	1.6 L (1.7 qts.)
4 pinion	1.3 L (1.4 qts.)
Center Housing Oil Capacity	12.3 L (13 qts.)
FNH Limited Slip Oil Additive #9706315DS	0.47 L (16 oz.)

SPECIAL TOOLS


Engine splitting stand	FTC50817
Transmission support stand	FTC60296
Pinion/diff setting tool set	FNH00400
Pinion seal installer	FNH00410
Bearing installer	FNH00411
Step plate	FNH00412
Spanner wrench (rotates wheel hubs)	FNH00413
Hub seal installer	380000014

HUB OVERHAUL TOOLS

1 Seal installer 380000014

2 Roller torque check tool #FNH00413

3 Bearing installer #FNH00411




1

DIFFERENTIAL OVERHAUL TOOLS


Drive Flange Wrench Tool Dimensions
Fabrication of 70S021 from 10 mm (3/8″) thick mild steel plate.

A = 40 mm (1-37/64″)
B = 220 mm (8-21/32″)
C = 140 mm (5-1/2″)
D = 95 mm (3-3/4″)
E = 10 mm (3/8″)
F = 110 mm (4-21/64″)
G = 46 mm (1-3/16″)
H = 65 mm (2-55/64″)
J = 9 mm (3/8″)




2

1 Drive flange wrench local fabrication
2 Drive flange installing tool FNH part #00408
3 Oil seal installing tool FNH part #00410



3

1 Differential bearing preload adjuster wrench FNH part #00409
2 Handle and shaft FNH part #00401/2
3 Threaded spacer FNH part #00403
4 Gauge block FNH part #00404
5 Sleeve FNH part #00406
6 Gauge block FNH part #00407



4

DESCRIPTION OF OPERATION


INTRODUCTION

Three different variations of the FWD front axle are used. The features and differences are described below.

All FWD axles feature an overall reduction ratio of 21.525:1

All FWD axles feature easy component access and simple service procedures.


All seals can be replaced without removing the front axle, and the internal axle shafts U-joints are lube for life style.



5

One variation is the standard steerable axle with automatic limited slip differential and three pinion outboard planetary reduction hubs.


The second variation is the standard steerable axle with automatic limited slip differential and four pinion outboard planetary reduction hubs.



6

The third variation is the SuperSteer™ FWD axle with automatic limited slip differential and four pinion outboard planetary reduction hubs.

The SuperSteer FWD axle casting is different than the standard steer axle because of the mounting surfaces for the axle subframe.




7

Op. 25 100


STANDARD STEER FWD AXLE

The FWD axle oscillates on a pin which is fastened on the front frame support similar to the two-wheel drive axle. This provides for 10° - 11° oscillation. The axle housing contains bushings, 1, which rotate on the pin.




8

The outer spuckles, 1, (swivel housings) pivot up to 50°. This provides the axle with the steering ability. The term “spuckle” comes from a combination of the words spindle and knuckle.




9

The steering linkage is operated by two externally mounted double-acting steering cylinders, 1. The standard FWD axle cylinders are 57.15 mm (2.25″) diameter.




10

There are adjustable stops to limit the turn angle from 18° - 50°. These stops can be set at 18/24/27/33/36/42/44/50 to limit the turning radius to prevent wheel to frame contact.




11

The axle is equipped with a hypoid gear reduction differential. The differential is located on the centerline of the axle and the tractor. The gear ratio of the differential is 4.1:1.




12

The automatic limited slip differential provides for limited torque biasing to the wheel that has the best traction. The unit will sense when a wheel is slipping and transfer up to a large percentage of available torque to the other wheel that has some traction.



13


The power flow then goes out through the constant velocity universal joints to the outboard planetary reduction hubs.



14


The outboard hubs use planetary gears to provide additional 5.25:1 gear reduction.

The 8670 tractor uses a three-pinion, 1, planetary hub because of the lower front axle loads.



15


The larger model tractors and all SuperSteer FWD axles use a four-pinion, 1, planetary hub.



16

The axles are lubricated with 80W-90 GL5 fluid. Each axle center section holds 12.3 L (13 quarts) of fluid. The fill plug, 1, is located in the axle housing.

NOTE: *The center section must also have 473 ml (16 ounces) of the FNH limited slip oil additive #9706315DS added to the fluid.*




17

The three-pinion hubs contain 1.6 L (1.7 quarts) each, and the four-pinion hubs each contain 1.3 L (1.4 quarts) of the 80W-90 GL5 fluid.

The fluid drain plugs, 2, are located in the hubs as shown.

The arrow, 1, is an indicator of the hub rotation during the checking, draining, or filling of the hub fluid.




18

Op. 25 100


SUPERSTEER FWD AXLE

The SuperSteer FWD axle, 1, has all the features of the four-pinion standard steer FWD axle plus the axle offers a smaller front turning radius. A maximum of 65° steering angle is available due to the mounting arrangement of the FWD axle to the tractor.




19

The tractor front-end weights, 1, attach directly to the SuperSteer FWD axle assembly. This is done so that the weight load is carried directly on the axle. The weight package can be removed with two chains as shown. Use extreme caution because this weight package weighs over 1800 kg (4000 lbs).



20



21

The design of the pivoting front axle mount linkage and the steering linkage permit articulation of up to 15° relative to the tractor frame.

The important part of this design is that the spuckle housings are connected to the tractor frame with the tie rods which makes the tractor chassis a link in the system.


This steering action occurs when one of the steering cylinders apply force to the outer spuckle housings as the turn is started. The tie rods which connect the spuckle housings to the tractor front frame cause the axle to move under the front frame. This action causes the entire front axle assembly to pivot underneath the tractor on the rear spherical bushing.

Axle and wheel spuckle steering occur simultaneously. When steering, the cylinder on the same side as the direction of the turn will shorten causing the spuckle and wheel to rotate into the turn. Simultaneously, the action of the cylinder causes the tie rod to push the chassis away from the direction of the turn.

Depending on the speed and rate of turn, the tractor chassis could initially travel in a straight line while the wheels turn and the axle swings out from its center position.

The movement of the chassis relative to the turning wheels gives greater tire to tractor clearances allowing for much tighter turns.

The SuperSteer FWD steering cylinder displacement is 31% greater than the standard steer axle which increases the lock to lock turns by about one turn while providing much shorter turnaround diameters. The SuperSteer cylinders are 63.5 mm (2.50″).



22

The axle is mounted to subframe plates, 1, which are mounted to the tractor frame with an articulation bushing, 2, at the rear pivot.

The axle is mounted to the front of the tractor with a vertical link, 3, that pivots on bushings.

This allows the entire axle assembly to articulate 15° relative to the tractor frame.

Two rollers, 4, mounted under the front frame serve as oscillation stops and assist in carrying the front-end load while articulation and oscillation is taking place.

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor is hard to steer	Spuckles(spindles) will not rotate	Grease the bearings
	Low power steering pressure	Check power steering operation (see Section 41, Chapter 1)
	Limited slip differential won't release	Add limited slip oil additive
Tractor wanders on ridged roads/rough fields	Toe-in set incorrectly	Adjust toe-in
	Loose steering linkage	Replace worn parts/tighten tie rod mounting bracket
	Air in the cylinder	Bleed the cylinder hoses
	Steering cylinder seals worn	Rebuild steering cylinder
	Worn tires or low tire pressure	Replace tires/check tire pressure for the load
	Worn steering control valve	Troubleshoot steering control valve (see Section 41, Chapter 1)
	Limited slip differential not working	Add oil additive or inspect clutch plates for wear
	FWD tire match is incorrect	Review tire pressure and tire loaded radius
Oil leaks from steering cylinder	Worn steering cylinder seals	Rebuild/replace the steering cylinder
FWD clutch slips	Clutch plates worn	Rebuild clutch
FWD clutch won't disengage	Electric or hydraulic circuit malfunctioning	Troubleshoot the control circuits
		Release park brake
Tires contact the frame/hood	Steering stops set wrong	Set stops to limit radius
Differential makes clicking noises	Limited slip clutches are not releasing	Add limited slip oil additive

ADJUSTMENTS

Op. 41 106

WHEEL TOE-IN (FWD)


Checking Toe-in on Standard and SuperSteer Axles

Use the following procedure to check and adjust toe-in:

The correct toe-in is 0 mm - 6 mm (0″ - 1/4″).

1. Position the front wheels straight ahead.
2. Mark the inside front of each rim at hub height. Mark the rim where the tire and rim meet.
3. Measure distance, 1, between the two marks.
4. Drive the tractor forward until the tires rotate 180° and the marks are at hub height at the rear of the wheels.
5. Measure distance, 2, between the two marks.
6. Subtract the front measurement from the rear measurement to get the toe-in.
7. The toe-in should be 0 mm - 6 mm (0″ - 1/4″).

If adjustment is required, proceed to the procedure for the style FWD axle installed.




23

Adjusting Toe-in on Standard Steer FWD

To adjust the toe-in:

1. Loosen jam nuts, 1, on each side of the tie rod.
2. Turn the tie rod tube, 2, to adjust the toe-in to 0 mm - 6 mm (0″ - 1/4″).
3. Tighten the jam nuts, 1, on each side of the tie rod.
4. Check the adjustment of the steering stops.



24


Adjusting Toe-in on SuperSteer FWD Axle
To adjust the toe-in:

1. Park the tractor on level ground with front axle steering straight ahead.

NOTE: *Check that the center of the axle is aligned with the center of the tractor before adjusting toe-in. Turn angle will be affected if the axle is not centered.*

NOTE: *Before adjusting toe-in, measure distance, 1, between the outer, 2, and inner, 5, tie rod ends on both tie rods. Adjust the tie rods to achieve equal measurements before proceeding.*

2. Loosen the two jam nuts, 3, on each tie rod.
3. Turn each tie rod tube, 4, evenly to adjust the toe-in to 0 mm - 6 mm (0″ - 1/4″).
4. Tighten the two jam nuts, 3, on each tie rod.
5. Check the adjustment of the steering stops.



25

Op. 25 108

FWD STEERING STOPS


A steering stop is incorporated at each end of the axle. The stops are adjustable and must be set to provide a minimum clearance of 38 mm (1-1/2″) between the tires or, if installed, fenders, and any part of the tractor with the wheels turned full left and right with the axle fully oscillated.

NOTE: *If your tractor is equipped with optional front fenders, ensure there is adequate clearance under all operating conditions. Adjust the steering stops as necessary.*

Each hole, 1, in the steering stop is marked with a number, 2, and arrow, 3. The stop has four holes.

When the arrow points to the steering knuckle, the number indicates the turn angle. Arrows appear in both directions on the stop so the stop can be installed in either direction to provide eight different turn angles.

Adjust the steering stops at both ends of the axle to the same turn angle.



26


Op. 25 108

HUB BEARING PRELOAD ADJUSTMENT (HUB BEARING ROLLING RESISTANCE)

The hub bearing preload adjustment can be made by first assembling the hub components without shims to measure required shim thickness. Then add appropriate shims and check hub rolling resistance.


Locate hub on swivel housing.

NOTE: *Dust seal and oil seal are not fitted at this stage.*




27

Install ring gear, 1, and taper roller bearing, 2, onto splines, 3.




28

Install retainer plate without shims.




29

Tighten retainer plate bolts evenly and slowly until a hub bearing rolling resistance of 6 N·m - 10 N·m (50 in. lbs. - 90 in. lbs.) is obtained.



30

Install tool, 1, #FNH00413 and use torquemeter, 2, to measure hub rolling resistance with sun gear installed. Torquemeter reading should be 6 N·m - 10 N·m (50 in. lbs. - 90 in. lbs.).




31

Calculate hub bearing preload shim thickness as follows:


- Using depth micrometer, 1, measure depth from retainer plate, 2, to end of splined shaft on swivel housing. Call this dimension A.
- Measure thickness of retainer plate. Call this dimension B.
- Shims thickness required = A–B.

  Shim thicknesses available:
  0.05/0.075/0.125/0.25/0.5/0.75 mm
  (0.002/0.003/0.005/0.010/0.020/0.030″)




32

Install selected shims and retainer plate and torque retaining bolts to 88 N·m -102 N·m (65 ft lbs - 75 ft lbs).




33

Install sun gear shaft and ensure shaft is engaged into drive shaft yoke snap ring.



34

Use tool, 1, #FNH00413 to check hub rolling resistance with shims Installed. The torquemeter, 2, reading should be 6 N·m - 10 N·m (50 in. lbs. - 90 in. lbs.).



35


Op. 25 102

CHECKING FOR CORRECT PINION TO RING GEAR TOOTH CONTACT

Put Prussian blue or red lead on the flanks of the ring gear teeth. Turn the ring gear over the pinion gear teeth in both directions to determine the correct contact pattern. See the contact patterns in the following illustrations.

Correct adjustment is made when the pattern of the tooth contact area (both horizontal and vertical) is as shown.

NOTE: *The contact patterns of the ring gear teeth that are shown are approximate shapes. The gear teeth contact patterns can change from the illustrations, but the same general shape must be seen. The tooth contact pattern can change in a used gear set because of wear of the parts. Try to get a contact pattern that is similar to the illustrations to get the best results. The pinion depth setting must be repeated if the contact pattern is not correct.*




36

Op. 25 102


WRONG TOOTH CONTACT PATTERN

Pattern A
The pinion gear is out too far. Remove some of the pinion shim pack that was installed. Adjust the backlash again and check the contact pattern.




37

Pattern B
Not enough backlash. Move the ring gear away from the pinion gear. Readjust the backlash and recheck the contact pattern.




38

Too much backlash. Move the ring gear toward the pinion gear. Readjust the backlash and recheck the contact pattern.




39

The pinion gear is in too far. Add some more shims to the pinion shim pack that was installed. Readjust the backlash and recheck the contact pattern.



40

1. Move the pinion gear, 1, toward the ring gear, 2, to correct pattern A.
2. Move the ring gear, 2, away from the pinion gear, 1, to correct pattern B.
3. Move the ring gear, 2, toward the pinion gear, 1, to correct pattern C.
4. Move the pinion gear, 1, away from the ring gear, 2, to correct pattern D.



41

Op. 25 108

SWIVEL PIN BEARING ADJUSTMENT


NOTE: *The swivel bearing oil seals need to be removed to check the torque.*

1. Turn the swivel housing to the right without the tie rod connected and position the torquemeter on a swivel pin bolt.
2. Using the torque meter, measure the torque required to turn the swivel housing.
3. If the turning torque is not within the specification of 11 N·m - 20 N·m (8 ft lbs - 15 ft lbs), adjust shim thickness until correct torque is achieved. Reducing shim thickness will increase turning torque. Increasing shim thickness will reduce torque.
4. Shims are available in the following sizes:


   0.05/0.15/0.25/0.375/0.75 mm
   (0.002/0.006/0.010/0.015/0.030″)

NOTE: *Be sure that the shims, 3 and 4, installed are divided equally between the upper swivel pin, 1, and the lower swivel pin, 2.*

5. After selection of shim, install new swivel pin oil seals.



42



43

Op. 25 104

FWD RATIOS


Front and rear tire sizes must be matched correctly to provide the proper FWD axle operation. For proper operation the FWD axle will operate within a range of 0% to 6% lead. (The optimum lead ratio for best steering, traction and tire performance is 0.5% to 3%.) This means that the front tires should appear to be pulling slightly faster than the rear tires.

The relationship of the front axle overall ratio to the rear axle overall ratio is called the FWD factor and is established by the installation of a specific clutch drum and gear assembly in the FWD clutch. This FWD factor is printed on the serial number plate on the tractor.

The FWD factor can be changed by selecting a different clutch drum and gear assembly if the front and/or rear tires are changed from the sizes that were factory installed. If changing tire sizes use information in the appropriate table that follows along with the tractor serial number and gear ratio installed in the tractor or the appropriate table combined with a different gear ratio being selected for use.

Tractors BSN D415637

For tractors prior to serial number D415637, the following table shows the relationship of the basic tire sizes used.



44

Op. 25 104

FOUR WHEEL DRIVE TIRE VS GEAR RATIOS (ORIGINAL EQUIPMENT BSN D415637)

The code letters in the boxes show the gear ratios and FWD factors for the tire combination that lines up in the columns and rows. Complete front and rear tires sets can be interchanged as long as the same gear set letter is shown. If a different gear set is listed, then the clutch hub driven gear will have to be changed.

FRONT TIRES / **REAR TIRES**	**18.4 x26**	**14.9 x28**	**14.9 R28**	**16.9 x28**	**16.9 R28**	**14.9 R30**	**480/70 R30**	**16.9 R30**	**18.4 x30**
18.4R38			B						
20.8x38	B	A		B					
20.8R38	B		A		B				
710/70R38							A		
18.4R42			A		B	B			
20.8R42						A		A	B
14.9R46			A			A			
420/80R46						A		B	
18.4R46						A		A	B
R2 TIRES	**16.9 x26**	**18.4 x26**	**16.9 R30**						
20.8x38R2	B	B							
18.4R42R2	A	A							
20.8R42R2			A						

CODE LETTER	DRIVE GEAR TEETH	CLUTCH DRIVEN GEAR TEETH	FWD FACTOR 87/88/8970	8670
A	41	38	1.37799	1.393
B	41	40	1.30909	1.324

NOTE: *For non-standard tire options, see information on calculating lead (slip) factor after the tables in this section.*

NOTE: *Detailed information about tire options can be found in the Price and Data book.*

CAUTION


The front end of the tractor should not be weighted excessively in an attempt to eliminate this wheel slip (lead). This slip/lead is for shock absorption that protects the fwd components from excessive torque loads.

Tractors SN D415637 and Above

For tractors with SN D415637 and above, only one clutch-driven gear tooth per model is offered.

MODEL	DRIVE GEAR TEETH	CLUTCH DRIVEN GEAR TEETH	FWD FACTOR
8670	41	40	1.324
8770,8870,8970	41	39	1.342

The FWD factor is printed on the serial number plate on the tractor. The 39-tooth gear is also stamped, as shown in Figure 44, on the clutch driven gear.



45

For tractors SN D415637 and above the following tables show the relationship of basic tire sizes used as original factory equipment.

8670 (ASN D415637) FWD TIRE COMBINATIONS (40 TOOTH GEAR) 1.324 FWD FACTOR

The G, A, and F refer to Goodyear, Armstrong, and Firestone tires originally supplied as factory options.

8670 Bias Tire Combinations (40 tooth gear)				
FRONT TIRES → / **REAR TIRES ↓**	14.9 x 28, 10 PR (R1) BIAS	16.9 x 28, 10 PR (R1) BIAS	18.4 x 30, 8 PR (R1) BIAS	18.4 x 30, 10 PR (R2) BIAS
20.8 x 38, 10 PR (R1) BIAS	G-A-F	A-F		
18.4 x 42, 10 PR (R1) BIAS		F		
20.8 x 42, 10 PR (R1) BIAS			F	
20.8 x 42, 14 PR (R2) BIAS				F

8670 R2 Radial Tire Combinations (40 tooth gear)			
FRONT TIRES → / **REAR TIRES ↓**	16.9R28**	16.9R30**	18.4R28**
18.4R42**	G-F	G	
20.8R38**	G-F		
18.4R46***		G	
20.8R42**		G	G

8670 R1 Radial Tire Combinations (40 tooth gear)						
FRONT TIRES → / **REAR TIRES ↓**	14.9R28***	14.9R30***	14.9R34***	16.9R28**	16.9R30***	320/85R34***
18.4R38**	G-A-F					
14.9R46***		G-A				G
18.4R42**		G-A-F		G-A-F	G-F	G
18.4R46***			G-A-F			
20.8R38**				G-A-F		
20.8R42**					G-A	
420/80R46***						G
320/90R50***						G

8670 R1W Radial Tire Combinations (40 tooth gear)							
FRONT TIRES → / **REAR TIRES ↓**	16.9 R28**	16.9 R30**	18.4 R30**	480/70 R30***	520/70 R30**	540/65 R30**	600/65 R28**
18.4R42**	G-A						
20.8R42**		G-A-F	F	G-A-F			
710/70R38***			F		G	G	G-A-F
650/65R42**						G	

8770, 8870 & 8970 (ASN D415637) FWD TIRE COMBINATIONS (39 TOOTH GEAR) 1.342 FWD FACTOR

The G, A, and F refer to Goodyear, Armstrong, and Firestone tires originally supplied as factory options.

8770, 8870 & 8970 Bias Tire Combinations (39 tooth gear)			
FRONT TIRES → / **REAR TIRES ↓**	16.9 x 28, 10 PR (R1) BIAS	16.9 x 28, 10 PR (R1) BIAS	18.4 x 30, 10 PR (R2) BIAS
18.4 x 42, 10 PR (R1) BIAS	F		
20.8 x 42, 10 PR (R1) BIAS		G	
20.8 x 42, 14 PR (R2) BIAS			F

8770, 8870 & 8970 R1 Radial Tire Combinations (39 tooth gear)				
FRONT TIRES → / **REAR TIRES ↓**	14.9R30***	14.9R34***	16.9R28**	16.9R30***
14.9R46***	G-A-F			
18.4R42**	G-A-F		G-A-F	G-A-F
18.4R46***		G-A-F		
18.4R42**				
20.8R38**	G-A-F			G-A-F
20.8R42**		G-A-F		
420/80R46***	G			

8770, 8870 & 8970 R2 Radial Tire Combinations (39 tooth gear)			
FRONT TIRES → / **REAR TIRES ↓**	16.9R28**	16.9R30**	18.4R28**
18.4R42**	G-F		
18.4R46***		G	
20.8R38**	G		
20.8R42**		G	F

8770, 8870 & 8970 R1W Radial Tire Combinations (39 tooth gear)						
FRONT TIRES → / **REAR TIRES ↓**	16.9R28**	16.9R30**	420/70R30***	480/70R30***	540/65R30**	600/65R28**
18.4R42**	G-A		G			
20.8R38**			G			
20.8R42**		G-A-F		G-A-F		
710/70R38***		G-A-F		G-F	G	
650/65R42**						G

FOUR-WHEEL DRIVE LEAD FACTOR

To achieve the best tractor efficiency and tire life, the four-wheel drive system must have a lead factor between 0% and 6% (i.e., front wheels drive faster than rear). The optimum lead is 0.5% to 3%.

The lead factor is calculated by a simple formula:

$$\%\ \text{LEAD} = \left(\frac{\text{FWD FACTOR X *FRONT WHEEL ROLLING CIRCUMFERENCE}}{\text{*REAR WHEEL ROLLING CIRCUMFERENCE}} - 1 \right) \text{X } 100$$


**Weighting and tire pressures for application.*

NOTE: Where radial ply tires are used, the rolling circumference must be multiplied by 1.015. If the FWD factor is unavailable it can be calculated with the following formula using the driveline schematic and ratios follow this section.


$$\text{FWD FACTOR} = \frac{\text{REAR AXLE RATIO}}{\text{FRONT AXLE RATIO X TRANSFER BOX RATIO}}$$

To ensure correct front and rear wheel compatibility where manufacturer's rolling circumference figures are not available, establish front and rear loaded wheel rolling circumferences on hard level surface with tire pressures and weights as for normal operation.

- Mark the point where the front and rear tires contact the ground using a plumb line.
- Ensure 4-wheel drive is DISENGAGED.
- Drive slowly forward in 1st gear until the front and then rear wheel marks contact the ground, marking the ground in both cases.
- Measure the distance between the respective front and rear wheel first and second marks which are the respective loaded wheel rolling circumference.
- Use figures in the above formula to calculate % slip, which must be 0% - 6%.


70-240-1777

46



47

DRIVELINE SCHEMATIC

TRANSFER BOX		A	Or	B	Or	C*
A	Pinion Drive Gear	41		41		41
B	Transfer Box Output Gear	38		40		39
	TRANSFER BOX RATIO	0.926829	Or	0.975610	Or	0.951219

*Used only after serial number D415637.

FRONT AXLE		
C	Ring Gear	41t
D	Pinion	10t
Ring Gear/Pinion Ratio		4.1 : 1
E	Ring Gear	68t
F	Sun Gear	16t
*Planetary Ratio		5.25 : 1
	FRONT AXLE OVERALL RATIO	21.52 : 1

REAR AXLE		8670	8770-8970
C	Ring Gear	45t	54t
D	Pinion	8t	11t
Ring Gear/Pinion Ratio		5.625 : 1	4.9091 : 1
E	Ring Gear	67t	69t
F	Sun Gear	17t	15t
*Planetary Ratio		4.94 : 1	5.60 : 1
	REAR AXLE OVERALL RATIO	27.79 : 1	27.49 : 1

$$\text{*PLANETARY REDUCTION} = \frac{\text{Ring Gear teeth + Sun Gear teeth}}{\text{Sun Gear teeth}}$$

$$\text{FOUR-WHEEL DRIVE FACTOR} = \frac{\text{Rear Axle Ratio}}{\text{Front Axle Ratio X Transfer Box Ratio}}$$

FOUR-WHEEL DRIVE FACTOR
1.378 (38t driven gear)
1.309 (40t driven gear)
1.324 (39t driven gear)

FRONT AXLE SERVICEABILITY


Op. 00 400

LUBRICATION

Hub Oil Capacity -
1.6 L (1.7 US qts.) on 3 pin hub.
1.3 L (1.4 US qts.) on 4 pin hub.


Center Housing Oil Capacity - 12.3 L (13 US qts.)

1 Data plate




48

1 Axle oil drain plug
2 Axle fill/check plug




49

Rotate the wheel so that arrow, 2, is pointing straight down. Remove plug, 3, to fill or check hub oil. Rotate the wheel until the fill/drain/check plug is at its lowest point, 1, to drain oil.




50

Lube the rod ends, both axles.




51

Lube kingpin bearings, both axles.




52

Lube axle steering pivots, both axles.




53

Lube the standard steer pivot pin.




54

Lube SuperSteer pivot pin.




55

Lube SuperSteer front pivot pins.




56

Lube the SuperSteer rear pivot.




57

Lube the SuperSteer kingpin bearings.



58

Lube the axle cylinders.




59

COMPONENT SERVICE

Components serviced with the axle installed on the tractor:

1 Power steering cylinders
2 Track rod
3 Reduction hubs and oil seals
4 Swivel housings, swivel pin bearings, drive shafts and oil seals
5 Pinion oil seal

Components serviced with the axle removed from the tractor and the previously listed items removed.



60

Differential assembly*

When servicing the axle, disassemble, adjust and reassemble the item to be repaired using the illustration sequence shown. Inspect all components for wear and replace all seals. During reassembly, tighten components to the torques detailed in “Specifications.”

*****The differential assembly can be removed with the axle assembly still attached to the tractor.

DISASSEMBLY AND REPAIR

Op. 25 100


FRONT AXLE

Removal

⚠ WARNING ⚠

When overhauling the axle, always ensure that the tractor and axle is fully supported on axle stands and that the rear wheels are blocked to prevent movement of the tractor.


It is not necessary to remove the complete axle assembly to service the outboard planetary reduction units or the center differential assembly. Some illustrations may show the axle removed for clarity.



61


The SuperSteer axle does not have to be removed to service the front drag link bushings or the rear pivot bushing. Some illustrations may have other components removed for clarity.

1. Block the rear wheels to prevent tractor movement.
2. Remove the front-end weights using a suitable hoist.
3. Jack up the front end of the tractor, and install engine side rail support stands and safety stand under the transmission.
4. Remove the front wheels, drive shaft, and shield, then disconnect the hydraulic steering hose connections.



62


5. Support the front axle using the transmission splitting stand as shown.



63


NOTE: *If the axle is being removed for overhaul of the differential, the hubs, swivel housings and axle shafts can, if required, be removed while the axle is installed on the tractor.*

6. Remove the two bolts which hold the SuperSteer tie rod mounting bracket, 1.




64

7. On standard FWD, loosen the front and rear mounting bracket retaining bolts, 1.




65

8. On a SuperSteer axle, loosen the bolts, 1, which attach the side plates to the rear pivot bracket.




66

9. Loosen the four front bolts which hold the side plates to the axle assembly.




67

10. Remove bolt,1, which retains the front pin, and remove the front pivot pin.



68

11. Remove the front axle assembly by lowering the support stand, so the front drag link, 1, will clear the front bolster.
12. Roll the axle assembly forward until it is clear of the tractor.



69


Installation

Where new bearings have been installed, it is essential that the swivel housing turning torque and hub bearing preload adjustments are also performed as shown in “Adjustments.”

For installation, reverse steps one through twelve.

Refill the center housing and reduction hubs with 80W-90GL5 oil. Limited slip oil additive must be installed in the center housing. Refer to the operator’s manual for more information.

Replace the front wheels and carry out the front axle toe-in; check and, if required, adjust to obtain correct toe-in of 0 mm - 6 mm (0″ - 0.25″).



70

Op. 41 216

STEERING CYLINDERS


IMPORTANT: *The left-hand piston rod is approximately 18 mm longer than the right-hand rod.*

Disassembly

1. Remove setscrew, 5.
2. Tap cylinder head, 2, inward.
3. Remove, 1, wire retaining ring.
4. Pull rod, 6; piston, 3; and cylinder head assembly, 2, out of the cylinder.
5. Inspect parts.

Reassembly

1. Install new seals on 2 and 3, as shown in Figure 69.
2. Torque nut, 4, to 165 N·m - 190 N·m (120 ft lbs - 130 ft lbs).
3. Install piston assembly, 5; rod, 6; and head assembly, 2, back into the cylinder. Load area of the head with grease.
4. Insert wire retaining ring, 1.
5. Pull head up against retaining ring.
6. Install setscrew, 5.




71

1. Seal
2. Back-up washer
3. O ring
4. Piston
5. Seal
6. Nut
7. Cylinder assembly
8. Piston rod
9. Seal
10. Cylinder head
11. Retaining ring

Installation

Torque the cylinder/track rod ball end joint nuts to a torque of 190 N·m (140 ft lbs) and further tighten until a split pin can be installed.

Check and adjust toe-in to 0 mm - 6 mm (0″ - 0.25″).




72

Op. 25 108

PLANETARY REDUCTION


Removal

Drain oil by removing allen screws, 1, and drain plug, 2, from the hub.




73

To remove the planetary housing, chisel between the housing and the hub to break the seal. Pull the housing away from the hub.




74

Remove the sun gear shaft by levering behind the gear while pulling out.




75

Remove the six bolts, 2, which hold the retaining plate, 1, and shims, 3, to the splined support, 4.



76

The ring gear, 1, and taper roller bearing, 2, can now be pulled from the splined support, 3.



77


Overhaul

Inspect the components for wear or damage to determine parts to be replaced.

The planetary reduction housing is serviced complete with pinion support shafts.

All parts are interchangeable between three- and four-pinion reduction gears except for the housing and thrust plates.


Use a hydraulic press and bearing clamp to remove taper roller bearing, 2, from ring gear, 3. Install a new bearing using adaptor, 1, #FT-3161 and flat spacer, 4, #N 804659-S36 as shown.



78

Planetary reduction components, 3-pinion reduction


1 Planetary pinions (25 teeth)
2 Sun gear shaft (16 teeth)
3 Planet pin
4 Needle bearing
5 Thrust plate
6 Retainer ring
7 Drain level plug
8 Allen screw
9 Planetary housing
10 Needle spacer
11 Retainer plate
12 Shims
13 Ring gear (68 teeth)



79

Planetary reduction components, 4-pinion reduction


1 Planetary pinions (25 teeth)
2 Planet pin
3 Needle bearings
4 Thrust plate
5 Retainer ring
6 Drain level plug
7 Planetary housing
8 Needle spacer
9 Sun gear shaft (16 teeth)
10 Retainer plate
11 Shims
12 Ring gear (68 teeth)



80

Installation


Apply Loctite 271 to retainer plate bolts. Install shims, 3, and retainer plate, 1, on splined shaft, 4. Torque bolts, 2, to 88 N·m - 102 N·m (65 ft lbs - 75 ft lbs).



81


Check hub rolling resistance with tool, 1, #FNH00413. If you do not obtain a torquemeter, 2, reading of 6 N·m - 10 N·m (50 in. lbs. - 90 in. lbs.), perform hub bearing preload adjustment as described under “Adjustments” in this chapter.

NOTE: *Preload is checked w/o seal drag.*



82

Lightly oil the sun gear and install sun gear, 2. Ensure that the sun gear shaft is engaged into the drive shaft yoke snap ring. Apply anaerobic adhesive to the flange surface. Install the planetary housing, 1, over ring gear, 3, and secure with allen screws. Install the drain plug and fill with oil (see Specifications at the beginnign of this chapter).




83

Op. 25 108

HUB

Removal

Remove the planetary reduction components as previously described. The hub, inner bearing, 2, and oil seal, 1, can then be pulled off as an assembly. Remove dust seal, 3.




84

Disassembly

The bearing cups can be driven outwards using a hammer and punch; the oil seal and inner bearing will be removed when removing the inner bearing cup.

The inner bore of the hub casting is machined to allow access to the inner face of the bearing cup.




85

Hub Components

1. Outer bearing cup
2. Taper roller bearing
3. Wheel stud
4. Taper roller bearing
5. Oil seal
6. Inner bearing cup
7. Hub

Reassembly

Press bearing cone, 2, into the hub using adaptor, 1, #FNH00411.




86

Press both inner and outer taper roller bearings, 2, into the hub before installing oil seal, 1.

NOTE: *Measure rolling resistance prior to installing seal. See planetary reduction, Installation Section on previous pages.*


NOTE: *If using the new seal number 86505056 in the old Dana hub, use the adaptor ring that comes with seal installer #380000014. This prevents the seal from being driven too far into the hub before the tool bottoms out.*

If using the new seal number 86505056 with the new Dana hub, use just the seal installer #380000014.




87

Press oil seal, 2, into the hub.



88


Installation
Locate dust seal, 1, over seal location, 2, machined into the swivel housing.



89

Install the hub onto the swivel housing.

1 Oil seal
2 Bearing
3 Dust seal



90


Op. 25 108

SWIVEL HOUSING

NOTE: *Drain oil from the center housing before removing the drive shaft.*


Removal

Remove tie rod, 4. Remove the eight bolts holding the top and bottom swivel pins, 2 and 3. Remove swivel pins and shims, 1.



91


The swivel housing can now be separated from the axle housing.



92

Overhaul

Using a drive handle and special tool step plate #FNH00412 drive bushing, 1, inwards to remove oil seal, 3.




93

Install bushing, 3, and then oil seal, 4, using drive handle, 1, and special tool step plate #FNH00412, 2.

NOTE: *When replacing the sun gear shaft oil seal, the following should also be carried out:*


1. Inspect the sun gear shaft for signs of scoring or damage on the surface in contact with the seal. Replace if scored or damaged.
2. Inspect the bushing and replace if scored or damaged.
3. Check the axle serial number. If prior to 77186, replace the original bushing with the improved type.
4. Lightly oil the sun gear shaft prior to insertion.



94

Swivel Housing Assembly


1 Retaining bolt
2 Swivel housing
3 Shims
4 Grease nipple
5 Bushing
6 Oil seal
7 Swivel pin



95

Installation
Coat the swivel pins and bearings with No. 2 lithium grease.


Position the swivel housing onto axle housing, 1, and ensure that yoke, 2, is guided into the swivel housing bore.



96

Install 0.357 mm (0.015″) shim packs, 3 and 4, beneath the upper, 1, and lower, 2, swivel pins, then tighten the swivel pin retaining bolts evenly to 136 N·m -155 N·m (100 ft lbs - 115 ft lbs).

Check to see if the swivel housing turning torque is within 11 N·m - 20 N·m (8 ft lbs - 15 ft lbs). If it is not, see “Adjustments” to set the turning torque. Install the tie rod end.



97


Op. 25 108

CENTER HOUSING SWIVEL BEARING

Removal

To remove swivel bearings:

1. Remove oil seal, 3, and taper roller bearing, 5.
2. Drive grease retainer, 4, through the hole in the axle housing lug, 2, using a punch.



98


3. Use slide hammer, 1, and extractors, 3, to remove bearing cup, 2.

Installation

To replace swivel bearings:

1. Clean housing bore, apply Loctite sealant 515 to grease retainer, and drive into position.
2. Fit new bearing cup and bearing.

NOTE: *Before installing oil seal, assemble swivel housing and check swivel pin bearing turning torque as described under "Adjustments" in this chapter.*



99

3. Install oil seal.

Op. 25 108


DRIVE SHAFT

Removal

NOTE: *The drive shaft installed in the right-hand side of the axle housing is approximately 33 mm longer than the shaft in the left-hand side.*


Remove the three bolts, 1, securing the drive shaft retainer plate, 2.

NOTE: *The retainer plate is secured with Loctite to the center housing.*




100

Use a pry bar to pull the drive shaft free of the axle housing.




101

The drive shaft assembly is made up of the universal joint, 1, retainer plate, 2, and drive shaft, 3.



102



103

1. Retaining bolt
2. Oil seal
3. Dust seal
4. Yoke
5. Oil seal
6. Snap ring
7. Needle rollers and cup
8. Spider
9. Center yoke
10. Retaining clip
11. Spider
12. Drive shaft
13. Collar
14. Bearing
15. Retainer plate

Component Inspection And Repair

Inspect the drive shaft assemblies for wear or damage to determine the replacement parts required.

Service assemblies or kits are available:

Complete drive shaft and universal joint assembly.


Drive shaft assembly.

Universal joint kit.

If the drive shaft oil seal is to be replaced, use a hydraulic press to remove and replace the drive shaft.


Disassembly

Press the retainer, bearing, and collar off the shaft using hydraulic press. Remove the oil seal from the bearing retainer.



104


Support bearing retainer, 3, in the press and use stop plate, 1, #FNH00412 to remove bearing, 2.



105

Assembly

Apply Loctite 515 to the seat on the bearing retainer. Support the bearing retainer and use stop plate, 1, FNH00412 to install bearing. Install a new seal into the bearing retainer. Install the seal with the lip toward the bearing.




106

Fill the seal lip with grease and slide the bearing and bearing retainer onto the axle shaft. Push the collar onto the axle shaft firmly against the bearing.

Place the axle shaft in a press. Press the bearing and bearing retainer onto the axle shaft until the seal is seated against the outer yoke. Place the collar in a bearing oven and heat to 120°C (250°F).

CAUTION

Always wear heat protective gloves to prevent burning hands when handling heated parts.




107

Op. 25 108

OUTER YOKE


Disassembly
Remove the outer seal, 1, inner seal, 2, and the retainer ring, 3, from the yoke.



108

Assembly
Using standard seal installation tools install a new retaining ring, new inner and new outer seal. Install the yoke seals with the lip facing away from the yoke.


Apply grease to needle roller bearing, seal, and bushing, 1, and install needle bearing.



109

Installation


Apply anaerobic sealer, 2, to retainer plate, 3, and install with bolts, 1.



110

After drive shaft retainer plate, 2, is installed, torque retainer bolts, 1, to 47 N·m - 67 N·m (35 ft lbs - 45 ft lbs).

IMPORTANT: *If the drive shaft and planetary hub assembly have been preassembled, make certain the drive shaft U-joint yoke, 3, has engaged the snap ring groove in the sun gear shaft properly. Failure to engage the groove correctly will result in excessive preload on the sun gear shaft and will damage the planetary hub assembly.*




111

Op. 25 102

DIFFERENTIAL


Removal

Remove the differential carrier housing retaining bolts.




112

Support and slide the differential from the dowels using two suitable length locating bolts,1.



113

Pull the differential from the locating pads in the axle center housing.



114


Differential removal with axle attached to tractor

Support both sides of the axle with safety stand, 1.

Remove the four bolts which hold drive shaft flange, 2.


Wrap the lifting chain around the planetary hub assembly, 3.

Drain oil from the differential and planetary hubs.



115


Slide the planetary hub assembly out of the axle. Repeat the same steps on the other side of the axle.



116


Install a support stand under the differential assembly.

Remove the bolts which hold the differential to the axle and pry the differential off the dowel pins.




117

Remove the assembly from under tractor.




118

Lift the assembly up to a workbench.




119

The axle is shown under the tractor with the planetary hubs and differential assembly removed. Two safety stands are supporting the front of the tractor.



120




121

1. Separator plate
2. Differential lock clutch pack
3. Half casing
4. Pinion drive shaft (10 teeth)
5. Inner taper roller bearing
6. Pinion engagement (positioning) shims
7. Adjuster lock plate
8. Bearing preload adjuster
9. Bearing preload shims
10. Outer taper roller bearing
11. Oil slinger
12. Dust shield
13. Pinion oil seal
14. Side gear
15. Spider
16. Pressure plate
17. Spider gears
18. Differential bearing
19. Half casing
20. Crown wheel (41 teeth)
21. Internally splined plate


Disassembly

Remove the differential bearing cap bolts, 2, and differential bearing caps, 3. The crown wheel and differential case assembly, 1, can then be removed.




122

Casing alignment marks should be applied with a center punch or paint pen prior to disassembly.




123

Use drive flange tool, 1, to loosen the nut securing the drive flange. See “Special Tools” in the “Specifications” portion of this chapter for the dimensions to fabricate the tool.




124

Use puller tool and the drive flange tool to remove the drive flange from the pinion shaft.



125

Secure the bearing in bearing clamp tool, 1, and press the shaft out.




126

Component Inspection

Check the following items for wear or damage to determine if replacement parts are required:


- Crown wheel and pinion teeth.
- Differential side gear teeth.
- Differential lock plate surfaces and splines.
- Bearings and cups.

The crown wheel and pinion is supplied as a matched set. Pinion bearing engagement shim check and adjustment must be carried out if new parts are fitted.



127


Reassembly
Install inner bearing cups. Do not install inner bearing cup shims.



128

Install pinion engagement tools:

1 Sleeve #FNH00406
2 Gauge #FNH00404
3 Spacer#FNH00403
4 Tool #FNH00401 and #FNH00402




129

Pinion Engagement Shim Thickness Calculation Procedure:


1. Use a feeler gauge, 4, to measure the clearance between the gauge block, 5, and the sleeve, 3 (Dimension A).
2. Note the pinion correction marking, 1, etched on the end of the pinion.
3. If the pinion marking is positive (+), subtract this value from Dimension A.

   If the pinion marking is negative (-), add this value to Dimension A.



130

4. Install required shims, 1, (from step 3) and bearing cup, 2.




131


EXAMPLE :		**1**		**2**	**3**
DIMENSION A:		0.75 mm (0.030″)		0.75 mm (0.030″)	0.75 mm (0.030″)
PINION CORRECTION MARKING:	+	0.10 mm (0.004″)	–	0.05 mm (0.002″)	NONE NONE
SHIM THICKNESS REQUIRED:		0.65 mm (0.026″)		0.80 mm (0.032″)	0.75 mm (0.030″)

NOTE: *Pinion marking is in imperial (inch) dimensions.*

Using a sleeve, 1, press the pinion bearing onto the pinion shaft.



132



133


Assembling Pinion Components

1. Pinion
2. Housing
3. Spacer
4. Bearing
5. Nut
6. Washer
7. Drive flange
8. Oil slinger
9. Bearing preload shims

Install bearing preload shims, 9, of the same thickness as removed during disassembly and re-assemble the pinion as shown in Figure 133.


NOTE: *Do not install the oil seal and the dust shield until after the pinion bearing preload turning torque has been adjusted and pinion engagement checked as shown in Figures 136 and 137.*

Push drive flange, 1, onto the shaft with tool, 2, #FNH00408.



134

Hold the drive flange with the drive flange tool, 1, and torque the shaft nut to 325 - 410 N·m (240 - 300 ft lbs).




135

Using a torque meter adjust the bearing preload torque to 2.5 - 4.5 N·m (20 - 40 ft lbs).

To increase torque, reduce pinion bearing shim pack thickness.

To decrease torque, increase pinion bearing shim pack thickness.


Record the measured preload for use during diffrential installation.



136

To verify the pinion engagement, the dimension measured using the feeler gauge must be 0.508 mm (0.020 in.) plus or minus correction dimension marked on end of pinion. Using Example 1 on page 25-63, the dimension in Figure 137 should be 0.508 mm - 0.10 mm = 0.408 mm (0.016 in.).


1 Sleeve #FNH00406
2 Pinion
3 Gauge block #FNH00407



137


Remove the drive flange as described earlier in this section.

Install the dust shield.




138

Place the pinion seal, 2, onto the special tool #FNH00410, 1.



139


Install the pinion seal.



140


Install the drive flange as described earlier in this section.

Install the differential bearings, 2, using adaptor, 1, #FT 3161.



141


Torque the crown wheel retaining bolts to 165 N·m -190 N·m (120 ft lbs - 140 ft lbs).



142


NOTE: *Replace differential lock clutch pack if plates are worn more than .10 mm (.004 in.) from new.*

Install the differential lock clutch packs.




143

Assemble the spider, 1; spider shaft, 4; and gears. Lower the assembly into the casing, 3, so the spider gears engage the side gear, 2.




144

Reassemble the differential housings. Align the casing marks, 1, that were applied before disassembly.



145

Torque the differential bolts to 130 N·m - 150 N·m (95 ft lbs - 110 ft lbs).




146

Op. 25 102

CROWN WHEEL TO PINION BACKLASH ADJUSTMENT

Locate the differential assembly and install the bearing cups and adjusting rings. Tighten the bearing cap bolts finger tight.




147

Using tool #FNH00409, 1, turn the adjuster rings, 2, equally to obtain crown wheel to pinion backlash of 0.225 mm (0.009″).


While maintaining backlash, tighten each adjuster ring to a torque of 115 N·m -129 N·m (85 ft lbs - 95 ft lbs).

Using a dial indicator gauge, measure the backlash and turn each adjuster ring by **equal** amounts until the backlash is 0.125 mm - 0.225 mm (0.005″ - 0.009″).



148

Measure the combined differential and pinion bearing turning torque. Torque should be 0.5 N·m - 1.1 N·m (5 in. lbs. - 10 in. lbs.) greater than pinion bearing torque measured with the oil seal installed.




149

Tighten the bearing cap bolts to a torque of 240 N·m - 270 N·m (180 ft lbs - 200 ft lbs).

Install the bearing adjuster locking plates, 1, at a torque of 47 N·m - 54 N·m (35 ft lbs - 40 ft lbs).


When assembling the differential, it is essential to adjust for correct pinion to ring gear tooth contact as described in the “Adjustments” portion of this chapter.



150


Installation
Center Housing

1 Differential locking plates




151

Support the differential with a transmission jack and apply anaerobic sealer to the mounting faces around the locating dowels and the eight holes threaded through the axle casting. The differential is now ready to be installed.




152

Use locating bolts, 1, to aid in differential installation.



153

Torque the differential retaining bolts, 1, to 190 N·m - 217 N·m (140 ft lbs - 160 ft lbs).



154


SECTION 25 – FRONT MECHANICAL DRIVE

Chapter 2 – Dana Supersteer™ Linkage

CONTENTS

Section	Description	Page
25 100	Description of Operation	2
25 100	Supersteer Linkage Removal	3
25 100	Removal of Rear Support Assembly and Spherical Ball Bushing	5
41 106	Supersteer Linkage Adjustment	9

DESCRIPTION OF OPERATION




1

1. Support assembly
2. Roller
3. Bushing
4. Roller pin
5. Cap screw, HS, 3/4″-10x3″
6. Washer
7. Front pivot pin
8. Cap screw, HH, CL8.8, M16x30
9. Washer
10. Grease fitting, 1/8″
11. Tie bar
12. Cap screw, HH, CL10.9, M20x80
13. Tie rod end
14. Bushing link assembly
15. Bushing
16. Seal
17. Pin weld assembly
18. Retaining plate
19. Pin
20. Link
21. Cap screw, HH, GR5, 1″-8x13-1/2″
22. Washer
23. Axle support
24. Cap screw, HH, GR5, 1″-8x2-1/2″
25. Rear support assembly
26. Shroud
27. Grease fitting, 1/8″
28. Internal snap ring
29. Spherical ball bushing
30. Spacer
31. External snap ring
32. Dust cap
33. O ring
34. Tie down plate
35. Cap screw, HH, CL10.9, M20x50
36. Lock washer
37. Heat treated washer

Op. 25 100

SUPERSTEER LINKAGE REMOVAL


1. Support tractor and front axle with safety stands.
2. Remove the front wheels.



2

3. Remove the cap screw, 1, which retains the front pivot pin.


   The cap screw is torqued to 240 N·m - 270 N·m (177 ft lbs - 200 ft lbs).
4. Remove the front pivot pin and inspect for wear.



3


5. Move the axle assembly forward just enough so the drag link assembly can be held with a nylon strap and the upper two retaining bolts, 1, taken out of the retaining plate.

   The retaining bolts, 1, are torqued to 960 N·m - 1017 N·m (708 ft lbs - 750 ft lbs).




4

6. To remove the bushing assembly, pull away from the mounting pins on the axle assembly.




5

7. To remove the links, 1, remove retaining bolt, 2, and pin weld assemblies, 3.



6

8. Replace worn or damaged bushing, pins, and links. Reassemble in the reverse order of disassembly.
   - Lubricate all components.
   - Torque the pin retaining cap screw, 4, to 240 N·m - 270 N·m (177 ft lbs - 200 ft lbs).




7

Op. 25 100


REMOVAL OF REAR SUPPORT ASSEMBLY AND SPHERICAL BALL BUSHING

1. Support the axle assembly.
2. Loosen front cap screws, 2; side plate cap screws, 3; and tie bar cap screws, 1, (if required).




8

3. Repeat steps for bracket cap screws on both sides of the rear support assembly.




9

4. Loosen the steering hose clamp bolts, 1.



10


5. Rear support assembly ready for removal.



11


6. To remove the rear spherical ball bushing, the engine front crank pulley must be removed first to gain access to the cover plate.

   Refer to “Engine” - Section 10, Chapter 1 for details regarding the front crankshaft pulley removal.




12

7. Remove the O ring, 1, then remove the cover plate, 2.
8. Snap ring, 3, holds the rear support assembly into the bushing.




13

9. The snap ring must be removed using snap ring pliers, 1. Hold the rear support assembly from the underside because it can easily slide down through the bushing.




14

10. Snap ring, 1; spacer, 2; and spherical ball bushing, 3.




15

11. Inspect the rear support assembly for damage in the pin area, 1.




16

12. The spherical ball bushing assembly, 1, must be pressed out of the front frame. You can also see the grease fitting, 2, that lubricates this bushing.
13. The bushing is retained by a snap ring on the underside of the front support. The bushing comes out the bottom of the front support.




17

14. Machined within the front support casting is an upper shoulder, 1, and a snap ring retaining groove, 2.
15. The standard ID of the bore is 120.595 mm - 120.635 mm (4.747″ - 4.749″).



18

16. Reassemble the rear spherical ball bushing in the reverse order of disassembly. Lubricate the bushing with grease.
17. Torque all hardware to the standard torques.
18. Tie bar cap screws, 1, must be torqued to 671 N·m (495 ft lbs).




19

Op. 41 106

SUPERSTEER LINKAGE ADJUSTMENT


Tire Track and Toe-In Adjustment

1. When reassembling the tractor, the front axle must be centered under the tractor first to ensure the front and rear wheels track correctly. This can be done by measuring the center link position, 1, and looking at the tractor to make sure the front and rear wheels are tracking straight. Adjust either the left or right tie rod to get the tracking correct.




20

2. After the tracking is set, adjust both tie rods equally either in or out to achieve the proper toe-in specification of 0.0 - 6.4 mm (0.00″ - 0.250″).



21

3. The nominal starting point on the tie rod adjustment is 578 mm (22.750″) between the center of the grease fittings, 1 and 2. The tie rods should be within ± 1 mm equal length.
4. Torque the castle nuts at the end of the tie rods to 271 N·m (200 ft lbs).
5. Torque the small nuts to 325 N·m - 360 N·m (240 ft lbs - 265 ft lbs).
6. Adjust the steering cylinder lengths to allow each stop rod to bottom against the axle stop.
7. Torque cylinder end clamps to 325 N·m - 360 N·m (240 ft lbs - 265 ft lbs).



22

SECTION 25 - FRONT MECHANICAL DRIVE

Chapter 3 - Four Wheel Drive Carraro Axle

CONTENTS

Section	Description	Page
	Specifications	2
	Special Tools	3
	General Information	7
	Front Axle Differential Line	8
	Overall Dimensions	11
	General Checks Prior to Disassembly	16
	Disassembly Operations	17
25 100	Front Axle Removal/Installation	17
41 216	Steering Cylinders Group Disassembly	17
41 216	Steering Cylinders Group Assembly	23
25 310	Final Drive Removal	25
25 108	Wheel Hub Disassembly	27
25 108	Wheel Hub Assembly	29
25 108	Swivel Housing Removal	32
25 100	Swivel Housing Assembly	33
25 100	Axle Housing Swivel Bearing	34
25 102	Differential Support Group Disassembly	36
25 102	Differential Support Group Assembly	38
25 102	Input Flange End Play Adjustment	39
25 102	Limited Slip Differential Removal	40
25 102	Limited Slip Pinion Disassembly	41
25 104	Limited Slip Differential Disassembly	43
25 104	Limited Slip Differential Assembly	45
25 102	Lockable Differential Removal	48
25 102	Lockable Pinion Disassembly	50
25 104	Lockable Differential Disassembly	52
25 104	Lockable Differential Assembly	54
25 102	Adjustment - Pinion Shaft	57
25 104	Differential - Adjustments	61
25 102	Pinion to Ring Gear Tooth Contact Adjustment	64
	Wrong Tooth Contact Pattern	64
25 108	Swivel Housing Bearing Adjustment	66
41 106	Standard Steer/Toe-In Adjustment	67
41 106	Supersteer Linkage Adjustment	68
25 108	Potentiometer Removal	70
25 108	Potentiometer Installation	70
25 108	Potentiometer Calibration	72
	Mode 12: Tractor Features Configuration	72
	Mode 13: Steering Angle Sensor Operation/Calibration	73
	New Parameter Code	74
	New Fault Codes	77
	Testing After Assembly	78
	Troubleshooting	79

SPECIFICATIONS

Carraro Axle Code
- Super Steer/Lockable Differential CA140247
- Super Steer/Limited Slip Differential CA140242
- Standard Steer/Lockable Differential CA140491
- Standard Steer/Limited Slip Differential CA140490

Carraro Axle Model
- Super Steer/Lockable Differential . . . . . 20.80 SS
- Super Steer/Limited Slip Differential . . . . . 20.80 SS
- Standard Steer/Lockable Differential . . . . . 20.80 ACP
- Standard Steer/Limited Slip Differential . . . . . 20.80 ACP

Bevel gear reduction 3.083/1

Epicyclic reduction 7.000/1

Total reduction 21.583/1

Dry Weight
- Super Steer/Lockable Differential . . . . . 755 Kg (1,664 lbs)
- Super Steer/Limited Slip Differential . . . . . 750 Kg (1,653 lbs)
- Standard Steer/Lockable Differential . . . . . 778 Kg (1,715 lbs)
- Standard Steer/Limited Slip Differential . . . . . 770 Kg (1,697 lbs)

Input Rotation . . . . . Counterclockwise (CCW)

Steering angle . . . . . Max 55° 0/-2°

Toe-in . . . . . A 0/-2

Oil Specification ESN-M2C 134-D

Differential oil capacity
- Super Steer/Lockable Differential . . . . . 14.5 Liter (15.5 qts)
- Super Steer/Limited Slip Differential . . . . . 14.5 Liter (15.5 qts)
- Standard Steer/Lockable Differential . . . . . 14.0 Liter (15 qts)
- Standard Steer/Limited Slip Differential . . . . . 14.0 Liter (15 qts)

Gear box epicyclic oil capacity . . . . . 5 + 5 Liter (5.25 + 5.25 qts)

Grease . . . . . Lithium base EF high temperature

Bevel gear set backlash . . . . . 0.21 - 0.29 mm (0.008 - 0.011 in.)

Input flange end play
- Standard Steer/Lockable Differential . . . . . 0.00 - 0.10 mm (0.00 - 0.004 in.)
- Standard Steer/Limited Slip Differential . . . . . 0.00 - 0.10 mm (0.00 - 0.004 in.)

Swivel housing backlash
- Standard Steer/Lockable Differential . . . . . 0.00 - 0.10 mm (0.00 - 0.004 in.)
- Standard Steer/Limited Slip Differential . . . . . 0.00 - 0.10 mm (0.00 - 0.004 in.)


Pinion bearings “P” rotation pull
(measured D = 39.7 mm [1.59 in.] without seal) . . . . . P = 8 - 12 daN (8 - 27 lbs)

Total pinion-ring gear bearing pull “T”
(measured D = 39.7 mm [1.59 in.] without seal)
- Super Steer/Lockable Differential . . . . . T = (P + 9.5) - (P + 11.5) daN
- Super Steer/Limited Slip Differential . . . . . T = (P + 2.6) - (P + 3.9) daN
- Standard Steer/Lockable Differential . . . . . T = (P + 9.5) - (P + 11.5) daN
- Standard Steer/Limited Slip Differential . . . . . T = (P + 2.6) - (P + 3.9) daN

SPECIAL TOOLS


The following tools mentioned can be found in Carraro Axle Kit #380050004.

Bushing Driver
380000200




1

False Differential Box
380000202




2

False Pinion
380000203




3

False Differential Bearing Set
380000204




4

Pinion Shaft Lock Wrench
380000205




5

Pinion Nut Wrench
380000201




6

Wheel Hub Oil Seal Driver
380000206




7

Bearing Driver
380000207




8

Bearing Driver
380000208




9

Interchangable Handle/Screws
380000209



10



11

GENERAL INFORMATION

Product Identification
The axle identification plate is located on the rear of the right arm of the Carraro forward axle.

Axle Versions
There are four different versions of the Carraro axle. This manual provides information for all versions. The differences are identified and separate procedures are shown for each version as required by axle differences.

The four versions of the Carraro axle are listed below:

- Standard steer limited slip differential
- Standard steer lockable differential
- Super steer limited slip differential
- Super steer lockable differential

General Description (all axles)
The axle consists of a beam casing (axle housing), housing the differential in the middle and a wheel hub unit at each end.

The differential, type “Limited Slip” or “100% lockable hydraulically controlled,” is supported by two bearings mounted on a suitable structure allowing the bevel gear set to be adjusted.

The ring bevel gear is adjusted by means of two ring nuts located opposite each other.


The position of the bevel pinion, supported by two bearings, is adjusted by inserting adjusting shims.

The wheel hubs containing the epicyclic reduction gears are supported by two tapered roller bearings and are powered by a hydraulically operated steering unit.


FRONT AXLE DIFFERENTIAL LINE

NOTE: *70A Series tractors only.*

To operate the front axle differential lock, a new hydraulic line, 1, has been added from the test port on the rear differential, along the left-hand side of the tractor, to the front differential. You will use this one test port, 2, to check pressure for both the front and rear differentials.




12



13


Lockable Differential Front Axle



14

Limited Slip Differential Front Axle

Sealing Compounds and Adhesives




A1= LOCTITE® 510	●
B2= LOCTITE® 270	●
C2= LOCTITE® 496	●

◁ - - - - - -	*Apply on the contact surfaces*
◀——	*Apply on bolt screws / on pins*

15

OVERALL DIMENSIONS (MILLIMETER)

Super Steer/Lockable Differential and Limited Slip Differential




A = 2330
B = 1890
C = Ø 370.8
D = Ø 425

16

Filling and Checks


Position	Specific Description
1	Differential oil filling and level plug
2	Oil breather
3	Fill/Drain and level plug of epicyclic reduction gear oil
4	Differential oil drain plug
5	Greasing points

Super Steer Axle



17

Standard Steer Axle



18

Periodical Lubrication Program

▲ First Time	Seasonaly or Every 1500 Operating Hours (1)	Operation
150-200 hours	◆	Axle oil change
▲	◆	Lubrication works
50-100 hours	monthly	Check and adjust oil level
150-200 hours	every oil change	Clean magnetic oil plugs
▲	monthly	Clean oil breather
150-200 hours	weekly	Greasing


(1)Which ever of both conditions comes first

Tightening Torques

Description	Pos. No.	Thread	N·m	ft lbs
Planetary gear carrier retaining screw	1	M10 x 25	50	37
Planetary gear retaining screw	2	M10 x 25	70	52
Wheel carrier retaining screw	3	M14 x 65	220	162
Magnetic plug	4	M30 x 2	80	59
Wheel hub stud bolt	5	M22	70	52
Grease fitting	6	M10 x 1	10	7
Flange retaining screw	7	M12 x 25	139	103
Differential box/Crown wheel retaining screw	8	M14 x 40	190	140
Ring nut stop retaining screw	9	M6 x 10	13	10
Oil fill plug	10	M24 x 1.5	60	44
King pin retaining screw	11	M16 x 38	300	221
Grease fitting	12	M10 x 1	10	7
Stop steering bolt nut and bolt	13	M27	250	185
Pin cylinder retaining screw	14	M10 x 25	50	37
Breather	15	M10 x 1	10	7
Differential support retaining screw	16	M14 x 40	266	196
Oil drain plug	17	M22 x 1.5	60	44
Half-collar retaining screw	18	M16 x 95	413	305
Potentiometer cover retaining screw	19*	M8 x 35	23	17
Potentiometer retaining screw	20*	M4 x 20	3	2
Lock potentiometer pin washer retaining screw	21*	M4 x 10	4	3
Steering arm ball joint retaining nut	22**	M27 x 1.5	275	203
Steering arm retaining nut	23**	M35 x 1.5	450	332
Differential box cover	24*	M10 x 25	70	52

*Lockable differential

**Supersteer only




19

GENERAL CHECKS PRIOR TO DISASSEMBLY

Super Steer/Standard Steer
The disassembly/assembly instructions presume that the unit has been removed from the vehicle and positioned on a suitable workbench.

Some of the following pictures may not show exactly your axle, but the procedure is the same.




20

Center Housing
Before draining the oil, loosen the breather to release possible internal pressure, then tighten the plug with a torque wrench to the prescribed torque (ref. Tightening torques).

Drain the oil from the appropriate plug, then tighten the plug with a torque wrench to the prescribed torque (ref. Tightening torques).

Epicyclic Hubs
Before draining the oil, position the wheel hub so that the filer cap is in the highest point, then loosen the plug to release possible internal pressure.

After draining the oil, tighten the plug with a torque wrench to the prescribed torque (ref. Tightening torques).



21

DISASSEMBLY OPERATIONS

Op. 25 100

FRONT AXLE REMOVAL/INSTALLATION


⚠ WARNING ⚠

When overhauling the axle, always ensure that the tractor and axle is fully supported on axle stands and that the rear wheels are blocked to prevent movement of the tractor.


It is not necessary to remove the complete axle assembly to service the outboard planetary reduction units. On standard steer axles, the center differential assembly can also be repaired without removal of the complete axle from the tractor. Some illustrations may show the axle removed for clarity.

The SuperSteer axle does not have to be removed to service the front drag link bushings or the rear pivot bushing. Some illustrations may have other components removed for clarity.

1. Block the rear wheels to prevent tractor movement.
2. Remove the front-end weights using a suitable hoist.
3. Jack up the front end of the tractor, and install engine side rail support stands and safety stand under the transmission.
4. Remove the front wheels, drive shaft, and shield, disconnect the hydraulic steering hose connections, and disconnect the TerraLock electrical harness if equipped.




22



23


5. Support the front axle using the transmission splitting stand as shown.



24


NOTE: *If the axle is being removed for overhaul of the differential, the hubs, swivel housings and axle shafts can, if required, be removed while the axle is installed on the tractor.*

6. Remove the three bolts which hold the SuperSteer tie rod bolster plate, 1, or remove the tie rod end from the swivel housings and fasten the tie rods out of the way with suitable wire, rope, or lifting strap.




25

7. On standard FWD, loosen the front and rear mounting bracket retaining bolts, 1.




26

8. On a SuperSteer axle, loosen the bolts, 1, which attach the side plates to the rear pivot bracket.



27


9. Loosen the four front bolts which hold the side plates to the axle assembly.



28


10. Remove bolt,1, which retains the front pin, and remove the front pivot pin.

NOTE: *The axle may be removed in Step 11 by either completely removing the bolts in Step 8 or Step 9.*



29

11. Remove the front axle assembly by lowering the support stand, so the front drag link, 1, will clear the front bolster.
12. Roll the axle assembly forward until it is clear of the tractor.




30

Standard Steer Axle (Disassembly)
Remove the covers, 1, from the pivot pin housings in the axle housing.

Take the oil seals, 2, out of the axle housing with a lever.

In order to replace the bushes inside the axle housing, the bushing, 3, needs to be cut and destroyed with a chisel.


Take the bushings out of the pin housings cutting.



31

Standard Steer Axle (Assembly)
Assemble the pivot pin bushes, 1, on the axle housing with a bushing driver.

Install new seals, 2, and protecting rings, 3, with a driver and a hammer.



32

Installation
Where new bearings have been installed, it is essential that the swivel housing turning torque and hub bearing preload adjustments are also performed as shown in “Adjustments.”

For installation, reverse steps one through twelve.

Refill the center housing and reduction hubs with NH 134D oil. Limited slip oil additive must be installed in the center housing. Refer to the operator’s manual for more information.

Replace the front wheels and carry out the front axle toe-in; check and, if required, adjust to obtain correct toe-in of 0 - 6 mm (0 - 0.25″).


Op. 41 216

STEERING CYLINDERS GROUP DISASSEMBLY

Some of the following pictures may not show exactly your axle, but the process is the same. Any differences between the Supersteer and Standard steer axles and Lockable and Limited slip differentials will be noted.

Remove the fastening screw, 1, and rod pin, 2, from the swivel housing.

Collect the spacers, 3, and oil seals, 4.




33

Using a pin punch, drive out the retaining Spirol pin from the rod pin, 1.

Extract the rod pin, 1, from the steering cylinder and from the differential support, collecting the relative spacers and oil seals.

Remove the snap ring, 2, in order to extract the spherical joint, 3, from its housing on the differential support.

Do the same operation for the other cylinder.




34

NOTE: *Note the position and orientation of the spacers. Some spacers are beveled and some are flat.*

Remove the snap ring, 1, and the scraper ring, 2.

Remove the cylinder head from the cylinder case, extracting the piston rod. Extract and collect all the seals and O rings, both from the cylinder head and from the piston.


If needed, disassemble the piston, 3, from the rod, 4, then remove and collect the cylinder head, 5, from the rod.



35

Standard Steer Axle Only
Remove the split pin, 1, of the guide rod locknut.

Loosen the guide rod locknut, 2, until it is flush with the threaded pin.




36

Strike the nut with a hammer in order to loosen the guide rod from the swivel housing.

Repeat the same operation on the other end of the guide rod.

Remove and check the condition of the guide rod.




37

Op. 41 216

STEERING CYLINDERS GROUP ASSEMBLY

Standard Steer Only
Assemble all parts of the swivel housings joint rod, then screw (or unscrew) the guide rods so that the ball joints can be inserted in the swivel housings.

NOTE: *Unscrew the locking nut to carry out this operation.*




38

Insert the ball joints into its housing on the swivel housings.

Install and tighten the lock nut with a torque wrench to 275 N·m (203 ft lbs).

Install the split pin of the guide rod locknut.


NOTE: *Tighten screw in the lock nut, 1, of the tie rod only when the toe-in adjustment has been carried out.*



39

Assemble new seal rings: onto the cylinder head, 1, on piston, 2, and on cylinder body, 3.

Assemble all cylinder parts, fit new scraper ring, 4, insert the head into the cylinder barrel and lock the head with the locking ring, 5.



40

Insert the spherical joint, 1, in its housings on the differential support and insert the lock ring, 2.

⚠ WARNING ⚠

Failure to use the proper procedure to assemble the steering cylinders on to the Carraro axle could result in seal deformation.


Use two bushings part #105969 to help the installation. Cut the bushing so it can be spread slightly to fit snug in the axle cylinder mount, 4. Slip the washers, 5, and seals, 6, over the bushing. (use grease to 'glue' the bottom washer and seal on.)

Chamfer the cylinder clevis slightly.

Slide the cylinder clevis into position.

Install the retaining Spirol pin outer rod pin, 3, leaving approximately 7 mm (0.28 in.) protruding out of the pin. The pin will push out the bushings through the mount as the pin is pushed into place.

NOTE: *Any light weight tubular insert of the correct dimension will do. Cut and spread the insert slightly to make it snug when inserted. The insert dimensions are: 15.8 mm (5/8″) long x 30.1 mm (1-3/16″) O.D. x 2.3 mm (3/32″) thick.*




41

Insert the head rod into its housing on the swivel housing and position the spacers and oil seals; and then install the cylinder retaining rod pin, 1.

Lock the rod pin, 1, in the swivel housing with the fastening screw, 2, tighten to 50 N·m (37 ft lbs).

Repeat for the other cylinder.




42

Op. 25 310

FINAL DRIVE REMOVAL

Before draining the oil, position the hub with the plug on the upper part and loosen it in order to eliminate any possible inner pressure, then remove it completely. Rotate the hub until the hole is in the lowest point.

Drain the oil completely.




43

Unscrew and remove the two fastening screws, 1, of the planetary carrier with a internal hex wrench.

Remove the planetary carrier from the wheel hub.

NOTE: *Secure planetary carrier with suitable lifting device to support the carrier hub weight as it is removed.*


Position the planetary carrier on a table and check its wear conditions.



44


To carry out any possible replacements of the planetary gears:

- Remove the fastening screws, 1, that lock the washers on every planetary gear.
- Remove the washers and remove the planetary gears off the pins.
- Collect the roller bearings; checking their conditions.



45

Final Drive Assembly
Collect all the components of the planetary gears.




46

Position the planetary carrier, 1, on a workbench.

Insert the planetary gears, 2, and the lower and upper roller bearings in the planetary carrier pins.

NOTE: *Bearing caps are an integral part of the planet gear.*

Assembly the washers and the retaining screw, then tighten the screws with torque wrench to 70 N·m (52 ft lbs).




47

Install a new O ring on the wheel hub.

Assemble the planetary carrier on the wheel hub.

Screw in the fastening screws and tighten with a torque wrench to 50 N·m (37 ft lbs).



48


Op. 25 108

WHEEL HUB DISASSEMBLY

Before disassembling the splined sleeve, it is advisable to secure it with a belt or a rope on a hoist or other supporting device, in order to avoid its accidental fall.


Remove the snap ring, 1, from the U-joint shaft, 2, using suitable pliers.

Remove and collect the axle shaft washer.




49

Unscrew and remove the fastening screws, 1, from the rear gear assembly.



50

To remove the rear gear assembly, 1, from its housing, screw at least two of the just removed screws in the threaded extraction holes.




51

Extract and remove the ring gear assembly.

Remove the steel lock ring, 1, and separate the ring gear carrier, 2, from the ring gear, 3. Check the wear conditions of the components.


If necessary, remove the centering bushes of the hub lock ring gear with a hammer and pipe matching the OD of the bushings.



52

Remove the wheel hub, using levers and a hammer to facilitate the operation.

NOTE: *Collect the bearing cone.*




53

Position the wheel hub on a flat surface and remove the oil seal, 1.

Remove the bearing caps, 2, out, on both sides of the hub, using a hammer and a suitable drift.

Remove the bearing cone from the swivel housing end, using a suitable extractor.

Remove the O ring, 3, from the wheel hub.




54

Op. 25 108

WHEEL HUB ASSEMBLY

Position the wheel hub on a workbench and install both cups of the taper roller bearings in position with the special tools 380000207 and 380000208.


Insert the oil seal into the wheel hub with the special tool 380000206.



55

Assemble the cone, 1, of the taper roller bearing on the swivel housing end.


Assemble the wheel hub on the swivel housing and fit the other cone, 2, of the taper roller bearing in position.



56


Position the ring gear, 1, on a workbench and force all but two of the bushings, 2, to the carrier surface level.

At least two bushings, 3, (diametrically-opposed) should be set slightly higher than the carrier surface level to be used later as dowel pins.




57

Preassemble the ring gear, 3, and ring gear carrier, 2, with the special locking ring, 1.



58


Assemble the ring gear assembly, 1, on the wheel hub using the two projecting bushings as dowel pins and two cap screws.



59

Force all the hub dowel bushings completely into the hub with a driver and a hammer.


Assemble the remaining cap screws and tighten to 220 N·m (162 ft lbs).



60


NOTE: *Bearing preload/endplay has been predetermined by the manufacturing tolerances of the components in this assembly. When fitting new components, check the dimensions of the new components only according the the chart below.*

A = 29. 995 - 30.000
B = 91. 175 - 91.225
C_1 = 29.000 - 29.150
C_2 = 32.000 - 32.150



61

Insert the washer into the U-Joint shaft and lock it with the retaining ring, inserting it at the end of the splined hub and pushing it into its housing with a pipe of suitable dimensions.



62

Op. 25 108

SWIVEL HOUSING REMOVAL

All Axles


NOTE: *On axles with lockable differential, see potentiometer removal in this section.*

Unscrew and remove the fastening screws from the upper and lower king pin.

Before removing the king pins, secure the swivel housing with a belt or a rope to a hoist or any other supporting device.


Remove the king pins.

NOTE: *Collect the shims from the upper side of the swivel housing under the king pins.*



63


Remove the swivel housing from the axle housing and from the short shaft of the U-joint.



64

Position the swivel housing on a flat surface and take the oil seal out with a lever.

Turn the swivel housing and take the bush out, using a drift and a hammer.




65

Op. 25 100

Swivel Housing Assembly
Install bushing into the swivel housing with standard driver and a hammer or press.


Assemble the oil seal on the swivel housing with a stud and a hammer.

Fill 3/4 of the oil seal cavity with grease.



66

Position the lower king pin on a workbench and assemble the cone of the spherical joint with a standard bushing driver.



67


Secure the swivel housing group with a rope and assemble it on the axle housing.

DANGER

This is dangerous for the operator.

Lubricate the oil seal lip. Protect the splined end of the axle shaft by winding it with some thin adhesive tape to avoid damaging the oil seal. After assembly, remove completely the adhesive tape.

Assemble the lower king pin and tighten the retaining screws with a torque wrench to 300 N·m (221 ft lbs).




68

Assemble the upper king pin, and tighten the retaining screws to 300 N·m (221 ft lbs).

NOTE: *Make sure that the shims remain in their position.*

See “Swivel Housing Bearing Adjustment” for correct swivel bearing end play.




69

Op. 25 100

AXLE HOUSING SWIVEL BEARING

Disassembly
Remove the U-joint from the axle housing.




70

Take the oil seal, 1, out of the axle housing with a lever.

Remove the covers, 2, and the seal rings, 3, from the axle housing.

Lockable Differential


NOTE: *If needed, unscrew the fastening screws and remove the splined washer, 4, of the potentiometer’s control pin.*



71

Remove upper bushing from the axle housing with a suitable extractor.

Remove spherical bushing, 1, from lower king pin, 2, and axle housing with suitable extractor.



72

Op. 25 100


AXLE HOUSING SWIVEL BEARING

Assembly

Lockable differential

Assemble the splined washer, 1, into its seat in the left hand upper swivel bearing housing in the axle housing, after having cleaned accurately the contact surface.

Apply Loctite® 270 on the threads of the fastening screws, then tighten them to 4 N·m (3 ft lbs).



73

Assemble the upper king pin bush, 1, on the axle housing using a standard bushing driver.


Insert a new seal, 2, in the same housing using a bushing driver.

Insert the cup, 3, of the spherical bushing on the lower part of the axle housing with a standard bushing driver.

NOTE: *To make the assembly easier, it is necessary to cool the cup of the spherical bushing to a temperature lower than 0°C (32°F).*

WARNING


Avoid frostbite, wear safety gloves.



74

Install the bushing on the axle housing using the special tool 380000200.

Assemble the seal into the beam with a standard bushing/seal driver and hammer.




75

Fill the cavity behind the seal with a common bearing grease.

Lubricate the bush and the oil seal lip.

Insert the U-Joint inside the axle housing.




76

Op. 25 102

DIFFERENTIAL SUPPORT GROUP DISASSEMBLY

Remove the fastening screw, 1, and the washers from the pinion end.

Take the flange, 2, out, then collect the O ring, 3, and the washer, 4.




77

Loosen and remove the screws on the differential support.

Remove the differential carrier.

⚠ WARNING ⚠


Support the differential carrier with a rope or other appropriate means.



78


Clamp the differential carrier in a vise.

Remove the sealing ring, 1, from the differential carrier with a lever or a suitable extractor.



79

Loosen and remove the screws, 1, to take out the two ring nut retainers, 2.




80

Op. 25 102

DIFFERENTIAL SUPPORT GROUP ASSEMBLY


Once you have completed adjustment operations, fit the adjuster ring nut retainers and their respective screws, tightening them to 13 N·m (10 ft lbs).

NOTE: *Turn the ring nut slightly in order to align it to the retainer.*




81

Tighten the bolts of both bearing caps to 413 N·m (305 ft lbs).



82

Fit a new oil seal inside the differential support, using a standard hollow seal driver with an OD equal in size to the oil seal.




83

Before matching two surfaces, make sure they are perfectly clean.

Degrease and clean them with appropriate cleaners.

Spread a film of Loctite® 510 on the contact surface between the axle housing and the differential carrier.

Position the differential carrier on the axle housing, and tighten the retaining screws to 266 N·m (196 ft lbs).




84

Op. 25 102

INPUT FLANGE END PLAY ADJUSTMENT

Assemble the yoke, 1, with washer, 2, onto the pinion end. Do not assemble the O ring.



85


Check that the yoke, 1, is inserted completely and measure the indicated dimension Q; this is measured from the pinion end to the machined surface at the bottom of the hole in the yoke.

Input flange end play:

0. 00 - 0. 10 mm (0.00 - 0.004 in.)

SHIM RANGE			
Thickness	0.05	0.10	0.20
Quantity	-		-

Choose the shims to be inserted to the pinion shaft end, so that dimension Q is within the requested range. This will provide proper “squash” to the O ring when fitted.




86

Remove the flange, 1, leaving the washer, 2, in its housing.

Assemble a new well lubricated O ring, 3, on the pinion end, than assemble the flange.

Fit the flange fastening screw, 5, with the relative washer, 4, and the chosen shims, 6, on the pinion end.

Tighten the screw, 5, with a torque wrench to 139 N·m (103 ft lbs).




87

Op. 25 102

LIMITED SLIP DIFFERENTIAL REMOVAL


Before removing the bearing cap bolts, mark both bearing caps and the differential carrier with permanent reference marks to avoid inverting them during re-assembly. Mark the area between the ring nuts and the differential carrier as well.



88


Unscrew the adjuster ring nuts. Count the number of revolutions required to remove each adjuster. Note these figures to aid in reassembly.

NOTE: *the two ring nuts are different, so take note of their position with regard to the bevel crown gear.*



89


Remove the four screws, 1, and remove both bearing caps, 2.



90

Take out the differential case, 1. Take care not to lose the cup bearings, 2, that are removed together with the differential case.

Do not mismatch the cup bearings if they are not to be replaced.




91

Op. 25 102

LIMITED SLIP PINION DISASSEMBLY


Fit the differential carrier in a vise.

Unscrew the lock nut using special tools 380000201 and 380000205.



92

Remove the ring nut and collect its retaining washer.




93

Tap the shaft with a soft hammer to remove the bevel pinion.

WARNING


Take care not to drop the pinion.

Collect the washer, the collapsible spacer and the inner cone of the tapered roller bearing.



94


Place the differential carrier on a flat surface as shown in the figure and remove the outer cups of the taper roller bearing using a drift and a hammer.



95


To remove the inner cone of the tapered roller bearing of the pinion, use a standard extractor.

Collect the bearing cone and the underlying shim.



96

Check all Pinion Components for Wear
The ring nut and the collapsible spacer must be replaced when reassembling the unit.



97


Op. 25 104

LIMITED SLIP DIFFERENTIAL DISASSEMBLY

Clamp the differential in a vise.


Unscrew all the fastening screws of the crown bevel gear.

This will make both differential half boxes free, so take care not to drop the internal components.




98

Mark the two half boxes before separating them, in order to reassemble them in the same position.




99

Disassemble the two half boxes and collect all the free components (planetary gear, discs and counterdiscs).



100

Using a punch, push out the three locking pins, 1, in order to take out the short and the long pins, 2.




101

Disassemble and collect all the components (sun gear, 1, thrust washers, 2, spider, 3, planetary gear, 4, plates, 5, and drive plates, 6).


Check the operating and wear conditions of all the components.

- Steel drive plates minimum thickness 1.5 mm (.060″)
- Friction discs minimum thickness 1.15 mm (.045″)



102

Take the bearings out of the differential half boxes, using two levers of a three-hold extractor.




103

Op. 25 104


LIMITED SLIP DIFFERENTIAL ASSEMBLY

Assemble the cones of the new taper roller bearings on both differential box covers, using a pipe and a hammer.



104

Position a half box on a workbench and assemble all its inner components (plates, 1, and drive plates, 2, sun gears, 3, thrust washers, 4, spider, 5), as shown.




105

Insert the short pins and the long pin in their housings, while holding the planetary gears and the spider.


Lock the just assembled pins with the locking pins, 1, in the holes on the box. Rotate the pins by hand, in order to align the locking pins holes to those on the box.

Completely insert the locking pins using a punch and a hammer.




106

Position all the inner components into the box (plates, drive plates, and sun gear), as shown in figure.




107

Join the two half boxes, aligning the reference marks made before disassembly.



108

Position the bevel crown gear, apply Loctite® 270 on the threads and assemble the bevel crown to the differential box assembly, tightening the screws to 190 N·m (140 ft lbs).




109

Position the complete differential box, with the outer cups of the taper roller bearings already assembled, on the differential carrier.

⚠ WARNING ⚠

Take care not to invert the outer cups of the taper roller bearings and check the right side of the bevel crown assembly.




110

TO CONTINUE LIMITED SLIP DIFFERENTIAL CARRIER ASSEMBLY, REFER TO DIFFERENTIAL ADJUSTMENTS.

Op. 25 102

LOCKABLE DIFFERENTIAL REMOVAL


Before removing the bolts, mark both bearing caps, 1, and the differential carrier, 2, with permanent reference marks to avoid inverting them during re-assembly. Mark the area between the ring nuts and the differential carrier as well.



111


Unscrew the adjuster ring nuts, 1. Count the number of revolutions required to remove each adjuster. Note these figures to aid in reassembly.

NOTE: *The two ring nuts are different, so take note of their position with regard to the bevel crown gear.*



112


Remove the four screws, 1, and remove both bearing caps, 2.



113


Take out the differential case, 1. Take care not to loose the cup bearings, 2, that are removed together with the differential case.

Do not mismatch the cup bearings if they are not to be replaced.




114

Collect the oil seals, 1, (ring gear side), the washer, 2, the spacer, 3, and the bearing set, 4, which are removed together with the differential case.



115

Collect the washer, 1, and the O ring, 2, from their seat on the ring gear side.




116

Op. 25 102

LOCKABLE PINION DISASSEMBLY


Fit the differential carrier in a vise.

Unscrew the lock nut using special tools 380000201 and 380000205.



117

Remove the ring nut and collect its retaining washer.




118

Tap the shaft with a soft hammer to remove the bevel pinion.

WARNING


Take care not to drop the pinion.

Collect the washer, the collapsible spacer and the inner cone of the tapered roller bearing.



119


Place the differential carrier on a flat surface as shown in the figure and remove the outer cups of the taper roller bearing using a drift and a hammer.



120

To remove the inner cone of the tapered roller bearing of the pinion, use a standard extractor.


Collect the bearing cone and the underlying shim.



121

Check all Pinion Components for Wear

The ring nut (not shown) and the collapsible spacer, 1, must be replaced when reassembling the unit.



122

Op. 25 104


LOCKABLE DIFFERENTIAL DISASSEMBLY

Clamp the differential in a vise.

Unscrew all the fastening screws of the crown bevel gear.


This will make both differential half boxes free, so take care not to drop the internal components.

NOTE: *The bevel gear cannot be completely removed from the differential until the cover is removed from the differential box described later.*



123


Mark the two half boxes before separating them, in order to reassemble them in the same position.



124

Disassemble the two half boxes and collect all the free components (side gear, 1, spacer, 2, plates, 3, drive plates, 4, and piston, 5).

Remove the O ring, 6, from the piston.




125

Remove the fastening screws of the differential half box's cover.

Disassemble the cover and collect all the free components in the half box (side gear, 1, spacer, 2, plates, 3, and drive plates, 4). Check the operating and wear conditions of all the components.

NOTE: *The ring gear, with bolts removed earlier, can now be removed from the differential housing assembly.*


- Steel drive plates minimum thickness 1.5 mm (.060″)
- Friction discs minimum thickness 1.15 mm (.045″)



126


Using a punch, push the four transmission pins, 2, out from their seats in the differential half box.

Remove the three locking pins, 1, in order to take out the short and the long pins.




127

Disassemble and collect all the free components in the half box (thrust washers, 1, planetary gears, 2, and the spider, 3). Check the operating and wear conditions of all the components.



128

Take the bearings out of the differential half boxes, using two levers of a three-hold extractor.




129

Op. 25 104


LOCKABLE DIFFERENTIAL ASSEMBLY

Assemble the cones of the new taper roller bearings on both differential box covers, using a pipe and a hammer.



130


Partially insert the short pins, 1, and the long pin, 2, in their housings. Assemble the planetary gears, 3, and the spider, 4, inside the housing and slide the short pins and long pin into position.



131

Lock the short pins (not shown) and long pin (not shown) with locking pins, 1, in the holes on the box. Rotate the pins by hand, in order to align the locking pins holes to those on the box.


Completely insert the locking pins, 1, using a punch and a hammer.



132


Position a half box on a workbench and assemble all its inner components (long pins, 1, sun gear, 2, plates, 3, and drive plates, 4), as shown.

Assemble the cover with the fastening screws, 5, tightening them to 70 N·m (52 ft lbs).




133

From the opposite side of the differential box, position all the inner components in the box (sun gear, 1, plates, 2, drive plates, 3, spacer, 4, and the piston, 5, with pre-assembled new O rings), as shown in figure.




134

Join the two half boxes, aligning the reference marks made before disassembly.




135

Position the bevel crown gear, 1, apply Loctite® 270 on the threads and assemble the bevel crown to the differential box assembly, tightening the screws to 190 N·m (140 ft lbs).



136

Assemble on both differential box bearings the outer cups of the taper roller bearings and on the bevel gear side: the washer and the spacer with new seal rings already assembled.




137

Before positioning the differential box on the differential carrier, insert a new O ring, 1, and the washer, 2, in bearing seat, at the bevel crown side, on the hydraulic oil hole.

Position the complete differential box on the differential carrier.

⚠ WARNING ⚠

Take care not to invert the outer cups of the taper roller bearings and check the right side of the bevel crown assembly.



138

TO CONTINUE LOCKABLE DIFFERENTIAL CARRIER ASSEMBLY, REFER TO DIFFERENTIAL ADJUSTMENTS.


Op. 25 102

ADJUSTMENT - PINION SHAFT

Some of the following pictures may not show exactly your axle, but the procedure is the same.


Place the differential support on a workbench.

Fit the outer cups of the new bearings using the proper drivers and a hammer.



139

In order to measure the distance, use the kit consisting of the special tools called “false pinion”, 380000203, 1, and “false differential box”, 380000204, 2, and 380000202, 3.




140

Insert the false pinion 380000203, 1, together with its bearings and its ring nut, in the just mounted bearing housings.


Tighten until the end play is just eliminated. Do not overtighten.

Install special tools 380000204, 2, and 380000202, 3, into the differential group supports and screw in the bearing cap bolts.




141

Use a depth gauge, 1, to measure distance (X) (distance between the axis of the differential bearings and the point at which the pinion head is supported, or base of the bearing).




142



143

In order to determine the necessary thickness (S) of shims required between the pinion and the bearing, subtract the value (V), stamped on the pinion head (V = requested conical distance), from the measured value (X), recorded in previous step.


$$S = X - V$$



144

Select the toal shim thickness (S) from the range of available shims, and fit to shaft under the pinion head.

NOTE: *Take care to assemble correctly.*




145

SHIM RANGE										
Thick	2.5	2.6	2.7	2.8	2.9	3.0	3.1	3.2	3.3	3.4
Q	-	-	-	-	-	-	-	-	-	-

Once you have chosen and inserted the suitable shim, 1, with the chamfer against the gear, force the bearing, 2, into the pinion shaft end with a press, making sure that it is well set.

Insert the washer, 3, and a new collapsible spacer, 4.

NOTE: *Always use a new collapsible spacer.*




146

Insert the bevel pinion shaft assembly, 1, into the differential support housing and the second bearing cone, 2, into the pinion end, from the opposite side.

In order to force the second bearing into position, use a pipe with an ID slightly larger than the OD of the pinion end and a hammer.

NOTE: *During assembly of second bearing, support the pinion with blocking or a large hammer.*



147


Insert a new ring nut washer and the locking ring nut.

Screw the ring nut in, using the wrench for ring nut, 380000201, 1, and for pinion retainer, 380000205, 2.

⚠ WARNING ⚠

The torque setting is given by the preloading measurement on bearings. Tighten the ring nut gradually.

NOTE: *If the tightening is excessive, the colapsible spacer must be replaced and the procedure repeated. When you check the preloading, it is advisable to use a soft hammer to hit the pinnion to help set the bearings.*



148

Carry out the preloading measurement (P) of the pinion taper roller bearings, using a spring scale, 1, whose cord is wound on the pinion splined end, 2.


P = 8 - 27 lbs

The adjustment is carried out by increasing the ring nut torque gradually, being careful not to exceed maximum range.

NOTE: *If using a torque wrench and the yoke retaining bolt as a means to measure the rolling torque. Proper rolling torque is 14 - 21 in. lbs*

⚠ WARNING ⚠

All preloading must be measured without oil seal.




149

Record preload value for later use.

A new oil seal must be installed after differential preload adjustment is performed.

If differential was not removed from carrier, a new oil seal should be installed at this time.

Once the required preloading value is achieved, stake the ring nut, using a hammer and a chisel.



150

Op. 25 104


DIFFERENTIAL - ADJUSTMENTS

Both Differential Types

Move the differential group to place the bevel crown gear on the pinion and position both bearing caps, 1, into their seats.

Make sure both bearing caps are aligned with reference marks, 2.

Tighten the bearing cap bolts finger tight.




151

Using the recorded number of turns for each ring nut from the disassembly procedure, assemble and tighten both adjustment ring nuts, 1, in the differential support until the end play is eliminated and the differential bearings are slightly preloaded.

⚠ WARNING ⚠

The two ring nuts are different, so take care not to invert their position with regard to the bevel crown gear.

Check that the differential bearings are well seated; if necessary, knock slightly with a soft hammer, in order to properly set the bearings in position.



152


Position a magnetic-base dial gauge on the differential carrier, so that the feeler stylus touches the surface of one tooth of the crown gear with a 90° angle.

Lock the pinion and move the crown gear alternatively back and forth; measure and note the pinion-ring gear backlash.

Repeat the operation on two or more points (teeth), rotating the crown gear, to obtain an average value.

Check if the measured backlash value is within the requested range:


0.21 - 0. 29 mm (0.008 - 0.012 in.)



153

If backlash is not within the specifid range:

Using the adjuster rings, move the differential assembly from one side to the other.



154


If backlash is below minimum tolerance:

Adjust the ring nuts, remembering that:

- unscrew the ring nut on the bevel crown gear side and screw in the opposite one by the same measure;

If backlash is greater than maximum tolerance:


- unscrew the ring nut on the side opposite to the bevel crown gear, and screw in the other one by the same measure.



155

Once the adjustment of the pinion-ring gear backlash has been carried out, also check that there is a minimum preloading on the differential box bearings.

Repeat the whole sequence of the above mentioned operations till the indicated conditions are reached.




156

Once the pinion-ring gear backlash has been established, measure the total preloading (T) of the bearings (pinion-crown bevel gear system), using a spring scale whose cord is wound on the pinion splined end. The measured value should be within the following range:

$T = P + 10.5 \pm 1$

where P is the effectively measured pinion preloading (see “Pinion Adjustment”).



157

WARNING

All preloading must be measured without oil seal. If the measurement is not within the required range, check the assembly of each component and rotate the adjusting ring nuts of the differential support:

- if the total preloading is less than the given range, screw in both ring nuts by the same amount, keeping the pinion ring gear backlash value unchanged;

- if the total preloading is greater than the given range, unscrew both ring nuts by the same measure, keeping the pinion-ring gear backlash value unchanged.

After differential preload adjustment is completed, a new oil seal should be installed over pinion shaft, 1.


Op. 25 102

PINION TO RING GEAR TOOTH CONTACT ADJUSTMENT

Put Prussian blue or red lead on the flanks of the ring gear teeth. Turn the ring gear over the pinion gear teeth in both directions to determine the correct contact pattern. See the contact patterns in the following illustrations.

Correct adjustment is made when the pattern of the tooth contact area (both horizontal and vertical) is as shown.

NOTE: *The contact patterns of the ring gear teeth that are shown are approximate shapes. The gear teeth contact patterns can change from the illustrations, but the same general shape must be seen. The tooth contact pattern can change in a used gear set because of wear of the parts. Try to get a contact pattern that is similar to the illustrations to get the best results. The pinion depth setting must be repeated if the contact pattern is not correct.*




158

WRONG TOOTH CONTACT PATTERN

Pattern A


The pinion gear is out too far. Remove some of the pinion shim pack that was installed. Adjust the backlash again and check the contact pattern.



159


Pattern B

Not enough backlash. Move the ring gear away from the pinion gear. Readjust the backlash and recheck the contact pattern.




160

Too much backlash. Move the ring gear toward the pinion gear. Readjust the backlash and recheck the contact pattern.




161

The pinion gear is in too far. Add some more shims to the pinion shim pack that was installed. Readjust the backlash and recheck the contact pattern.



162

1. Move the pinion gear, 1, toward the ring gear, 2, to correct pattern A.
2. Move the ring gear, 2, away from the pinion gear, 1, to correct pattern B.
3. Move the ring gear, 2, toward the pinion gear, 1, to correct pattern C.
4. Move the pinion gear, 1, away from the ring gear, 2, to correct pattern D.




163

Op. 25 108

SWIVEL HOUSING BEARING ADJUSTMENT

Assemble the upper king pin, 1, with shims removed during disassembly, 2, under the king pin head and fasten in position with cap screws.


NOTE: *Record shim thicknesses prior to installation for later use.*



164

Position a magnetic-base dial gauge on the axle housing so that the feeler touches the upper king pin head, and zero the gauge.

Position a lever between the swivel housing and the axle housing, lift the swivel housing till end of stroke and measure the end play (M) with the dial gauge. Repeat this operation, so to find an average value.



165

Calculate the total thickness of the shims to be inserted under the upper king pin as follows: add the master shim thickness value (S) to the measured thickness value (M). Then, subtract the prescribed end play value (G):

X = (S + M) – G

for example:
X = (1.00 + 0.50) – (0.00 – 0.10) = 1.4 mm
X = (total thickness to be used)
M = (measured backlash value) = [ex. 0.50 mm]
S = (shim used in the measurement) = [ex. 1 mm]
G = (prescribed end play value) = 0.00 – 0.10 mm




166

SHIM RANGE		
Thickness	0.1 mm	0.3 mm
Quantity	–	–

Choose from the available range the shims to be inserted under the upper king pin, in a way the end play value is within the requested range (X).

In our example, we will use for 0.3 mm shims and two 0.1 shims, to obtain a total thickness of 1.4 mm in the requested range (X):

Disassembly the upper king pin and replace the installed master shim with the just calculated shims.




167

Op. 41 106

STANDARD STEER/TOE-IN ADJUSTMENT

Standard Steer Only
Put two equal one-meter-long linear bars on the wheel sides and lock them with two nuts on the wheel hub stud bolt.

NOTE: *The two bars should be fixed on their middle so that they are perpendicular to the supporting surface. Align the two bars.*



168


Measure the distance in mm. between the bar ends with a measuring tape.

Falling within the tolerance range will give a toe in adjustment of 0.0° to 2.0°.

Check that the difference of the measurement between the wheel hub diameter ends is within the requested tolerance range.

A = 1873 - 1890 mm (74.9 - 75.6 in.)

B = 1890 - 1907 mm (75.6 - 76.3 in.)




169

Standard Steer Only

If the toe-in is not correct, loosen jam nuts, 1, and turn rod, 2, till the toe-in is within the requested tolerance.

After adjusting, tighten in the jam nuts, 1, of the rods, 2, to 450 N·m (332 ft lbs).




170

Op. 41 106


SUPERSTEER LINKAGE ADJUSTMENT

Tire Track and Toe-In Adjustment

1. When reassembling the tractor, the front axle must be centered under the tractor first to ensure the front and rear wheels track correctly. This can be done by measuring the center link position, 1, and looking at the tractor to make sure the front and rear wheels are tracking straight. Adjust either the left or right tie rod to get the tracking correct.
2. After the tracking is set, adjust both tie rods equally either in or out to achieve the proper toe-in specification of 0.0° to -2.0° as described in the previous section.
3. The nominal starting point on the tie rod adjustment is 578 mm (22.750″) between the centers, 1 and 2. The tie rods should be within ± 1 mm equal length.
4. Torque the castle nuts at the end of the tie rods to 275 N·m (200 ft lbs).
5. Torque the nuts of the steering tie rod to 450 N·m (332.1 ft lbs).



171




172

Steering Angle Adjustment
Adjust the steering mechanical retainer, 1, located on the rear of the swivel housing, in or out, locking them with a locknut to 250 N·m (184.5 ft lbs) torque.


Steer completely towards the other side and repeat the same operations.

The steering mechanical retainer screws should be positioned to the dimension (Z).

Z = 100 mm (4.0 in.)



173




174

Op. 25 108

POTENTIOMETER REMOVAL


Unscrew and remove both fastening screws, 1, of the cover, 2, in order to disassembly the potentiometer. If required, remove the connector cable, 3, unscrewing it from the cover, 2.



175

Unscrew and remove both fastening screws, 1, of the potentiometer, 2, and collect their respective washers. Extract the poteniometer, 2, from the control pin.

NOTE: *Handle all components of the potentiometer with care.*




176

Remove with suitable pliers the ring, 1, from its seat in the king pin. Collect the washer, 2.

NOTE: *Before removing the potentiometer's control pin, scribe alignment marks between the control pin and seat to allow for proper alignment during reassembly.*

Extract the potentiometer's control pin, 3, and the O ring, 4.

Check all components of the potentiometer for wear.



177

Op. 25 108

POTENTIOMETER INSTALLATION

Lockable Differential Only

NOTE: *Before the assembly of the potentiometer, it is necessary to verify the correct wheel alignment with the vehicle's driving direction.*


NOTE: *After steering angle or toe in adjustments are made, the potentiometer should be calibrated.*

Assemble a new O ring, 1, into its seat in the central hole of the king pin.

Insert the potentiometer's control pin, 2, on the king pin, respecting the alignment marks scribed during disassembly.

NOTE: *Check the angle shown in the diagram between the potentiometer mounting holes and the notch on the control pin with a protractor, the angle should be 45°.*


Place the washer, 3, on the control pin, 2, and lock it with the retaining ring, 4.



178

NOTE: *Handle all components of the potentiometer very carefully.*

Assemble the potentiometer, 1, and fasten it with cap screws, 2, tightening them to 3 N·m (2.2 ft lbs) torque.




179

Screw the potentiometer connector, 1, in the cover, 2.

Connect the harness to the potentiometer

Assemble the cover, 2, positioning the connector towards the central part of the axle.

Insert the screws, 3, tightening them to 23 N·m (17.0 ft lbs) torque.



180

Op. 25 108


POTENTIOMETER CALIBRATION (STEERING ANGLE SENSOR)

The 70A tractors feature new operation software referred to as Rev. 5 software. This software is also compatible with older tractors and adds new features in Modes 1 & 12, adds a new Mode 13, identifies a new parameter code, and identifies new fault codes. This software replaces Rev. 4 software that was used on previous models.

MODE 12: TRACTOR FEATURES CONFIGURATION

Mode 12 now has a 14th feature that allows the tractor to be configured for TerraLock.

- A 0 (zero) indicates the steering angle sensor is not present and TerraLock is turned off. Units equipped with a limited slip front axle will be configured as 0. When 0 is selected, the new Mode 13 is hidden. Mode 13 is used for steering angle sensor operation and calibration, and is explained under the next heading.
- A 1 (one) indicates the steering angle sensor is present and allows you to enter Mode 13. When 1 is selected, TerraLock will engage or disengage the front and rear differential lock and four wheel drive. This depends upon the position of the diff. lock and four wheel drive switches, the tractor speed, and wheel angle.




181

MODE 13: STEERING ANGLE SENSOR OPERATION/CALIBRATION


When Mode 12's feature 14 is set to 1, then Mode 13 is present and the system is looking for the steering angle sensor. To enter Mode 13, you must hold the SET UP/SELECT switch for 15 seconds.

The Mode 13 display will have a 4d at the top of the TPM and either the letters CEn, or an R or L with a number.



182

- The 4 indicates four wheel drive equipped.
- The "d" indicates diff lock equipped.
- "CEn" indicates the front wheels are centered.
- "R" indicates the wheels are turned to the Right and the number indicates the turning diameter in feet.
- "L" indicates the wheels are turned to the Left and the number indicates the turning diameter in feet.



183

NEW PARAMETER CODE (TERRALOCK OPTION/LOCKABLE DIFFERENTIAL)

With the addition of TerraLock, a new parameter code 414 has been added to Mode 3 for checking the steering angle sensor. You must check the steering angle sensor for its sweep through the entire steering angle, left to right or right to left.

There are two ways to check the steering angle sensor:


1. Using Mode 3.
2. Using information from Mode 13, TerraLock calibration.

Checking the Steering Angle Sensor Using Mode 3

In Mode 3, you can check the steering angle sensor with the sensor removed or with the sensor in the axle.

To check the steering angle sensor with the sensor removed (standard steer or SuperSteer), follow these steps:

1. Using the EIC extension cable #FNH00549, position the EIC where it is easily visible.
2. With key switch ON, enter Mode 3.
3. Select the parameter code display “P” and enter the numbers 414.
4. Rotate the sensor slowly back and forth as you watch the display.
5. The display will give readings somewhere between 0 and 99. If the readings are erratic, jump, or cannot be repeated, replace the sensor.



184

To check the steering angle sensor with the sensor in the axle (standard steer axle), follow these steps:

1. Raise the front of the tractor until both front wheels are off the ground. You can do this by raising the front axle and placing jack stands under the axle.
2. With key switch ON, enter Mode 3.
3. Select the “P” display and enter the numbers 414. Do not start the tractor.
4. Turn the tractor steering wheel from center to left or right, then back to center again. Then turn the wheel in the opposite direction.
5. As the steering wheel is rotated from one stop to the other, the display will give readings somewhere between 0 and 99.

NOTE: *The maximum steering angle in either direction is limited by the setting of the steering stops. Zero to 99 is the maximum display achievable by the sensor when out of the chassis. The full range will not be displayed because the steering angle is less than the range of the sensor.*

6. If the readings are erratic, jump, or cannot be repeated, replace the sensor.

To check the steering angle sensor with the sensor in the axle (SuperSteer axle), follow these steps:

1. Raise the front of the tractor until both front wheels are off the ground. You’ll need to support the tractor by the front frame. Use special engine frame bracket tool number FNH00530. Do not support the tractor by the axle. The SuperSteer axle moves when steering the tractor.

DANGER


Do not support the SuperSteer axle with jack stands under the axle. During steering, the SuperSteer axle moves. The axle may fall off the stands. Support the wheels off the ground by using front frame supports.

NOTE: *The remaining steps are the same as for the standard steer axle with the sensor in the axle.*

Checking the Steering Angle Sensor Using Mode 13, TerraLock Calibration

To check the steering angle sensor with the tractor running and standing still, follow these steps:


1. Start the tractor and make sure the front wheels are pointing straight ahead.
2. Enter Mode 13 on the dash.
3. Depress the SET UP/SELECT switch for 15 seconds until you see 4d and CEn, or an R or L with a two- or three-digit number, on the display. This is the calibration mode for TerraLock feature.



185

4. Rotate the wheel left or right slowly until the steering stop is reached. The display will show the letter R or L followed by numbers, as you turn the steering wheel. The numbers represent the turn around diameter of the tractor.
5. Watch the numbers in the display. They should rise or drop evenly as you rotate the wheel from left to right and back. If the numbers being displayed are irregular, have blank spots, or cannot be repeated, replace the steering sensor.

NOTE: *The numbers to the extreme right and left may be different due to the steering stops positions. The steering stops can be set evenly right and left using this feature.*



186

Calibrating the Steering Angle Sensor Using Mode 13

You can also calibrate the steering angle sensor in Mode 13. The preferred method for calibration is with the tractor moving because it is more accurate. To calibrate the tractor while sitting in a shop service bay, the following procedure can be used with wheels pointing straight ahead and not driving the tractor.

1. Start the tractor.
2. Enter Mode 13 on the dash.
3. Start driving the tractor in a straight line. Use the line of sight ornament on the front of the hood to follow a predetermined straight line on the ground.

NOTE: *If the tractor wheels are not pointing straight ahead and you continue to follow this calibration procedure, the system will record the wheel position as centered (CEn), and TerraLock will engage and disengage at different steering angles left to right.*

4. While driving in a straight line, depress the SET UP/SELECT switch for 3 seconds until you see CAL on the display. This is the calibration mode for TerraLock feature.
5. Release the button. When the display shows 4d and CEn, the system has recorded that the current position of the front wheels is centered, and calibration is complete.
6. Rotate the wheel left or right slowly until the steering stop is reached. The display will show the letter R or L followed by numbers as you turn the steering wheel. The numbers represent the turn around diameter of the tractor.
7. If the calibration is correct and the steering stops are equally adjusted, you should get equal numbers from left to right.

NOTE: *The numbers to the extreme right and left may be different due to the steering stops positions. The steering stops can be set evenly right and left using this feature.*

NEW FAULT CODES

Steering Angle Sensor TPM Display

70A Series tractors now have two new fault codes that report in the tractor electronic system to identify the steering angle sensor status. The new fault codes are:

- 371 – Steering angle sensor circuit open
- 370 – Steering angle sensor short to ground

See Section 55 for more information.

TESTING AFTER ASSEMBLY

Step 1
With engine off, lift the front axle so that the tires do not have contact with the ground.

Step 2
With the help of another person standing on the opposite side, begin the assembly testing by attempting to rotate both the wheels forward. The wheels should roll slightly, taking up all gear and driveline backlash and then stop. (The driveline is locked since the 4WD clutch is spring applied and hydraulically relaeased).

Step 3
Free the right wheel and rotate the left one.

The wheel will move freely without difficulty and the right wheel will move in the opposite direction if the assembly has been carried out correctly.

Repeat the same operation in the opposite direction.

IF ONE WHEEL DOES NOT ROTATE FREELY IN BOTH DIRECTIONS, then an assembly error is suspect.

TROUBLESHOOTING

PROBLEMS	POSSIBLE CAUSES									
	1	2	3	4	5	6	7	8	9	10
Wheel vibration; front tire resistance; driveline failure	●	●	●		●					
Steering is difficult; tractor goes straight while its turning	●	●	●	●						
No differential action; jamming while steering	●	●	●	●	●		●		●	
Uneven tire wear	●	●	●	●	●	●	●			
Noise	●			●	●			●	●	●
Vibration during forward drive, intermittent noise	●	●	●							

1. Incorrect Installation/Defective Axle
Correct installation or repair or replace the differential in case it does not pass any one of the tests listed at the end of the assembly procedures.

2. Overloading/Incorrect Weight Distribution
Remove excessive weight and redistribute load, following information on ballasting.

3. Different Tire Circumference
If one tire has a smaller radius, it will cause partial wheel slipping when force is applied. The other tire with bigger radius will have to support all the work. Replace the tire or adjust pressure to have same radius on both tire.

4. Failed axle shaft
It is not advisable to operate the tractor with a failed axle shaft. It is acceptable to move the tractor with the engine off.

5. Bent Axle Shaft
Replace axle shaft.

6. Locked Differential
Abnormal functioning of the differential or breakage/ blocked control valve. Verify assembly and all components. Tractors in sharp steer may Vehicles with wide steering angle may proceed with kicks, have steering difficulty or cause pneumatic wearing at sharp turns. Reduce the steering angle to minimum and decelerate when the vehicle begins to kick.=

7. Incorrect Wheel Adjustment
Verify proper assembly and wheel side bearings installation. Adjust accordingly.

8. Failed or Worn Axle Parts
Check the condition of ring gear, pinion gear, bearings etc. Replace as necessary.

9. Contamination in the Axle Box or Incorrect Assembly of Parts
Look for foreign particles. Check assembly of the various parts of the axle.

10. Incorrect Adjustment of Bevel Gear Set Failed/Worn Components
Replace or adjust as required.

TROUBLESHOOTING

This section is a descriptive and explanatory guide to common axle problems. This guide suggests the repair correct procedures to be followed.

PROBLEM	CAUSE	REMEDY
Ring gear tooth broken at the outer side	1. Excessive gear load 2. Incorrect gear adjustment (excessive play) 3. Pinion nut loosened	Replace bevel gear set Follow the recommended operations for the adjustment of bevel gear set free play
Ring gear tooth broken side	1. Load impact 2. Incorrect gear adjustment (insufficient play) 3. Pinion nut loosened	Replace bevel gear set Follow the recommended operations for the adjustment of bevel gear set free play.
Pinion or ring gear teeth or worn	1. Insufficient lubrication 2. Contaminated oil 3. Incorrect lubrication or depleted additives 4. Worn out pinion bearings that cause an incorrect pinion axle play and wrong contact between pinion and ring.	Replace bevel gear set. Follow the recommended operations for the adjustment of bevel gear set free play. Use correct lubricants, fill up to the right levels and replace according to the recommended program
Overheated ring and pinion teeth. See if gear teeth have faded.	1. Prolonged functioning at high temperatures 2. Incorrect lubrication 3. Low oil level 4. Contaminated oil	Replace bevel gear set. Use proper lubrication, fill up to right level and replace at recommended program
Pinion teeth pitting	1. Excessive use 2. Insufficient lubrication	Replace bevel gear set. Use correct lubrication, fill up to the right level and substitute at recommended intervals
Axle beam body bent	1. Vehicle over loaded 2. Vehicle's accident 3. Load impact	Replace axle housing body
Worn out or pitted bearings	1. Insufficient lubrication 2. Contaminated oil 3. Excessive use 4. Normal wear out 5. Pinion nut loosened	Replace bearings. Use correct lubrication fill up, to the right level and replace at recommended intervals

PROBLEM	CAUSE	REMEDY
Oil leakage from gaskets and seals	1. Prolonged functioning at high temperature of the oil 2. Oil gasket assembled incorrectly 3. Seal lip damaged 4. Contaminated oil	Replace the gasket or seal and matching surface if damaged. Use correct lubrication and replace at recommended intervals.
Input yoke spline wear.	1. Normal wear with high hour use 2. Pinion nut loosened 3. Pinion axle play	Replace the flange. Check that the pinion spline is not excessively worn out. Replace bevel gear set if required.
Fatigue failure of pinion teeth See if the fracture line is well defined (wave lines, beach lines)	1. Normal high hour wear 2. Continuous overload	Replace bevel gear set
Pinion and ring teeth breakage	1. Impact load of differential components	Check and/or replace other differential components.
Side gear spline worn out.	Normal high hour wear	Replace differential gear group. Replace axle shaft if required
Thrust washer surface worn out or scratched.	1. Insufficient lubrication 2. Incorrect lubrication 3. Contaminated oil	Use correct lubrication and fill up to right level. Replace at intervals recommended. Replace all scratched washers and those with 0.1 mm thickness lower than the new ones.
Inner diameter of tapered roller bearing worn out.	1. Normal high hour wear 2. Excessive pinion axle play 3. Insufficient lubrication 4. Contaminated oil	Replace bearing. Check pinion axial play. Use proper lubrication, fill up to right level and replace at recommended intervals.
Bent or broken axle shaft	Overload or high frequency speed/ direction charges	Replace
Axle shaft broken at wheel side	1. Wheel support loosened 2. Beam body bent	Replace Check that wheel support is not worn out or wrongly adjusted.

AXLE PROBLEM AND DIAGNOSIS

PROBLEM	CAUSE	RECOMMENDED REPAIR
Noise while driving	1. Excessive play between pinion and ring gear	1. Adjust
	2. Worn out pinion and gear ring	2. Replace
	3. Worn out pinion bearings	3. Replace
	4. Pinion bearings loosened	4. Adjust
	5. Excessive axial pinion play	5. Adjust
	6. Worn out differential bearings	6. Replace
	7. Differential bearings loosened	7. Adjust
	8. Ring gear out of roundness	8. Replace
	9. Low lubricant level	9. Oil level
	10. Poor or wrong lubricant	10. Replace
	11. Bent halfshaft	11. Replace
Noise while driving with 4WD off	1. Noise coming from the axle is usually heard when vehicle moves in neutral gear but is not loud.	Replace or adjust (see above)
	2. Incorrect play between pinion and ring (sound heard while decelerating disappears while increasing the speed)	Replace
	3. Pinion or input flange worn out	Adjust
Intermittent noise	1. Ring gear damaged	Replace bevel gear set
	2. Differential box bolts loosened	Tighten to torque
Constant noise	1. Ring gear teeth or pinion damaged	1. Replace bevel gear set
	2. Worn out bearings	2. Replace
	3.Pinion spline worn out	3. Replace
	4. Bent halfshaft	4. Replace
Noise while steering	1. Worn out differential gears	1. Replace
	2. Worn out differential box or spider	2. Replace
	3. Differential thrust washers worn out	3. Replace
	4. Half shaft spline worn out	4. Replace

SECTION 27 – REAR DRIVE AXLE

Chapter 1 – Rear Axle Assembly

CONTENTS

Section	Description	Page
27 000	Specifications	2
	Special Tools	3
	Description of Operation	10
	Differential Carrier	12
	Final Reduction Drive	13
	Differential Lock Mechanical Operation	14
	70 Series Differential Lock Control System Operation	15
	70A Series Differential Lock Control System Operation	16
	Differential Lock Electrical Circuit Operation	17
	Differential Lock Hydraulic Circuit Operation	19
	Front Axle Differential Line	19
	Troubleshooting	21
	Adjustments	30
	Disassembly and Repair	51
27 100	Axle Assembly	51
27 120	Axle Housing	64
27 120	Planetary Overhaul	85
	Axle Seal	91
	Top Cover	93
27 106	Differential Assembly	95
27 106	Pinion Assembly	112
27 110	Differential Lock Solenoid	125
	Pressure Testing	127
	Circuit Pressure Test	129

SPECIFICATIONS

AXLE ASSEMBLY:	8670 8670A	87/88/8970 87/88/8970A
Type	Double reduction inboard planetary	
Planet ring gear teeth	67	69
Number of planet gears	4	3
Planet gear teeth	24	27
Sun gear teeth	17	15
Final drive ratio	4.941	5.600
Differential final drive reduction	27.794:1	27.491:1
Output axle type	Bar	Bar
Axle diameter	92 mm (3.625″)	105 mm (4.125″)
Axle length	243.8 cm (96″), 284.5 cm (112″), or 304.8 cm (120″)	

DIFFERENTIAL:

Pinion teeth	8	11
Pinion preload	1.1-2.2 N·m rolling torque (10-20 in. lbs.)	
Ring gear backlash	Etched on ring gear ± 0.05 mm (0.002″)	
Ring gear teeth	45	54
Reduction ratio	5.625	4.909
Support bearing preload	0.025-0.152 N·m (0.001-0.006 in. lbs.)	
Number of spider gears	4	4
Spider gear teeth	13	13
Side gear teeth	43	43
Side and spider gear support	Needle bearings	

DIFFERENTIAL LOCK:

Type	Electrohydraulic	
Method of engagement	Switch activated, hydraulically applied	
Number of friction plates	3	3
Number of separator plates	3	3
Solenoid type	Normally closed	Normally closed
Solenoid coil	12 volts	12 volts
Solenoid coil resistance	9.4 ohms	9.4 ohms
Hydraulic apply pressure (at 1900 ERPM)	16.5 bar -18.9 bar (240 PSI - 275 PSI)	

SEALERS:

Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595, or 596 LOCTITE ULTRA BLUE 587
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)

TIGHTENING TORQUES

	N·m	Ft Lbs
Axle shaft retaining bolt	600	440
Axle housing retaining bolts	270	200
Differential case bolts	244	180
Differential bearing housing support bolts	108	80
Outer pinion jam nut	122	90
Ring gear bolts	338	250
Cab mount bolts	217	160
Cab mount bracket to rear axle		
Model 8670/8670A	306	226
Models 8770/8770A, 8870/8870A, 8970/8970A	239	177
Top cover bolts	380	280
Drawbar support bolts	635	470
Drawbar support anchor bolts	635	470
Drain plug	68	50
Pinion shaft jam nut	128	95
Park brake bolts	60	45
FWD cover plate belts	81	60
Hydraulic pump drive housing bolts	108	80
Differential lock solenoid	27	20
Differential lock coil nut	6.5	5

LUBRICANTS	**8670 8670A**	**87/88/8970 87/88/8970A**
Oil type	M2C134D spec. hydraulic/transmission fluid F200A all season	
Transmission and Rear Axle Oil Capacity:		
Liters	117	140
U.S. Gallons	30.9	36.9

NOTE: *More oil will be required if the total system is drained and cleaned.*


SPECIAL TOOLS

Description	Part Number	Usage
Axle seal installation tool	FNH00540	Install axle seals on all models
Pinion nut spanner wrench	FNH00547	Remove and install pinion adjusting and locknuts

DEALER CONSTRUCTED SPECIAL TOOLS


Refer to the appropriate figure for tool dimensions and construction information.

70S001
Cab tilting tool
All Models




1

70S002
Rear axle shaft housing lifting tool
All Models




2

70S003
Rear axle differential lifting tool
All Models




3

70S005
Pinion rotating tool
All Models




4

70S006
Needle bearing retainer - Differential spider gears
All Models




5

70S007
Planetary gear assembly lifting tool
Model 8670/8670A




6

70S008
Planetary gear assembly lifting tool
Models 8770/8770A, 8870/8870A, 8970/8970A




7

70S009
Rear axle shaft housing rolling torque tool
Models 8770/8770A, 8870/8870A, 8970/8970A




8

70S010
Rear axle shaft housing rolling torque tool
Model 8670/8670A




9

70S011
Needle bearing retainer - Planetary gear
Models 8770/8770A, 8870/8870A, 8970/8970A




10

70S012
Needle bearing retainer - Planetary gear
Model 8670/8670A




11

70S013
Pinion shaft removal plate
All Models




12

70S015
Axle removing tool
Models 8770/8770A, 8870/8870A, 8970/8970A




13

70S018
Axle removing tool
Model 8670/8670A




14

70S019
Stationary planetary ring gear removing tool
Model 8670/8670A



15

70S020
Axle housing support stand
All Models



16

DESCRIPTION OF OPERATION

INTRODUCTION

Two style rear axle assemblies are used on 70 Series tractors.


The Model 8670/8670A tractor uses one style of rear axle assembly, while Models 8770/8770A, 8870/8870A, and 8970/8970A use a second version capable of handling higher horsepower.

The chart below identifies some of the differences between the two axle assemblies.

The rear axle assembly is attached to the rear of the transmission. The rear axle assembly connects the power from the engine and transmission to the rear wheels.

- Drive pinion and differential ring gear
- Differential carrier
- Hydraulic differential lock assembly
- Final reduction gears
- Axle shaft and housing
- PTO components
- Park brake
- Front wheel drive clutch assembly, if equipped

AREA	8670 8670A	87/88/8970 87/88/8970A
Axle Diameter	92 mm (3.625″)	105 mm (4.125″)
PTO Speeds	540/1000	1000
Brake Friction Discs (Each Side)	1 (8670 BSN D411606) 2 (8670 ASN D411605/8670A)	2




17

1. Drive pinion
2. Park brake
3. Differential ring gear
4. Differential lock assembly
5. PTO components (Models 8770/8770A, 8870/8870A, 8970/8970A shown)
6. Planetary gears
7. Wheel brake components
8. Left-hand axle housing
9. Left-hand axle shaft
10. Sun gear
11. Planetary ring gear
12. Differential carrier

PINION AND RING GEAR

The drive from the transmission output shaft is transmitted through a drive coupling to the pinion gear, 1. The pinion is located in the rear axle center housing by two preloaded, tapered roller bearings.

The pinion gear transfers power to the ring gear, 3, which is bolted to the differential carrier assembly, 12.




18

DIFFERENTIAL CARRIER

The ring gear, 2, and differential carrier assembly, 1, are supported between tapered roller bearings, 3 and 10. The bearings are mounted in supports, 4 and 11, which bolt in from each side of the center housing.

The differential carrier assembly consists of three differential pinion shafts, 8; four pinion gears, 12; two side gears, 9; the differential lock cover plate, 5; differential lock piston, 6; and plates, 7.

Drive from the pinion gear is transmitted through the ring gear, 2, and differential carrier assembly, 1, to the differential pinion shafts, 8. The shafts pass through and are pinned to the differential carrier. Each differential pinion shaft has one or two pinion gears, 12. All four pinion gears are in constant mesh with two side gears, 9, that deliver power to intermediate shafts.



19


FINAL REDUCTION DRIVE

The inner end of the intermediate shaft is splined to the differential side gears. The outer end forms the sun gear, 4, for the planetary reduction gear sets in the axle housing. The planetary assembly increases torque to the rear wheels.

Around the sun gear, 4, are planet gears, 2. Model 8670/8670A tractors use four planet gears while Models 8770/8770A, 8870/8870A, and 8970/8970A tractors use three planet gears. The planet gears are mounted in a carrier, 5, which is splined to the inner end of the rear axle shaft, 3.

The planet gears mesh with a fixed position ring gear, 1. As the sun gear end of the intermediate shaft revolves, the planet gears are forced to rotate around the inside of the fixed position ring gear. This causes the planet gear carrier to rotate at a reduced speed which transmits increased torque to the axle shaft.

The inner end of the axle shaft is splined to the planet gear carrier. The outer end of the axle shaft is supported by a bearing. Power is transmitted through the shaft to the wheels.



70-240-1274

20

DIFFERENTIAL LOCK MECHANICAL OPERATION

When the tractor is operating without the differential lock engaged, when one wheel starts to slip, all the drive is transmitted to the slipping wheel and traction is lost.


To regain traction, the tractor is equipped with an electrohydraulically operated differential lock.

When engaged, the differential lock forces the right-hand side gear, 2, to lock against the differential carrier assembly, 1, which provides direct drive to both wheels.

The differential lock assembly is composed of three plates, 4, internally splined to the right-hand side gear, 2, and three plates with external lugs, 5, that engage the differential carrier.

A piston, 3, housed within the differential carrier is used to compress the plates.

70 SERIES DIFFERENTIAL LOCK CONTROL SYSTEM OPERATION



21

Normal Operation

An electrohydraulically activated, self-holding differential lock is installed on all models. In conditions inducing wheel slip, momentarily press the front (orange) part of the switch, 2, to lock the rear wheels together. When the differential lock is engaged, the switch is internally illuminated.

NOTE: *Diff-lock will automatically disengage if one brake is applied. Both modes of diff-lock will automatically disengage if the tractor is operated above 16 km/h (10 MPH).*

Automatic Operation

NOTE: *Lamp, 1, on the instrument cluster will only illuminate when automatic differential lock is engaged.*

Press the front of the switch, 2, two times within one second for automatic diff-lock. When in this mode, the diff-lock will automatically disengage and reengage when one brake is applied then released, or when the three-point hitch Raise/Work switch is activated to raise, then lower, the hitch. This function allows the diff-lock to disengage on end rows when turning and reengage when the implement is lowered.

Depress the rear of the switch, 2, to disengage diff-lock.

70A SERIES DIFFERENTIAL LOCK CONTROL SYSTEM OPERATION

INTRODUCTION

A self-holding differential lock is installed in the rear axle to lock the rear wheels together in conditions where wheel slip is encountered.

Units equipped with TerraLock™ traction management four wheel drive, also come with a fully locking electro-hydraulically engaged front axle differential lock.

ENGAGING AND DISENGAGING DIFFERENTIAL LOCK

To engage the differential lock, the FAST RAISE/WORK switch must be in the lower position, then depress and release the front part of the switch,1. The switch will return to the center position, but the differential lock will be activated.

The switch indicator light will illuminate to indicate the differential lock is engaged.

NOTE: *Diff-lock will disengage if one brake is applied or when the 3-point hitch FAST RAISE/WORK switch is in the fast raise position or if the unit is operated above 16 kph (10 MPH). Terralock will disengage at 10 kph (6 MPH) or below at turn angles of 20 degrees or higher or between 10-15 kph (6-9 MPH) at turn angles of 10 degrees or higher. In manual operation mode as described above the differential lock or Terralock will not reengage automatically and must be reengaged manually.*


To turn off the differential lock, depress then release the rear part of the switch or apply either of the foot brakes.

ENGAGING AND DISENGAGING THE DIFFERENTIAL LOCK IN EITHER THE AUTOMATIC MODE OR TERRALOCK MODE

To engage the differential lock in either the Automatic mode or Terralock mode press and release the front of the lock switch twice within one second.

The amber differential lock lamp in the instrument panel will illuminate to indicate the differential lock is on in either Automatic mode or Terralock mode.

Auto differential lock will disengage when one brake is applied or when the 3-point hitch FAST RAISE/WORK switch is in the fast raise position.



22

Auto differential lock will reengage when the brake is released or when the FAST RAISE/WORK switch is returned to the work position.

If equipped with Terralock, the front and rear differential locks will disengage and reengage the same as in AUTO mode as well as with turn angles. Terralock will disengage at 10 kph (6 MPH) or below at turn angles of 20 degrees or higher and reengage at angles less than 20 degrees, or between 10-15 kph (6-9 MPH) at turn angles of 10 degrees or higher and reengage at angles less than 10 degrees.

The indicator light on the instrument panel will go out when auto differential lock or Terralock has disengaged.


To turn off auto differential lock or Terralock, depress the rear part of the switch.

NOTE: *Auto differential lock or Terralock will automatically disengage if the unit is operated above 16 kph (10 MPH).*

⚠ WARNING ⚠

Never use the differential lock at speeds above 8 kph (5 mph) or when turning the tractor. When engaged, the differential lock will prevent the tractor from turning.

IMPORTANT: *If a rear wheel spins at high speed, reduce engine speed before engaging the differential lock to avoid shock loads to the driveline.*



23

DIFFERENTIAL LOCK ELECTRICAL CIRCUIT OPERATION

An electrical circuit, consisting of fuses, a control switch, control modules, Fast Raise/Work switch, brake switches, and a solenoid, controls oil flow to the differential lock piston that engages the differential lock.

Current to operate the circuit originates at the 5-amp right-hand console fuse (MDP-21) and travels to the differential lock switch.

Depressing the front or rear of the switch momentarily sends current to the right-hand Control Module (RHC) on the appropriate wire.

The terminal on which the RHC module receives current from the switch indicates to the module if the differential lock should be engaged or disengaged.

The RHC module then signals the Chassis Control Module (CCM) to activate or deactivate the differential lock solenoid.

When the solenoid is powered with battery voltage, the differential lock is engaged. The differential lock is not engaged when the solenoid is not powered.

Applying one brake switch will disengage the differential lock. This is accomplished by supplying current from the 5-amp front console fuse (MDP-22) through the normally closed contacts on the stop light switches to the appropriate terminals at the Electronic Instrument Cluster (EIC) module.

When a brake switch is depressed, current flow to the EIC is interrupted. This current loss indicates to the EIC to signal the CCM to stop current flow to the differential lock solenoid.

The differential lock also disengages when the fast raise circuit is activated or the tractor exceeds 16 km/h (10 MPH). In both cases, the CCM receives a signal to stop current flow to the differential lock solenoid.


When the tractor is in Automatic or Terralock mode, FWD will automatically disengage when either brake pedal is used to assist in turning or at transport speeds above 24.2 km/h (15 MPH) which reduces tire wear. The FWD will automatically reengage when transport speed drops below 24.2 KPH (15 MPH) and when the applied foot brake is released.

TerraLock will also disengage and reengage under the following conditions:

At speeds of 0-10 kph (0-6 MPH) disengage at turn angles of 30 degrees or higher and reengage at angles less than 30 degrees.

Or between 10–20 kph (6–13 MPH) disengage at turn angles of 25 degrees or higher and reengage at angles less than 25 degrees.

The differential lock solenoid, 1, is located on the PTO housing at the rear of the tractor. The solenoid has a resistance of 9.4 ohms.



When the tractor has a steering sensor and the differential lock switch is turned on, the steering angle pot may send a signal to the CCM depending on the angle of the front wheels. The CCM then will activate or deactivate the differential lock solenoid on the PTO housing at the rear of the tractor.


DIFFERENTIAL LOCK HYDRAULIC CIRCUIT OPERATION

NOTE: *70 Series art is shown.*

Oil to operate the differential lock is regulated at 16.5 bar -18.9 bar (240 PSI - 275 PSI) by the low pressure regulating in the transmission valve body.

Oil enters the PTO housing at 2, and is directed to the differential lock solenoid, 1.


The differential lock is engaged when the differential lock solenoid receives battery voltage.




25

FRONT AXLE DIFFERENTIAL LINE (70A SERIES)

To operate the front axle diff. lock, a new hydraulic line, 1, has been added from the test port on the rear differential, along the left-hand side of tractor, to the front differential. You will use this one test port, 2, to check pressure for both the front and rear differentials.



26



27

When powered, the solenoid opens to allow pressurized oil to flow through a steel line to fitting, 2, and through passage, 3, to the differential lock piston, 1.

Oil pressure acts against the piston causing it to compress the clutch plates, 4 and 5, which locks the differential.

When the solenoid is not powered, it blocks oil flow to the piston releasing the clutch discs.

TROUBLESHOOTING
DIFFERENTIAL LOCK WILL NOT ENGAGE

Perform the following preliminary steps before proceeding to the troubleshooting charts:

1. Check the following systems for proper operation:
   - PTO
   - Transmission
   - 3-point fast raise
   - FWD (if equipped)
   - TerraLock™ (If equipped)

NOTE: *If all these systems do not operate, check for a common current supply problem. Refer to the wiring schematics in Section 55, Chapter 6.*

2. Verify the differential lock system is not operating properly. Proceed if the system is not working properly.

NOTE: *The 3-point Fast Raise/Work switch must be in the work position and both brake pedals must be fully released for the differential lock system to operate properly.*

Make sure that the fast raise/work system operates properly before proceeding.

NOTE: *If equipped with TerraLock, the steering must be centered and properly calibrated for the differential lock system to work properly.*


Make sure the TerraLock system is working properly before proceeding.

3. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.


NOTE: *Proceed to step four if current fault codes exist. Proceed to step five if no current fault codes exist.*

4. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
5. Perform an inspection of the diff-lock system and correct loose or damaged electrical wires, connectors, or hydraulic components.
6. Proceed to the following electrical troubleshooting chart:


DIFFERENTIAL-LOCK WILL NOT ENGAGE ELECTRICAL CIRCUIT TROUBLESHOOTING




DIFFERENTIAL-LOCK WILL NOT ENGAGE (CONTINUED FROM PREVIOUS PAGE)



DIFFERENTIAL-LOCK WILL NOT ENGAGE (CONTINUED FROM PREVIOUS PAGE)




DIFFERENTIAL-LOCK WILL NOT ENGAGE (CONTINUED FROM PREVIOUS PAGE)



DIFFERENTIAL-LOCK WILL NOT ENGAGE HYDRAULIC CIRCUIT TROUBLESHOOTING

NOTE: Complete electrical troubleshooting before starting hydraulic testing.



TROUBLESHOOTING
DIFFERENTIAL LOCK WILL NOT DISENGAGE

Perform the following preliminary steps before proceeding to the troubleshooting charts:

1. Check the following systems for proper operation:
   - PTO
   - Transmission
   - 3-point fast raise
   - FWD (if equipped)
   - TerraLock™ (If equipped)

NOTE: *If all these systems do not operate, check for a common current supply problem. Refer to the wiring schematics in Section 55, Chapter 6.*

2. Verify the differential lock system is not operating properly. Proceed if the system is not working properly.

NOTE: *The 3-point fast raise/work switch must be in the work position and both brake pedals must be fully released for the differential lock system to operate properly.*

Make sure Fast Raise/Work system operates properly before proceeding.


NOTE: *If equipped with TerraLock, the steering must be centered and properly calibrated for the differential lock system to work properly.*

3. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.

NOTE: *Proceed to step four if current fault codes exist. Proceed to step five if no current fault codes exist.*


4. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
5. Perform an inspection of the diff-lock system and correct loose or damaged electrical wires, connectors, or hydraulic components.
6. Proceed to the following electrical troubleshooting chart:

DIFFERENTIAL-LOCK WILL NOT DISENGAGE ELECTRICAL CIRCUIT TROUBLESHOOTING



DIFFERENTIAL-LOCK WILL NOT DISENGAGE HYDRAULIC CIRCUIT TROUBLESHOOTING

NOTE: Complete electrical troubleshooting before starting hydraulic testing.



ADJUSTMENTS

AXLE SHAFT BEARING PRELOAD ADJUSTMENT - ALL MODELS


The preload adjustment procedure is the same for the Model 8660 axle assembly and Models 8770/8770A, 8870/8870A, and 8970/8970A axle assembly.

The preload adjustment procedure is the same for all models.

NOTE: *Check preload anytime the pinion assembly is disassembled.*

Tools Required:
Assorted hand tools
Torque wrenches
- 675 N·m (500 ft lbs)
- 11 N·m (100 in. lbs.)

Depth micrometer
Micrometer 0 to 25 mm (0 to 1″)
Dealer-constructed tools (see “Special Tools” heading for details)
- Axle housing support stand - 70S020
- Axle rolling torque measuring tool - 70S010 (Model 8670/8670A)
- Axle rolling toque measuring tool - 70S009 (Models 8770/8770A, 8870/8870A, 8970/8970A)



28

PRELOAD ADJUSTMENT


IMPORTANT: *Check preload with bearings lubricated and axle seal removed.*

IMPORTANT: *Rotate pinion shaft 10 revolutions before rolling torque is measured. Measure torque while housing is rotating.*

1. Install retaining bolt, 1, and retaining washer, 2.

NOTE: *Do not install shims between washer and axle.*


NOTE: *Inspect retaining washer for bending or deflection. Any type of a bend or deflection in this part will cause a loss of axle preload, which can contribute to an axle seal failure. Maximum bend/deflection should not exceed 0.05 mm (0.002″).*



29

2. MODEL 8670/8670A - Install #70S010 rolling torque tool, 1, and measure rolling torque.


***IMPORTANT**: Rotate axle housing ten revolutions before measuring rolling torque while housing is rotating.*



30

MODELS 8770/8770A, 8870/8870A, 8970/8970A - Install #70S009 rolling torque tool and measure rolling torque.

***IMPORTANT:** Rotate axle housing ten revolutions before measuring rolling torque while housing is rotating.*




31

3. Perform rolling torque testing while gradually tightening retaining bolt until specified rolling torque is obtained:


   MODEL 8670/8670A
   5.5 N·m -11 N·m (50 in. lbs. - 100 in. lbs.)

   MODELS 8770/8770A, 8870/8870A, 8970/8970A
   3.3 N·m - 8.8 N·m (30 in. lbs. - 80 in. lbs.)




32

4. Remove bolt, 1, and washer, 2, after specified rolling torque is obtained.



33

5. Use a depth micrometer to measure distance to the axle.




34

6. Measure distance to the planetary carrier.
7. Subtract measurement obtained in Step 6 from dimension obtained in Step 5. The remainder is the thickness of the shim pack.


   EXAMPLE:

Step 5 dimension	53.34 mm	(2.100″)
Step 6 dimension	- 52.07 mm	(2.050″)
Shim pack	1.27 mm	(0.050″)




35

8. Select shims, 3, to equal calculated shim pack thickness ± 0.050 mm (0.002″).
9. Install shims, 3; retaining washer, 2; and bolt, 1.



36

10. Torque the retaining bolt to 608 N·m (450 ft lbs).



37


11. Check rolling torque for specified value stated in step 3.

IMPORTANT: *<u>If torque is low</u> - Remove retaining bolt, washer, and shims, then return to step 1.*

<u>If torque is high</u> - Remove retaining bolt, washer, and shims. Lift up on housing and strike shaft to establish slight free play between bearing and race. Return to step 1.

IMPORTANT: *If rolling torque is correct, check for end play by prying between planetary carrier and axle housing. If there is free play, return to step 1.*

12. When proper rolling torque is established, return to the appropriate axle housing reassembly instructions and complete reassembly.



38


PINION DEPTH ADJUSTMENT - ALL MODELS

The procedure to determine pinion depth is similar for all models.

NOTE: *The formula to calculate the pinion depth shim pack for the Model 8670/8670A is different from the formula used on Models 8770/8770A, 8870/8870A, and 8970/8970A.*

NOTE: *Check pinion depth anytime the pinion shaft, rear pinion bearing, or center housing is changed. Improper pinion depth adjustment will result in premature wear of the ring and pinion gears.*

Tools Required:
Assorted hand tools
Depth micrometer - 51 mm - 76 mm (2″ - 3″)
Micrometer - 0 to 25 mm (0 to 1″)




39

ADJUSTMENT PROCEDURE

1. Record the Center Housing Machine Depth (CHMD) dimension that is stamped in the housing flange above the pinion shaft.

NOTE: *The CHMD dimension is in millimeters.*

EXAMPLE: Record CHMD 312020 stamped in housing as 312.020 mm.




40

2. Record the + or - symbol and Pinion Machining Deviation (PMD) number etched in the end of the pinion gear.

NOTE: *The PMD dimension is in inches. Multiply dimension by 25.4 to convert to millimeters.*

EXAMPLE:
PMD dimension = 0.009″
0.009″ x 25.4 = 0.2286 mm



41

3. Place the rear pinion bearing assembly on a hard, flat, smooth surface as shown.

NOTE: *If the bearing is measured in any way other than with the bearing cup on top of the bearing cone, the measurement will not be accurate.*

4. Rotate the cone in the cup while applying 9 kg - 13.5 kg (20 lbs. - 30 lbs.) to seat the bearing.
5. Measure the thickness of the bearing assembly to three decimal points with a depth micrometer while applying 9 kg - 13.5 kg (20 lbs. - 30 lbs.) to seat the bearing.
6. Record the dimension in step 5 as the Pinion Bearing Thickness (PBT).

NOTE: *If the measurement was taken in inches, multiply the dimension by 25.4 to convert to millimeters.*

EXAMPLE:


Pinion bearing thickness = 2.080″

2.080″ x 25.4 = 52.830 mm

NOTE: *Bearing thickness should fall within the following dimensions. Check measurement if not within limits.*

MODEL 8670/8670A
53.98 mm - 54.18 mm (2.125″ - 2.133″)


MODELS 8770/8770A, 8870/8870A, 8970/8970A
52.76 mm - 52.96 mm (2.077″ - 2.085″)



42

7. Calculate shim pack thickness, 1, by substituting the dimensions obtained in steps 1, 2 and 6, then proceed to step 8.

NOTE: *Select the example that corresponds to the tractor model being worked on and the appropriate + or - sign on the pinion shaft.*



43

MODEL 8670/8670A - EXAMPLE #1

(Use this example if there is a + or no sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**		277.440 mm
Pinion Depth Constant used for Model 8670/8670A			– 222.377 mm
Pinion Machine Deviation (+)	**(From step 2)**		– 0.228 mm
Pinion Bearing Thickness	**(From step 6)**		– 54.070 mm
Constant used for Model 8670/8670A			– 0.130 mm
	SHIM PACK	=	**0.635 mm**

MODEL 8670/8670A - EXAMPLE #2

(Use this example if there is a – sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**		277.440 mm
Pinion Depth Constant used for Model 8670/8670A			– 222.377 mm
Pinion Machine Deviation (–)	**(From step 2)**		+ 0.228 mm
Pinion Bearing Thickness	**(From step 6)**		– 54.070 mm
Constant used for Model 8670/8670A			– 0.130 mm
	SHIM PACK	=	**1.09 mm**

MODELS 8770/8770A, 8870/8870A, 8970/8970A - EXAMPLE #1

(Use this example if there is a + or no sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**		312.020 mm
Pinion Depth Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A			– 258.000 mm
Pinion Machine Deviation (+)	**(From step 2)**		– 0.228 mm
Pinion Bearing Thickness	**(From step 6)**		– 52.830 mm
Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A	– 0.080 mm		
	SHIM PACK	=	**0.882 mm**

MODELS 8770/8770A, 8870/8870A, 8970/8970A - EXAMPLE #2

(Use this example if there is a – sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**		312.020 mm
Pinion Depth Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A			– 258.000 mm
Pinion Machine Deviation (–)	**(From step 2)**		+ 0.228 mm
Pinion Bearing Thickness	**(From step 6)**		– 52.830 mm
Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A			– 0.080 mm
	SHIM PACK	=	**1.338 mm**

MODEL 8670/8670A - TEMPLATE #1

(Use this template if there is a + or no sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**	_____
Pinion Depth Constant used for Model 8670/8670A		– 222.377 mm
Pinion Machine Deviation (+)	**(From step 2)**	– _____
Pinion Bearing Thickness	**(From step 6)**	– _____
Constant used for Model 8670/8670A		– 0.130 mm
	SHIM PACK =	_____

MODEL 8670/8670A - TEMPLATE #2

(Use this template if there is a – sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**	_____
Pinion Depth Constant used for Model 8670/8670A		– 222.377 mm
Pinion Machine Deviation (–)	**(From step 2)**	+ _____
Pinion Bearing Thickness	**(From step 6)**	– _____
Constant used for Model 8670/8670A		– 0.130 mm
	SHIM PACK =	_____

MODELS 8770/8770A, 8870/8870A, 8970/8970A - TEMPLATE #1

(Use this template if there is a + or no sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**	_____
Pinion Depth Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A		– 258.000 mm
Pinion Machine Deviation (+)	**(From step 2)**	– _____
Pinion Bearing Thickness	**(From step 6)**	– _____
Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A		– 0.080 mm
	SHIM PACK =	_____

MODELS 8770/8770A, 8870/8870A, 8970/8970A - TEMPLATE #2

(Use this template if there is a – sign in front of the PMD dimension on the pinion gear.)

Center Housing Machine Depth	**(From step 1)**	_____
Pinion Depth Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A		– 258.000 mm
Pinion Machine Deviation (–)	**(From step 2)**	+ _____
Pinion Bearing Thickness	**(From step 6)**	– _____
Constant used for Models 8770/8770A, 8870/8870A, 8970/8970A		– 0.080 mm
	SHIM PACK =	_____

NOTE: *The above templates are for figuring Pinion Bearing Thickness only. There are four total givens; the Pinion Depth Constant, the Constant for either model (8670/8670A, 8770/8770A, 8870/8870A and 8970/8970A) and the two other givens, the CHMD and the PMD will be found on the machine and the pinion gear itself.*


8. Round off the calculated shim pack dimension to one decimal point.

   EXAMPLE:
   1.338 mm = 1.3 mm

9. Select shims, 1, required to equal the rounded off shim pack dimension.

NOTE: *Shims are available in the following thicknesses: 0.50 mm, 0.60 mm, 0.70 mm, 0.80 mm, 0.90 mm.*

10. Measure shims with a micrometer to verify thickness.
11. Proceed to step 2 in the “Reassembly” portion of the “Pinion Assembly Overhaul” section in this chapter.



44


PINION BEARING PRELOAD ADJUSTMENT - ALL MODELS

The preload adjustment procedure is the same for all models.

NOTE: *Check preload anytime the pinion assembly is disassembled.*

Tools Required:
Assorted hand tools
Torque wrenches
- 135 N·m (100 ft lbs)
- 1 N·m (100 in. lbs.)

Rear axle pinion nut tool - FNH00547
Dealer-constructed tool (see “Special Tools” heading in this chapter for details.)
- Pinion rotating tool - #70S005


70-240-1979


45

PRELOAD ADJUSTMENT

IMPORTANT: *Check preload with pinion bearings lubricated with specified rear axle assembly oil.*

IMPORTANT: *Rotate pinion shaft 15 revolutions before rolling torque is measured. Measure rolling torque while pinion shaft is rotating. Correct preload is 1.1 N·m - 2.2 N·m (10 in. lbs. - 20 in. lbs.) of rolling torque.*


1. Check to make sure adjusting nut, 1, is installed with flat side contacting the bearing.



70-240-1980

46


2. Install FNH00547 special tool, 1, on nut and #70S005 dealer-made pinion rotating tool, 2, on pinion shaft.
3. Tighten nut until slight rolling resistance is obtained.



70-240-1981

47


4. Measure rolling torque after rotating pinion shaft 15 revolutions.
5. Continue to adjust nut and measure rolling torque until the correct preload of 1.1 N·m - 2.2 N·m (10 in. lbs. - 20 in. lbs.) of rolling torque is obtained.



48


6. Install lock washer, 1, and jam nut, 2.

NOTE: *Install jam nut with tapered side facing the adjusting nut.*



49


7. Install FNH00547 special tool, 1, on nut and #70S005 dealer-made pinion rotating tool, 2, on pinion shaft.
8. Torque jam nut to 128 N·m (95 ft lbs).



50


9. Check for proper rolling torque.

IMPORTANT: *Adjust preload if not to specification.*



51

10. Seat lock washer tabs in a slot on each nut.




52

DIFFERENTIAL SUPPORT BEARINGS PRELOAD ADJUSTMENT - ALL MODELS

The preload adjustment procedure is the same for all models.

NOTE: *Check preload anytime the differential assembly is removed or end caps are removed. Preload must be within specifications before pinion backlash is checked or adjusted.*


Tools Required:
Assorted hand tools
Torque wrench - 135 N·m (100 ft lbs)
Micrometer - 0 to 25 mm (0 to 1″)
Feeler gauge



53


PRELOAD ADJUSTMENT

1. Install the left-hand support using the original shims removed,or new shims of the same thickness.




54

2. Tighten six retaining bolts to 108 N·m (80 ft lbs).



55


3. Install the right-hand support using the original shims removed, or new shims of the same thickness.



56

4. Tighten right-hand retaining bolts hand tight.

IMPORTANT: *Ensure there is backlash between the ring and pinion gears before proceeding. Remove shims from left support and add shims to right support to increase backlash.*



57


5. Use a feeler gauge to measure the gap between the right-hand shims and center housing. Measure at four different locations 90° apart.

   Proceed to the indicated step based on measurement results:

   - Feeler gauge measurement is 0.025 mm - 0.152 mm (0.001″ - 0.006″). Bearing preload is correct, proceed to step 8.
   - Feeler gauge measurement is below 0.025 mm (0.001″), proceed to step 6.
   - Feeler gauge measurement is over 0.152 mm (0.006″), proceed to step 7.


6. If measurement is below 0.025 mm (0.001″), remove shims from the right-hand side and repeat step 5.

7. If measurement is over 0.152 mm (0.006″), add shims to the right-hand side and repeat step 5.




58

8. Torque the right side hardware to 108 N·m (80 ft lbs).



59

9. Check “Pinion Backlash,” as described in the “Adjustment” heading of this chapter, before proceeding to reassemble the rear axle.



60


RING AND PINION GEAR BACKLASH ADJUSTMENT - ALL MODELS

The backlash adjustment procedure is the same for all models.

NOTE: *Check backlash anytime the differential assembly is removed or adjusted. Improper backlash will result in premature wear of the ring and pinion gears.*

IMPORTANT: *Check backlash after the differential bearing preload has been properly adjusted and before installing axle assemblies.*

Tools Required:
Assorted hand tools
Dial indicator
Torque wrench - 0-135 N·m (0- 100 ft lbs)




61

BACKLASH ADJUSTMENT


NOTE: *The amount of backlash is etched in inches on the ring gear. The ring gear shown has .014 etched as the backlash.*
Backlash adjustment may vary by +/- 0.050 mm (0.002″) from the amount indicated on the ring gear.

EXAMPLE:
Backlash on gear is 0.35 mm (0.014″)
Set backlash to 0.30 mm - 0.40 mm (0.012″ - 0.016″)



62

1. Position a dial indicator so the magnetic base is firmly positioned on the center housing.
2. Position the plunger on one of the ring gear teeth. The plunger should be as vertical as possible to the gear tooth.
3. Note the dial indicator reading while moving the ring gear backward and forward with the pinion gear held stationary.




63

4. Backlash is acceptable when the dial indicator reading is within ± 0.050 mm (0.002″) of the amount indicated on the ring gear.


NOTE: *Proceed to the indicated step based on the reading obtained:*

- Backlash is correct. Go to step 7
- Backlash is above upper limit. Go to step 5
- Backlash is below lower limit. Go to step 6




64

5. If backlash is above the upper limit, remove shims from the right-hand support and install them under the left-hand support. Retorque the support hardware to 108 N·m (80 ft lbs), then repeat steps 3 and 4.




65

6. If backlash is below the lower limit, remove shims from the left-hand support and install them under the right-hand support. Retorque the support hardware to 108 N·m (80 ft lbs), then repeat steps 3 and 4.



66

7. Perform a ring and pinion gear tooth contact pattern check, as described in this chapter.



67

RING AND PINION GEAR TOOTH CONTACT PATTERN - CHECK AND ADJUSTMENT - ALL MODELS

The procedure to check the contact pattern is the same for all models.

NOTE: *The contact pattern for the Model 8670/8670A is different from the contact pattern for Models 8770/8770A, 8870/8870A, and 8970/8970A.*


NOTE: *Check contact pattern anytime the differential assembly is removed or adjusted. Improper contact pattern will result in premature wear of the ring and pinion gears.*

Tools Required:
White lead paint or equivalent

CONTACT PATTERN CHECK PROCEDURE

1. Paint the convex side, 1, of the ring gear teeth with white lead paint or equivalent.


NOTE: *Paint six teeth at three locations approximately 120° apart.*



68

2. Rotate the pinion shaft counterclockwise while applying resistance to the rotation of the ring gear.

NOTE: *Continue to rotate the pinion shaft until the ring gear completes three revolutions.*




69

3. Check for acceptable contact pattern as shown at all three locations on the ring gear.

NOTE: *If the pattern is acceptable, return to step 3 of the "Installation" section under the "Differential and Differential Lock Assembly - Overhaul" heading in this chapter.*


NOTE: *If the pattern is not as shown, proceed to step 4.*

MODEL 8670/8670A - acceptable pattern



70


MODELS 8770/8770A, 8870/8870A, and 8970/8970A - acceptable pattern



71

4. If any of the unacceptable patterns are obtained, check ring and pinion backlash and pinion depth adjustments. Then check the contact pattern again, starting at step 1.

IMPORTANT: *An incorrect contact pattern will result in premature wear of the ring and pinion gears.*



72


DISASSEMBLY AND REPAIR

AXLE ASSEMBLY - REMOVAL AND INSTALLATION

The Model 8670/8670A axle assembly differs from the Models 8770/8770A, 8870/8870A, and 8970/8970A assembly. The cab also mounts differently on the two axle assemblies; therefore, the following instructions are divided by model numbers. Refer to the instructions for the model to be worked on.

The following procedures detail removing the axle assembly with the rear axle installed in the tractor. If the rear axle is removed from the tractor, proceed to the appropriate step.


Tools Required:
Assorted hand tools
Two pilot bolts - M16 x 160
Jack stands
Portable crane
Floor jack
Dealer-constructed tools (see “Special Tools” heading in this chapter for details)
- Cab tilting tool - 70S001
- Axle shaft housing lifting tool - 70S002


70-240-1275

73

REMOVAL PREPARATION - ALL MODELS

1. Thoroughly clean the area of the tractor to be worked on.
2. Place the tractor on a level concrete surface.
3. Block both sides of the front wheels to prevent movement.
4. Jack the tractor up and support with jack stands.



70-240-1276

74

5. Drain the oil from the rear axle by removing drain plug, 1.

NOTE: *Approximately 136 liters (36 U.S. gallons) of oil will be drained.*

NOTE: *(70 Series) The fiber sealing washer, part #V65120, can yield causing the rear axle center housing drain plug to loosen up. To correct this, a new copper gasket, part #86010325, was released and put into production on October 11, 1994, at tractor serial #D404200.*




75

6. Remove the rear wheel as detailed in Section 44, Chapter 1.

7. Disconnect the electrical connector, 1, on the right rear corner of the cab.


NOTE: *When removing the left trumpet assembly, there are two electrical connectors at the left rear of the cab that must be disconnected.*



76

8. Disconnect the wire clamp, 1; ground strap, 2; and ground wire, 3, from the inside of the cab mount supports, 4.


NOTE: *Model 8670/8670A cab mount support shown.*



77

9. Loosen the right and left side rear cab retaining bolts, 3.
10. Install dealer-constructed cab tilting tool #70S001, 1, into the cab frame at 2.

NOTE: *See the "Special Tools" heading for tool dimensions.*




78

11. Slowly raise the 3-point lower link arm using a floor jack, 4, until the upper lift arms, 1, raise the cab tilting tool, 2, enough to take the weight off the rubber mount.

IMPORTANT: *Do not raise the rear of the cab higher than necessary to remove the rubber insulator. Raising the rear of the cab excessively may damage the windshield or cab.*

IMPORTANT: *Do not use the tractor hydraulic system to raise the 3-point linkage with the cab tilting tool in place.*


12. Install a jack stand, 3, under the lower lift arm after the cab has been raised to the desired height.



79


AXLE ASSEMBLY REMOVAL - MODEL 8670/8670A

1. Complete all steps in the “Removal Preparation - All Models” heading in this chapter.
2. Remove the cab mount bolt and insulators.



80

3. Remove the cab support, 1, from the axle housing.




81

4. Install dealer constructed axle lifting bracket #70S002, 2, on the axle housing using the second notches as shown.


NOTE: *See “Special Tools” heading in this chapter for dimensions.*

5. Remove two axle attaching bolts, 1 and 3.




82

6. Install two pilot bolts, 1 and 2.



83


7. Remove the remaining bolts and slide the axle assembly away from the center housing. Lower the axle assembly to the ground.



84


INSTALLATION - MODEL 8670/8670A

1. Install the three locator pins, 1, in the axle housing.



85


2. Thoroughly clean the center housing and axle housing mating surfaces. Place a bead of specified anaerobic sealer on the center housing as shown.



86

3. Install guide bolts.
4. Use the lifting device to raise the axle into position on the alignment pins. Slide the axle into position.


NOTE: *Place a bolt in the end of the axle shaft and turn with a wrench to align the planetary gears with the sun gear.*



87


5. Install all rear axle attaching bolts and torque in a cross pattern to 270 N·m (200 ft lbs).

NOTE: *Apply specified pipe thread sealant to the threads of bolt, 1. This bolt is exposed to rear axle oil.*



88


6. Install the cab support, 1, and torque the mounting hardware to 306 N·m (226 ft lbs).
7. Proceed to “Final Installation Steps - All Models” heading in this chapter.



89


AXLE ASSEMBLY REMOVAL - MODELS 8770/8770A, 8870/8870A, 8970/8970A

1. Complete all steps in the “Removal Preparation - All Models” heading in this chapter.
2. Remove the cab mount bolt and insulators.



90

3. Remove the four cab support to axle housing attaching bolts.
4. Remove the center isolator, then attach the cab support, 1, to the cab frame with mount bolt.




91

5. Install dealer-constructed lifting bracket #70S002, 2, on the axle housing using the inner notches as shown.


NOTE: *See "Special Tools" heading in this chapter for dimensions.*

6. Remove two axle attaching bolts, 1 and 3.



92


7. Install two pilot bolts.



93


8. Remove the remaining bolts and slide the axle assembly, 2, and planetary ring gear, 1, away from the center housing just enough to install a bolt and nut, as shown in step nine.

NOTE: *It may be necessary to pry the planetary ring gear from the center housing.*



94


9. Secure the planetary ring gear to the axle housing with a bolt and nut, 1.
10. Remove the axle housing and planetary ring gear and lower to the ground.



95


INSTALLATION - MODELS 8770/8770A, 8870/8870A, 8970/8970A

1. Thoroughly clean the center housing and planetary ring mating surfaces. Place a bead of specified anaerobic sealer on the center housing as shown.




96

2. Thoroughly clean the axle housing and planetary ring mating surfaces. Place a bead of specified anaerobic sealer on the axle housing as shown. Ensure both dowel pins, 1, are installed.



97


3. Install the planetary ring gear on the axle housing locator pins. Use a bolt and nut, 1, to keep the parts together during installation.



98


4. Install guide bolts, 1.
5. Use the lifting device to raise the axle into position on the alignment pins and slide the axle into position. Remove the bolt installed in step 3.

NOTE: *Place a bolt in the end of the axle shaft, and turn with a wrench to align the planetary gears with the sun gear.*




99

6. Install all rear axle attaching bolts and torque in a cross pattern to 270 N·m (200 ft lbs).



100


7. Install the cab support and torque the mounting hardware to 239 N·m (177 ft lbs).
8. Proceed to “Final Installation Steps - All Models” heading in this chapter.



101

FINAL INSTALLATION STEPS - ALL MODELS


1. Reinstall the cab insulators and attaching bolt.
2. Lower the 3-point lift arms to allow the cab to sit back on the insulators.
3. Torque each of the rear cab mount bolts to 217 N·m (160 ft lbs).
4. Remove the cab tilting tool #70S001.



102

5. Reattach the wire harness retaining clamp, 1, the ground strap, 2, and ground wire, 3, to the cab support mounts, 4.

NOTE: *Some models have grounds attached to the rear axle.*




103

6. Reconnect the electrical connector, 1.

NOTE: *Two connectors are used on the left side.*


7. Reinstall the rear wheel as detailed in Section 44, Chapter 1.



104

8. Refill the rear axle assembly with ESN-M2C134-D hydraulic oil through filler tube, 1, until the oil level is to the full mark, 3, on the dipstick, 2.


NOTE: *Do not fill above the full mark.*




105

NOTE: *(70 Series) Oil seepage can occur from the rear axle housing breather located at the upper left-hand rear location of the rear axle center housing. This seepage most likely occurs while driving at higher speeds or with the PTO operating.*


To correct this problem, the rear axle housing breather has been relocated to a boss mounted to the top of a new oil filler tube assembly, Figure 106. This change is effective from tractor serial #D417700. Also, at this time, the coupler drain hose was rerouted to drain back to the former breather location, using hose coupling elbow, part #86018978, and new hose 90 mm (3.5″) long, part #86018977, Figure 107. Note that this coupler drain is only on units equipped with the Bruning style coupler. On earlier units equipped with the Snap-Tite coupler, the former breather location may be plugged, using plug, part #236622.



106



107




108

1. Bolt lock
2. Retaining bolt
3. Retaining washer
4. Shim(s)
5. Planetary assembly
6. Inner bearing cone
7. Inner bearing cup
8. Axle housing
9. Outer bearing cup
10. Outer bearing cone
11. Oil seal ring
12. Oil seal
13. Axle shaft

AXLE HOUSING ASSEMBLY - OVERHAUL - MODEL 8670/8670A

Tools Required:
Assorted hand tools
Torque wrenches
- 675 N·m (500 ft lbs)
- 11 N·m (100 in. lbs.)


Slide puller
Bearing puller
Bearing race puller
Bearing race driver
Bottle jack - 20 ton
Depth micrometer
Micrometer - 0 to 25 mm (0 to 1″)
Petroleum jelly
Specified thread-locking compound
Hydraulic press
Dealer-constructed tools (see “Special Tools” heading for details)
- Axle housing support stand - 70S020
- Planetary gear assembly lift tool - 70S007
- Axle removing tool - 70S018
- Planet ring gear removing tool - 70S019



109


DISASSEMBLY

1. Remove the axle housing assembly as described in this chapter.




110

2. Install eyebolts, 1, and place the axle assembly, 2, in the dealer-constructed axle housing stand, #70S020, 3.



111


3. Remove separator plate, 1, from the axle housing.



112


4. Remove bolt lock, 1.

NOTE: *The bolt lock is held in place with thread-locking adhesive.*




113

5. Install eyebolts, 1; pipe, 2; and brass drift, 3, then loosen the retaining bolt.



114


6. Remove axle retaining bolt, 1; retaining washer, 2; and shims, 3.



115


7. Install the dealer-constructed planetary assembly lifting tool #70S007, 1.
8. Lift the planetary assembly from the axle shaft.

NOTE: *If planetary repair is required, refer to the appropriate heading in this chapter.*




116

9. Install the dealer-constructed axle removing tool #70S018, 1.
10. Place the 20-ton bottle jack, 2, on the axle shaft and press the shaft from the bearing.




117

11. Remove the inner bearing from the axle shaft.



118

12. Lift the housing from the axle shaft and place the housing on the ground.




119

NOTE: *Perform steps 13, 14, 15, and 16 as required based on parts condition.*


13. Remove planetary ring gear if replacement is required.

    Install dealer-constructed removing tool #70S019, 1. Tighten the bolts evenly to pull the gear from the housing.




120

14. Remove the inner and outer bearing cups using a slide puller with internal jaw puller. Only remove cups if replacement is required.




121

15. Place the axle shaft in a press and remove the outer bearing. Only remove if replacement is required.



122


16. Press the oil seal ring from the axle shaft. Only remove if replacement is required.



123

INSPECTION AND REPAIR

1. Clean all components thoroughly.
2. Inspect components for wear or damage and replace as required.
3. Inspect oil seal ring, 1, closely. Replace if any imperfections are found since it forms the inner sealing surface for the axle seal, 2.




124

REASSEMBLY

Reassembly follows the disassembly process in reverse order.

***IMPORTANT**: Use an induction heater, 1, or oven to heat the bearings and oil ring seal to specified temperature prior to installation. This allows components to be installed with no resistance. Components can be damaged if driven on.*




125

1. Install axle shaft in axle housing stand.
2. Install oil ring seal, 2, if removed. Heat the oil ring seal to 130° C (266° F) then install on the axle shaft until it seats against the shaft shoulder, 3. If needed, tap with a brass drift to seat.

***IMPORTANT:** The ring seal must seat against the shoulder.*


3. Install outer bearing, 1, if removed. Heat the outer bearing to 130° C (266° F), then install on the shaft until it seats against the oil ring seal, 2. If needed, tap with a brass drift to seat.

***IMPORTANT:** The bearing must seat against the oil ring seal.*




126

4. Install three locating pins, 1, and install planet ring gear, 2, if removed. Fully seat the gear in the housing.




127

5. Install the inner and outer bearing cups if removed. Use appropriate size drivers, 1.



128

6. Oil the bearing with specified oil after the bearing has cooled.
7. Install the housing on the axle shaft.




129

8. Heat the inner bearing to 130° C (266° F), then install on the shaft until it seats against the cup. If needed, tap with a brass drift to seat.


IMPORTANT: *The bearing must seat against the cup.*

9. Oil the bearing with specified oil after the bearing has cooled.



130


10. Install the planetary assembly on the axle shaft. Remove the dealer-constructed lifting tool, 1.



131

11. Install bolt, 1, and retaining washer, 2. Tighten the bolt finger tight.


NOTE: *Rear axle oil seal leak and failure can result from loss of axle bearing preload. If loss of axle bearing preload was evident, inspect the axle retaining washer, 2, for bending deflection. With the washer on a flat surface, using firm finger pressure, press down on the outer edge of the washer and release. If the washer "rocks", then it is not flat, replace with a new one and inspect the new one the same way. Turn the washer over and repeat this check. Alternately, on a flat surface, use a feeler gauge to check for 0.05 mm (0.002") maximum out of flatness. Turn the washer over and repeat. Replace washer if there is more than 0.050 mm (0.002") space.*



132


12. IMPORTANT: Adjust the axle shaft bearing preload as detailed in the ”Adjustment” heading of this chapter before proceeding.

NOTE: *Do not proceed without checking bearing preload.*




133

13. Apply thread-locking compound to bolt lock.




134

14. Install bolt lock. Allow the compound to set up and hold bolt lock, 1, in position.




135

15. Install separator plate, 1.




136

16. Install the axle seal as described in this chapter.
17. Install the axle housing as described in this chapter.



137




138

1. Bolt lock
2. Retaining bolt
3. Retaining washer
4. Shim(s)
5. Planetary assembly
6. Inner bearing cone
7. Inner bearing cup
8. Axle housing
9. Outer bearing cup
10. Outer bearing cone
11. Oil seal ring
12. Oil seal
13. Axle shaft

AXLE HOUSING ASSEMBLY - OVERHAUL - MODELS 8770/8770A, 8870/8870A, 8970/8970A

Tools Required:
Assorted hand tools
Torque wrenches
- 675 N·m (500 ft lbs)
- 11 N·m (100 in. lbs.)


Slide puller
Bearing puller
Bearing race puller
Bearing race driver
Bottle jack - 20 ton
Depth micrometer
Micrometer - 0 to 25 mm (0 to 1″)
Petroleum jelly
Specified thread-locking compound
Hydraulic press
Dealer-constructed tools (see “Special Tools” heading for details)
- Axle housing stand - 70S020
- Planetary gear assembly lift tool - 70S008
- Axle removing tool - 70S015
- Axle rolling torque tool - 70S009



139


DISASSEMBLY

1. Remove the axle housing assembly as described in this chapter.




140

2. Remove planet ring gear, 2, from the axle housing, 1.



141


3. Install eyebolts, 1, and place axle assembly, 2, in #70S020 dealer-constructed axle housing stand, 3.



142


4. Remove bolt lock, 1.

NOTE: *The bolt lock is held in place with thread-locking adhesive.*




143

5. Install eyebolts, 2; pipe, 3; and brass drift, 1, as shown, then loosen retaining bolt.




144

6. Remove axle retaining bolt, 1; retaining washer, 2; and shims, 3.



145


7. Install dealer-constructed planetary assembly lifting tool #70S008, 1, then attach removable leg, 2, to the tool.



146


8. Lift the planetary assembly from the axle shaft.

NOTE: *If planetary repair is required, refer to the appropriate heading in this chapter.*




147

9. Install dealer-constructed axle removing tool #70S015, 1.
10. Place 20-ton bottle jack, 2, on the axle shaft and press the shaft from bearing, 3.




148

11. Remove inner bearing, 1, from the axle shaft.



149


12. Lift the housing from the axle shaft and place the housing on the ground.



150


NOTE: *Perform steps 13, 14, and 15 as required based on parts condition.*

13. Remove inner and outer bearing cups using a slide puller with internal jaw puller. Only remove cups if replacement is required.




151

14. Place the axle shaft in a press and remove the outer bearing. Only remove if replacement is required.



152


15. Press the oil seal ring from the axle shaft. Only remove if replacement is required.



153

INSPECTION AND REPAIR

1. Clean all components thoroughly.
2. Inspect components for wear or damage and replace as required.
3. Inspect oil seal ring, 1, closely. Replace if any imperfections are found since it forms the inner sealing surface for the axle seal, 2.




154

REASSEMBLY

Reassembly follows the disassembly process in reverse order.

IMPORTANT: *Use an induction heater or oven to heat the bearings and oil ring seal to the specified temperature prior to installation. This allows components to be installed with no resistance.*

Components can be damaged if driven on.




155

1. Install the axle shaft in the axle housing stand.
2. Install oil ring seal, 2, if removed. Heat the oil ring seal to 130° C (266° F), then install on the axle shaft until it seats against the shaft shoulder, 3. If needed, tap with a brass drift to seat.

IMPORTANT: *The ring seal must seat against the shoulder.*


3. Install outer bearing, 1, if removed. Heat the outer bearing to 130° C (266° F), then install on the shaft until it seats against the oil ring seal, 2. If needed, tap with a brass drift to seat.

IMPORTANT: *The bearing must seat against the oil ring seal.*




156

4. Install the inner and outer bearing cups if removed. Use appropriate size drivers, 1.



157

5. Oil the bearing with specified oil after the bearing has cooled.
6. Install the housing on the axle shaft.




158

7. Heat inner bearing, 1, to 130° C (266° F), then install on the shaft until it seats against the cup. If needed, tap with a brass drift to seat.


IMPORTANT: *The bearing must seat against the cup.*

8. Oil the bearing with specified oil after the bearing has cooled.



159


9. Install the planetary assembly on the axle shaft.



160

10. Install bolt, 1, and retaining washer, 2. Tighten the bolt finger tight.


NOTE: *Rear axle oil seal leak and failure can result from loss of axle bearing preload. If loss of axle bearing preload was evident, inspect the axle retaining washer, 2, for bending deflection. With the washer on a flat surface, using firm finger pressure, press down on the outer edge of the washer and release. If the washer "rocks", then it is not flat, replace with a new one and inspect the new one the same way. Turn the washer over and repeat this check. Alternately, on a flat surface, use a feeler gauge to check for 0.05 mm (0.002") maximum out of flatness. Turn the washer over and repeat. Replace washer if there is more than 0.050 mm (0.002") space.*



161


11. *IMPORTANT: Adjust the axle shaft bearing preload as detailed in the "Adjustment" heading of this chapter before proceeding.*

NOTE: *Do not proceed without checking bearing preload.*




162

12. Apply specified thread-locking compound to the bolt lock.




163

13. Install the bolt lock. Hold the bolt lock to the washer, allowing the compound to set up.




164

14. Install the axle seal as described in this chapter.



165

15. Install the axle housing as described in this chapter.




166

PLANETARY OVERHAUL - ALL MODELS

The overhaul procedure is the same for the Model 8670/8670A four-planet gear assembly and the Models 8770/8770A, 8870/8870A and 8970/8970A three-planet gear assembly.


Where components differ, the specific models will be identified.

1. Thrust washer
2. Needle bearings (27)
3. Planet gear
4. Spacer washer
5. Needle bearings (27)
6. Thrust washer
7. Planet gear shaft
8. Lockwire
9. Retaining ring
10. Carrier




167

MODEL 8670/8670A assembly.



168


MODELS 8770/8770A, 8870/8870A, 8970/8970A assembly.



169

Tools Required:
Assorted hand tools
Petroleum jelly
Dealer-constructed tools (see “Special Tools” heading in this chapter for details)


- Needle bearing retainer - #70S012 (Model 8670/8670A)
- Needle bearing retainer - #70S011 (Models 8770/8770A, 8870/8870A, 8970/8970A)



170


DISASSEMBLY

1. Cut ends from lockwire, 1, and pull from behind retaining ring, 2.




171

2. Compress the retaining ring so it disengages slots in planet gear shafts, 1.




172

3. MODEL 8670/8670A
   Use #70S012 needle bearing retainer, 3, to push shaft, 2, from planet carrier, 1. The tool will keep the bearings in place.




173

4. MODELS 8770/8770A, 8870/8870A, 8970/8970A
   Use #70S011 needle bearing retainer, 3, to push shaft, 2, from planet carrier, 1. The tool will keep the bearings in place.




174

5. Remove shaft, 1; planet gear, 2; and thrust washers, 3.
6. Repeat the process and remove the remaining planet gears.



175


7. Remove all 54 needle bearings, 2, and center spacer, 1, from each gear.



176

INSPECTION

1. Clean all components thoroughly.
2. Inspect the components for wear or damage and replace as required.




177

REASSEMBLY


Reassembly follows the disassembly procedure in reverse.

1. Coat the needle bearings with petroleum jelly and install one row (27) of needle bearings around the appropriate needle bearing retaining tool, 1.
2. Install spacer.
3. Coat and install another row (27) of needle bearings.




178

4. Install planet gear, 2, and thrust washers, 3, in the carrier.
5. Install gear shaft, 1, so the slotted end will be on the retaining ring side of the carrier.




179

6. Push the shaft through the housing, thrust washers, and gear.
7. Retrieve the needle bearing retaining tool.




180

8. Install retaining ring, 2, in the shaft slots.
9. Install new lockwire, 1, under the retaining ring.



181

10. Wrap the wire end around the retainer and trim the excess wire.




182

AXLE SEAL

The Model 8670/8670A seal is a different style than the seal used on Models 8770/8770A, 8870/8870A, and 8970/8970A tractors.

The removal and installation procedures are the same for all models.


Tools Required:
Slide puller with screw end
Petroleum jelly
Seal installation tool #FNH00540



183


REMOVAL

1. Remove the rear wheel as described in Section 44.
2. Thoroughly clean the area to be worked on.



184

3. Punch small holes in the seal, 1, and use a slide remover with a screw tip, 2, to pull the seal from the housing.




185

INSPECTION

1. Clean the oil seal ring, 1, then check for wear or damage. Replace as required.

NOTE: *The oil seal ring forms the inner sealing surface.*

2. Clean the inside axle flange area, 2.




186

INSTALLATION


1. Put petroleum jelly on oil ring seal, 1, and inside flange area, 2.

2. Position seal, 1, in place.




187

3. Thread 7/8-9 UNC x 560 mm (24″) rod, 2, in the end of the axle and install the axle seal installation tool #FNH00540, 1.
4. Tighten the nut until the tool bottoms against the housing.



188

5. Remove the tool and check the seal for proper installation.
6. Reinstall the wheel as described in Section 44.



189

TOP COVER - REMOVAL AND INSTALLATION - ALL MODELS


The top cover must be removed to perform work on the differential or pinion assemblies.

Tools Required:
Assorted hand tools
Lifting device

REMOVAL

1. Remove the cab as described in Section 90, Chapter 3.
2. Separate the rear axle assembly from the transmission as described in Section 21, Chapter 3.

NOTE: *Only separate if required to perform repairs.*




190

3. Remove the hoses and lines attached to the remote valves if the rear axle assembly and transmission do not require separation.

NOTE: *The top cover can be removed with the remote valve assembly attached.*

4. Remove brake lines, 1 and 2, and line, 3.
5. Remove the top cover attaching hardware and note the location as different bolt lengths are used.
6. Remove the top cover using a lifting device.




191

INSTALLATION

Installation follows the removal procedure in reverse order.


1. Clean the mating surfaces of the top cover and axle center section.
2. Place a thin bead of specified silicone sealer on the housing.

NOTE: *Circle all bolt holes and oil return hole as shown.*




192

3. Install the top cover.
4. Put bolts in the original locations and torque to 380 N·m (280 ft lbs).
5. Reinstall the components taken off to access the top cover.



193



194


1. Left-hand support
2. Shim(s)
3. Bearing cup
4. Bearing cone
5. Ring gear
6. Differential carrier housing
7. Washer
8. Thrust bearing
9. Left-hand side gear
10. Pinion shaft-short (2)
11. Outer roll pin (6)
12. Inner roll pin (6)
13. Thrust washer
14. Spacer-thick (4)
15. Pinion gear (4)
16. Needle bearings (112)
17. Spacer-thick (4)
18. Right-hand side gear
19. Thrust bearing
20. Washer
21. Differential lock friction discs
22. Differential lock piston
23. O ring (large)
24. O ring (small)
25. Differential cover assy.
26. Seal rings (2)
27. Separator plates
28. Spider
29. Pinion shaft (long)
30. Right-hand support
31. Shim(s)
32. Bearing cup
33. Bearing cone

DIFFERENTIAL AND DIFFERENTIAL LOCK ASSEMBLY - OVERHAUL ALL MODELS

The overhaul procedure is the same for all models.

Tools Required:
Assorted hand tools
Torque wrenches:
- 135 N·m (100 ft lbs)
- 405 N·m (300 ft lbs)

Petroleum jelly
Bearing puller
Bearing remover
Dealer-constructed tools (see “Special Tools” heading for details)
- Needle bearing retainer for spider gears - #70S006
- Rear axle differential lifting tool - #70S003




195

REMOVAL

1. Remove the cab as described in Section 90, Chapter 3.


NOTE: *The differential assembly can be removed without splitting the tractor. Perform step 2 only when repairs require access to the front of the rear axle components.*

2. Separate the rear axle assembly from the transmission if the pinion assembly requires repair. Refer to Section 21, Chapter 3, for splitting details.
3. Remove the top cover as described in this chapter.
4. Remove both rear axle assemblies as described in this chapter.




196

5. Remove the PTO assembly and PTO input shaft as described in Section 31, Chapter 1.




197

NOTE: *If the rear axle assembly is separate from the transmission, pull the PTO input shaft out as shown.*




198

6. Remove the differential lock hydraulic line, 1, and adaptor from the right-hand differential support, 2.




199

7. Install #70S003 dealer-constructed differential lifting tool, 1. Use a suitable lifting device to support the differential.




200

8. Remove the retaining bolts from the right-hand differential support.




201

9. Remove the support and shims and keep them together.




202

10. Remove the left-hand support and shims and keep them together.



203


11. Lift the differential assembly from the center housing.



204


DISASSEMBLY

1. Mark the position of the components.




205

2. Remove the retaining bolts.




206

3. Remove ring gear, 1, from housing, 2.




207

4. Separate the cover, 1, from the housing, 2, by applying compressed air through the oil hole in the cover.
5. Remove the cover.



208


6. Remove piston, 1.



209


7. Remove separator plates, 3, and friction discs, 2, from the right-hand side gear, 1.

NOTE: *The separator plate is against the piston.*




210

8. Remove thrust bearing, 1, and washer, 2, from the right-hand side gear, 3.




211

9. Remove the right side gear.




212

10. Drive the inner and outer roll pins from three pinion shafts.




213

11. Remove the long pinion shaft from one pinion gear.
12. Remove pinion gear, 1; spacer, 3; and thrust washer, 2.
13. Remove the remaining pinion gears using the same process.
14. Remove spider, 4.




214

15. Remove spacer, 1; twenty-eight needle bearings, 3; and spacer, 4, from each gear, 2.



215

16. Remove the left-hand side gear, 3; thrust bearing, 2; and washer, 1, from the housing.




216

INSPECTION AND REPAIR


1. Clean all components thoroughly.
2. Inspect the components for wear or damage and replace as required.

IMPORTANT: *The ring and pinion gears are a matched set. If the ring gear is replaced, the matched pinion must be installed as described in this chapter.*



217

3. Replace outer, 1, and inner, 2, piston O rings.




218

4. Replace damaged bearings using a suitable bearing puller.


CAUTION

The puller must be pulled against the inner race. Do not allow the puller to pull against rollers, or cage, as the bearings may separate.



219

5. Press new bearings in place using an appropriate step plate or sleeve.
6. Inspect seal rings, 1, on the cover assembly and replace if damaged.



220


7. Inspect inner sealing area, 1, on the right-hand support. Replace if worn or damaged.
8. Replace damaged bearing cups, 2.
9. Inspect friction discs and separator plates for warpage, scoring, evidence of overheating and circular guaging.

   Measure the thickness of the friction discs and separator plates from the differential assembly.

   Minimum friction disc thickness is 3.79 mm (.149″).

   Minimum separator plate thickness is 2.58 mm (.101″).

   Replace if the minimum spec is not made.



221


REASSEMBLY

Reassembly follows the disassembly process in reverse order.

Observe the following during reassembly.


Lubricate the components with specified oil during reassembly.

1. Coat washer, 1, and thrust bearing, 2, with petroleum jelly and install on gear, 3.
2. Install the gear in the housing.




222

3. Install thick spacer, 1, in the gear.




223

4. Insert needle bearing retaining tool #70S006, 1, in the gear.




224

5. Coat 28 needle bearings with petroleum jelly and install.



225


6. Coat the rear of washer, 1, and install in the housing.



226


7. Place gear, 1, in place and insert pinion shaft, 2, through the housing and gear. Retrieve the needle bearing retaining tool, 3, from the gear as the shaft enters the gear.

IMPORTANT: *Install the pinion shaft so the holes in the shaft align with the roll pin holes in the housing.*




227

8. Install the remaining gears and shafts.
9. Insert spider, 1.
10. Install spacer, 2, between each gear and spider, then push the shaft into the spider.




228

11. Install the outer and inner roll pins through the housing and shafts.




229

12. Coat the O rings with petroleum jelly.
13. Install the piston in the cover and fully seat in the cover.



230


14. Install separator plate, 1, against the piston. Place the tabs on the separator plate in slots in the cover.



231


15. Install the remaining friction discs and separator plates in an alternate fashion.

IMPORTANT: *Soak new friction discs in specified oil for ten minutes before installation.*




232

16. Coat washer, 1, and thrust bearing, 2, with petroleum jelly, then install on the right-hand side gear, 3.




233

17. Install the side gear in the clutch plates. Make sure the gear is fully seated.



234


18. Install housing, 1, on cover assembly, 3.
19. Insert two bolts and nuts, 2.



235


20. Tighten the bolts evenly until the cover and housing come together, then remove the bolts.

NOTE: *Make sure the gears are aligned before tightening the bolts.*



236

21. Install the ring gear and torque the hardware to 338 N·m (250 ft lbs).




237

INSTALLATION

Installation follows the removal procedure in reverse order.


1. Lower the differential assembly into the rear axle housing.



238


2. Check and adjust the differential support bearing preload and pinion backlash as detailed in the "Adjustment" heading in this chapter.

IMPORTANT: *Do not proceed without checking bearing preload and backlash.*




239

3. Install and tighten the differential hydraulic line and adaptor, 1, to the retainer, 2.
4. Reassemble the tractor components removed to access the differential assembly.



240



241


1. Pinion gear
2. Bearing cone (rear)
3. Bearing cup (rear)
4. Shim (3)
5. Park brake disc (3)
6. Jam nut
7. Lock washer
8. Bearing cup (front)
9. Adjusting nut
10. Bearing cone (front)
11. Pinion sleeve

PINION ASSEMBLY OVERHAUL - ALL MODELS

The overhaul procedure is the same for all models.

The Model 8670/8670A pinion assembly uses different size components than Models 8770/8770A, 8870/8870A, and 8970/8970A pinion assemblies.

Tools Required:
Assorted hand tools
Hydraulic press
Portable hydraulic pump and ram
Pinion nut spanner tool FNH #00547
Induction heater or heating oven
Dealer-constructed tools (See “Special Tools” heading for details)
- Pinion rotating tool - 70S005
- Pinion removal plate - 70S013




242

REMOVAL


1. Remove the cab and separate the rear axle housing from the transmission as described in Section 21, Chapter 3.

2. Remove the differential assembly as described in this chapter.




243

3. Remove the hydraulic pump drive as described in Section 35.




244

4. Remove the park brake actuator as described in Section 33, Chapter 2.



245


5. Remove the Four Wheel Drive (FWD) clutch if equipped. Refer to Section 23, Chapter 1.



246


6. Remove the FWD drive gear, 1, if equipped, by removing snap ring, 3, and shims, 2.

NOTE: *FWD gear, 1, is not installed on 2WD models.*




247

7. Slide FWD drive gear, 1, from pinion shaft, 2.




248

8. Straighten lock tabs, 1, on the lock washer.




249

9. Install special tool FNH00547, 1, on jam nut and dealer-made pinion rotating tool #70S005, 2.




250

10. Loosen jam nut.




251

11. Remove jam nut, 2; lock washer, 1; and adjusting nut, 3.




252

12. Place a block of wood in the housing to prevent damage to the housing and pinion gear when it is pressed from the bearings.




253

13. Install the dealer-made pinion removal plate #70S013, 1, on the housing.




254

14. Install a hydraulic ram, 1, between the pinion shaft and pinion removal plate tool, 2.




255

15. Press the pinion shaft from the front bearing.
16. Remove the pinion from the housing.



256


17. Remove the three park brake discs from the housing.



257


NOTE: *Perform steps 18, 19, 20 and 21 as required based on parts condition. Step 20 is required when replacing pinion shaft or rear pinion bearing.*

18. Drive the pinion sleeve, 1, from the housing using a brass drift.




258

19. Drive the front bearing cup, 2, from sleeve, 1, with a brass drift.




259

20. Drive the rear pinion cup and shims, 1, from the housing using a brass drift. Retain the shims for reference or reuse if not damaged.



260


21. Press the rear bearing from the pinion shaft.



261


INSPECTION AND REPAIR

1. Clean all components thoroughly.
2. Inspect the components for wear or damage and replace as required.



262

IMPORTANT: *The ring and pinion gears are a matched set. If the pinion gear is replaced, the matched ring gear must be installed as described in this chapter.*


70-240-2023

263


REASSEMBLY

Reassembly follows the disassembly process in reverse order.

Observe the following during reassembly.

Lubricate the components with specified oil during reassembly.

IMPORTANT: *Use an induction heater or oven to heat the bearings to specified temperature prior to installation. This allows the bearings to be installed with no resistance. Components can be damaged if the bearings are driven on.*


70-240-1412

264


IMPORTANT: *Start at step 1 if <u>any</u> of the following were done:*

- *The rear pinion bearing cup was removed or replaced.*
- *The rear pinion bearing was removed or replaced.*
- *The pinion gear and ring gear were replaced*.
- *The center housing was replaced.*

Start at step 3 if <u>none</u> of the above were done.

1. Determine the pinion depth adjustment shim pack thickness as described in the “Adjustment” portion of this chapter. This will provide the correct engagement of the ring and pinion gears.

IMPORTANT: *Failure to adjust the pinion depth properly will result in improper ring and pinion gear engagement and premature failure of the components. Do not proceed without completing this adjustment.*



70-240-1977

265

2. Install a new rear bearing on the pinion shaft if the bearing was removed or a new pinion is being installed.

   Heat the bearing to 140° C (280° F) then install on the shaft until fully seated.

IMPORTANT: *The bearing must fully bottom on the shaft.*




266

3. Install the correct shim pack, 1, in the housing.


NOTE: *This shim pack will determine the engagement of the ring and pinion gears.*

4. Install the bearing cup using a driver that corresponds to the outside diameter of the cup.




267

5. Install the front bearing cup, 2, in sleeve, 1, if removed. Use a driver that corresponds to the outside diameter of the cup.



268

6. Install sleeve, 1, in the center housing if removed. Use a driver that corresponds to the lip on the sleeve.




269

7. Install park brake discs in the housing if removed.

IMPORTANT: *Install the discs on the pinion shaft so the oil holes in the three discs are staggered. Failure to stagger the holes will result in premature wear of the park brake components.*


IMPORTANT: *The discs should slide freely on the pinion shaft. Correct binding if encountered. Binding will result in premature wear of the park brake components.*



270

8. Install the pinion assembly and hold it in place with a jack and wood blocks.


IMPORTANT: *Ensure that the park brake discs are installed as described in step 7.*



271

9. Heat the front bearing in an oven or induction heater to 140° C (280° F), then install on the shaft until fully seated in the bearing cup.


   Allow the bearing to cool before proceeding.



272

10. Install adjustment nut, 1, hand tight.


NOTE: *The wide side of the nut must contact the bearings.*



273

11. Adjust the pinion bearing preload as described in the “Adjustment” heading in this chapter.


IMPORTANT: *Failure to adjust the pinion bearing preload will result in premature failure of the rear axle components. Do not proceed without completing this adjustment.*



274


12. Adjust ring and pinion gear backlash as described in the “Adjustment” heading in this chapter.

IMPORTANT: *Failure to adjust ring and pinion gear backlash will result in premature failure of rear axle components. Do not proceed without completing this adjustment.*



275

13. Install FWD gear, 1, if equipped.
14. Install shims, 2, as required, to eliminate gear end play with snap ring, 3, installed.
15. Reassemble the tractor components removed to access the pinion assembly.




276

DIFFERENTIAL LOCK SOLENOID

NOTE: *The solenoid can be serviced on the tractor.*


Tools Required:
Assorted hand tools
Torque wrench: 0-135 N·m (0-100 ft lbs)
Ohmmeter



277

REMOVAL


1. Remove the solenoid coil retaining nut, 2, and coil, 1.
2. Unscrew the solenoid body from the housing.



278


INSPECTION AND REPAIR

1. Inspect and replace damaged parts.



279


2. Perform a continuity check on the coil. Resistance should be approximately 9.4 ohms. Replace the coil if defective.



280

3. Install the coil on the solenoid body. When the coil has no voltage, air pressure directed in hole, 1, should exit at holes, 2, but not through holes under screen, 3. Replace the solenoid if defective.
4. With the coil installed on the solenoid body, use a 12-volt supply to energize the coil.

   Air pressure directed in hole, 1, should exit holes, 2, and through holes under screen, 3. Replace the solenoid if defective.




281

REASSEMBLY

Reassembly follows disassembly in reverse.

1. Coat O rings, 3, with petroleum jelly. Install solenoid body, 2, and torque to 27 N·m (20 ft lbs).
2. Install coil, 1, and tighten nut to 7 N·m (5 ft lbs).



282


DIFFERENTIAL LOCK SYSTEM PRESSURE TESTING

INTRODUCTION

(70 Series)

A quick-release coupler, 1, is provided to pressure test the differential lock circuit.


The coupler is located at the rear of the tractor on the PTO housing. The housing is labeled to identify the coupler.



283

(70A Series)

To operate the front axle diff. lock, a new hydraulic line, 1, has been added from the test port on the rear differential, along the left-hand side of tractor, to the front differential. You will use this one test port, 2, to check pressure for both the front and rear differentials.



284

PRE-TEST PREPARATION


NOTE: *70 Series art shown.*

1. Install PD female coupler special tool FNH00535 on all gauge hose ends used for testing.
2. Warm the oil to a minimum of 60° C (140° F).
3. Perform tests with the engine operating at 1900 RPM, then repeat at 1200 RPM.
4. Perform a pressure test on the low pressure regulating circuit by installing a 40 bar (600 PSI) gauge on coupler, 2, located on the transmission valve, 1.


   Pressure should be 16.5 bar -18.9 bar (240 PSI - 275 PSI).

NOTE: *If pressure is out of specification, repair the low-pressure regulating circuit before continuing.*

NOTE: *70A Series art shown.*



285



286

CIRCUIT PRESSURE TEST

This test checks the differential lock apply pressure.

When clutch apply pressure is present, the differential lock is applied.


When apply pressure is not present, the differential lock is not engaged.

Apply pressure should be 16.5 bar - 18.9 bar (240 PSI - 275 PSI) when the diff-lock is activated.

0 bar (0 PSI) when the differential lock is not activated.

Test Procedure

1. Complete pre-test items.
2. Connect a 40 bar (600 PSI) gauge to coupler, 1.
3. Start the engine and operate at 1900 RPM.
4. Record the pressure with the differential lock not activated.
5. Record pressure with the differential lock activated.
6. Repeat steps four and five with the engine at 1200 RPM and compare to the original readings.
7. If pressure is out of specified range, refer to the “Troubleshooting” heading in this chapter.



287

SECTION 31 – POWER TAKE-OFF

Chapter 1 – Mechanical System

CONTENTS

Section	Description	Page
31 000	Specifications	2
	Special Tools	3
	Description of Operation	4
	Introduction	4
	Power Flow - All Models	5
	Engaging and Disengaging the PTO	7
	Troubleshooting and Diagnosis	8
	Disassembly and Repair	9
	PTO Assembly - Removal and Installation	9
	Upper PTO Input Shaft - Removal and Installation	15
	PTO Output Shaft and Driven Gear - Overhaul	30
	PTO Clutch Assembly - Overhaul	39

SPECIFICATIONS

	8670/8670A	8770/8770A, 8870/8870A, 8970/8970A
Type Independent	Independent	Independent
PTO Clutch		
Type	Wet/multi-plate	Wet/multi-plate
Number of friction plates	6	7
Diameter of plates (OD x ID)	148.6 x 114.3 mm (5.85″ x 4.50″)	148.6 x 114.3 mm (5.85″ x 4.50″)
Method of operation	Hydraulic/modulated engagement	Hydraulic/modulated engagement
Modulation time	1.5 - 2.0 seconds	1.5 - 2.0 seconds
Method of Engagement	Electrical solenoid	Electrical solenoid
Output Shafts		
6 spline - 540 RPM	35 mm (1.375″)	
21 spline - 1000 RPM	35 mm (1.375″)	
20 spline - 1000 RPM		44.5 mm (1.75″)
21 spline - 1000 RPM		35 mm (1.375″)
PTO Band Brake	Yes	Yes
Power Take-Off Speed		
PTO speed at rated engine speed (2100 RPM)		
540 RPM shaft	600	N/A
1000 RPM shaft	1100	1100
Engine speed		
540 PTO RPM	1880 RPM	N/A
1000 PTO RPM	1900 RPM	1900
Output ratio (engine speed/PTO speed)		
540	3.478	N/A
1000	1.903	1.903
Direction of rotation		
(view from behind tractor)	Clockwise	Clockwise
PTO Shaft End Play		
PTO upper input shaft end play	0.03 - 1.5 mm (0.001″ - 0.06″)	0.03 - 1.5 mm (0.001″ - 0.06″)

PTO Hydraulic Pressures are listed in Chapter 2 of this section.

Sealers


Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595, OR 596 LOCTITE ULTRA BLUE 587
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)

TIGHTENING TORQUES	N·m	Ft Lbs
PTO assembly to axle center housing	641	475
PTO output shaft retainer	108	80
PTO bottom cover plate	63	47
Drawbar retaining pin cover	60	45
Valve body to housing bolts	24	18
Solenoid body to housing	27	20
Solenoid coil retaining nut	7	5
Solenoid blanking plug (less FWD only)	27	20
Hydraulic pressure supply tube to fitting	47	35
Hydraulic lubrication tube to fitting	24	18
Hydraulic supply fitting to housing	27	20
Hydraulic lubrication fitting to housing	14	10

SPECIAL TOOLS

DESCRIPTION	PART NUMBER	USAGE
PTO assembly lifting tool	FNH00527	Support PTO assembly during removal and installation.
Support for 540 PTO driven gear	FNH00531	Retains and supports 540 PTO gear during removal and installation.
PTO clutch puller	FNH00528	Pulls PTO clutch assembly from the housing.
Seal installation tool	FNH00532	Installs the PTO output shaft seal and rock shaft seals.
PTO clutch piston compressor	FNH01312 FT. 4101 (N775)	Compresses PTO piston return spring.
M20 x 120 fully threaded bolt	NH28RT96	Prevent PTO driven gear from falling into the center housing when the PTO shaft and retainer are removed.

DESCRIPTION OF OPERATION



1


INTRODUCTION

All models are equipped with an independent power take-off (IPTO) which means the PTO is engine driven and can be operated anytime the engine is running.

The PTO is electrohydraulically activated and has automatic feathering for smooth engagement.

Model 8670/8670A tractors are equipped with a 540 and 1000 RPM, two-speed PTO, 2.

Models 8770/8770A, 8870/8870A and 8970/8970A are equipped with a 1000 RPM, single-speed, PTO, 1.



2

POWER FLOW - ALL MODELS

The power to turn the PTO originates at the engine. When the engine is running, the flywheel turns the transmission shaft, 1, at engine speed.

The front of the PTO input shaft, 3, is splined to the transmission shaft through the hydraulic pump drive gear, 2. The rear of the shaft is splined to the PTO assembly input hub, 4.

When the engine is running, the input hub, 4, rotates at engine speed. When the PTO is not engaged, no power is transmitted through the assembly because the PTO clutch pack, 5, is not compressed.

The PTO brake band prevents the PTO housing, 6, and output shaft from turning when the PTO is not activated.


When the PTO is activated, the internally and externally splined clutch discs in the clutch pack are hydraulically engaged. Rotation of the input hub is transferred through the discs to the PTO housing, 6.

Power Flow - Model 8670/8670A Two-Speed PTO

The clutch housing, 1, turns the PTO drive cluster gear, 2, which turns the PTO driven gears, 4 and 5, and the PTO output shaft, 3.

When the 21-splined shaft is installed, splines on the shaft engage with the 1000 RPM gear, 4. The output shaft rotates at 1000 RPM when engine speed is set at 1900 RPM.


When the 6-spline PTO shaft is installed, splines on the shaft engage with the 540 RPM gear, 5. The output shaft rotates at 540 RPM when engine speed is set at 1880 RPM.



3

Power Flow - Models 8770/8770A, 8870/8870A and 8970/8970A

The clutch housing, 1, turns the PTO drive gear, 2, which turns the 1000 RPM driven gear, 3, and the PTO output shaft, 4. The PTO output shaft rotates at 1000 RPM when engine speed is set at 1900 RPM.




4

ENGAGING AND DISENGAGING THE PTO


NOTE: *Figure 5 is for the 70 Series. Figure 6 is for the 70A Series.*

Engage the PTO by depressing center button, 1. Pull up on the knob, 2, to the stop, then release the knob and button.

The PTO status light, 3, will illuminate when the PTO is activated. A status light on the instrument cluster will also illuminate.



5




6

Disengage the PTO by fully depressing then releasing knob, 1.

Refer to Chapter 2 of this section for details on operation of the PTO electrohydraulic control system.

NOTE: *The PTO will automatically disengage if the engine is stopped with the PTO engaged.*



7

TROUBLESHOOTING AND DIAGNOSIS

NOTE: *Refer to the “Troubleshooting” heading in Chapter 2 of this section.*

DISASSEMBLY AND REPAIR

PTO ASSEMBLY - REMOVAL AND INSTALLATION


Introduction
Model 8670/8670A tractors are equipped with a 540/1000 RPM PTO.

NOTE: *The PTO driven gears and PTO output shaft must be removed on this model before the PTO assembly can be removed.*

Models 8770/8770A, 8870/8870A and 8970/8970A tractors use a 1000-speed PTO.

NOTE: *The PTO assembly can be removed on these models without removing the PTO driven gear and output shaft.*

Tools Required:
Torque wrench 675 N·m (500 ft lbs)
PTO assembly lift tool FNH #00527
Specified pipe thread sealant
Lifting crane
30 mm socket
Specified anaerobic sealer
Pinch bar
Assorted hand tools


70-230-1066


8

Removal - Model 8670/8670A

1. Remove the PTO output shaft and driven gears as detailed later in this chapter.
2. Follow the PTO assembly removal procedure for Models 8770/8770A, 8870/8870A and 8970/8970A.


Removal - Models 8770/8770A, 8870/8870A and 8970/8970A

1. Remove the PTO master shield, 1, and top link, 2.



9


2. Remove the top link retaining bracket, 1.



10

3. Disconnect the supply pressure line, 1, and lube pressure line, 2.


NOTE: *Both connectors are O ring sealed. Save the O rings if they are not damaged.*



11


4. Disconnect the electrical connectors for the control solenoids.

NOTE: *Mark the connector halves to be sure they are reconnected properly.*




12

5. Install the PTO lifting tool FNH #00527, 1. Use the center link clevis to attach the tool to the PTO assembly. Attach the lifting tool to a suitable lifting device.
6. Remove the eight retaining bolts, 2.



13

7. Free the PTO assembly from the two locator pins. Swing the PTO clutch to the left to ease removal.
8. Place the PTO assembly on a workbench if it is to be disassembled.



14


Reassembly - Model 8670/8670A

1. Reinstall the PTO assembly as detailed under heading “Reassembly - Models 8770/8770A, 8870/8870A and 8970/8970A” later in this chapter.
2. Also reinstall the PTO output shaft and driven gears as detailed under that heading.

Reassembly - Models 8770/8770A, 8870/8870A and 8970/8970A


Reassembly follows the disassembly procedure in reverse.

1. Thoroughly clean the mating surfaces of the PTO assembly and rear axle housing.
2. Place a bead of specified anaerobic sealer on the rear axle housing as shown.




15

3. Install new O rings, 1. Make sure that the O rings stay in place as the assembly is installed.




16

4. Install the PTO assembly onto the two locator pins. Install the upper six retaining bolts.
5. Apply specified pipe thread sealant to the lower two mounting bolts and install. Torque the retaining bolts in a crossing pattern to 641 N·m (475 ft lbs).



17

6. Install new O rings on the supply tube, 1, and lube line, 2, and tighten.




18

7. Reconnect the electrical connectors as follows:

   Wire RM92 connects to the PTO solenoid.


   Wire RM94 connects to the differential lock solenoid.

   Wire RM96 connects to the four-wheel-drive solenoid.



19


8. Reinstall the center link retaining bracket; center link, 2; and the PTO master shield, 1.




20

9. Connect the tractor to a dynamometer and check the PTO for proper operation.

NOTE: *During testing, pressure gauges should be attached to the PTO test ports as shown and the pressures checked as detailed under the "Pressure Testing" heading in Chapter 2 of this section.*



21




22

UPPER PTO INPUT SHAFT - REMOVAL AND INSTALLATION

The following instructions pertain to removal and installation when the rear axle is installed in the tractor.

Tools Required


Snap ring pliers
Antiseize compound
Models 8770/8770A, 8870/8870A and 8970/8970A only:
Allen wrench set
Gauge block 187 mm (7.36″) long



23

Removal - Model 8670/8670A


1. Remove the PTO assembly as detailed in this chapter.
2. Remove the PTO shaft, 1, from the rear axle center housing.



24

Removal - Models 8770/8770A, 8870/8870A and 8970/8970A

1. Remove the PTO assembly as detailed in this chapter.
2. Remove the park brake assembly as detailed in Section 33.
3. Loosen the setscrews on the lock collar, 4. Access is obtained through the park brake assembly opening.
4. Slide the PTO shaft, 3, from the pump drive gear, 1.
5. Remove the front snap ring, 2, and the lock collar, 4.
6. Remove the PTO shaft from the rear axle center housing, 5.




25

Inspection

1. Inspect the splines on the shaft for damage.
2. Check that the shaft is not bent or twisted.
3. Replace the shaft if damaged.

Installation - Model 8670/8670A


1. Install snap rings, 2 and, 4, on the shaft.
2. Apply antiseize to the front splines.
3. Insert shaft into hydraulic pump drive gear, 1.
4. Install PTO assembly as detailed in this chapter.



26

Installation - Models 8770/8770A, 8870/8870A and 8970/8970A

1. Install the rear snap ring, 6.
2. Apply antiseize to the front splines.
3. Insert the shaft, 3, through the hole, 5, in the center housing.
4. Slide the lock collar, 4, over the shaft and install the front snap ring, 2.
5. Install the shaft into the hydraulic pump drive gear, 1.
6. Place dealer-made gauge block, 7, against the front snap ring. The gauge block should be 187 mm (7.36″) long.
7. Position the lock collar, 4, against the gauge block and tighten the setscrews.
8. Reinstall the park brake assembly.
9. Reinstall the PTO assembly.




27

PTO OUTPUT SHAFT AND DRIVEN GEARS - OVERHAUL - MODEL 8670/8670A

1. Needle bearing
2. Thrust washer
3. Thrust needle bearing
4. 540 RPM driven gear
5. Thrust needle bearing
6. 1000 RPM driven gear
7. Thrust needle bearing
8. Sleeve
9. PTO bearing
10. PTO seal
11. PTO retainer
12. Output shaft
13. Snap ring
14. Snap ring
15. O ring

Tools Required:
Torque wrenches
- 675 N·m (500 ft lbs)
- 135 N·m (100 ft lbs)

Slide puller
Expandable internal jaw puller
Dealer-fabricated end for slide puller
Specified pipe thread sealer
Petroleum jelly
Gear support tool - FNH 00531
Assorted hand tools
M20 x 120 fully threaded bolts (2)
Support rod (1/2″ extension)
Specified RTV silicone sealer


70-230-1082

28

Preparation


1. Thoroughly clean the area of the tractor to be worked on.
2. Drain oil from the rear axle housing as follows:

   Output shaft removal only - drain 38 L (10 gal) of oil.

   Remove PTO driven gears - completely drain rear axle assembly. Approximately (121 L) 32 gal will be drained.

Removal - PTO Output Shaft

1. Remove the PTO master shield, 1, and PTO shaft cover, 2.




70-230-1083

29

2. Remove the original M20 x 60 bolts, 1.
3. Install M20 x 120 fully threaded bolts (special tool #NH28RT96), at 1.

NOTE: *These bolts will contact the 1000 RPM PTO driven gear to support the gear and prevent the gear from moving forward when the PTO shaft and retainer are removed. Use the bolts in conjunction with a support rod or PTO shaft to prevent the gear and thrust bearing from falling.*


Turn the bolts in by hand until they just contact the gear. Do not tighten the bolts because they'll cock the gear and make removal of the shaft difficult.



30

4. Remove the internal snap ring, 3, and PTO shaft, 2. Reinstall the snap ring.
5. Remove the four retaining bolts, 1.
6. Remove the retainer, 4, by installing two of the retainer bolts in the threaded holes, 5. Tighten the bolts to push the retainer from the housing.


NOTE: *If the retainer does not have threaded holes, 5, proceed to step 7.*



31

7. Use a slide puller with a fabricated end to remove the retainer. Install a bolt through the PTO cover and fabricated puller.

NOTE: *The fabricated end consists of a nut that fits the puller with a second nut welded to it.*



32


8. Attach a slide puller with an expandable internal jaw puller to the internal snap ring and remove the PTO bearing assembly.

CAUTION

Place a rod through the bearing assembly and gears and fully insert in the inner needle bearing to prevent the gears and thrust bearings from dropping in the center housing.

9. Remove the support rod and install the PTO shaft to support the driven gears.

NOTE: *Leave the support rod in place if the PTO shaft requires service.*




33

Removal - PTO Driven Gears

If the driven gears do not need service, proceed to "Disassembly - PTO Output Shaft."

If the driven gears are to be removed, proceed as follows:

1. Remove the drawbar pin retaining bolts, 2, and retaining pin, 1. Slide the drawbar from the rear of the tractor.
2. Make sure that the rear axle housing has been drained of all oil.




34

3. Remove the PTO bottom cover plate, 1.


CAUTION

The PTO gears are heavy. Ensure they are supported by an assistant, by a bar, or have the PTO shaft installed to support the gears while removing the cover or when working around the gears.




35

4. Support the 1000 RPM gear, 1, and install special tool, 4, FNH 00531 tight against the 540 RPM gear, 2, to prevent movement while removing the 1000 RPM gear. Adjust bolt, 3, to contact gear, 2.




36

5. Support gear, 2, while an assistant loosens the two long bolts installed to retain the gear.
6. Remove gear, 2, and thrust bearing, 1.




37

7. Support the 540 RPM gear, 1, and remove special tool, 2.



38


8. Remove the 540 RPM gear, 3: thrust bearing, 2; and thrust washer, 1.



39


Disassembly - PTO Output Shaft

1. Remove seal, 2, from retainer, 1.



40

2. Remove snap ring, 1; bearing, 2; and O ring, 3, from the sleeve, 4.




41

Inspection and Repair

1. Wash all parts and dry prior to inspection.
2. Examine the PTO shaft splines for damage.
3. Inspect gears for tooth wear and damage.
4. Examine bearings and thrust washers for wear and damage.
5. Inspect the needle bearing, 1, in the center housing. If the bearing must be replaced, install with the writing on the bearing against the installation tool. Install the bearing flush to 0.250 mm (0.010″) recessed in the housing.
6. Inspect all other components for wear and damage.

   Replace damaged parts prior to reassembly.




42

Reassembly - PTO Driven Shaft

The reassembly process follows the disassembly process in reverse.


1. Install the new PTO seal, 1, in the retainer using seal installing tool, 2, FNH #00532A.

NOTE: *Install the seal with the inscription AIR SIDE facing down during installation.*




43

The seal must be pressed in straight. Press in seal to 0.58 mm (0.200″) as shown. This dimension applies from steel face of seal (rubber base which protrudes slightly beyond steel face) to machined face of casting.



44


2. Install a new O ring, 3, in the sleeve, 4.
3. Install bearing, 2, on the sleeve, 4, and secure with snap ring, 1.



45


Installation - PTO Driven Gear

1. Coat the thrust bearing, 2, and thrust washer, 1, with petroleum jelly and install on the 540 drive gear, 3.




46

2. Install the 540 drive gear, 1, thrust washer and thrust bearing into the rear axle housing. Have an assistant support the gear while special tool, 2, is positioned to hold the gear in place.



47

3. Coat thrust bearing, 1, with petroleum jelly and insert in the 540 drive gear, 2.




48

4. Install 1000 RPM gear, 1. Have an assistant position the two long bolts against the gear to hold it in place.


NOTE: *Install the 1000 RPM gear so the part number faces the front of the tractor.*

5. Temporarily reinstall the PTO shaft to support the gears, 1 and 2.
6. Remove special tool, 4, and support bolt, 3.



49


7. Apply a bead of specified RTV silicone sealer on the cover. Install the PTO cover plate and torque the retaining bolts to 63 N·m (47 ft lbs).
8. Install the drawbar and torque the drawbar pin retaining plate bolts to 60 N·m (45 ft lbs).



50

Installation - PTO Output Shaft


1. Coat thrust bearing, 3, with petroleum jelly and install in bearing assembly, 1. When the shaft is installed, the trust bearing will run against the 1000 RPM drive gear, 2.



51

2. Install the bearing assembly.


NOTE: *During installation, place a support rod through the bearing assembly and gears to prevent the thrust bearing from dropping into the center housing.*



52


3. Put a new gasket on the retainer and install in the axle housing. Torque bolts, 1, to 108 N·m (80 ft lbs).
4. Lubricate the internal O ring, then install PTO shaft, 2, and snap ring, 3.

NOTE: *Installation of the 540 PT shaft can be made easier by aligning all the internal splines. Use the 1000 RPM shaft to align the three sets of splines and insert the 540 shaft. Push down on the end slightly and push it in. The shaft should slide freely until it is deep enough to install the snap ring.*




53

5. Remove the two long threaded bolts (special tool #NH28RT96), 1.
6. Put specified pipe sealant on the threads of the original PTO bolts and install. Torque to 641 N·m (475 ft lbs).




54

7. Reinstall the master PTO shield, 1, and PTO shaft cover, 2.



55


8. Refill the rear axle assembly through filler tube, 1, with specified hydraulic oil to the full mark, 3, on the dipstick, 2.
9. Run the tractor to ensure proper PTO operation.



56

PTO OUTPUT SHAFT AND DRIVEN GEAR - OVERHAUL - MODELS 8770/8770A, 8870/8870A AND 8970/8970A

1 Needle bearing
2 Thrust washer
3 Thrust needle bearing
4 PTO driven gear
5 PTO bearing
6 Snap ring
7 PTO seal
8 PTO retainer
9 Output shaft




57

Tools Required

Torque wrenches
- 675 N·m (500 ft lbs)
- 135 N·m (100 ft lbs)

Slide puller
Dealer-fabricated end for slide puller
Gear puller
Specified pipe thread sealer
M20 x 120 fully threaded bolts (2)
Petroleum jelly
Assorted hand tools
Specified RTV silicone sealer



58

Preparation


1. Thoroughly clean the area of the tractor to be worked on.
2. Drain oil from the rear axle housing as follows:

   Output shaft removal only - drain 38 L (10 gal) of oil.

   Remove PTO driven gear - completely drain rear axle assembly. Approximately 136 L (36 gal) will be drained.

Removal - PTO Output Shaft

1. Remove the PTO master shield, 1, and PTO shaft cover, 2.




59

2. Remove the original M20 x 60 bolts, 1.
3. Install M20 x 120 fully threaded bolts at 1.

NOTE: *These bolts will contact the PTO driven gear to prevent the gear from falling into the center housing when the PTO shaft and retainer are removed.*

Turn the bolts in by hand until they just contact the gear. Do not over tighten the bolts because they will cock the gear and make removal of the shaft difficult.



60


⚠ CAUTION ⚠

Make sure the rear axle oil level is at or below the full mark. Any oil above the full mark will be lost when the retainer is removed.

4. Remove the four retaining bolts, 2.

5. Remove the retainer, 1, by installing two of the retainer bolts, 2, in the threaded holes. Tighten the bolts to push the retainer from the housing.

NOTE: *If the retainer does not have threaded holes at 2, proceed to step 6.*




61

6. Remove the retainer and seal, 1, using a slide puller, 3, with a fabricated end, 2. Install a bolt through the PTO cover and fabricated puller.


NOTE: *The fabricated end consists of a nut that fits the puller with a second nut welded to the first nut.*

NOTE: *The seal can be replaced at this point without further disassembly. Refer to "Reassembly - PTO Driven Shaft" later in this chapter for installation instructions.*



62

7. Use a slide puller and bearing puller to remove the PTO shaft.




63

Removal - PTO Driven Gear

If the driven gear does not need service, proceed to "Disassembly - PTO Output Shaft" later in this chapter.


If the driven gear is to be removed, proceed as follows:

1. Remove the drawbar pin retaining bolts, 2, and retaining pin, 1. Slide the drawbar from the rear of the tractor.
2. Make sure that the rear axle housing has been drained of all oil.




64

3. Remove the PTO bottom cover plate, 1.




65

4. Support the PTO driven gear while an assistant loosens the two long bolts, 1, installed to retain the gear.



66


5. Remove gear, 1; thrust bearing, 2; and thrust washer, 3.



67


Disassembly - PTO Output Shaft

1. Remove PTO seal, 2, from the retainer, 1.



68

2. Remove snap ring, 1, and press or pull bearing, 2, from the shaft, 3.




69

Inspection and Repair

1. Wash all parts and dry prior to inspection.
2. Examine the PTO shaft splines for damage.
3. Inspect the gears for tooth wear and damage.
4. Examine the bearings and thrust washer for wear and damage.
5. Inspect the needle bearing, 1, in the center housing. If the bearing must be replaced, install with the writing on the bearing against the installation tool. Install the bearing flush to 0.250 mm (0.010″) recessed in the housing.
6. Inspect all other components for wear and damage.

   Replace damaged parts prior to reassembly.




70

Reassembly - PTO Driven Shaft
The reassembly process follows the disassembly process in reverse.


1. Install new PTO seal, 1, in the retainer using FNH #00532A seal installing tool, 2.

NOTE: *Install the seal with the inscription AIR SIDE facing down during installation.*




71

The seal must be pressed in straight. Press in seal to 0.58 mm (0.200″) as shown. This dimension applies from steel face of seal (rubber base which protrudes slightly beyond steel face) to machined face of casting.



72


2. Press bearing, 2, on the output shaft, 3, and secure with snap ring, 1.



73

Installation - PTO Driven Gear


1. Coat the thrust bearing, 2, and thrust washer, 3, with petroleum jelly, and install onto the driven gear, 1.



74


2. Install gear, thrust washer and thrust bearing into the rear axle housing. Have an assistant install the long threaded retaining bolts, 1, to hold the gear in place.

NOTE: *Install the gear with the long neck facing the front of the tractor.*



75


3. Place a bead of specified RTV silicone sealer on the cover. Install the PTO cover plate, 1, and torque the retaining bolts to 63 N·m (47 ft lbs).



76


Installation - PTO Output Shaft

1. Install the output shaft assembly.




77

2. Put a new gasket on the retainer. Install the retainer in the axle housing. Torque bolts, 2, to 108 N·m (80 ft lbs).
3. Remove the two long threaded bolts, 1.




78

4. Put specified pipe sealant on the threads of the original PTO bolts and install. Torque to 641 N·m (475 ft lbs).




79

5. Reinstall the master PTO shield, 1, and PTO shaft cover, 2.



80

6. Refill the rear axle assembly through filter, 1, with specified hydraulic oil to the full mark, 3, on the dipstick, 2.
7. Run the tractor to ensure proper PTO operation.



81


PTO CLUTCH ASSEMBLY - OVERHAUL

The overhaul procedure for the Model 8670/8670A two-speed PTO is the same as the procedure for the Models 8770/8770A, 8870/8870A and 8970/8970A single-speed PTO. Where components differ, the procedure will be identified with the appropriate model number.

NOTE: *If only the clutch friction discs and separation plates are to be serviced, refer to the appropriate steps for their removal and installation.*

Tools Required

Assorted hand tools
Vise grip pliers
Internal snap ring pliers
Clutch spring compressor FN01312, FT 4101 (N775)
PTO clutch hub puller FNH 00528
Specified thread-locking compound
Hydraulic press
Bearing remover
Puller




82

Disassembly


1. Mark the location of the PTO solenoid, 1; differential lock solenoid, 2; and, if equipped, four-wheel-drive solenoid, 3.
2. Remove the solenoids, test fittings, and pressure fittings.

NOTE: *For detailed information, see "PTO Solenoid" heading in Chapter 2 of this section.*




83

3. Remove the control valve, 1, from the housing by removing the four retaining bolts.
4. Slide the control valve and brake band, 2, from the clutch housing, 3.



84


5. Remove the snap ring, 1, from the housing.



85

6. Remove the hub, 4; end plate, 3; clutch friction discs, 2; and clutch separator plates, 1.


NOTE: *Model 8670/8670A uses six discs and plates. Models 8770/8770A, 8870/8870A and 8970/8970A use seven discs and plates.*



86


7. Remove the thrust washer, 1, from the housing if the washer is damaged or worn.

NOTE: *The thrust washer must be pried from the housing because adhesive is used to keep it in position. Removing the washer may damage it.*




87

8. Compress snap ring, 1, and raise it upward to release the bearing.



88


9. Remove clutch hub, 3, and the shaft assembly from the housing. Remove using FNH #00528 clutch hub puller, 2, on puller, 1.



89

10. **Model 8670/8670A only**:


    Remove the cluster gear, 1, from the housing.



90

11. **Models 8770/8770A, 8870/8870A, 8970/8970A only**:


    Remove the drive gear, 1, from the housing.



91


12. Remove the bearing, 1, and baffle, 2, from the housing.

NOTE: *The bearing will slide in and out of the housing by hand.*




92

13. Remove the pressure connector, 1, using a small slide puller and M6 threaded bolt.




93

14. Place the clutch hub assembly in a press. Use FNH01312 (N775) (Churchill FT. 4101) spring compressor tool, 2, to compress the PTO piston return spring. Remove the snap ring, 1, then slowly release pressure on the spring.




94

15. Remove the snap ring, 4; spring seat, 3; spring, 2; and piston, 1, from the housing.



95

NOTE: *Low pressure compressed air injected through the center passage in the rear of the clutch housing shaft will force the piston from the housing.*




96

16. Remove snap ring, 1. Use a suitable puller to remove the bearing, 2, from the shaft. Remove snap ring, 3.

NOTE: *Place a piece of flat steel on the end of the shaft to protect the sealing surface.*


NOTE: *Inspect the sealing surface inside the bore, 4. Replace if the sealing surface is damaged.*



97


Inspection and Repair

1. Check the clutch discs and plates for warpage. Replace if warped. Minimum thickness for the friction plates is 2.69 mm (.105″). Minimum thickness for the steel plates is 2.43 mm (.095″).
2. Wash all components thoroughly in a suitable cleaning solvent and dry before inspection.
3. Inspect all components for wear and damage.
4. Replace piston O ring seals, 1 and 2.




98

5. Replace connector seal, 1.



99

6. Inspect needle bearing, 1. If replacement is necessary, install a new bearing with the writing on the bearing facing out. Install the bearing flush to 0.250 mm (0.010″) below flush with the hub.




100

Reassembly
Reassembly follows the disassembly procedures in reverse.


Observe the following during reassembly:

1. Coat all O rings with petroleum jelly, then install piston, 1, in the housing.
2. Position spring, 2; spring seat, 3; and snap ring, 4, in place.




101

3. Compress the PTO piston return spring using spring compressor tool, 2, then install the snap ring, 1. Slowly release the press to put pressure against the snap ring.




102

4. Install snap ring, 3, press bearing, 2, on the shaft, and secure with snap ring, 1.



103

5. Install pressure connector, 1, and seat in the housing using a brass drift. Apply petroleum jelly to the seal area.




104

6. Coat the lower side of the baffle, 1, with petroleum jelly and install the baffle, ensuring it is fully seated against the bottom of the housing.

NOTE: *The baffle must be properly installed or the clutch pressure lube oil will escape through the bearing and not be directed to the clutch plates.*

7. Install the bearing, 2, making sure it is seated against the shoulder in the housing.


IMPORTANT: *If the baffle or bearing is not fully seated, the snap ring will not fit in the groove in step 12.*



105

8. **Model 8670/8670A only**:


   Install cluster gear, 1, as shown.



106


9. **Models 8770/8770A, 8870/8870A, 8970/8970A only**:

   Install drive gear, 1, with raised lip facing up.



107


10. Insert clutch hub through gear, lower bearing and onto the pressure connector.



108

11. Use a press or mallet to fully seat the bearing in the housing.
12. Install snap ring, 1.


NOTE: *If the snap ring cannot be inserted in the groove, disassemble and repeat steps 6 through 11.*



109


13. Place three drops of specified thread-locking compound on the hub, then install thrust washer, 1. Allow the adhesive to set up for ten minutes before continuing assembly.

NOTE: *Check the clutch discs and plates for warpage. Replace if warped. Minimum thickness for the friction plates is 2.69 mm (.105″). Minimum thickness for the steel plates is 2.43 mm (.095″). Soak the clutch discs and plates in specified oil for ten minutes while waiting for the adhesive to dry.*



110


14. Install a metal separator plate, 1, in the base of the housing.



111


15. Install the remaining friction discs and plates on the hub, 1.

NOTE: *Model 8670/8670A uses six discs and plates. Models 8770/8770A, 8870/8870A and 8970/8970A use seven discs and plates.*




112

16. Insert clutch discs and hub into clutch housing.
17. Install end plate, 2, and snap ring, 1.



113

18. Slide brake band, 2, over clutch housing, 3, and attach control valve, 1, with four bolts. Torque the bolts to 24 N·m (18 ft lbs).
19. Adjust brake band tension as detailed in “Adjustments” in Chapter 2 of this section.




114

20. Install PTO solenoid, 1, differential lock solenoid, 2, and, if equipped, four-wheel- drive solenoid, 3, in their original positions.

NOTE: *Torque solenoid body to 27 N·m (20 ft lbs). Torque solenoid retaining nut to 7 N·m (5 ft lbs).*

21. Install pressure and test fittings and torque to 27 N·m (20 ft lbs).



115

SECTION 31 – POWER TAKE-OFF

Chapter 2 – Electro-hydraulic System

CONTENTS

Section	Description	Page
31 000	Specifications	2
	Special Tools	3
	Description of Operation	4
	Introduction	4
	Engaging and Disengaging the PTO	5
	PTO Hydraulic System Operation	6
	PTO Control Valve Operation	8
	Lubrication Oil	12
	PTO Electrical System Operation	14
	Troubleshooting	22
	PTO will not Engage	23
	PTO will not Disengage	25
	PTO Clutch Slips Under Load	30
	PTO Shaft Continually Turns Slowly with Engine Running when PTO is Turned Off	32
	PTO Retaining Ring is Difficult to Replace	33
	Adjustments	34
	PTO Clutch Brake Band	34
	Disassembly and Repair	35
	PTO Solenoid	35
	PTO Control Valve Assembly	38
	PTO System Pressure Testing	44
	Introduction	44
	Pre-test Preparation	44
	Pilot Oil Circuit Pressure Test	45
	Clutch Apply Circuit Pressure Test	46
	PTO Lubrication Circuit Pressure Test	47

SPECIFICATIONS

Electrical System	
Operating voltage at coil	12 volts
Coil resistance	7.6 ohms
Solenoid type	Normally open
PTO Hydraulic System Testing	
Preparation	
Hydraulic oil	ESN-M2C 134-D
Oil temperature	60° ± 3° C (140° F ± 6° F)
Engine speed	1900 RPM
PTO Disengaged	
Pilot oil pressure	12.5 - 15.3 bar (180 - 220 PSI)
Clutch apply oil pressure	0 bar (0 PSI)
PTO Engaged	
Pilot oil pressure	0 bar (0 PSI)
Clutch apply oil pressure	16.5 - 18.9 bar (240 - 275 PSI)
PTO Lubrication pressure	
Pressure	1.4 - 3.5 bar (20 - 50 PSI)
Flow	7.4 - 11.4 L/min (2 - 3 GPM)
Regulating Valve Locations	
PTO pilot, brake apply, clutch apply circuits	Transmission-Clutch pressure regulating valve.
PTO lubrication circuit	Transmission lubrication relief valve.

Sealers

Anaerobic sealer	LOCTITE GASKET ELIMINATOR 518
RTV silicone sealer	LOCTITE SUPERFLEX 593, 595, OR 596 LOCTITE ULTRA BLUE 587
Pipe sealant	PST 592 PIPE SEALANT WITH TEFLON
Thread-locking compound	LOCTITE 271 THREADLOCKER/SEALANT (red)

TIGHTENING TORQUES	N·m	Ft Lbs
Valve body to housing bolts	24	18
Solenoid body to housing	27	20
Solenoid coil nut	7	5
Solenoid blanking plug (FWD only)	27	20
PTO valve spool end cap	22	15
PTO valve control orifice	22	15
	N·m	**In. Lbs.**
Brake band adjusting screw (specified torque, then loosen 2-1/2 turns)	1.1	10
Brake band adjusting screw jam nut	3.8	35
PTO valve control orifice cap	5.5	50

SPECIAL TOOLS

DESCRIPTION	PART NUMBER	USAGE
PD female coupler	FNH00535	Attaches gauge hose to male PD coupler.
PTO lubrication test fitting	FNH00548	Allows installation of a gauge in the PTO lubrication circuit.
PD male coupler	FNH00533	Attach to FNH00548 to check PTO lubrication circuit pressure.

DESCRIPTION OF OPERATION

INTRODUCTION


NOTE: *See Chapter 1 in this section for information on mechanical operation and power flow.*

All models are equipped with an independent power take-off (IPTO) which means the PTO is engine driven and can be operated any time the engine is running. An automatic feathering feature provides smooth engagement when the PTO is activated.


PTO engagement and disengagement is controlled electrohydraulically.

NOTE: *Figure 1 is for the 70 Series. Figure 2 is for the 70A Series.*

A switch, 1, on the right-hand console controls the electrical circuit.



1




2

The PTO switch controls current flow to the PTO solenoid, 1, on the outside of the PTO housing. Energizing and de-energizing the solenoid controls oil flow through the PTO valve, 2. The valve is attached to the PTO housing but is located inside the rear axle housing.

When the solenoid is not energized, oil flow through the valve applies the PTO brake while exhausting the PTO clutch.

When the solenoid is energized, oil flow through the valve applies the PTO clutch while exhausting the PTO brake.

The electrical and hydraulic circuits are covered in detail in this section. Locate the appropriate heading for additional information.




3

ENGAGING AND DISENGAGING THE PTO

Engage the PTO by depressing the green center button, 1. Pull up on knob, 2, to the stop, then release the knob and button.


PTO status light, 3, on the console and the PTO status light on the instrument cluster will illuminate when the PTO is activated.



4

Disengage the PTO by fully depressing, then releasing, knob, 1.

NOTE: *The PTO will automatically disengage if the engine is stopped with the PTO engaged.*



5

PTO HYDRAULIC SYSTEM OPERATION


Oil to operate the PTO is regulated between 16.5 - 18.9 bar (240 - 275 PSI). The pressure is regulated by the low-pressure regulating valve located in the transmission control valve.

Regulated oil enters the PTO housing at 2.

Regulated oil flow is directed to the PTO valve, 3, by the PTO solenoid, 1.

When the solenoid is not energized, oil flow through the valve engages the PTO brake, and oil vents from the PTO clutch pack.


When the solenoid is energized, oil flow through the valve, engages the PTO clutch pack and vents oil from the PTO brake.



6

PTO lubrication oil is supplied at 1.

PTO lubrication fluid pressure is regulated between 1.4 bar and 3.5 bar (20 PSI and 50 PSI) by the transmission lubrication circuit relief valve located in the transmission.



7

This Page Intentionally Left Blank

PTO CONTROL VALVE OPERATION

The PTO control valve directs oil flow to the PTO brake, or the PTO clutch, by moving the valve spool, 12. The valve is also equipped with a feathering piston, 15, that controls automatic feathering upon engagement of the PTO clutch.

The PTO valve operates in one of the three following modes:

- PTO disengaged
- PTO feathering
- PTO engaged

Operational details and oil flow for each of the modes are provided under the corresponding heading.

PTO Disengaged Mode

When the PTO is disengaged, the PTO solenoid coil, 4, is not energized, so the PTO solenoid poppet, 8, is off its seat.


Regulated pressure oil enters the PTO housing at connector, 5. Some of the oil passes between the solenoid poppet and seat and fills the pilot oil pressure passage, 7.

The pilot oil fills the cavity between the valve cap, 11, and the valve spool, 12. The oil forces the valve spool away from the cap and against the valve sleeve, 1. Some of the pilot oil is allowed to vent to sump through vent hole, 10. This lowers pilot oil pressure to 12.4 - 15.2 bar (180 - 220 PSI).

With the spool against the sleeve, regulated oil passes around the outside of the solenoid and into the low-pressure apply passage line, 2.

This oil passes through the sleeve, 1, and the passage in the spool, and is directed by the main spool to the PTO brake piston, 27, which applies the brake.

With the spool positioned against the sleeve, the PTO clutch piston, 22, is vented to sump through oil passage, 14, and vent passage, 9.



8

PTO Disengaged

1. Sleeve
2. Apply oil
3. PTO brake vent
4. Solenoid coil
5. Regulated low-pressure oil supply
6. Pilot pressure test port
7. Pilot oil
8. Solenoid poppet
9. Clutch vent
10. Pilot oil vent
11. End cap
12. Spool
13. Clutch pressure testport
14. Clutch oil passage
15. Feathering piston
16. Feathering orifice
17. Brake band
18. PTO gear
19. Connector
20. Lubrication oil
21. Piston return spring
22. Clutch piston
23. Clutch discs
24. Hub
25. PTO input shaft
26. Brake band actuator
27. PTO brake piston
28. Feathering bleed hole
29. Feathering spacer
30. Feathering spring
31. Brake oil passage

PTO Feathering Mode
When the PTO is engaged, the PTO solenoid, 4, is energized forcing the poppet, 8, against the seat.

Regulated oil, 5, is blocked from entering the pilot pressure passage, 7. Pilot pressure is vented to sump through vent, 10.

Regulated oil passes around the outside of the solenoid housing and enters the apply passage, 2. This oil acts on the left side of the spool, 12, forcing the spool to the right against the end cap, 11.

With the spool fully to the right, regulated apply oil, 2, passes through the small passage in the center of the spool and is directed into the clutch oil passage, 14.

This oil acts against the feathering piston, 15, and forces it to the left against the spring, 30. As the feathering piston moves to the left, it accepts a volume of oil, which reduces the pressure at the PTO piston allowing the piston to gradually engage which feathers the clutch pack engagement.

As the feathering piston is compressed against the spring, pressure gradually rises in the clutch oil passage circuit.

The feathering rate is controlled by bleeding oil through the feathering orifice, 16, back to sump through the feathering bleed hole, 28.


Feathering continues until the feathering piston, 15, travels far enough to the left to block the feathering bleed hole, 28.

NOTE: *The feathering mode lasts for approximately 2-1/2 seconds. During feathering, system pressure will rise from 0 bar (0 PSI) to approximately 5.5 bar (80 PSI).*

As soon as the PTO solenoid is activated and the spool is moved to the right, feathering begins and the PTO brake is vented to sump through passage, 31, and bleed hole, 3. This releases the brake band so the PTO can turn freely.

Action	Time of Action - Seconds -	Total Time - Seconds -	Clutch Pressure bar (PSI)
Operator actuates PTO	0	0	0 (0)
Electronic delay	0.5	0.5	0 (0)
Feathering	2.5	3.0	Rises from 0 (0) to 5.5 (80)
Full PTO engagement	0.5	3.5	Rises from 5.5 (80) to Regulated Pressure*

*Regulated Pressure is 16.5 - 18.9 bar (240 - 275 PSI)



9

PTO Feathering

1. Sleeve
2. Apply oil
3. PTO brake vent
4. Solenoid coil
5. Regulated low-pressure oil supply
6. Pilot pressure test port
7. Pilot oil
8. Solenoid poppet
9. Clutch vent
10. Pilot oil vent
11. End cap
12. Spool
13. Clutch pressure testport
14. Clutch oil passage
15. Feathering piston
16. Feathering orifice
17. Brake band
18. PTO gear
19. Connector
20. Lubrication oil
21. Piston return spring
22. Clutch piston
23. Clutch discs
24. Hub
25. PTO input shaft
26. Brake band actuator
27. PTO brake piston
28. Feathering bleed hole
29. Feathering spacer
30. Feathering spring
31. Brake oil passage

PTO Engaged Mode
Oil flow for the PTO engaged mode is the same as the PTO feathering mode.

With the solenoid activated, the solenoid poppet, 8, prevents oil from entering the pilot pressure passage, 7, allowing the passage to vent to sump through bleed hole, 10.

Regulated oil passes around the solenoid body int o the supply passage, 2. This oil acts on the left side of the spool, forcing the spool fully to the right against the end cap, 11.

With the spool fully to the right, regulated oil passes through the passage in the spool to the clutch oil passage, 14.


The PTO clutch is fully engaged when the feathering piston, 15, blocks off the feathering bleed passage, 28. With the bleed passage covered, oil cannot bleed through the feathering orifice, 16, and the feathering piston is forced against the feathering spacer, 29.

When the feathering piston can no longer accept any volume of oil, the PTO piston, 22, fully compresses the PTO clutch discs, 23, and the clutch applied circuit stabilizes at regulated pressure of 16.5 - 18.9 bar (240 - 275 PSI).

With the valve spool fully to the right, the brake system is vented through passage, 31, and bleed vent hole, 3.

LUBRICATION OIL

Lubrication oil is supplied to the PTO clutch, via the lube oil passage, 20. Lubrication oil is routed through a hole in the PTO shaft to the PTO clutch pack and clutch hub bushings.



10

PTO Engaged

1. Sleeve
2. Apply oil
3. PTO brake vent
4. Solenoid coil
5. Regulated low-pressure oil supply
6. Pilot pressure test port
7. Pilot oil
8. Solenoid poppet
9. Clutch vent
10. Pilot oil vent
11. End cap
12. Spool
13. Clutch pressure testport
14. Clutch oil passage
15. Feathering piston
16. Feathering orifice
17. Brake band
18. PTO gear
19. Connector
20. Lubrication oil
21. Piston return spring
22. Clutch piston
23. Clutch discs
24. Hub
25. PTO input shaft
26. Brake band actuator
27. PTO brake piston
28. Feathering bleed hole
29. Feathering spacer
30. Feathering spring
31. Brake oil passage

PTO ELECTRICAL SYSTEM OPERATION

The electrical system controls PTO operation through electrical circuits that use a PTO control switch, relays, control modules and a solenoid.

The following electrical system circuits control PTO operation when the engine is running. The circuits are arranged in the order they normally occur.


- PTO off
- PTO start-up
- PTO running
- PTO shutdown

Circuit operation details are provided under the corresponding heading.

PTO Off Circuit

When the PTO is not activated, the PTO switch is in the neutral position and PTO switch contacts A and B are open. Current from the 5-amp Right-Hand Control fuse (MDP-21) stops at the switch so the PTO Relay (MDP-5) is not activated.

When the PTO Relay is not activated, there is no current flow from the 15-amp Trans/PTO fuse (MDP-20).



70-580-1482

11

PTO Off Circuit

PTO Start-Up Circuit


When the operator activates the PTO by pulling up on the PTO switch to the engage position, a bar in the switch completes the circuit between switch contacts A and B. This allows current from the 5-amp Right-Hand Control fuse (MDP-21) to pass through the switch to Splice-B. At the splice some current travels on wires RH84 and CM84 to activate the coil of the PTO relay (MDP-5). Some current travels on wire RH31 to the Right-Hand Control (RHC) to signal the RHC to activate the two PTO status lamps.

With the PTO relay (MDP-5) activated, relay contacts, 87 and 30, are connected so current from the 15-amp Trans/PTO fuse (MDP-20) flows through the relay.

As current passes through the relay some flows through wires CM85 to RH85. This current passes through the PTO switch on the connecting bar for the lower contacts, C and D. At Splice-B some current travels to the coil of the PTO relay to keep it activated. Some current travels to the Right-Hand Control (RHC) to signal the RHC to activate the two PTO status lamps.

Another path for current passing through PTO relay contacts, 87 and 30, is on wire CM86 to the Chassis Control Module (CCM). This current signals the CCM to power the PTO solenoid.

NOTE: *The CCM must receive a signal from the engine speed sensor before the PTO solenoid receives power.*



12


PTO Start-Up Circuit

PTO Running Circuit

When the PTO control switch is released from the start-up position, the switch returns to the neutral position opening contacts, A and B.

Current to keep the coil of the PTO Relay (MDP-5) activated comes from the 15-amp Trans/PTO fuse (MDP-20) through the lower contacts, C and D, of the PTO switch.

Current flow for keeping the PTO Relay coil activated, and PTO solenoid powered are the same as described under the “Start-Up Circuit” heading.



70-580-1484


13

PTO Running Circuit

PTO Shutdown Circuit

When the PTO switch is depressed to the disengage position, both sets of contacts in the PTO switch open interrupting current flow to the PTO Relay coil. Contacts, 87 and 30, in the PTO Relay open disconnecting current from the 15-amp Trans/PTO fuse. This stops the current flow to the PTO solenoid and the PTO disengages.

For additional PTO electrical circuit information, refer to the “Electrical Schematic” in Section 55, Chapter 6.



14

PTO Shutdown Circuit

TROUBLESHOOTING

PTO WILL NOT ENGAGE

Perform the following preliminary steps before proceeding to the troubleshooting chart:

1. Check the following systems for proper operation:
   - Transmission
   - Differential lock
   - FWD (if equipped)

NOTE: *If all systems do not operate, check for a common current supply problem, then check the low-pressure hydraulic circuit, as detailed in the following chart.*

NOTE: *If only the transmission and PTO do not operate, check the transmission electrical supply circuit before proceeding.*

2. Verify the PTO system will not engage. Proceed if the system is not working properly.
3. Check that engine RPM is displayed on the Electronic Instrument Cluster (EIC). Repair engine RPM circuit if it is not displayed.


NOTE: *An engine RPM signal must be present for the PTO system to engage.*

4. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.


NOTE: *Proceed to step 5 if current fault codes exist. Proceed to step 6 if no current fault codes exist.*

5. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
6. Perform an inspection of the PTO system and correct loose or damaged electrical wires, connectors, or hydraulic components.
7. Proceed to the following troubleshooting chart.

PTO WILL NOT ENGAGE
Electrical Circuit Troubleshooting




PTO WILL NOT ENGAGE
(Continued From Previous Page)



PTO WILL NOT ENGAGE
Hydraulic Circuit Troubleshooting

NOTE: Complete electrical troubleshooting before starting hydraulic testing.



PTO WILL NOT DISENGAGE


Perform the following preliminary steps before proceeding to the troubleshooting chart:

1. Verify the PTO system will not disengage. Proceed if the system is not working properly.
2. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.

NOTE: *Proceed to step 3, if current fault codes exist. Proceed to step 4, if no current fault codes exist.*


3. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
4. Perform an inspection of the PTO system and correct loose or damaged electrical wires, connectors, or hydraulic components.
5. Proceed to the troubleshooting chart.

PTO WILL NOT DISENGAGE
Electrical Circuit Troubleshooting



PTO WILL NOT DISENGAGE
Hydraulic Circuit Troubleshooting

NOTE: Complete electrical troubleshooting before starting hydraulic testing.



PTO CLUTCH SLIPS UNDER LOAD

Perform the following preliminary steps before proceeding to the troubleshooting chart:

1. Check the following systems for proper operation:
   - Transmission
   - Differential lock
   - FWD (if equipped)

NOTE: *If all systems do not operate, check the low-pressure supply hydraulic system.*

2. Verify the PTO system is not operating properly. Proceed if the system is not working properly.
3. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.


NOTE: *Proceed to step 4 if current fault codes exist. Proceed to step 5 if no current fault codes exist.*

4. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
5. Perform an inspection of the PTO system and correct loose, or damaged electrical wires, connectors, or hydraulic components.
6. Proceed to the troubleshooting chart.

NOTE: *When performing hydraulic system testing, perform the low-pressure system test first, and adjust pressure as required. Compare pressures taken at 1900 ERPM to those taken at 1200 ERPM. A large difference in the readings indicates leakage in the system.*

PTO CLUTCH SLIPS UNDER LOAD

NOTE: Complete preliminary steps before proceeding.



PTO SHAFT CONTINUALLY TURNS SLOWLY WITH ENGINE RUNNING WHEN PTO IS TURNED OFF

Perform the following preliminary steps before proceeding to the troubleshooting chart:


1. Verify the PTO continually turns. Proceed if the system is not working properly.
2. Retrieve current fault codes from Mode 1. Refer to Section 55, Chapter 1 for details on retrieving current fault codes.


NOTE: *Proceed to step 3 if current fault codes exist. Proceed to step 4 if no current fault codes exist.*

3. Correct fault codes using the diagnostic charts in Section 55, Chapter 2.
4. Perform an inspection of the PTO system and correct loose, or damaged, electrical wires, connectors, or hydraulic components.
5. Proceed to the troubleshooting chart.

PTO SHAFT CONTINUALLY TURNS SLOWLY WITH ENGINE RUNNING WHEN PTO IS TURNED OFF

NOTE: Complete preliminary steps before proceeding.





15

PTO RETAINING RING IS DIFFICULT TO REPLACE

A change was made to the PTO shaft sleeve, 1, on Model 8670 tractors. The change resulted in the retaining ring groove being relocated closer to the outboard side of the retainer. Due to this change, the PTO shaft retaining ring, 2, may seat more easily in the groove.


If it is difficult to replace the retaining ring, 2, on some tractors, it may be necessary to replace the PTO shaft sleeve to ease installation.

ADJUSTMENTS

PTO CLUTCH BRAKE BAND

Adjust brake band after servicing the PTO assembly or replacing the brake band.

1. Loosen jam nut, 1.
2. Tighten adjuster screw, 2, to tighten brake band until screw torque is 1.1 N·m (10 in. lbs.).
3. Loosen adjuster screw by 2-1/2 turns.
4. Secure screw, 2, to jam nut, 1, with a drop of specified thread-locking compound.
5. Torque jam nut to 3.8 N·m (35 in. lbs.).




16

6. Ensure clutch housing, 2, turns freely in the brake band, 1.

NOTE: *Reshape brake band with a mallet if drag is observed.*

7. Repeat steps 1 through 6 if brake band drag was encountered in step 6.




17

DISASSEMBLY AND REPAIR

PTO SOLENOID

NOTE: *The solenoid can be serviced with the PTO assembly in the tractor.*


Tools required
Assorted hand tools
Torque wrench - 0-135 N·m (0 - 100 ft lbs)
Ohmmeter



18


Removal

1. Remove solenoid coil retaining nut, 2, and coil, 1.



19


2. Unscrew solenoid body, 1, from the housing.



20


Inspection and Repair

1. Inspect and replace damaged parts.



21


2. Perform a continuity check on the coil. Resistance should be approximately 7.6 ohms. Replace coil if defective.



22

3. Install coil on solenoid body. When coil has no voltage, air pressure directed in hole, 1, should exit at hole, 2. Replace solenoid if defective.
4. With coil installed on the solenoid body, use a 12-volt supply to energize the coil.


   Air pressure directed in hole, 1, should not exit hole, 2. Replace solenoid if defective.




23

Reassembly
Reassembly follows disassembly in reverse.

1. Coat 0 rings, 3, with petroleum jelly. Install solenoid body, 2, and torque to 27 N·m (20 ft lbs).
2. Install coil, 1, and tighten nut to 7 N·m (5 ft lbs).



24




25

1. End cap
2. Control spool
3. Valve body
4. Brake piston assembly
5. Feathering piston
6. Sleeve
7. Spacer
8. Snap ring
9. Spring
10. Plug

PTO CONTROL VALVE ASSEMBLY

The same control valve is used on all models.


Tools Required:
Assorted hand tools
Snap ring pliers
Phillips head socket
Torque wrench - 0 - 6 N·m (0 - 50 in. lbs.)
Torque wrench - 0 - 68 N·m (0 - 50 ft lbs)



26


Removal

1. Remove four retaining bolts.



27

2. Slide control valve, 1, and brake band, 3, from clutch housing, 2.




28

Disassembly

1. Remove pin, 6, then remove brake band, 1, and actuator arm, 7.


NOTE: *Perform step 2 if the brake band is to be replaced.*

2. Loosen jam nut, 3, then remove bolt, 4. Remove pins, 2 and 5, to release brake band.



29


3. Remove end cap, 1, and spool, 2.



30


4. Remove cap, 1, and control orifice, 2.

NOTE: *It may be necessary to apply heat to the valve body to aid removal of the end cap and orifice. Do not use excessive heat or the valve body may be damaged.*




31

5. Remove cotter pin, 1.
6. Thread a 10-32 machine screw into plug, 2, then remove the plug.




32

7. Remove accumulator assembly snap ring, 5; washer, 4; spring, 3; spacer, 2; and piston, 1, from the valve body.



33


8. Remove brake valve assembly snap ring, 5; sleeve, 4; spring, 3; and piston, 2, from brake valve bore, 1.



34

Inspection and Repair

1. Thoroughly clean all components in a suitable solvent. Be sure to clean the filter screen, 1, located inside passage, 2.
2. Inspect parts for damage. The valve should be replaced if the spool or valve body is damaged.
3. Replace all O rings.



35


Reassembly
Reassembly follows the disassembly procedure in reverse.

Observe the following during reassembly:


1. Coat O rings 3, 6, and 9, with petroleum jelly during assembly.
2. Coat valve spool, 8; brake piston, 2; and accumulator piston, 1, with specified oil during assembly.
3. Torque end cap, 7, to 22 N·m (15 ft lbs).
4. Torque control orifice, 4, to 22 N·m (15 ft lbs) and cap, 5, to 5.5 N·m (50 in. lbs.).
5. Install brake assembly if removed from actuator arm.

NOTE: *Soak a new brake band in specified oil for ten minutes before installation.*

6. Insert pin, 1, as shown.




36




37

Installation
1. Slide brake band and control valve over clutch housing.
2. Torque four retaining bolts to 24 N·m (18 ft lbs).



38

3. Adjust brake band, 1, as previously detailed under “Adjustment” heading in this chapter.



39

PTO SYSTEM PRESSURE TESTING


INTRODUCTION

Quick-release coupler, 1, is provided to pressure test the PTO pilot circuit. Quick-release coupler, 2, is provided to test the clutch apply circuit.

The couplers are located at the rear of the tractor on the PTO housing. The housing is labeled to identify the couplers.

Special Tool FNH00548 can be installed in place of connector, 3, to test the PTO lubrication circuit.

NOTE: *Before proceeding, review the information under the "PTO Control Valve Operation" heading in this chapter.*



40


PRE-TEST PREPARATION

1. Install PD female coupler special tool #FNH 00535 on all gauge hose ends used for testing.
2. Warm oil to a minimum of 60° C (140° F).
3. Perform tests with the engine operating at 1900 RPM, then repeat at 1200 RPM.
4. Perform a pressure test on the low-pressure regulating circuit by installing a 40 bar (600 PSI) gauge on coupler, 2, located on the transmission valve, 1.


   Pressure should be 16.5 - 18.6 bar (240 - 270 PSI).

NOTE: *If pressure is out of specification, repair the low-pressure regulating circuit before continuing.*

5. Install gauges so pilot pressure and clutch apply pressure can be checked at the same time.



41



42

PILOT OIL CIRCUIT PRESSURE TEST

This test checks pilot oil pressure.

When pilot oil is present, the PTO brake is applied (by low-pressure regulated apply oil) and the PTO clutch is disengaged.

When pilot oil is not present, the PTO clutch is applied (by low-pressure regulated apply oil) and the PTO brake is disengaged.

Pilot oil pressure should be:

- 12.4 -15.2 bar (180 - 220 PSI) when the PTO **is not** activated.
- 0 bar (0 PSI) when the PTO **is** activated.

NOTE: *This test does not measure PTO brake apply oil pressure.*

Test Procedure:


1. Complete pre-test items.
2. Connect a 40 bar (600 PSI) gauge to coupler, 1.
3. Start engine and operate at 1900 RPM.
4. Record pressure with PTO not activated.

NOTE: *Pressure should be 12.4 - 15.2 bar (180 - 220 PSI).*

5. Record pressure with PTO activated.

NOTE: *Pressure should be 0 bar (0 PSI).*

6. Repeat steps 4 and 5 with engine at 1200 RPM and compare to the original readings.
7. If pressure is out of specified range, refer to the “Troubleshooting” heading in this chapter.



43

CLUTCH APPLY CIRCUIT PRESSURE TEST

This test checks the PTO clutch apply pressure.

When clutch apply pressure is present, the PTO clutch is applied.

When clutch apply pressure is not present, the clutch is not engaged.

Clutch apply pressure should be:

- 16.5 - 18.9 bar (240 - 275 PSI) when the PTO **is** activated.
- 0 bar (0 PSI) when the PTO **is not** activated.

Test Procedure:


1. Complete pre-test items.
2. Connect a 40 bar (600 PSI) gauge to coupler, 1.
3. Start engine and operate at 1900 RPM.
4. Record pressure with PTO not activated.

NOTE: *Pressure should be 0 kPa (0 PSI).*

5. Record pressure with PTO activated.

NOTE: *The initial pressure should gradually rise from 0 bar (0 PSI) to approximately 5.5 bar (80 PSI) in approximately 2-1/2 seconds. After this feathering period, pressure should go directly to 16.5 - 18.9 bar (240 - 275 PSI).*

6. Repeat steps 4 and 5 with engine at 1200 RPM and compare to the original readings.
7. If pressure is out of specified range, refer to the “Troubleshooting” heading in this chapter.



44

PTO LUBRICATION CIRCUIT PRESSURE TEST

This test checks the PTO lubrication pressure.

Lubrication pressure should be present when the engine is running.


Lubrication pressure should be 1.4 - 3.5 bar (20 - 50 PSI).

Test Procedure:

1. Complete pre-test items.
2. Replace the original elbow with fitting FNH00548, 1. Install PD coupler FNH00533 on the fitting.
3. Connect a 13.8 bar (200 PSI) gauge.
4. Start engine and operate at 1900 RPM.
5. Record pressure reading.

NOTE: *Pressure should be 1.4 - 3.5 bar (20 - 50 PSI).*

6. Repeat steps 4 and 5 with engine at 1200 RPM.
7. If pressure is out of specified range, refer to the “Troubleshooting” heading in this chapter.



45

SECTION 33 – BRAKES AND CONTROLS

Chapter 1 – Power Brakes

CONTENTS

Section	Description	Page
33 202	Specifications	2
	Description of Operation	4
	Boosters	7
	Master Cylinders	11
	Rear Axle Brake Assemblies	15
	Four Wheel Braking	17
	Troubleshooting	18
	Adjustments	21
	Bleeding the Brakes	21
	Brake Pedal Adjustment	25
	Brake Switch Adjustment	25
	Disassembly and Repair	26
	Power Brake Valve - Overhaul	26
	Inspection	33
	Reassembly	34
	Installation of the Brake Lube Kit	39
	Rear Axle Brakes - Overhaul	44
	Hydraulic Trailer Brake	SEE SECTION 35

SPECIFICATIONS


Brakes

Brake Type	Inboard, wet disc
Brake Operation	Hydraulic with booster
Brake Friction Discs (per side)	
Model 8670 BSN D411606	1
Model 8670 ASN D411605, 8670A	2
Models 87/88/8970, 87A/88A/8970A	2
Brake Discs Total Friction Area (Total)	
Model 8670 BSN D411606	671 cm^2 (104 in^2)
Model 8670 ASN D411605, 8670A	1342 cm^2 (208 in^2)
Models 87/88/8970, 87A/88A/8970A	1342 cm^2 (208 in^2)
Hydraulic Oil	ESN-M2C134-D
Brake Cooling (ASN D411605)	5.7 - 18.9 L/min (1.5 - 5.0 GPM) change pressure oil
Hydraulic Supply Pressure	16.5 - 18.9 bar (240 - 275 PSI)
Brake Pedal Free Play	5 - 6 mm (0.187 - 0.250″)

Tightening Torques

	N·m	Ft Lbs
Master cylinder to booster bolts	13	9
Reservoir to master cylinder hose nuts	22	16
Reservoir cap bolt	5	4
Bridge pipe nuts	10	7
Push rod locknuts	31	23
Power brake valve to cab bolts	31	23
Power brake valve feed tube	27	20
Power brake valve return tube	27	20
Rear brake cylinder supply tubes	14	10
Brake housing to center housing (87/88/8970, 87A/88A/8970A)	306	226
Brake switch attaching bolts	5	4
Brake bleeder screws	12	9

DESCRIPTION OF OPERATION



1

INTRODUCTION

The power brake system consists of the following components:

1 Brake pedals
2 Power brake valve
3 Hydraulic lines
4 Trailer brake valve (if equipped)
5 Rear axle brake assemblies

Power brakes with hydraulic boosters are used to ensure positive braking and precise equalization with minimum pedal pressure.

The power brake valve assembly, 2, is located on the fire wall at the front of the cab and is charged with 16.5 - 18.9 bar (240 - 275 PSI) oil from the low-pressure hydraulic circuit.

Each brake pedal, 1, operates a separate master cylinder and hydraulic booster in the power brake valve. This allows the right and left brake circuits to be operated independently.


The use of hydraulic boosters in the power brake valve assembly ensures only light pedal effort is required to operate the brakes.

The rear axle brake assemblies, 5, are wet disc type. The brake assemblies consist of an actuating piston located in a cylinder machined into each side of the rear axle center housing. Brake friction disc and separator plates are positioned between the piston and the axle reduction gears.

Each brake friction disc is splined to the planetary sun gear. The steel separator brake plates are located on, and prevented from rotating, by three retaining pins in the axle center housing.


When a brake pedal is depressed, pressurized hydraulic oil is sent from the master cylinder to the respective rear axle brake piston. The oil forces the piston to move against the friction disc, which causes braking.

When the brake pedals are coupled together and applied, the system balances the pressure to the right and left rear axle brake assemblies to compensate for uneven brake wear.



2

To reduce heat and prevent warpage to the brake discs in severe braking applications, 1 - 5 GPM of oil from the change pressure system is used for coding on tractors ASN D411605. The oil from the charge pressure system is routed to the rear of the tractor and splits off, equalizing flow to the right and left brakes.



3

Power Brake Valve with Brakes Released

Low Pressure Hydraulic Circuit Oil

Return to Sump Oil

A. Pump pressure inlet port
B. Overflow port

C. Left-hand brake pressure port
D. Right-hand brake pressure port

1. Center valve seal
2. Master cylinder
3. Bridge pipe
4. Master cylinder
5. Flow valve
6. Seal
7. Boost piston
8. Flap valve

9. Seal
10. Booster housing
11. Input plunger
12. Rear P.T.F.E. seal
13. Front P.T.F.E. seal (with groove)
14. Master cylinder plunger
15. Reservoir

BOOSTERS

Brakes Released Position


The power brake valve consists of one casting with two hydraulic chambers (boosters) positioned side by side and a fluid reservoir, 15. Pressurized hydraulic operating oil is supplied from the low-pressure hydraulic circuit to both boost chambers.

The integral reservoir, 15, is filled by low- pressure oil that passes between the input plunger, 11, and the oil gallery hole in the center of the boost piston, 7. The reservoir feeds the two master cylinders and returns excess oil to sump through the reservoir overflow port, B.

Pressurized oil, from the low-pressure hydraulic circuit, is fed to both boost chambers. In the brakes "released" position, pressurized oil is prevented from entering the booster by the boost piston's rear PTFE seal, 12, which seals off the booster inlet port from the low-pressure hydraulic circuit.

The second PTFE seal, 13, is installed on the boost piston to ensure alignment and smooth operation of the piston.

To prevent any buildup of pressure between the boost piston seals, a small groove is incorporated in the front seal, 13. The groove allows any high-pressure fluid between the seals to slowly bleed through to the low-pressure side of the piston. The absence of this groove could result in the piston sticking in its bore due to unequal expansion between the piston and the bore.



4

Power Brake Valve with Pedals Coupled and Brakes Applied

Low-Pressure Hydraulic Circuit Oil

Boost Pressure Oil

Brake Pressure Oil

Return to Sump Oil

1. Center valve seal
2. Master cylinder
3. Bridge pipe
4. Master cylinder
5. Flow valve
6. Seal
7. Boost piston
8. Flap valve
9. Seal
10. Booster housing
11. Input plunger
12. Rear P.T.F.E. seal
13. Front P.T.F.E. seal (with groove)
14. Master cylinder plunger
15. Reservoir


Brakes Applied Position

When a brake is applied, the pushrod contacts the booster input plunger, 11, which, in turn, moves the boost piston, 7, forward. This uncovers the pressurized oil inlet port releasing pressurized fluid into the chamber behind the boost piston, which closes the flap valve, 8.

The fluid pressure behind the boost piston, 7, is proportional to the pedal effort. The pressure forces the piston along the bore where it contacts the master cylinder plunger, 14, and moves it forward.

As the boost piston moves forward, the low-pressure oil on the front side of the boost piston is forced up into the reservoir, 15. When the fluid in the reservoir reaches the maximum level, the excess oil is returned to sump through the overflow port, B.

If the speed of pedal application is very rapid and oil from the hydraulic system fails to fill the chamber behind the boost piston quickly enough, the flap valve, 8, opens allowing low-pressure fluid from the front side of the boost piston to flow back through the boost piston until the pressure rises enough on the back side of the piston to close the flap valve again. This ensures that the high-pressure side of the boost piston is always full of oil for smooth pedal action.



5

Power Brake Valve with Single Pedal Operation and Brake Applied

Low-Pressure Hydraulic Circuit Oil

Boost Pressure Oil

Brake Pressure Oil

Return to Sump Oil

1. Center valve seal
2. Master cylinder
3. Bridge pipe
4. Master cylinder
5. Flow valve
6. Seal
7. Boost piston
8. Flap valve
9. Seal
10. Booster housing
11. Input plunger
12. Rear P.T.F.E. seal
13. Front P.T.F.E. seal (with groove)
14. Master cylinder plunger
15. Reservoir


MASTER CYLINDERS

Single Braking

The two master cylinders are bolted directly in front of the booster units and are supplied with oil from the reservoir, 15. Both master cylinders are hydraulically interconnected by an external bridge pipe, 3, and flow valves, 5, which provide the brake compensating feature.

Under single-pedal braking (brakes uncoupled), effort applied to a single pedal causes the boost piston, 7, and master cylinder plungers, 14, to move forward. This initial plunger movement and fluid displacement moves the center valve seal, 1, over the reservoir supply port closing the inlet from the reservoir. As the plunger continues to move along the bore, the rise in pressure in the master cylinder is applied to the respective rear axle brake.

As the brake is applied, the flow valve, 5, in the activated master cylinder moves away from its seat and fluid is displaced towards the inactive master cylinder through the bridge pipe, 3, which closes and holds the flow valve in the inactive master cylinder on its seat. This prevents oil flow from entering the inactive master cylinder.



6

Power Brake Valve with Pedals Coupled and Brakes Applied

Low-Pressure Hydraulic Circuit Oil

Boost Pressure Oil

Brake Pressure Oil

Return to Sump Oil

1. Center valve seal
2. Master cylinder
3. Bridge pipe
4. Master cylinder
5. Flow valve
6. Seal
7. Boost piston
8. Flap valve
9. Seal
10. Booster housing
11. Input plunger
12. Rear P.T.F.E. seal
13. Front P.T.F.E. seal (with groove)
14. Master cylinder plunger
15. Reservoir

Coupled Braking

During coupled braking, the brake wear compensating function of the master cylinders is controlled by the flow valves, 5, built into each master cylinder. The flow valves are interconnected by the bridge pipe, 3.

Under coupled braking, the flow valves, 5, are opened allowing fluid to transfer from one cylinder to the other which equalizes pressures.

During coupled braking, effort applied to the brake pedals causes the boost pistons, 7, and master cylinder plungers, 14, to move forward. This initial plunger movement and fluid displacement moves the center valve seals, 1, over the reservoir supply ports closing the inlets.

Further movement of the master cylinder plunger, 14, down the bore causes the flow valve, 5, to travel up the taper of the plunger, lifting the flow valve from its seat and prevents it from closing. This allows fluid movement through the bridge pipe, 3, to the other cylinder. The same process takes place in the opposite master cylinder allowing pressure to be equalized in the two cylinders.

If the brake discs on each brake are worn evenly, the same amount of fluid displacement will be needed on both sides of the tractor to apply the brakes. In this case the amount of fluid displaced between cylinders will be small and the brakes will be applied evenly.


If the brake friction plates are unevenly worn, which will be the condition in field use, the amount of fluid needed to apply the brakes will differ from one side of the tractor to the other. The different amount of fluid displacement is achieved by compensation between the two cylinders.

The plunger operating the brake with the least worn plates will displace sufficient fluid to bring the brake plates into contact, but the plunger will continue to move down the bore since effort is still being applied to the pedal because the other brake is not yet applied. If more oil is supplied to the least worn brake, the brake would be applied. To prevent the brake from applying, the master cylinder begins to compensate for the other plunger which is operating the most worn brake. By displacing fluid through the open flow valves and bridge pipe, hydraulic pressures will equalize in the master cylinders and both brakes will apply evenly.

Boost Pressure Control

During braking, the pressure applied to the boost piston, 1, is proportional to the effort applied to the brake pedal(s). This pressure is controlled by the amount of leakage of pressurized hydraulic boost oil between the tip of the input plunger, 3, and the oil gallery hole in the center of the boost piston, 1. The harder the pedal is depressed, the more effective is the metal to metal contact between the input plunger tip and boost piston, resulting in less leakage of boost oil through the oil gallery hole in the piston, and more pressure to the boost piston.

The brakes can be applied with the engine stopped, or if low pressure hydraulic boost oil pressure is lost during operation. In either instance, pedal effort will increase and be directly related to the pressure applied to the input plunger because no boost pressure oil is available.



7


Boost Pressure Control

Hydraulic Pressure Oil

Regulated Boost Pressure Oil

Return to Sump Oil

1. Boost piston
2. Master cylinder plunger
3. Input plunger



8


REAR AXLE BRAKE ASSEMBLIES

Wet disc type brake assemblies are used on all models.

Model 8670/8670A

Model 8670 tractors BSN D4411606 use one brake friction disc, 1, and one separator plate, 2, per side as shown.

Model 8670 tractors ASN D411605 and 8670A use two brake friction disc, 1, and two separator plates, 2, per side as shown.




9

Models 8770/8770A, 8870/8870A and 8970/8970A
Model 8770/8770A, 8870/8870A and 8970/8970A tractors use two brake friction discs, 2; an inner separator plate, 4; and an outer housing, 3, per side as shown.

Operation - All Models
The friction discs are internally splined to (and turn with) the sun gear, 5. The separator plates are attached to the center housing (and held from turning) by three pins.

When a brake pedal is depressed, pressurized oil enters the machined cylinder in the center housing. The oil forces the piston, 1, against the rotating friction disc(s) and the stationary separator plate(s), and housing to cause braking.



10

FOUR WHEEL BRAKING

Four wheel braking is available on tractors equipped with four wheel drive (FWD).

When both brake pedals are depressed together, the brake switches interrupt current flow to terminals D10 and D11 of connector C007. When the EIC senses the current loss, it signals the CCM to interrupt electrical power to the FWD control solenoid. This stops hydraulic oil flow to the FWD clutch. Since the FWD clutch is engaged by a spring and released by hydraulic pressure, interrupting hydraulic flow allows the spring to engage the FWD clutch to provide four wheel braking.

Four wheel braking may be selected or eliminated as described in Chapter 2 of the Electrical Section (Section 55).

NOTE: *FWD is automatically engaged when the parking brake is applied with the engine running regardless of the FWD switch position. This assists in holding the tractor in a stationary position. FWD is also automatically engaged to assist in braking when both brakes are applied.*

TROUBLESHOOTING

BRAKE SYSTEM

As a first step in troubleshooting the brakes, perform the following preliminary checks:

1. Check for kinked or pinched brake lines.
2. Check for external leaks at the master cylinder, lines, bleeders, and when equipped, the trailer brake valve.
3. Bleed the brakes.

PROBLEM	POSSIBLE CAUSE	CORRECTION
Excessive pedal travel or kickback with engine running	Incorrect brake pedal free play	Adjust free play
	Air in system	Bleed brakes
	Leakage in brake valve	Repair valves
	Brake piston seal leaking	Replace seal
	Brake bleeder not sealing	Replace bleeder
	Leak at line connections or bleed screw	Inspect for leaks
	Brake piston seal rings leaking	Apply oil pressure to brake piston and observe loss of pressure
One or both brake pedals feel spongy	Air in system	Bleed brakes
	Leak at line connections or bleed screw	Inspect for leaks
	Brake piston seal rings leaking	Apply oil pressure to brake piston and observe loss of pressure
	Brake friction plates worn	Replace friction plates
Pedal bottoms with engine stopped	Brake piston seal leaking	Replace seal
	Brake friction plates worn	Replace plates
	Brake bleeder not sealing	Replace bleeder
	Leakage in brake valve(s)	Repair valve(s)

FOUR WHEEL BRAKING

NOTE: *Be sure the front wheel drive (FWD) system engages and disengages properly using the FWD switch. If the system does not operate properly, refer to Section 25, Chapter 2 for FWD system pressure testing and troubleshooting information.*


Perform the following preliminary steps before proceeding to the troubleshooting chart:

1. Verify four wheel braking is not operating properly. Proceed if the system is not working properly.
2. Retrieve current (mode 1) and stored (mode 2) fault codes.

NOTE: *Proceed to step 3 if relevant current code(s) exist in mode 1. Proceed to step 4 if no relevant code(s) exist.*

3. Correct relevant current fault code(s) using diagnostic charts in Section 55, Chapter 2.
4. Proceed to the troubleshooting chart.


NOTE: *The FWD circuit will not activate when the park brake is engaged.*


Does the Front Wheel Drive (FWD) system engage and disengage normally?
NO
Repair FWD circuit. Refer to Section 25, Chapter 2.
YES
Check mode 12 to be sure four wheel braking is enabled. Refer to Section 55, Chapter 1 for details on entering mode 12.
NO
Enable Four Wheel Drive Braking.
YES
Check for open circuit at the Front Console Fuse (MDP-F22).
FUSE BLOWN?
YES
Replace fuse.
NO
Check for +12 volts at Front Console Fuse (MDP-F22) terminals with key switch on.
+12 VOLTS ON EITHER TERMINAL?
YES
Remove Fuse MDP-F22 and disconnect connectors C071 & C070. Check for open circuit in Cab Main Harness between connector C071 pin 4 to MDP-F22 terminal B (wire CM43E), and between C070 pin 4 to C071 pin 4.
NO
Find and repair open circuit in auxiliary power circuit.
OPEN CIRCUIT?
YES
Find and repair open circuit in Cab Main Harness.
NO
Check for open circuit in Cab Main Harness between C071 pin 3 to C007 pin D10, also C070 pin 3 to C007 pin D11.
OPEN CIRCUIT?
YES
Find and repair open circuit in Cab Main Harness.
NO
With brake pedals released, check for open circuit in brake switches between pins 3 and 4 of both switches.
OPEN CIRCUIT?
YES
Check adjustment of brake switches and replace if defective.
NO
Replace EIC if FWD circuit engages and disengages using FWD switch.

ADJUSTMENTS

BLEEDING THE BRAKES

Tools Required:
7 mm wrench
(1/4″, 3/8″, and 9/16″) wrenches
6 mm (1/4″) I.D. plastic tubes:
one 1524 mm (60″) and two 1220 mm (48″) long
(1/4″) hex socket or wrench



11


Preparation
Park the tractor on a level surface, apply the park brake, and block the front and back of the rear wheels.

NOTE: *Clean the areas around all bleed screws and drain plugs.*

IMPORTANT: *Drain the rear wheel brake chambers using the following procedure prior to bleeding the brakes.*

1. Remove the right-hand brake chamber drain plug, 1.
2. Allow oil to drain until only clean oil is present, then reinstall and tighten the drain plug.
3. Repeat steps 1 and 2 on the left-hand brake chamber.


NOTE: *Catch oil in a suitable container and dispose of oil properly.*



12

Filling the Brake System

1. Attach a transparent bleed hose, 1, to each rear brake bleed screw, 2. Insert the open ends of the hoses into the rear axle oil filler tube, 3, at the rear of the tractor.
2. Open both bleed screws a minimum of 1-1/2 turns.
3. Start the engine and set the engine speed to idle.




13

4. Fill the brake system by depressing and holding down the latched brake pedals 100 - 125 mm (4 - 5″).

   Continue to hold the pedals in the depressed position for approximately 1 minute after the oil flowing through the hoses is free of air bubbles.

NOTE: *If a hydraulic or air trailer brake valve is fitted, do not release the pedals until an assistant has closed the bleed screws. Proceed to step 5 for bleeding the hydraulic trailer brake valve. Proceed to step 12 for bleeding the air trailer brake valve.*

NOTE: *If the tractor is not equipped with a trailer brake valve, proceed to step 15.*




14

Bleeding The Hydraulic Trailer Brake Valve (When Applicable)


5. Connect a transparent bleed tube to the trailer brake valve left brake bleed screw, 3. Insert the open end of the tube in the rear axle oil filler tube.
6. Open the left bleed screw, 3, and open the bleed screw on the left axle brake.
7. Repeatedly depress the left brake pedal until the fluid in one of the tubes is free of air, then close the bleed screw for that tube. Continue to repeatedly depress the left brake pedal until the remaining tube is clear of air, then close the bleed screw with the brake pedal depressed.
8. Transfer the transparent tube to the trailer brake valve right brake bleed screw, 1.
9. Repeat the bleeding process on the right brake circuit.
10. Transfer the transparent tube to the trailer brake valve center brake bleed screw, 2.
11. Lock the brake pedals together and repeatedly depress the brake pedals until the fluid in the tube is free of air, then close bleed screw, 2, with the brake pedals depressed.

    Proceed to step 12.

NOTE: *The center circuit is orificed so only a little oil will flow from the center bleed screw.*



15



16

Bleeding The Air Trailer Brakes Valve, Dual Control Valve (When Applicable)

12. Connect a transparent bleed tube to the dual control valve bleed screw, 1, and right brake bleed screw, 2. Insert the other end of the tubes in the rear axle oil filter tube, 3.
13. Open the dual control bleed screw and the right brake bleed screw.
14. Repeatedly depress the right brake pedal until the fluid in one of the tubes is free of air, then close the bleed screw for that tube. Continue to repeatedly depress the right brake pedal until the remaining tubes is clear of air, then close the bleed screw with the brake pedal depressed.

Bleeding The Rear Axle Brake System


15. If closed, open both rear wheel bleed screws a minimum of 1-1/2 turns.
16. With the brake pedals unlatched, repeatedly fully stroke the right-hand brake pedal, 1, until the fluid in the bleed tube is free of air, then close the right wheel bleed screw with the pedal depressed.
17. Check the right-hand brake pedal for correct operation. If bleeding has been unsatisfactory, repeat the procedure for both the trailer brake (when equipped) and the right rear brake.
18. Latch the brake pedals together and repeatedly stroke the brake pedals until the fluid in the left bleed tube is free of air, then close the left-hand bleed screw with the pedal depressed.

NOTE: *When bleeding with the pedals coupled, increased pedal effort will be observed and it will not be possible to achieve a full pedal stroke due to the master cylinder compensation block.*


19. Stop the engine.
20. Depress the latched brake pedals 50 mm (2″).
21. Open right-hand and left-hand rear bleed screws 1/2 turn.
22. Start the engine and run it at idle for a minimum of four minutes or until the tubes are free of air bubbles.
23. Tighten the bleed screws when the tubes are free of air bubbles.

NOTE: *Torque bleed screws to 12 N·m (9 ft lbs).*

24. Stop the engine.
25. Check that the pedal free travel is 5 - 6 mm (3/16 - 1/4″). To adjust, loosen the jam nut, 1, and adjust rod, 2. Tighten the jam nut to 31 N·m (23 ft lbs).
26. Individually check the travel on each brake pedal and ensure that when the brakes are applied, the travel for each pedal is the same. Recheck the travel with both pedals coupled together.
27. With the engine running, check for leaks.




17



18

28. Check the rear axle oil level, with dipstick, 2. Add specified oil as required through the fill tube, 1, until oil is at the fill mark, 3.
29. Road test the vehicle.

IMPORTANT: *If the brake pedals feel spongy, repeat the bleeding process with oil at the normal operating temperature.*



19

BRAKE PEDAL ADJUSTMENT


Tools Required:
Assorted hand tools

Adjustment

1. With the brake pedals in the released (foot off pedal) position, be sure the free play at the end of the pedal is 5 - 6.3 mm (3/16 - 1/4″).
2. Adjust the free play where necessary by loosening the pushrod locking nut, 1, and turning the pushrod, 2. Retighten the locknuts to 31 N·m (23 ft lbs).

NOTE: *After any adjustment, be sure the free travel is equal for each pedal with the brake pedal locking bar disengaged. Make sure the lock bar engages with the brakes released.*

3. Check for correct operation of the stop lamp switches. Adjust as detailed in “Adjustments” in this section.




20

BRAKE SWITCH ADJUSTMENT

Tools Required:
Assorted hand tools
Feeler gauge

Adjustment

1. Be sure the brake pedals are adjusted properly and fully against the stop.
2. Remove the right side steering console cover.
3. Place a 5 mm (0.20″) thick feeler gauge between the actuator arm of the pedal, 3, and the switch, 1.
4. Move the switch down until the actuator button bottoms out.
5. Torque retaining bolts, 2, to 5 N·m (4 ft lbs).




21

DISASSEMBLY AND REPAIR

POWER BRAKE VALVE - OVERHAUL

Tools Required:
Assorted hand tools
15 mm, 17 mm, 19 mm wrenches
(1/4″, 9/16″, 5/8″, 13/16″ and 15/16″) wrenches
13 mm, 19 mm sockets
(1/4″) hex socket
(5/8″) socket
Ratchet and extension
Phillips screwdriver



22


Removal

NOTE: *Clean the areas around the power brake valve, steering motor and brake bleed screws. Cap all open hydraulic lines and fittings.*

1. Remove the rear axle brake drain plugs, 1, from the left and right side of the center housing. Repeatedly depress the locked brake pedals until oil flow stops.


NOTE: *Catch oil in a suitable container and dispose of properly.*

2. Reinstall both drain plugs, 1, after oil flow stops.



23

3. Open the hood to access the brake valve.
4. Remove side panels, 2 and 4.
5. Remove the exhaust stack, 1, by removing bolts, 3 and 5. On tractors ASN D405349 remove the exhaust pipe clamp at the exhaust brace.




24

6. Disconnect brake lines, 2, 3, 6 and 7, from the power brake valve assembly, 1.

NOTE: *Lines, 2 and 3, are connected to the valve with O ring seals.*


NOTE: *A certain amount of oil may be retained in the booster unit even though the system was drained.*

7. Disconnect lines, 4 and 5, from the steering motor. These lines have O ring seals.




25

8. Remove the right side steering console cover, 1.




26

9. Remove the three bolts, 1, that retain the brake valve to the cab fire wall. It is not necessary to disconnect the pushrods, 2, at the brake pedals in order to remove the brake valve assembly.




27

10. Remove the brake valve assembly, 1, from the fire wall by tilting it down and removing it under support, 2.



28



29


POWER BRAKE VALVE - EXPLODED VIEW

1. Push rod
2. Dust cap
3. Gasket
4. Reservoir cap
5. Washer
6. Booster body and reservoir
7. Reservoir supply hose
8. Seal
9. Master cylinder assembly
10. Input plunger
11. Boost piston
12. Return spring
13. Valve seal
14. Valve stem
15. Curved washer
16. Valve spacer
17. Return spring
18. Spring retainer
19. Bridge pipe
20. Insert
21. Flow valve assembly
22. Cylinder body
23. Shim(s)
24. O ring
25. Plunger master cylinder
26. Seal

Disassembly


IMPORTANT: *Each side of the brake valve assembly has identical parts. Keep the parts from the right and left sides separated to avoid mixing components.*

Tools Required:
Assorted hand tools
10 mm, 11 mm, 12 mm, 13 mm wrenches
13 mm socket
Seal remover
Hydraulic oil
Ratchet




30

1. Remove the reservoir cap and drain out any oil remaining in the valve assembly.



31

2. Place the assembly upside down on the workbench and remove the bridge pipe, 1.




32

3. Remove the flow valves, 2, and inserts, 3, from each master cylinder by tilting the valve until the components fall out.

NOTE: *It may be necessary to tap the master cylinders with a soft piece of wood to release the flow valves.*

4. Remove the reservoir supply hose, 1, from the cylinder that is to be overhauled first.




33

5. Place identification marks, 1, on the booster and master cylinder to ensure proper assembly.
6. Remove the two retaining bolts that attach the master cylinder to the booster.


NOTE: *Spring pressure will push on the cylinder as the bolts are removed. Keep hand pressure on the cylinder to counteract the spring.*

7. Separate the master cylinder from the booster unit and place it on a clean surface.



34

8. Remove the return spring, 1; boost piston, 2; and input plunger, 3, from the booster.
9. Remove the dust cover, 4.




35

10. Remove the O ring, 1, and shim(s), 2, from the master cylinder flange.


IMPORTANT: *The shims (any number between 0 and 4) are factory fitted during assembly to give the required clearance between the master cylinder plunger and the boost piston. The same shims must be retained and reinstalled on reassembly.*

11. Remove the plunger assembly, 3, from the master cylinder.




36

12. Lift the leaf, 3, of the spring retainer with a small screwdriver and pull the spring assembly, 2, from the plunger, 1.




37

13. Compress the spring, 5, to free the valve stem, 4, from the keyhole, 1. This will release the spring tension.
14. Remove the spring, 5, valve spacer, 2, and curved washer, 3, from the valve stem, 4.



38


15. Remove the valve seal, 1, from the head of the valve stem.



39


16. Remove the seal, 1, from the master cylinder plunger using a small screwdriver that has had the end rounded off and polished. Squeeze the seal until the polished blade can be inserted under the seal, then release the seal and slide it off the plunger.

NOTE: *It is important that the screwdriver be prepared and polished as described to avoid damaging the surface of the plunger.*



40

17. Remove the seal, 1, from the input plunger using the procedure described in step 16.



41

INSPECTION

1. Examine the booster and master cylinder bores for visible score marks. Check that the bores are smooth to the touch. Examine all pistons and plungers in the same way.

IMPORTANT: *If there is any doubt as to the condition of the parts, a new unit should be installed.*


2. Inspect all other components to ensure that they are in good working order. Comparison of the parts contained in the service kit will indicate which parts to discard.
3. If the old seals appeared to be loose when they were removed, compare them with their new replacement seals. DO NOT LET THEM TOUCH. If the old seals appear larger and swollen compared to the new ones, oil contamination is indicated, and the whole hydraulic system should be flushed out and refilled with new oil to correct specification as detailed in the Operator's Manual.
4. Thoroughly clean and dry all parts before reassembly.

REASSEMBLY

Use the new parts in the service kit when reassembling. Lubricate the seals with clean hydraulic oil of the correct Specification before installation.


Master Cylinder

1. Install a new seal, 1, on the plunger.




42

2. Install a new seal, 5, on the valve stem, 4.
3. Position the curved washer, 3, on the valve stem so that it “flares” away from the valve stem shoulder.
4. Position the valve spacer, 1, on the valve stem, 4, and locate the return spring, 2, inside the spacer.




43

5. Fit the spring retainer, 2, to the end of the spring and compress the spring until the valve stem passes through the keyhole, 1, in the retainer and locks in place.




44

6. Slightly depress the leaf, 1, on the retainer, 2.
7. Slide the spring subassembly on the plunger until the leaf of the retainer locks on the plunger.



45


8. Install the original shim(s), 2, removed during disassembly.
9. Install a new O ring, 1.
10. Lubricate the plunger assembly, 3, and cylinder bore with new hydraulic oil as specified in the Operator's Manual. Insert the plunger assembly into the master cylinder bore taking care not to damage the plunger seal.
11. Place the master cylinder in a safe place until you are ready to fit it to the booster.



46


Booster Reassembly

1. Install a new seal, 1, on the input plunger.



47


2. Lubricate the input plunger, 3, and booster cylinder bore with new hydraulic oil as specified in the Operator's Manual.
3. Gently insert the plunger into the bore of the booster housing until the lip on the plunger makes contact with the chamfered edge of the bore.
4. Lubricate the new boost piston assembly, 2, with hydraulic oil and gently push the boost piston fully down the bore.
5. Grease the rear of the input plunger where the brake pedal pushrod will contact.
6. Install the new dust cover, 4.
7. Install the return spring, 1, inside the boost piston.



48


Attaching the Master Cylinder

1. Install the master cylinder to the booster body, making sure the plunger in the master cylinder passes down the center of the boost piston return spring and the spring fits over the boss on the master cylinder.
2. Install the cylinder retaining bolts, 1, and tighten to 12 N·m (9 ft lbs).




49

3. Turn the booster/master cylinder assembly upside down and install a new flow valve, 2, and insert, 3, into each master cylinder.
4. Install a new hydraulic hose, 1, from the master cylinder to the reservoir and tighten the hose nuts to 22 N·m (16 ft lbs).




50

5. Repeat the overhaul procedure for the other side of the unit.
6. Install the bridge pipe, 1, and tighten the retaining nuts to 10 N·m (7 ft lbs).



51


7. Install the reservoir cap using the new gasket and washer from the service kit. Tighten the cap bolt to 5 N·m (4 ft lbs).



52


Installation

1. Position the brake valve assembly to the fire wall of the tractor making sure the brake pedal pushrods, 2, pass through the rubber dust covers.
2. Install the three mounting bolts, 1, and tighten to 31 N·m (23 ft lbs).



53


3. Install new O rings and connect steering lines, 4 and 5. Torque to 43 N·m (32 ft lbs).
4. Connect lines, 2 and 3, to the power brake valve assembly, 1, using new O rings. Torque to 27 N·m (20 ft lbs).
5. Connect lines, 6 and 7. Torque to 14 N·m (10 ft lbs).



54

6. With the brake pedals in the released (foot off pedal) position, check that the free play at the end of the pedal is 5 - 6.3 mm (3/16 - 1/4″).
7. Adjust the free play where necessary by loosening the pushrod locking nut, 1, and turning the pushrod, 2. Retighten the locknuts to 31 N·m (23 ft lbs).

NOTE: *After any adjustment, check that the free travel is equal for each pedal with the brake pedal locking bar disengaged. Make sure the lock bar engages with the brakes released.*



55

8. Bleed the brake system as detailed in the “Adjustment” heading.
9. Check for correct operation of the stop lamp switches. Adjust as detailed in “Adjustment” heading.

Accelerated brake disc wear may be experienced when operating tractors in certain applications, such as driving high-speed roading where brakes are applied frequently.

Additional brake cooling has been added to the tractors in production. In addition, the Model 8670 tractor had an additional brake disc added. This change was cut in on the Model 8670 tractor, beginning with serial #D411606, and on the Models 8770, 8870, and 8970, beginning with serial #D411583.

Both systems divert a total of 1.5 to 5.0 US gal/min. (5.3 to 18.9 L/min), dependent on temperature, from the charge pump output and feeds this flow directly over the brake disc assembly on each side of the rear axle.


If this problem is experienced on a prior built unit, the unit can be upgraded with a brake cooling kit which is available through Service Parts. The kit includes the hardware and plumbing necessary to add the brake cooling system. In addition, the Model 8670 kit also includes the parts necessary to add an additional brake disc to each side. Both kits would require drilling and tapping oil passages into the existing cast housings.

The kits are as follows:

Model	Part Number
8670	86014468
8770	86014467
8870	86014467
8970	86014467

INSTALLATION OF THE BRAKE LUBE KIT


Drain the oil, support the tractor, and remove the axle housing(s) as detailed in Section 27.



56

On the 8770, 8870, and 8970 tractors, the thick ring (planet ring) that sits between the trumpet and the rear housing should be removed with the trumpet. The sun gear may or may not come out with the assembly. Remove the sun gear from the housing.

On the 8770, 8870, and 8970 tractors, remove the brake housing, 1, friction discs, 2, and separator plate, 3.




57

On the 8670 tractor, remove the brake housing plate and the brake disc.


⚠ WARNING ⚠

Do not remove the brake piston.

On the 8770, 8870, and 8970 tractors, mark the position of the hole to be drilled from the inside of the rear housing assembly as shown in (Figures 58 and 59).



58




59

On the 8670 tractor, mark the position of the hole to be drilled on the inside of the trumpet housing as shown in Figure 60.

On the 8770, 8870, and 8970 tractors, use the brake disc or separator plate as a template to cut a piece of cardboard or similar material to fit against the piston or against the inner end of the axle and bearing on the 8670 tractor to prevent drill shavings from entering the assembly.

Center punch the holes so the drill bit will have a good start location.

NOTE: *The inside hole location is the most critical as it is necessary for the oil to dump on to the separator plate. A second disc and separator plate will be added on the 8670 tractor.*



60

Drill a 1/4″ pilot hole first. Then drill a 7/16″ hole.

THE INSIDE ENTRY LOCATION OF THE HOLE IS MOST IMPORTANT AS IT IS REQUIRED TO DUMP THE COOLING OIL DIRECTLY OVER THE SEPARATOR PLATE BETWEEN THE TWO FRICTION DISCS.

The exterior exit must be in a reasonable position for tapping of the hole for a fitting. On the 8670 this will be in the trumpet to flange radius area.

Using a chamfering tool or 3/4″ drill bit, chamfer the inside of the hole to a width of 3/4″. This will aid in good oil distribution across the edge of the two friction discs.

Tap the hole from the outside using a 1/4–18 NPT tap. Clean the area of all debris and try a fitting in the threads. If ok, put pipe thread sealant on the threads and install the fitting. Cap the fitting temporarily.

Remove any temporary protective material used during the process and clean the components thoroughly.


On the 8770, 8870, and 8970 tractors, install new friction discs, separator plate, and brake housing plate as required. Moisten the friction discs with ESN–M2C134–D hydraulic oil.

On the 8670 tractor, install two new friction discs (only used one previously), a new separator plate (did not use before), and a new brake housing plate (thinner than original).

Bleeder screws may have to be loosened to force the piston back to allow room for the new disc thickness.

Reinstall the other items removed according to Section 27. Use a liquid gasket sealer such as RTV Blue.

Remove the CCLS pump charge elbow,1, located just above and to the back of the CCLS pump.




61

Drill a 9/16″ hole on the flat of the elbow, 1. Tap the hole to 3/8–18 NPT, clean and install the fitting with pipe thread sealant.

Reinstall the elbow to the CCLS charge line.


Pre–assemble the main feed line and individual brake feed lines to the bulk head “T” and bracket.

From the back of the tractor just above the implement valve, route the left hand brake line to the left axle and the right hand line and main feed line to the right hand side of the tractor.




62

Install the bulkhead “T” fitting complete with the bracket,1, to the top two mounting holes, 2, of the implement valve.




63

Connect the main feed line to the CCLS charge elbow, 1.



64

Connect the individual brake lines to the new fittings on the trumpet housings, 2. See Figures 65 and 66.




65

Change the oil and the filters as deemed necessary by circumstances dictating the installation of this kit.

Complete the installation of the ground cables, electrical connectors, cab mount bolts, and wheels.

Check the brake function with the engine off. Bleed and fill–up the brakes as necessary.



66


Start the tractor and test the brake function.

REAR AXLE BRAKES - OVERHAUL

Note: *Refer to the appropriate heading for the model tractor.*

Tools Required:
Assorted hand tools
Feeler gauge
Straightedge
Mallet
Seal pick
Air blow gun
Petroleum jelly
24 mm socket*
Torque wrench*

*Models 87/88/8970, 87A/88A/9070A only.




67

Removal - Model 8670/8670A

1. Drain the oil, support the tractor, and remove the axle housing(s) as detailed in Section 27.
2. Remove sun gear, 2; friction disc, 1; three locating pins, 3; and separator plate, 4.

NOTE: *Tractors ASN D411605, have two friction discs and separator plates that must be removed.*




68

3. Remove brake piston, 1, by pressing on the corresponding brake pedal.

NOTE: *If the brakes are inoperative, inject low-pressure compressed air through the bleed screw to remove the piston.*

CAUTION


To prevent personal injury and piston damage, install bolts and plates at 2 and 3, to keep the piston from popping out of the center housing when the brake or air is applied.



69


Removal - Models 87/88/8970, 87A/88A/8970A

1. Drain the oil, support the tractor, and remove the axle housing(s) as detailed in Section 27.




70

2. Remove twelve bolts, 1, that retain the brake housing, 2.



71

3. Remove brake housing, 3, friction discs, 2; separator plate, 4; and sun gear, 5.




72

4. Remove the brake piston, 1, by pressing on the corresponding brake pedal.

NOTE: *If the brakes are inoperative, inject low-pressure compressed air through the bleed screw to remove the piston.*

⚠ CAUTION ⚠

To prevent personal injury and piston damage, install bolts and plates at 2 and 3, to keep the piston from popping out of the center housing when the brake or air is applied.




73

Inspection and Repair

1. Clean brake friction discs and piston with mineral spirits or kerosene (paraffin).


IMPORTANT: *Use of any other solvents or cleaning agents may cause premature wear, deterioration or flaking of the friction material.*

2. Place each separator plate against the piston and check for warpage. Warpage should not exceed 0.1 mm (0.003″). Replace warped parts.



74


3. Insert one friction disc at a time between the piston and brake housing. Use feeler gauges to measure the clearance on either side. If the clearance exceeds 0.2 mm (0.008″), the disc is warped and must be replaced.
4. If the friction disc is not warped, place a straightedge over the disc and check that the splines clear the straightedge. Do this on both sides. If the splines do not clear the straightedge on either side, replace the disc.
5. Inspect the piston for wear. Replace if necessary.
6. Check the locating pins and the notches in the separator plates and piston for wear. Replace worn parts.



75


Installation - Model 8670

1. Install new inner, 1, and outer, 2, seals on the piston. Lubricate seals with petroleum jelly or specified hydraulic oil.



76

2. Insert three locating pins, 2, then install the piston, 1. After the piston is installed, remove the three pins, 2.




77

3. Install sun gear, 2, and friction disc, 1. Install the three locating pins, 3, and the separator plate, 4.


NOTE: *Install two friction discs and separator plates on tractors ASN D411605.*

NOTE: *Model 8670 BSN D411606 can be upgraded with 2 friction discs and separator plates with kit part number 86014468.*



78


4. Install the axle housing, torque bolts and fill with oil as detailed in Section 27.
5. Bleed the brakes if the brake piston was removed. Bleed brakes as detailed in the “Adjustment” heading of this section.



79


Installation - Models 87/88/8970, 87A, 88A, 8970A

1. Install new inner, 1, and outer, 2, seals on the piston. Lubricate the seals with petroleum jelly or specified hydraulic oil.




80

2. Insert three locating pins, 2, then install the piston, 1.




81

3. Install sun gear, 5; friction discs, 2; separator plate, 4; and housing 3.




82

4. Secure housing, 2, with twelve retaining bolts, 1. Torque to 306 N·m (226 ft lbs).



83

5. Install the axle housing, torque bolts and fill with oil as detailed in Section 27.
6. Bleed the brakes if the brake piston was removed. Bleed brakes as detailed in the “Adjustment” heading of this section.



84

SECTION 33 – BRAKES AND CONTROLS

Chapter 2 – Parking Brake

CONTENTS

Section	Description	Page
33 110	Specifications	2
	Special Tools	2
	Description of Operation	3
	Adjustments	4
	Adjust the Park Brake	4
	Troubleshooting	5
	Disassembly and Repair	6
	Parking Brake - Overhaul	6

SPECIFICATIONS

Parking Brake Components

Type	Wet, multiplate caliper
Brake element location	Ahead of differential pinion gear
Method of actuation	Mechanical lever, pull cable, cam action
Number of discs	3
Number of active friction surfaces	6
Friction brake packs	4

Sealers


Anaerobic sealer	Loctite Gasket Eliminator 518
RTV silicone sealer	Loctite Superflex 593, 595 or 596 Loctite Ultra Blue 587
Pipe sealant	PST 592 Pipe Sealant with Teflon
Thread-locking compound	Loctite 271 Threadlocker/Sealant (red)

Tightening Torques

	N·m	Ft Lbs
Brake pad mount bolts	40	30
Sealing plug - metal	162	120
Parking brake housing to center housing bolts	61	45

SPECIAL TOOLS


Description	Tool Number	Usage
Parking brake alignment tool	FNH00529	Keeps parking brake pads aligned during installation



1


DESCRIPTION OF OPERATION

The parking brake lever is connected by a cable to the actuator, 1, on the left side of the rear axle housing.



2

The three parking brake discs, 1, are splined to the rear axle pinion gear shaft, 2. When the parking brake lever is raised, the actuator forces the four brake pads, 3, against the brake discs which prevents the pinion gear and rear wheels from turning.



3


ADJUSTMENTS

ADJUST THE PARK BRAKE

The park brake, 1, should be fully applied when the park brake handle is raised to the third or fourth notch (click), 3, on the quadrant. The brake should not be engaged in the first or second notch, 2.

IMPORTANT: *Adjust the park brake when the park brake handle must be raised above the fourth notch on the quadrant to fully apply the park brake.*


Adjust the park brake with the tractor parked on level ground, the engine off, and the wheels blocked front and rear.



4


To adjust the park brake:

1. Position the park brake handle, 1, in the fully lowered, 0, position.
2. Raise the park brake handle to the second notch on the quadrant.



5

3. Loosen the forward jam nut, 1, as far as possible on the cable housing, 2.
4. Pull the cable housing, 2, rearward until a 9 kg (20 lb.) resistance is felt. Hold in position.
5. Tighten the rear jam nut, 3, until it contacts the bracket, 4. DO NOT OVER TIGHTEN.
6. Tighten both jam nuts, 1 and 3, against the bracket, 4.
7. Raise the park brake handle and check for proper adjustment.



6


TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Parking brake does not hold tractor	Improper adjustment. Parking brake pads worn	Adjust cable Replace pads
Parking brake drags	Improper adjustment. Binding, or damaged components, or linkage.	Adjust cable. Inspect components, and repair as required.

DISASSEMBLY AND REPAIR

PARKING BRAKE - OVERHAUL


Tools Required:
Assorted hand tools
Snap ring and common pliers
5/8″ socket
Ratchet
Torque wrench
Hand tools
Brake alignment special tool - FNH00529
Specified RTV silicone sealer
Ruler
Combination square
Chisel
Hammer



7


Removal

1. Block the front and back of both rear tires.
2. Thoroughly clean all areas of the tractor to be worked on.
3. Remove the fuel tank, 1, as detailed in Section 10.




8

4. Remove drain plug, 1. Drain 45 L (12 gallons) of oil from the rear axle into a clean container and store for reuse.




9

5. Release the parking brake handle and disconnect the cable clevis, 1, from the actuator arm, 2.
6. Remove the six parking brake housing attaching bolts, 3.



10


7. Remove the parking brake assembly, 1, from the center housing.



11


Disassembly

1. Straighten the locking tabs, 1, on the mount bolts.



12


2. Remove the brake mount bolts, 1, and brake pads, 2.



13


3. Place index marks on actuator cam, 1, and shaft, 2.

NOTE: *Do not use the chisel marks on the cam and shaft as index marks. They are not accurate.*




14

4. Remove snap ring, 1.




15

5. Remove cam, 1, from shaft, 2.



16

6. Remove actuator shaft, 2; spacer, 4; O ring, 3; and spring, 1, from the housing.



17

Inspection


1. Clean and inspect all components for excessive wear or damage.
2. Replace parts as required.

Reassembly

1. Install spring, 4.

   Put spacer, 2, and a new O ring, 3, on actuator shaft, 1.

   Insert shaft in the housing until the O ring and spacer enter the housing. Tap the end of the shaft to fully seat the O ring and spacer.




18

2. Install cam, 4, on actuator shaft using index marks stamped during disassembly.

   To ensure that the cam is properly installed, place a combination square, 2, on the housing. Align the actuator arm, 1, with the square.


   With the actuator arm in the vertical position, the distance, 3, between the cam and housing should be 35 mm (1.38″). Adjust the cam on the shaft to obtain the correct dimension.

NOTE: *If the cam is not installed correctly, the park brake will not operate properly.*




19

3. Install snap ring, 1.




20

4. Install brake plates, mount bolts, and new locking tabs.




21

5. Torque mount bolts to 40 N·m (30 ft lbs), then continue to tighten bolt until the nearest flat on the bolt head aligns with the locking tab.



22

6. Bend locking tabs over the bolt heads.




23

7. Install sealing washer and metal plug. Torque metal-style plug, 1, to 168 N·m (125 ft lbs).

   Tighten rubber-style plug, 2, until it is firmly sealed.


NOTE: *Two style plugs were used depending on production date.*



24


Installation

1. Check that the two dowel pins, 1 and 3, are installed.
2. Clean center housing and parking brake housing mounting faces and apply a continuous bead of specified RTV silicone sealer, 4, as shown.
3. Position discs, 5, on pinion shaft, 2, to align approximately with spaces between friction pads on parking brake assembly.




25

4. Insert FNH00529 brake plate alignment tool, 1, between brake friction pads, 3. Push the actuator arm, 2, forward until the friction pads capture the tool.



26

5. Position park brake assembly into center housing, making sure the discs, 1, are located between friction pads, 2.




27

6. Remove alignment tool, 2, and position the parking brake assembly on the two dowel pins, 1.

NOTE: *Check park brake actuator for proper operation. Remove and reinstall if actuator does not operate properly.*

7. Install retaining bolts and torque to 61 N·m (45 ft lbs).

NOTE: *Engage and disengage the park brake five times to seat the discs on the pinion shaft.*




28

8. Adjust yoke, 1, so end of threads on the cable are flush with the inside of the cable. Tighten jam nut, 2.
9. Position park brake lever in the off position.
10. Connect the yoke to the actuator arm and insert clevis pin, 6, and cotter pin.
11. Install the cable in the mount bracket.
12. Position park brake in the second detent position.
13. Adjust nut, 3, to take up all free travel out of the system, then tighten nut, 4, to secure cable.

NOTE: *There should be a minimum of 35 mm (1.38″) of threads on the cable at 5, to compensate for wear. Adjust yoke back on the cable as required to achieve this dimension.*

14. Assemble the tractor and partially apply the park brake three times while operating the tractor. This will allow the components to seat.
15. Adjust the park brake as detailed in the “Adjustments” portion of this chapter.



29

SECTION 33 – BRAKES AND CONTROLS

Chapter 3 – Trailer Air Brakes (Not Used in North America)

CONTENTS

Section	Description	Page
33 000	Specifications	2
	Torque Specifications	3
	Safety	7
	General Air Brake Safety	7
	General Maintenance Instructions	7
	Description of Operation	8
	System Operation	9
	Air Compressor	10
	Unloader Valve	10
	Reservoir Tank	14
	Right Hand Brake Lamp Switch	14
	Solenoid Valve	14
	Dual Control Valve	15
	Single Control Valve	20
	Air Pressure Switch	24
	Trailer Brake Solenoid Power	24
	Disassembly and Repair	25
	Air Compressor	25
	Air Compressor Lubrication Supply Line	29
	Air Compressor Lubrication Return Line	29
	Air Pressure Supply LIne	32
	Unloader/Valve Silencer	33
	Reservoir	34
	Pressure Switch	34
	Single Control Valve	35
	Dual Control Valve	38
	Solenoid Control Valve	39
	Coupler Connectors	41
	Adjustments	42
	Adjusting the Air Brake Parking Brake	42
	System Testing	44
	Troubleshooting - Air Brake System	47
	Towed Vehicle	51
	Troubleshooting - Towed Vehicle	52

SPECIFICATIONS

Air Compressor

Bore	7.5 mm (0.29″)
Stroke	36 mm (1.4″)
Sweep volume	159 cm^3 (9.7 cu. in.)
Max working speed	3000 RPM
Max working pressure	18 bar (260 PSI)
Lubrication	Supplied from Tractor Engine

Unloader Valve

Cut-out pressure	8.1 bar (118 PSI)
Operating range	7.5 - 8.1 bar (109 - 118 PSI)
Operating temperature range	–40°C to + 150°C (–40°F to +302°F)
Permissible medium	AIR

Single Control Valve

Operating pressure	8.0 bar (116 PSI) maximum
Operating temperature range	–40°C to + 80°C (–40°F to +176°F)
Permissible medium	AIR

Dual Control Valve


Operating pressure (pneumatic)	10 bar (145 PSI) maximum
Operating pressure (hydraulic)	120 bar (1740 PSI) maximum
Operating temperature range	–40°C to + 80°C (–40°F to +176°F)
Permissible medium	AIR
Control medium	Mineral oil

Solenoid Valve

Voltage	12 volts
Operating pressure	8.0 bar (116 PSI)

TORQUE SPECIFICATIONS

Coupler to bulkhead coupler . . . . . 41 N·m (30 ft lbs)




1

Compressor

1. Pulley . . . . . 115 N·m (85 ft lbs)
2. Tube (compressor to unloader valve) . . . . . 75 N·m (55 ft lbs)
3. Elbow (compressor to inlet hose) . . . . . 62 N·m (46 ft lbs)
4. Top port plugs . . . . . 75 N·m (55 ft lbs)
5. Connector (compressor to unloader valve tube) . . . . . 62 N·m (46 ft lbs)
6. Elbow (lube oil pressure supply line to compressor) . . . . . 9.5 N·m (7 ft lbs)
7. Oil pressure supply tube (both ends) . . . . . 9.5 N·m (7 ft lbs)
8. Elbow (compressor to lube oil return) . . . . . 41 N·m (30 ft lbs)
9. Lube oil return tube . . . . . 75 N·m (55 ft lbs)

Compressor bracket bolts


1. Bracket to water pump . . . . 92 N·m (68 ft lbs)
2. Bracket to engine . . . . . 75 N·m (55 ft lbs)




2

Reservoir

1. Connector . . . . . 47 N·m (35 ft lbs)
   (unloader to reservoir and supply to unloader)
2. Swivel connector . . . . . 62 N·m (46 ft lbs)
3. Drain valve . . . . . 47 N·m (35 ft lbs)
4. Top plug . . . . . 47 N·m (35 ft lbs)
5. Elbow . . . . . 41 N·m (30 ft lbs)




3



4

Hydraulic Brake Connections

1. Pressure switch . . . . . 19 N·m (14 ft lbs)
2. Elbow to control valve . . . . . 20 N·m (15 ft lbs)
3. Tube to elbow . . . . . 20 N·m (15 ft lbs)
4. Tube to TEE . . . . . 27 N·m (20 ft lbs)
5. Supply tube (reservoir to single control valve, both ends) . . . . 75 N·m (55 ft lbs)



5

Single Control Valve

1. Valve to bracket bolts . . . . . 62 N·m (46 ft lbs) minimum
2. Couple connectors . . . . . 47 N·m (35 ft lbs)
3. Elbow and TEES to valve . . . . . 41 N·m (30 ft lbs)

Dual Control Valve

4. Valve to bracket bolts . . . . . 15 N·m (11 ft lbs) minimum
5. Couple connector . . . . . 27 N·m (20 ft lbs)
6. Branch TEES . . . . . 27 N·m (20 ft lbs)
7. Ball Stud Nut . . . . . 27 N·m (20 ft lbs) minimum

Solenoid Valve

8. Valve to bracket bolts . . . . . 15 N·m (11 ft lbs) minimum
9. Coupler connector . . . . . 27 N·m (20 ft lbs)

SAFETY

GENERAL AIR BRAKE SAFETY

⚠ WARNING ⚠

When disconnecting the trailer, always disconnect the red hose coupling (supply) first. This locks the trailer brakes and prevents the trailer from moving away when disconnecting.

When connecting the trailer always connect the yellow hose coupling first.

- Do not operate with trailer connected when the low pressure indicator is illuminated.
- When driving without trailer, the covers of the coupling heads in the towing vehicle must be closed.
- The coupling head covers of parked trailer must also be closed. Furthermore the coupling heads of the trailer shall be plugged into the existing empty coupling heads.
- Before connecting the trailer; attention must be paid that the sealing rings of the coupling heads are faultless. The sealing must be clean and not damaged.
- Regular slight greasing of the coupling head sealing improves service life.
- Before starting to drive with one or more trailers, the lever of the trailer load sensing valve must be set into the corresponding position (unloaded, 1/2 load, full load).
- Plastic pipes must not be placed near the engine or the exhaust system.
- Use caution with welding on vehicles with plastic pipes.
- Regularly check the tension of the compressor belt.
- The suction side of the compressor must be connected to the air filter of the engine. This makes sure that only clean air is drawn in.
- Trailers being operated faster than 25 km/h must be examined according the German legislation, StVZO §&29, Annex VIII.
- The reservoir drain valve must be the lowest point of the air braking system.
- The hose connection to the brake actuators must not be lower than the cylinder body (to avoid contact to the ground).
- After assembly all pipe and hose connections must be checked for stable and chafe-free fit. Leakages must be eliminated.

GENERAL MAINTENANCE INSTRUCTIONS

- Check and correct the tension of the compressor poly V-belt every 50 hours.
- The compressor mounting bracket bolts must be checked regularly.
- The air reservoir must be drained daily by means of the drain valve.

Quarterly Maintenance

- Clean the outside of the air reservoir checking for possible corrosion and damage. If damaged, the reservoir must be replaced.
- Grease all joints at the brake devices every 200 - 300 operating hours.
- Check and clean, as necessary, the suction port of the compressor.
- Check all connections of the hydraulic tractor brake and air brake system for leaks. Correct any leaks.
- Check all pipes and hoses for chafe marks and damage. Replace any chaffed or damaged pipes and hoses as required.
- Check the operation of the stoplight switch.
- Check the operation of the low pressure warning system (warning light, audible alarm, and “STOP” message).
- Check travel reserve of the brake pedal.


$$\text{Formula: } \frac{Smax - S}{Smax} * 100 \geq 20\ \%$$

Smax = max. possible travel at the pedal

S = existing operating travel

- Perform the system tests at the coupling heads according to the test instructions.


DESCRIPTION OF OPERATION



6

Air Trailer Brake System Components

1. Air compressor
2. Unloader valve
3. Air reservoir
4. Air pressure switch
5. Single control valve
6. Solenoid valve
7. Dual control valve
8. Couplers (Red, Yellow & Black)



7

SYSTEM OPERATION

The air trailer brakes are controlled from the driver's seat by the tractor foot brake pedal.

The system uses the output from an engine mounted air compressor system and the low pressure hydraulic system to operate a combination single and dual control trailer air brake system. System braking pressure is regulated by the dual control valve that senses the load on the tractor foot brake pedals.

This foot brake operated trailer brake system uses an air compressor to pressurize air, which is collected in a reservoir. The compressed air collected in the reservoir supplies the air pressure required to operate the trailer brakes.

The right hand brake lamp switch controls the solenoid valve used for the advanced braking feature. The brake lamp switch is used to partially open the dual control valve output, resulting in partial application of the trailer brakes before the tractor's hydraulic brakes begin to be applied.

Hydraulic pressure, tapped off the right brake line and controlled by the service brake master cylinder, is used to regulate operation of the dual control valve. As hydraulic pressure in the right brake line increases, output air pressure from the dual control valve increases.


The single control valve operation is controlled by the output pressure from the dual control valve.

Electrical power for the pressure switch and solenoid valve are supplied from keyed power.

Air pressure is monitored by the air pressure switch. If the reservoir pressure is below 5.0 bar (72 PSI) the trailer brake light illuminates, a "STOP" message appears in the engine speed display and an audible alarm will sound.


AIR COMPRESSOR

The air compressor is belt driven via the crankshaft. The compressor takes filtered air, from the tractor air filter, and compresses it to supply the reservoir tank with pressurized air. The compressor, 1, is lubricated from engine oil supply.



8


The compressor is belt drive via the engine. As the piston, 1, moves downward the inlet reed valve, 2, opens as a consequence of the ensuing suction. When the piston reaches bottom dead center the inlet reed valve, 2, closes. The air taken in is compressed as the piston moves upward opening valve, 3, and the compressed air is delivered to the reservoir via the attached tubing.




9

UNLOADER VALVE

The unloader valve controls the operating pressure within the system to prevent system damage from excess pressure. Also removes any contamination from the system during unloading. A silencer valve is attached to the discharge port reducing the noise as air is discharged.



10




11

Delivery Position

The compressed air entering at the inlet port, 1, flows via the closed idle valve, 2, the filter, 3, and the opened check valve 4, into port 5, and from there to the air reservoir.

At the same time the pressure beneath the diaphragm, 6, in chamber 7, rises. The inlet valve, 8, is closed. The chamber, 9, above the valve body, 10, is kept pressureless via the opened outlet valve, 11.




12

Idle Position

If the pressure in chamber 1, is greater than the cut-out pressure set on the spring, 2, the diaphragm, 3, is raised together with the valve body, 4. This allows the outlet valve, 5, to close and the inlet valve, 6, to open. The pressure in chamber, 1, can now reach chamber, 7, thus opening the idle valve, 8, against the force of the spring, 9.

At the same time the check valve, 10, closes due to the fall in pressure in port 11. The compressed air delivered by the compressor escapes to atmosphere via the blow-off nozzle, 12.




13

Automatic Reversal of the Combined Unloader
As the pressure in the reservoir falls, the spring, 1, is again capable, depending on the operating range of the unloader, to push the diaphragm, 2, with the valve body, 3, downwards. Thus spring, 1, closes the inlet valve, 4, and opens the outlet valve, 5. Since the pressure in chamber, 6, is reduced via outlet, 5, into chamber, 7, which is connected with the blow-off nozzle, the spring, 8, will rise the valve body, 9, and close the idle valve, 10. The compressor once again returns to its delivery position.

The operating range of the unloader essentially results from the difference in the surfaces of the diaphragm, 2, the inlet valve, 4, and the outlet valve, 5, in terms of the delivery and idling ranges of the unloader.

RESERVOIR TANK


The reservoir, 1, provides storage for the compressed air generated by the compressor.



14

RIGHT HAND BRAKE LAMP SWITCH


The right hand brake lamp switch, 1, supplies electrical power, from the normally closed side of the switch, to control the solenoid valve when the brake is not applied. When the brake pedal is applied the switch opens.



15

SOLENOID VALVE

The solenoid valve, 1, (Time Advance Solenoid Assembly) controls air pressure to the dual control valve to actuate the advanced braking system. The solenoid valve is closed when powered, from the right hand brake lamp switch, and open when right hand brake pedal is depressed.




16


DUAL CONTROL VALVE

The dual control valve, 1, controls air pressure to the yellow coupler for dual line brake applications and single control valve with inputs from the solenoid valve, right hand service brake valve, and park brake allowing four modes of operation. The Modes of operation are:

1. Released
2. Advanced braking
3. Braking
4. Park brake operation




17




18

1. **Released** - In the released mode the compression spring, 1, pushes the valve sleeve, 2, onto the inlet, 3, keeping it closed. Pressure in the brake line port, 4, is allowed to escape past the park brake actuating piston, 5, and discharge through the exhaust port, 6.




19

2. **Advanced Braking** - When the brake pedal is depressed far enough to open the brake light switch, the solenoid valve opens (de- energized) and air pressure is supplied to port 1 partially opening the valve. This allows between 0.3 and 2.8 bar (4 and 41 PSI) air pressure to be delivered from port 2 to port 3, then to the yellow coupler and port 4 of the single control valve partially applying the trailer brakes.



20

3. **Braking** - As the brake pedal is depressed further applying hydraulic pressure to the right hand brake, pressure is sensed in port, 1, of the dual control valve. As hydraulic brake pressure increases at port, 1, air pressure increases in port 2 until full air reservoir pressure, 7.1 - 8.1 bar (100 - 120 PSI), is obtained.




21


4. **Park Brake Operation** - When the park brake is engaged the dual control valve is fully opened and full air reservoir pressure is supplied to the yellow coupler and to port 4 of the single control valve, black coupler pressure = 0.0 bar (0.0 PSI).

SINGLE CONTROL VALVE

The single control valve, 1, controls air pressure to the black coupler for single line brake applications. As air pressure from the dual control valve increases at port 4 of the single control valve, pressure at the black coupler is reduced.




22



23


Release Position
(Less than 5.2 bar [75 PSI] system pressure)
When the system pressure is less than 5.2 bar (75 PSI), piston, 1, is shifted upwards opening port, 2. The compression spring, 3, will hold diaphragm piston, 4, with sleeve, 5, in its lower end position, closing outlet, 6, and opening inlet, 2. Air pressure also enters chamber, 7, through passage, 8, and chamber, 9, through passage, 10.



24

System Pressure - No Brakes Applied

The compressed air from the tractor's air reservoir flows via port 1 to port 2. At the same time, the compressed air flows, via passage, 3, into chamber, 4, below piston, 5, and via passage, 6, into chamber, 7, above piston, 5. As soon as the pressure in the line to the trailer has reached 5.2 bar (75 PSI), valve, 8, is forced downwards against the force of compression spring, 9, until inlet, 10, is closed.



25

Braking


When the tractor's foot brake is actuated, pressure from the dual control valve, enters chamber, 1, through port 2 forcing the diaphragm piston, 3, with valve sleeve, 4, upwards against the force of compression spring, 5. Outlet, 7, opens, allowing pressure at the black coupler to exhaust through the center of sleeve, 4, and out the discharge/vent hole, 6. Sufficient air will now be emitted to atmosphere to achieve the reaction in pressure required for advanced retardation of the trailer brakes.

At the same time, the pressure in chamber, 8, will fall and piston, 9, is forced downwards by the supply pressure in chamber, 10, acting on its upper portion. It takes with it valve sleeve, 4, which in turn closes outlet, 7, as it settles on the double cone valve.

As described above, the increased braking effect of the tractor causes the pressure of the trailer's control line to be further reduced while the advanced retardation of the trailer is maintained. When the tractor brake is released, the pressure in chamber, 1, is reduced once again, causing Diaphragm piston, 3, and valve sleeve, 4, being forced downwards through the force of compression spring, 5. Inlet, 11, opens and the supply air present at port 12 flows to the trailer's control line via port 13.

AIR PRESSURE SWITCH

The air pressure switch, 1, is a normally open switch requiring 5.2 bar (75 PSI) air pressure to close. The switch is located in the system supply line between the reservoir and control valves.



26

TRAILER BRAKE SOLENOID POWER

When the key switch is turned on, power from the key switch, pin 6, flows through wire CM24 to pin 85 on the Auxiliary Power Relay (MDP-R12), then from pin 86 on MDP-R12 through wire CM31A to ground, energizing the relay. After relay MDP-R12 is energized, power from the main fuse panel flows from MFP-2 through wires CM15B and CM17B, relay MDP-R12, wire CM32, fuse MDP-F22, wire CM43, and wire CM47 to the right brake light switch. With the brake pedal full up, power flows from the brake light switch through wires CT04A and CT03A, connector C194 pin 3, and wire RT03 to the trailer brake solenoid. From the trailer brake solenoid power flows through wire RT04, connector C194 pin 4, and wires CT07B and CT08B to the cab floor ground.


A diode is also added to the trailer brake solenoid circuit to reduce arcing across the brake light switch and eliminate electromagnetic interference caused by the solenoid when it is de-energized. The diode is connected in the circuit by wires CT09B and CT05A.

DISASSEMBLY AND REPAIR

AIR COMPRESSOR


Removal

1. Park tractor, set parking brake, turn off engine and place lockout tag on ignition switch.
2. Open left side access door and raise hood.
3. Remove three bolts, 1, washers and nuts retaining fan guard, 2, and remove fan guard.




27

4. Use a 1/2 inch drive bar on the belt tensioner, 1, and rotate clockwise. Remove accessory drive belt from the compressor pulley and release tensioner.




28

5. Disconnect oil supply, 1, and return, 2, lines to compressor.
6. Loosen hose clamp, 3, and remove intake hose, 4, from fitting.
7. Disconnect air pressure line, 5.




29

8. Remove bolts and nuts, 1, securing compressor to mounting bracket. Remove compressor.




30

9. Remove air fittings, 1 and 2, and oil fittings, 3 and 4, fittings from compressor.



31

10. Secure compressor and compressor pulley from turning. Remove center nut on pulley.
11. Use a puller to remove the pulley from the shaft.




32

Disassembly

Individual compressor components are non- serviceable through New Holland Parts. For availability of individual components and rebuild specifications contact your local WABCO dealer.

Air Compressor Components


1. Mono block
2. Rear main sleeve bearing
3. End cover
4. Bottom plug
5. Crankshaft
6. O ring
7. Front end cover
8. Crankshaft seal
9. Cap screws
10. Washer
11. Nut
12. Connecting rod assembly
13. Piston, Rings, & Wrist pin assembly
14. Cylinder head gasket
15. Valve plate
16. Inlet reed valve
17. Discharge reed valve
18. Washer/Spacer
19. Discharge valve stop
20. Spacers/Washers
21. Cap screws
22. Inlet & Discharge cavity gasket
23. Cylinder head
24. O ring
25. Plug
26. Plug washer
27. Cylinder head bolt



33


Installation

1. Place pulley, 5, on compressor shaft and secure with washer and nut, 6. Torque nut to 115 N·m (85 ft lbs).
2. Install air and oil line fittings on compressor. Torque air fittings, 1 and 2, to 62 N·m (46 ft lbs). Leave oil fittings, 3 and 4, to loose to adjust angle.




34

3. Place compressor on bracket and tight with bolts and nuts, 1.



35


4. Attach oil return line, 2, to compressor. Torque elbow fitting, 6, to 41 N·m (30 ft lbs). Torque oil return tube, 2, fitting to 75 N·m (55 ft lbs).
5. Attach oil pressure line to compressor. Torque elbow fitting, 7, to 9.5 N·m (7 ft lbs). Torque hose fitting, 1, to 9.5 N·m (7 ft lbs).
6. Attach air supply tube to compressor on fitting, 8. Torque hose fitting, 5, to 75 N·m (55 ft lbs).
7. Install the air inlet hose on fitting, 3, and tighten hose clamp, 4.



36


8. Use a 1/2 inch drive bar the belt tensioner, 1, and rotate clockwise. Place belt over compressor pulley and release tensioner.

IMPORTANT: *Ensure that the belt is routed as shown in figure.*



37

9. Install fan guard, 1, with three bolts, washers and nuts.
10. Close hood and side access door and remove lockout tag.
11. Start engine and allow system air pressure to build to operating pressure. Perform leak- down test.




38

AIR COMPRESSOR LUBRICATION SUPPLY LINE

To remove the air compressor lubrication supply line, 1, disconnect the line at the engine oil pressure switch, 2, and air compressor. Then remove line.

Installation is the reverse of removal.




39

AIR COMPRESSOR LUBRICATION RETURN LINE

Removal


The oil return line is composed of two tubes, 1 and 2, connected by a hose, 3. Each section can be replaced individually. The upper tube, 1, and connector hose, 3, can be replaced by loosen- ing the hose clamps, 4 and 5, and disconnecting the tube from the compressor. To remove and replace the lower tube, 2, or entire tube assembly, use the following procedure.



40


1. Remove bolts, 4, securing side cover mounting brackets to the frame and remove the side cover, 2.
2. Remove bolt, nut and spacer, 1, connecting side cover, 2, to coolant reservoir, 3.
3. Remove bolt, washer and spacer, 5, attaching front of coolant reservoir to frame. Move reservoir so it rests on the front axle.

NOTE: *It is not necessary to disconnect coolant line from reservoir.*




41

4. Remove nuts, 1, and bolts securing lower tube section, 2, to timing gear cover, 3.




42

5. Loosen fitting, 1, at compressor and remove line assembly.




43

6. Loosen clamps, 1, on connector hose, 2. Pull connector hose from lower, 3, and upper, 4, tubes.
7. Assemble connector hose between upper and lower tubes with hose clamps. Tighten lower hose clamp. Leave upper hose clamp loose.



44

8. Attach lower end of tube assembly, 2, to timing gear cover, 3.




45

9. Attach upper end, 1, of tube assembly to compressor. Adjust orientation of upper tube in hose, as necessary. Torque tube fitting to 75 N·m (55 ft lbs).


NOTE: *If necessary, loosen elbow fitting in compressor to properly align tube.*

10. Tighten upper hose clamp, 5, on connector hose.



46

11. Loosely attach front of coolant reservoir, 3, to frame with bolt and spacer, 1.
12. Install side cover, 2, to frame. Leave bolts, 4, loose.
13. Carefully close side access door, making sure door latch is seated in bracket, 6, on side cover. Move side cover forward or rearward, as necessary. Tight side cover attaching bolts, 4.
14. Attach coolant reservoir to side cover using bolt, spacer, washer and nut, 5.
15. Tight front coolant reservoir bolt, 1.




47

AIR PRESSURE SUPPLY LINE

Removal

1. If equipped with front wheel drive, remove drive shaft, 1. Refer to Section 9 - Front Axle and Steering for proper procedures.
2. Loosen fitting, 2, at unloader valve and remove line.




48

3. Loosen fitting, 1, at compressor.

NOTE: *It may be necessary to loosen fittings at both ends before removing lines from fittings.*

IMPORTANT: *Do not damage ends, ferrule or nut of line if it is to be reused.*

4. Lower disconnected line, and remove from under tractor.



49

Installation


1. Raise compressor end of line, 2, inside frame rail, taking care not to damage end. Loosely attach end, 1, to fitting in compressor.
2. Attach line to unloader fitting, 1. Torque both ends of air pressure supply line to 75 N·m (55 ft lbs).
3. Install driveshaft, if equipped.

UNLOADER VALVE/SILENCER

Removal


1. Drain all air pressure in the system using the reservoir bleed port.
2. Remove unloader valve guard, 1.

NOTE: *The lower reservoir retaining strap may fall when loosened.*



50

3. Loosen clamp, 2, and remove the exhaust silencer, 1, on the unloader valve.
4. Disconnect the compressor supply tube, 3, and swivel connector, 4, from the reservoir. Remove the unloader valve.
5. Remove air inlet and outlet fittings, 5, from unloader valve.



51

Disassembly

The unloader valve is a non-serviceable component. Failure of the unloader valve requires replacement of the valve as an assembly.

NOTE: *The unloader valve and silencer are separate components and must be ordered individually when replacing both components.*


Installation

1. Install the air inlet and outlet fittings, 5, on the unloader valve. Torque each connector on the valve to 47 N·m (35 ft lbs).

IMPORTANT: *Improper installation of the fittings and unloader valve may result in system failure.*

2. Connect the unloader valve to the reservoir by the swivel connector, 4, on the reservoir, torque to 62 N·m (46 ft lbs). Attach the compressor supply tube, 3, to supply fitting, 5, torque to 75 N·m (55 ft lbs).
3. Reinstall unloader valve guard.
4. Pressurize the system checking for operation and leaks.

RESERVOIR



52


Removal

1. Drain all air pressure in the system using the reservoir bleed port.
2. Remove unloader valve, 1. (see unloader valve removal in this section).
3. Disconnect the reservoir discharge tube, 2, from the fitting, 3.
4. Support reservoir and remove the reservoir retaining strap bolts. Remove straps and reservoir from bracket.
5. Remove fittings, 3, 4, 5, & 6 as required.

Installation

1. Install fittings, 3, 4, 5, & 6. Torque unloader swivel connector, 5, to 62 N·m (46 ft lbs), elbow, 3, to 41 N·m (30 ft lbs), and drain valve, 6, and top plug, 4, to 47 N·m (35 ft lbs).
2. Install reservoir to mounting bracket with straps. Secure the top strap to hold the reservoir in place until all connections are made.
3. Connect the discharge tube, 2, torque to 75 N·m (55 ft lbs).
4. Install the unloader valve and guard (see unloader valve installation).
5. Pressurize the system checking for operation and leaks.

PRESSURE SWITCH



53

Removal

1. Drain all air pressure in the system using the reservoir bleed port.
2. Disconnect the air pressure switch connector C195, 1.
3. Remove air pressure switch, 2, from supply tube, 3.

Installation

1. Install the air pressure switch, 2, torque to 19 N·m (14 ft lbs).
2. Connect electrical connector C195, 1.
3. Pressurize the system checking for operation and leaks.


SINGLE CONTROL VALVE

Removal

NOTE: *Access for removal and installation of the control valve is increased by moving the right rear tire and wheel assembly out on the axle or by completely removing the tire and wheel assembly.*

1. Loosen fitting, 4, and disconnect supply line, 3, from elbow, 2.
2. Disconnect three hoses, 5, on front side of single control valve, 1.


NOTE: *Take care not to damage sealing rings on hose fittings.*



54


3. Remove elbow, 1, and tee fitting, 2.
4. Remove nuts, 3, securing valve to mounting bracket, 4.

IMPORTANT: *Do not loosen bolts from valve. Valve housing is threaded and mounting bolts hold valve housing together.*




55

5. Hold valve assembly to prevent stretching or damaging remaining attached air line (red), 1. Loosen and remove fitting, 1, securing air line to valve.



56

6. Remove adapter, 1, and tee, 2, from single control valve.



57

Disassembly

The single control valve is a non-serviceable component. Failure of the single control valve requires replacement of the valve as an assembly.

Installation


IMPORTANT: *Lube all sealing rings with petroleum jelly before assembly.*

1. Install fittings, 1, into ports 2 and 4 on single control valve**.**

NOTE: *The single control valve Ports are identified by numbers in the housing.*

   Torque adapter fittings, 1, to 47 N·m (35 ft lbs). Install tee fitting, 2, in port 1 and leave loose to allow angle adjustment.

2. While holding valve in hand, attach air line (red), 1, to tee fitting in port 1. Tight line.




58

3. Place valve assembly bolts through holes in mounting bracket, 4. Secure to mounting bracket with nuts, 3. Torque nuts to 62 N·m (46 ft lbs).

IMPORTANT: *Do not loosen bolts from valve. Valve housing is threaded and mounting bolts hold valve housing together.*

4. Attach tee, 2, and elbow, 1, to tee fitting on port 1. Leave fittings loose to allow angle adjustment.




59

5. Attach lines, 1, to ports as shown and torque to 47 N·m (35 ft lbs).

Single Control Valve	Connects To
Port 1	Port 1 on Dual Control Valve
Port 2	Black Coupler Line
Port 4	Port 2 on Dual Control Valve

6. Attach reservoir supply line, 2, to elbow fitting, 3. Torque to 75 N·m (55 ft lbs).
7. Torque tee fittings, 4, to 41 N·m (30 ft lbs).
8. Pressurize the system checking for operation and leaks.



60

DUAL CONTROL VALVE

Removal


NOTE: *Access for removal and installation of the control valve is increased by moving the right rear tire and wheel assembly out on the axle or by completely removing the tire and wheel assembly.*

1. Disconnect air lines, 1.


NOTE: *To aid access to hoses, loosen nut on tee fittings to allow fittings to rotate slightly.*

2. Lift the outer ring on the parking brake cable, 2, and remove from ball stud.

3. Using a suitable container to catch fluid, disconnect the hydraulic brake line, 1, from the dual control valve.
4. Remove fitting, 3, from port 42 and Tee fittings, 4.
5. Remove mounting bolts, 2, and nuts. Remove valve.



61



62

Disassembly

The dual control valve is a non-serviceable component. Failure of the dual control valve requires replacement of the valve as an assembly.


Installation

IMPORTANT: *Lube all sealing rings with petroleum jelly before assembly.*

1. Attach valve to mounting bracket with bolts and nuts, 2. Torque to 15 N·m (11 ft lbs).
2. Attach hydraulic brake line, 1, to port 41. Torque fitting to 27 N·m (20 ft lbs).
3. Install fitting, 3, in port 42, torque to 27 N·m (20 ft lbs).
4. Install Tee fittings, 4, in valve and leave loose to adjust angles.

5. 5. Attach air lines, 1, to fittings as shown. Torque to 27 N·m (20 ft lbs).

Dual Control Valve	Connects to
Port 1	Tee Fitting on Supply Line from Reservoir and Solenoid Valve
Port 41	Hydraulic Brake Line
Port 42	Solenoid Valve
Port 2	Port 4 on Single Control Valve and Yellow Outlet Line



63


6. Torque Tee fittings, 3, to 27 N·m (20 ft lbs).
7. Raise outer ring on parking brake cable, 2, and attach to ball stud. Ensure outer ring closes properly around ball stud and cable is securely attached.
8. Bleed brakes. Refer to Bleeding The Brakes in this section for proper procedures.
9. Check parking brake cable operation. Refer to Parking Brake Cable Adjustment in this manual.

SOLENOID CONTROL VALVE

Removal


NOTE: *Access for removal and installation of the control valve is increased by moving the right rear tire and wheel assembly out on the axle or by completely removing the tire and wheel assembly.*

1. Disconnect air lines to port 1 Tee, 1, and port 42, 2, at dual control valve, 3. Hoses should be removed with solenoid valve.



64

2. Disconnect wire harness, 2.
3. Remove bolts and nuts, 3, and control valve, 1, from mounting plate.



65

4. Secure valve, 4, in a vice. Remove hoses, 2, fitting, 1, and hose, 3.


Disassembly

The solenoid control valve is a non-serviceable component. Failure of the solenoid control valve requires replacement of the valve as an assembly.

Installation


IMPORTANT: *Lube all O rings with petroleum jelly.*

1. Use a vice to retain the valve, 4. Install fitting, 1, in port 2. Torque to 27 N·m (20 ft lbs).
2. Attach hose, 2, to fitting in port 2.
3. Attach hose, 3, to valve at top port.




66

4. Attach valve, 1, to mounting bracket, 4, using bolts, 3, and nuts. Torque nuts to 15 N·m (11 ft lbs).
5. Attach wire harness, 2, to valve. Tighten strain relief.




67

6. Attach hose, 1, and hose, 2, to dual control valve, 3. Torque to 27 N·m (20 ft lbs).



68

COUPLER CONNECTORS



69

Removal

1. Drain all air pressure in the system using the reservoir bleed port.
2. Remove the coupler, 1, from the bulkhead connector, 2.

NOTE: *Each coupler has a color coded cover that corresponds to the color line it is connected to; red, yellow, and black. The couplers are not interchangeable with each other because of the difference in operation of each.*

Installation

1. Install coupler, 1, on bulkhead connector and torque to 41 N·m (30 ft lbs).
2. Pressurize the system checking for operation and leaks.

ADJUSTMENTS


ADJUSTING THE AIR BRAKE PARKING BRAKE

The air trailer brakes must be applied when the park brake handle is in the third notch (click).

Adjust the air brake park brake with the air trailer brake system pressurized, tractor parked on level ground, the engine off, and the wheels blocked front and rear.


To adjust the air trailer brake park brake:

1. Position the park brake handle in the fully lowered position.
2. Position the park brake arm, 1, on the dual control valve at approximately 8 o'clock position.




70

3. Install trailer couplers equipped with a pressure gauge in each tractor coupler (red, yellow, and black). The coupler pressures should be: red 7.1 - 8.1 bar (100 - 120 PSI) system pressure, yellow - zero pressure, and black 4.8 - 5.2 bar (70 - 75 PSI).



71



72


4. Lift the park brake lever to the third notch (click). When the park brake lever goes from the second to third notch (click), pressure in the yellow coupler must equal the pressure in the red coupler and pressure in the black coupler must fall to zero.
5. Adjust the locking nuts, 1, on the park brake cable, 2, attached to the dual control valve, 3, until the proper black and yellow coupler pressures are obtained.

NOTE: *It may be necessary to start the tractor and build up system pressure after several cycles of the park brake handle.*

SYSTEM TESTING

CHECKING RESERVOIR FILL TIME

1. Drain the reservoir using the reservoir drain valve.
2. Connect a trailer coupler equipped with pressure gauge to the red coupler.
3. Start the tractor and using a timing device, begin timing the length of time for the compressor to build 7.1 bar (103 PSI). Total time must be less than 3 minutes at engine idle.



73

LEAKAGE TEST


1. Connect a trailer coupler equipped with pressure gauge to the red coupler.
2. Start the engine. Fill system up to cut-off pressure.
3. Stop the engine. Pressure supply must be between 7.1 - 8.1 bar (100 - 120 PSI).
4. Check all ports and connections for leakages by soaping.
5. The system is tight, if the pressure decrease within 10 minutes is less than 0.2 bar (3 PSI).

CHECKING UNLOADER VALVE OPERATION

1. Connect a trailer coupler equipped with pressure gauge to the red coupler.
2. Fill the system up to the cut-off pressure of the unloader.
3. With the engine at idle, reduce the supply pressure slowly by 1.0 to 2.5 bar (15 to 36 PSI), until system pressure is below 6.9 bar (100 PSI).
4. Unloader valve must close allowing air compressor to pressurize system again.

CHECKING PARK BRAKE OPERATION

1. 1. Connect a trailer coupler equipped with pressure gauge to each coupler (red, yellow, and black).
2. 2. Fill system to cut off pressure. Red coupler must be at 7.1 - 8.1 bar (100 - 120 PSI).
3. 3. Apply park brake. Yellow coupler pressure must be equal to red coupler pressure 103 - 118 PSI. Black coupler pressure must equal at 0 PSI.



74

CHECKING SINGLE AND DUAL LINE BRAKE OPERATION

1. Connect a trailer coupler with gauge to the red, yellow, and black couplers.
2. Fill system up to cut-off pressure. Red coupler should maintain between 7.1 - 8.1 bar (100 - 120 PSI).
3. Secure tractor against rolling away, and release parking brake.
4. Check Black coupler pressure. Pressure must be 4.8 - 5.2 bar (70 - 75 PSI).
5. Slowly depress brake pedal. At partial braking, yellow coupler, dual line) pressure is at 1.0 bar (14 PSI), the black coupler pressure, single line, must be between 2.3 - 4.3 bar (33 - 62 PSI). As you continue depressing the brake pedal, pressure at black coupler, single line, must decrease smoothly. Pressure at the yellow coupler must increase smoothly. At full braking, black coupler pressure must equal 0 bar (0 PSI), yellow coupler pressure must equal red coupler pressure 7.1 - 8.1 bar (100 - 120 PSI).
6. Slowly release foot brake. As the foot brake is slowly released pressure in the black coupler must increase smoothly.
7. Apply parking brake. Pressure in the black coupler must be 4.8 - 5.2 bar (70 - 75 PSI).

ADVANCE BRAKING OPERATION

1. Slowly depress brake pedal until rear brake lights illuminate.
2. Yellow coupler pressure must be between 0.3 - 2.8 bar (4 - 41 PSI).
3. Black coupler pressure must be between 1.8 - 4.8 bar (26 - 70 PSI).

CHECKING ALARM OPERATION

1. With engine off, de-pressurize the system using the reservoir drain.
2. Install trailer coupler with line port open in red coupler to prevent system from building pressure.
3. Block the wheels to prevent the tractor from moving. Release the park brake.
4. Using a timing device, start the engine. The trailer brake light must be illuminated on the dash.
5. After 60 seconds, the trailer brake light must still be illuminated, flashing “STOP” message must appear in the engine speed display, the audible alarm must be heard and fault code book flash.
6. Apply parking brake. Flashing “STOP” message, alarm, and fault code must stop.

NOTE: *When the air system is below 72 PSI and park brake disengaged, stop message, alarm and trailer brake light are activated.*


When the air system is above 72 PSI and park brake disengaged, stop message, alarm and trailer brake light must stop.


TROUBLESHOOTING - AIR BRAKE SYSTEM


As a first step in troubleshooting the air brake system, perform the following preliminary checks:

1. Check the compressor poly V-belt for proper tension and wear.
2. Check the system for leaks at all connections.
3. Check the system for kinked, pinched, or damaged components.

PROBLEM	PROBABLE CAUSE	CORRECTION
Fill time too long. Trailer brake warning light does not go out after 3 minutes with engine at idle.	Leakage in system.	Check system for leaks.
	Loose or damaged compressor drive belt.	Tighten and/or replace drive belt.
	Unloader valve not switching closed.	Check operation of unloader valve.
	Defective compressor.	Replace compressor.
	Defective pressure switch.	Replace switch.
Residual pressure at yellow coupling head with brake released.	Park brake not completely released.	Release park brake. Readjust if necessary.
	Master cylinder pressure not released in right brake.	Check pressure in master cylinder right brake line.
	Right brake light switch out of adjustment.	Adjust brake light switch.
	Right brake light switch defective.	Replace brake light switch.
Unloader blows off too often without braking.	Switching pressures of unloader adjusted improperly.	Replace unloader valve.
	Leaks in the system.	Check system for leaks.


Unloader blows off too often without brake application.
Check switching period of the unloader.
CORRECT
NOT CORRECT
Check compressed air system for leakages.
Adjust unloader or, if necessary, exchange it.
- fittings
- drain valve
- check valve in the unloader
Eliminate leakages.
END


Reservoir Pressure not okay.
Check pressure switch.
Switch okay.
Switch defective.
Check air system for leakage.
Exchange pressure switch.
END
Tight.
Leaky.
Eliminate leakage.
Check tension of V-belt.
Not okay.
END
OKAY
Tighten V-belt or exchange it, if necessary.
END
Check unloader and adjust or exchange it, if necessary.
Pressure not okay.
Pressure okay.
Check pressure at port 2 of the compressor.
Pressure okay.
END
END
Clean suction filter.
Pressure not okay.
Pressure not okay.
Pressure okay.
Clean cylinder head and valves and exchange them, if necessary.
END
END


Filling Time is too long.
Check pressure switch.
Switch okay.
Switch defective.
Check system for leakages.
Exchange switch.
END
Tight.
Leaky.
Eliminate leakage.
Check tension of V-belt.
Not correct.
END
CORRECT
Tighten V-belt and exchange it, if necessary.
END
Check compressor and exchange it, if necessary.
END

TOWED VEHICLE

GENERAL MAINTENANCE INSTRUCTIONS

Trailer Set-up

In trailers the lengths of the pipes from the drawbar to the towing vehicles (resp. to the first trailer) must be so chosen that a drawbar deflection of 75 degrees in both directions is possible.

In drawbar trailers a hose connection is to be chosen from the middle of the fifth wheel to the cylinder. The lines must be long enough that they do not twist when the drawbar is turned by 75 degrees in both directions.

Drain the trailer reservoirs daily by means of the drain valve.

Quarterly Maintenance

- Clean the pipe filters.
- Check brake lever and linkage movement, must be free-moving. Grease if necessary.
- Check condition and fixation of all dust sleeves and bellows. Damaged parts must be exchanged.
- Check pipes and hoses for leakages and possible damages. Any leakages and damage must be eliminated.
- Check the pressures at the cylinders according to the test instructions.
- Check brake cylinder stroke. The brake cylinders of the trailer must move only 1/2 to 2/3 of the possible total stroke in case of full brake application. Re-adjust if the brake actuators reach 2/3 of the total stroke.

TROUBLESHOOTING - TOWED VEHICLE

As a first step in troubleshooting the towed vehicle air brake system, perform the following preliminary checks:

1. Verify the tractor air brake system is functioning properly.
2. Check the system for leaks at all connections.
3. Check the system for kinked, pinched, or damaged components.


PROBLEM	PROBABLE CAUSE	CORRECTION
Towed vehicle does not brake (single line system)	Trailer supply pressure low	Check towing vehicle braking system
	In line filters (if equipped) blocked	Check and clean line filters
	Trailer reservoir pressure low	Check trailer brake valve and exchange if necessary
	Trailer brake cylinder travel greater than 2/3 total stroke	Adjust brake cylinder stroke
Towed vehicle does not brake (dual line system)	Trailer supply pressure low	Check towing vehicle braking system
	In line filters (if equipped) blocked	Check and clean line filters
	Trailer reservoir pressure low	Check trailer brake valve and exchange if necessary
	Trailer brake cylinder travel greater than 2/3 total stroke	Adjust brake cylinder stroke
Towed vehicle does not brake strong enough	In adequate pressure at coupling heads or towing vehicle	Check towing vehicle system operation
	Defective trailer control valve	Replace trailer control valve
	Trailer pressure lead inadequate	Check towing vehicle pressure lead operation
	Improperly adjusted trailer brake cylinder travel	Adjust trailer brake cylinder travel


Testing Checklist
For agricultural and forestry tractors and trailers.


Towing Vehicle			
Brake	**Position**	**Measuring point *0 KK**	**Pressure at coupling head (bar) required actual value**
one-line			
foot brake	not applied	1-line	4.8 to 5.6
	fully applied	1-line	0
hand brake	released	1-line	4.8 to 5.6
	engaged	1-line	0
one-line			
foot brake	not applied	supply	7.0 to 8.1
		brake	0
	fully applied	supply	7.0 to 8.1
		brake	7.0 to 8.1
hand brake	released	supply	7.0 to 8.1
		brake	0
	engaged	supply	7.0 to 8.1
		brake	7.0 to 8.1


*) KK → coupling head

SUPPLY = RED
BRAKE = YELLOW
ONE-LINE = BLACK


Trailer does not brake strong enough, it slides on.
Check pressure at the coupling heads of towing vehicle resp. trailer.
Pressures are okay.
Supply pressure is not okay.
Brake pressure is not okay.
Check braking system of the trailer.
Check reservoir pressure.
Check trailer control valve and exchange it, if necessary.
Pressure okay.
Pressure not okay.
Check pressure lead of the trailer brake valve according to trailer specifications.
Check pressure at port 2 of the compressor.
END
Pressure not okay.
Pressure okay.
END
Check tension of V-belt.
Check unloader.
Clean suction filter.
OKAY
Not okay.
If oil leaks at port 2 of the compressor, clean cylinder head and valves.
Check braking system of the trailer.
Adjust or exchange.
END


Trailer does not brake (one-line braking system).
Check supply pressure in the line filters.
OKAY
Not okay.
Check pressure reduction when braking.
Check braking system of the towing vehicle.
No pressure reduction.
Pressure reduction.
END
Check and clean line filters.
Check reservoir pressure.
Pressure not okay.
Trailer brakes.
Trailer does not brake.
Check trailer brake valve and exchange it, if necessary.
END
Pressure okay.
Check cylinders.
END
Check stroke, if more than 2/3 of total stroke, adjust the brake.
END


Trailer does not brake (two-line braking system).
Check supply pressure at the line filters.
Pressure okay.
Pressure not okay.
Check line filters and clean them, if necessary.
Check braking system of the towing vehicle.
Trailer brakes.
Trailer does not brake.
END
END
Check cylinders.
Check cylinder stroke, if more than 2/3 of total stroke, adjust the brake.
Trailer brakes.
Trailer does not brake.
END
Check reservoir pressure.
Pressure okay.
Pressure not okay.
Check trailer brake valve and exchange it, if necessary.
Check braking system of the towing vehicle.
END


Residual Pressure at Yellow Coupling with Park Brake released.
Park brake completely released?
YES
NO
Adjust park brake linkage.
Pressure okay.
Pressure not okay.
END
Check adjustment of master cylinder. The pressure in the hydraulic brake circuit is not reduced (check with gage).
Master cylinder is not okay.
Master cylinder is okay.
Pressure is not yet reduced.
Correct adjustment.
Check at port 2 of trailer control valve whether pressure is reduced. Exchange device, if necessary.
Adjustment is okay.
END


SECTION 33 – BRAKES AND CONTROLS

Chapter 4 – Trailer Air Brake Electrical System (Not Used in North America)

CONTENTS

Section	Description	Page
33 000	Description of Operation	2
	Trailer Brake light	2
	Low Pressure Alarm	2
	Air Pressure Switch Power	3
	Harness Removal and Installation	4
	Cab Trailer Wiring Harness	4
	Rear Trailer Harness	8
	Troubleshooting	11

DESCRIPTION OF OPERATION




1

TRAILER BRAKE LIGHT


The trailer brake lamp, 1, will illuminate when the system air pressure is below 5.0 bar (75 PSI).

LOW PRESSURE ALARM

When the air reservoir pressure is below 5.2 bar (75 PSI), the park brake is not engaged and engine has been running more than 60 seconds, a pulsating alarm will sound and a “STOP” message will flash in the engine speed display.



2



19994118

3

The trailer brake electrical system is powered from the main fuse MFP-2, through wires CM15B and CM16B which powers the Cold Start System (MDP-F27), Key Switch (MDP-F26), and Un-switched Memory Power (MDP-F25). Wires CM15B and CM17B supplies power to the Front Console (EIC), Turn Signals and Right Hand Console (RHC) when the Auxiliary Power Relay (MDP-R12) is energized by the key switch.

The air trailer brake electrical system contains two separate electrical circuits, one for the alarm system controlled by the air pressure switch and one for the trailer brake solenoid operation.

AIR PRESSURE SWITCH POWER

When the key switch is turned on, power flows from pin 5 through wire CT01, connector C194 pin 2, wire RT01, and to pin A on the air pressure switch. The switch is normally open, requiring 5.2 bar air pressure to close. When the system air pressure system is greater than 5.2 bar, the switch closes. Power then flows from pin B on the air pressure switch through wire RT02, connector C194 pin 2, wire CT02, to the CCM at connector C006 pin 8.

Input information from the air pressure switch, park brake switch, and engine oil pressure switch is processed in the CCM and communicated to the EIC through the CAN network. The EIC then reports the system status by illuminating the trailer brake light, flashing a “STOP” message, sounding the audible alarm, and/or reporting a fault code based on the system conditions.


HARNESS REMOVAL AND INSTALLATION

CAB TRAILER WIRING HARNESS

Removal

1. Remove battery cover, 1, and disconnect the battery.

NOTE: *To remove the battery cover on tractors equipped with air brakes the right side steps must be removed first.*




4

2. Remove the seat by removing the four nuts at the base of the seat, 1, and disconnecting the electrical plug at the rear of the seat. Remove the seat through the rear window.


NOTE: *If required, disconnect the two gas struts from the rear window. Support the window in the horizontal position.*

NOTE: *The seat is heavy and will require two people to lift it out of the cab.*




5

3. Remove the right side steering console cover, 1, as shown. Repeat on the left side.




6

4. Remove wire CT04A from pin 4 of the brake light switch, 1. Disconnect wire CT06 from CM58 at connector C197, 2. Remove wire CT01 from the ignition switch, 3, pin 5.
5. Remove wiring harness from under front console.




7

6. Remove the bolts, 1, (two on each side), and lift out the front section of the floor mat.
7. Remove the rear section of floor mat. Make sure the seat wiring harness has been pushed through the floor mat before removal.
8. Remove the left-hand side cab trim (see Section 90, Cab Components for more information).




8

9. Remove the floor plate screws and lift out the floor plate.
10. Remove the wiring harness, 1, from under the floor plate and along the left-hand side cab trim.




9

11. Remove wire CT02, 1, from connector C006, 2, pin 8.



10

12. Remove the bulkhead connector C194, 1, in the right rear corner of the cab by:
    - Disconnecting connector C194, 2, from under the cab.
    - Removing the retaining ring, 3, from under the cab.
    - Remove nut on the inside cab floor ground, 4, and remove wire CT08.
    - Remove the harness from the cab.




11

NOTE: *Access for removal and installation of the wiring harness connector C194 is increased by moving the right rear tire and wheel assembly out on the axle or by completely removing the tire and wheel assembly.*

Installation


1. Install the bulkhead connector C194 in the right rear corner of the cab by:
    - Inserting connector C194 into the cab floor opening.
    - Installing the retaining ring, 1, from under the cab.
    - Connecting connector C194, 2, from under the cab.
    - Attaching wire CT08 to the inside cab floor ground, 3.

2. Install wire CT02, 1, into connector C006 pin 8, 2.




12

3. Install the wiring harness, 1, along the left-hand side cab trim and along the cab main harness under the floor plate. Secure to cab main harness with strap ties, 2.
4. Install the floor plate and lift out the floor plate screws.



13

5. Install wiring harness under front console.
6. Install wire CT04A into pin 4 of the brake light switch, 1. Attach connector C197 to wire CM58. Install wire CT01 into the ignition switch, 2, pin 5.
7. Install left-hand cab trim.
8. Install front and rear floor mats.
9. Install steering console covers.
10. Install the seat.
11. Perform operational check on the system.




14

REAR TRAILER HARNESS


Removal

1. Disconnect connector RT194, 1, at right rear of cab.




15

2. Disconnect connector C196, 1, from the solenoid valve, 2.



16


3. Disconnect connector C195, 1, from the air pressure switch, 2.
4. Remove all wire ties securing rear trailer harness to rear main harness and remove rear trailer harness from tractor.



17


Installation

1. Connect connector RT194, 1, at right rear of cab.




18

2. Run wiring harness along rear main harness and connect C196 to the solenoid valve and C195 to the air pressure switch.
3. Use wire ties to secure rear trailer harness to rear main harness.




19


RT194
C196
C195
C007
C080
C071
C070
CT194
24 16 8
17 9 1
C006
CM19-P-18
C072
CM83-Y-18
CM82-Y-18
C195
C080
CM13-Y-18
C16 D16
C1 D1
C007
CM259-5-16
CM260-T-16
CT194
C196
4 2
3 1
C071
CM47-N-18
CT06-W-18
CT04A-W-18
RT194
C197
CT03A-W-18
RT03-U-18
CT05A-W-18
CT07B-W-18
RT04-N-18
CM46E-N-18
CM47-N-18
CT04A-W-18
CT07B-W-18
SPL-B
CT08A-W-18
CT06-W-18
CM58-Y-18
50A
CM158-R-8
CM168-R-10
CM178-R-10
CM32-N-10
CM31A-B-18
EIC
CM24-N-18
ACC
FEED
10A
CM26-R-18
IGN
ST
MODULE-EIC
TRAILER BRAKE LAMP
CAN SYS LINK
CCM MODULE
J3-8
CT02-Y-18
RT02-Y-18
CT01-N-18
RT01-N-18

TROUBLESHOOTING

FAULT CODE F337 - TRAILER BRAKE FAULT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (Section 55, Chapter 2, page 2) and "Troubleshooting Checklist" (Section 55, Chapter 2, page 5) before performing the procedures on this fault code.*



SECTION 35 - HYDRAULIC SYSTEMS

Chapter 1 - Introduction

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	4
	Introduction	4
	Closed Center Load Sensing (CCLS) Pump and Remote Valve System	5
	Standard Flow Hydraulic System	13
	Megaflow Hydraulic System	15
	Variable Displacement Pump	16
	Priority Flow Divider	16
	Remote Control Valves	17
	Standard Flow Tractors	17
	Megaflow Tractor	17
	Low-pressure Return Circuit	18

SPECIFICATIONS

RESERVOIR

Capacity	
8670/8670A	117 L (31 gal)
8770/8770A, 8870/8870A, 8970/8970A	140 L (37 gal)
Change interval	900 hours (annually)
Oil type	M2C134D spec. hydraulic/transmission fluid F200 all season

FILTERS

Inlet screen	Stainless steel, 60 mesh
Transmission	102 mm (4") spin-on
70 Series Standard flow (before serial number D419451)	102 mm (4") spin-on
70 Series Standard flow (after serial number D419451), all 70A Standard flow	127 mm (5") spin-on
MegaFlow	127 mm (5") spin-on
Change interval	900 hours (annually)
Bypass valve	3.45 bar (50 PSI)
Bypass sender	See Section 55 - Electrical System

TANDEM GEAR PUMP

Speed	2665 pump RPM (2100 engine RPM)
Low pressure control section	117 LPM (31GPM) 44.41 cm^3/rev (2.71 in^3/rev)
Typical operating pressure (70 Series)	17.2 -18.6 bar (250 - 270 PSI)
Typical operating pressure (70A Series)	16.5 -18.9 bar (240 - 275 PSI)
Charge pressure section	
Standard flow	151 LPM (40 GPM)
(1.750" gear)	56.37 cm^3/rev (3.44 in^3/rev)
MegaFlow	261 LPM (69 GPM)
(3.000" gear)	96.68 cm^3/rev (5.9 in^3/rev)
Typical operating pressure	1.03 - 2.07 bar (15 - 30 PSI)

CCLS AXIAL PISTON PUMP (0 - 2.77 in^3/rev)

Standard flow pump	
Speed	2665 pump RPM (2100 engine RPM)
Flow	117 LPM (31 GPM)
Low pressure	19.0 ± 1.7 bar (275 ± 25 PSI)
High pressure (70 Series)	190 ± 3.4 bar (2750 ± 50 PSI)
High pressure (70A Series)	200 ± 3.4 bar (2900 ± 50 PSI)
Case drain leakage	Less than 4 LPM (1 GPM)
MegaFlow pump	
Speed	2100 pump RPM (2100 engine RPM)
Flow	91 LPM (24 GPM)
Low pressure	19.0 ± 1.7 bar (275 ± 25 PSI)
High pressure (70 Series)	190 ± 3.4 bar (2750 ± 50 PSI)
High pressure (70A Series)	200 ± 3.4 bar (2900 ± 50 PSI)
Case drain leakage	Less than 4 LPM (1 GPM)

CHARGE PRESSURE REGULATOR VALVE

Cracking pressure	0.69 ± 0.34 bar (10 ± 5 PSI)

OIL COOLER BYPASS VALVE

Cracking pressure	6.9 bar (100 PSI)
Flow	95 LPM (25 GPM)

STEERING FLOW DIVIDER

Relief valve pressure	172.4 bar (2500 PSI)
Flow	38 LPM (10 GPM)

STEERING CONTROL VALVE TURNS LOCK TO LOCK

2WD	4.1 turns 139.3 cm^3/rev (8.9 in^3/rev)
4WD	4.3 turns 231 cm^3/rev (14.1 in^3/rev)
SuperSteer	5.5 turns 231 cm^3/rev (14.1 in^3/rev)

STEERING CYLINDERS

2WD	one - 2.50″ X 10.00″ B/S
4WD	two - 2.25″ X 8.88″ B/S
SuperSteer	two - 2.25″ X 8.88″ B/S

REMOTE VALVE ASSEMBLY

2, 3, or 4 sections	
Flow control range (70 Series)	0 - 91 LPM (0 - 24 GPM)
Flow control range (70A Series)	0 - 117 LPM (0 - 31 GPM)
70 Series has a Dentent Release	172.4 bar (2500 PSI)
70A Series has a Timed Dentent Release	Operator Set
70A Series valve solenoid voltage	Extend and Retract Solenoid Resistance - 24 ohms Solenoids are 12VDC pulse width modulated devices (PWM)

THREE-POINT HITCH


Control Valve	
Pilot pressure (70 Series)	72.5 bar (500 PSI)
Pilot pressure (70A Series)	16.5 - 19 bar (240 - 275 PSI)
Solenoid voltage	Raise Solenoid Resistance - 2.4 ohms PWM voltage 4.2V > 2.3V (40% > 26% duty cycle) Lower Solenoid Resistance 2.4 ohms PWM voltage 3.6V > 2.6V (35% > 26% duty cycle)
Lift circuit relief valve (70/70A Series)	207 bar (3000 PSI)
Lift relief valve (70A Series)	190 bar (2750 PSI) [High pressure standby - 200 bar (2900 PSI)]
Lift pressure (70 Series)	190 bar (2750 PSI) [High pressure standby]

Cylinders	
Diameter	
8670 (before serial number D409175)	88.9 mm (3.5″)
8670 (after serial number D409174)/8670A	101.6 mm (4.0″)
8770/8770A, 8870/8870A	101.6 mm (4.0″)
8970/8970A	114.3 mm (4.5″)

Lift capacity (CAT III)	kg	lbs
8670 (before serial number D409173)	4536	10000
8670 (after serial number D409174)/8670A	5670	12500
8770/ 8770A, 8870/8870A	5670	12500
8970/8970A	6804	15000

Couplers	
Rated flow	125 L/min (33 GPM)
Rated system pressure	186 bar (2700 PSI)

DESCRIPTION OF OPERATION



1

Hydraulic System Components

1. 60 mesh inlet screen
2. Low-pressure charge pump
3. Low-pressure transmission pump
4. Standard CCLS axial piston pump
5. MegaFlow CCLS axial piston pump
6. Pump drive gear case
7. Charge filter
8. Transmission filter
9. Steering priority valve
10. Steering control valve
11. Steering cylinder
12. Oil cooler
13. Remote valve assembly
14. Brake valve
15. Solenoid valve bank
    Four-wheel drive (FWD)
    Differential lock
    PTO brake

INTRODUCTION

The hydraulic system consists of a low-pressure and high-pressure system that utilizes the transmission and rear axle housing as a reservoir.


The low-pressure system consists of a tandem gear pump that supplies oil to the axial piston pump charging system and the low-pressure circuit which includes the transmission, cooler, differential lock, PTO and FWD solenoids.

The high-pressure system is a closed center load - sensing (CCLS) system that utilizes a variable displacement axial piston pump and is available in two configurations. The standard system uses one axial piston pump and the optional MegaFlow™ system uses two pumps.

The CCLS system provides oil flow for the power steering circuit, hydraulic trailer brake valve (if equipped), the remote valve circuit and the three-point hitch circuit (if equipped). O ring face seal (ORFS) fittings are used throughout the system.


CLOSED CENTER LOAD SENSING (CCLS) PUMP AND REMOTE VALVE SYSTEM

Two versions of the CCLS high-pressure system are available. The first is a standard flow system which utilizes a single variable displacement pump, 1.




2

The second system uses two variable displacement pumps, 1 and 2. The system is also known as the MegaFlow or deluxe high-pressure system.




3


HYDRAULIC SCHEMATIC (SERIES LOGIC)
SUCTION
HIGH PRESSURE
LOW PRESSURE
CHARGE PRESS
RETURN
LOAD SENSE
COOLER AND LUBRICATION
SERVICE BRAKE VALVE
ACCUMULATOR 4.5 CU IN, 1775 PSI
COOLER
2 WD STEERING CYLINDER
MFWD STEERING CYLINDERS
STEERING MOTOR
CREEPER VALVE
COOLER BYPASS VALVE
TRANS LUBE RELIEF
PRESSURE REGULATING VALVE
240-260 PSIG
TRANSMISSION PUMP 2.7 CID
TRANSMISSION FILTER 4" DIA
HYDRAULIC FILTER STANDARD 4" DIA
CHARGE PUMP STD 3.4 CID
CHARGE PRESSURE REGULATING VALVE 10 PSIG CRACK 22 PSIG FULL FLOW
INLET SCREEN 152 MICRON
SUMP
CENTER HOUSING
MFWD
DIFF LOCK
PTO
PTO BRAKE
PTO VALVE
TRANSMISSION
PTO LUBE
SERVICE BRAKES
PTO RETAINER
MFWD SOLENOID
DIFF LOCK SOLENOID
STEERING PRIORITY VALVE
HIGH PRESSURE PISTON PUMP
270 PSIG PRES COMP
265 PSIG FLOW COMP
2.77 CID
PRES/FLOW COMP
LOAD SENSE SHUTTLE
SERVICE BRAKE
COOLANT
500 PSIG
IMPLEMENT REMOTE VALVE
LIFT RELIEF VALVE
3000 PSIG
HYDRAULIC LIFT VALVE
QUICK COUPLER
SECTION 4
SECTION 3
SECTION 2
PRIORITY SECTION 1
QUICK COUPLER W/LOAD CHECK
LOW PRESSURE RETURN

Hydraulic Schematic (Series Logic)

Figure 4
The circuit shown represents a schematic view of the entire standard series logic hydraulic system. The type and method of operation of the system components are shown using standard hydraulic symbols. All of the various hydraulic components are shown in this figure.




HYDRAULIC SCHEMATIC (PARALLEL LOGIC)

5


Hydraulic Schematic (Parallel Logic)

Figure 5
The circuit shown represents a schematic view of the entire standard parallel logic hydraulic system. The type and method of operation of the system components are shown using standard hydraulic symbols. All of the various hydraulic components are shown in this figure.




6

Standard Electrohydraulic Remote Valve System (70A Series)



7

Megaflow Electrohydraulic Remote Valve System (70A Series)



8

Standard Flow System

STANDARD FLOW HYDRAULIC SYSTEM

The standard flow CCLS high-pressure system is shown in a pictorial view in Figure 8.

- The standard flow hydraulic system uses one variable displacement pump. The charge pump flow goes to the charge filter and on to the variable displacement pump.
- The variable displacement pump will supply fluid to any circuit that is demanding fluid. The maximum pump flow is 117 L/min (31 GPM).
- The steering priority flow divider has priority control on the system fluid flow so the steering demands can be met first.
- The fluid then goes to the trailer brake valve (if equipped).
- The fluid then goes to the remote valve assembly. Individual valve assemblies have access to the fluid based on the built in logic. All valve assemblies have a priority basis from section 1. 70 Series valve assemblies, part numbers 9821338, 9821339, 9821344, 9821345, 9821346, 9821409, and 86002601, are on a series circuit with priority going to the three point hitch (if equipped), #IV, #III, and #II. Valve assemblies, part numbers 86018025 - 86018031 are on a parallel circuit, sharing the fluid flow, with the valve section having the least resistance gaining access to the oil first.

NOTE: *The valves are identifiable by the ID tag on the valve assembly located on the top cap. See Series versus Parallel Logic Assemblies in this section.*


- The 70A valve assemblies are on a parallel circuit, sharing the flow, with the valve section having the least resistance gaining access to the oil access to the oil first.

  Section 1 part # is 86026993
  Section 2 part # is 86026994
  Section 2 megaflow ready part # is 86027015
  Section 3 & 4 part # is 86026995.

  Each individual valve is stamped on the top with a five-digit number for identification.

Valve	
#1 Priority	2-6-004
#2 Standard	2-6-005
#2 Megaflow Ready	2-6-005
#3, #4	2-3-009

- The return fluid leaves the remote valve assembly through the base plate and enters a tube which carries the fluid up to the inlet screen area of the rear axle center section.
- All the hydraulic control valve components can signal or control the variable displacement pump by load sensing signals sent to the control valve on the pump. This permits the system to respond to individual flow pressure requirements. The steering priority valve is connected into the load sense circuit with a shuttle ball tee fitting.



9

MegaFlow Hydraulic System

MEGAFLOW HYDRAULIC SYSTEM

The second system is a MegaFlow system or deluxe system which consists of two variable displacement pumps. The 208 L/min (55 GPM) flow from these two pumps is directed into a divided high-pressure system.

The standard upper pump provides up to 117 L/min (31 GPM) flow to the steering flow divider, trailer brake valve if equipped, and valve sections #1 and #2 of the remote control assembly.

The MegaFlow lower pump provides 91 L/min (24 GPM) flow to the remaining remote valve sections #3 and #4 and the three-point hitch (HPL) control valve.

IMPORTANT: *The maximum available flow from any one remote valve section is 83 ± 8 L/min (22 ± 2 GPM).*

The two pumps are driven from the same gear case and operate independently of each other with respect to the load sensing and flow compensating functions.

Both of the pumps receive oil from the charge pump system. The upper pump displacement is the same as the standard pump system.

The rest of the circuit operates like the standard system previously described.

The lower MegaFlow pump turns the same RPM as engine RPM and thus is rated at 91 L/min (24 GPM).

NOTE: *The actual system flow may be 5% less due to pump case drain flow and internal system leakage which can occur at higher operating pressures and temperatures.*

VARIABLE DISPLACEMENT PUMP

The variable displacement pump, consists of a housing, end plate, valve plate (lens plate) rotating group with nine axial pistons, drive shaft, shaft seal, swash plate bearings and control valve.


The pump parts are identical for both the standard and MegaFlow pumps except for the block end plate, swash plate and lens plate. The two pumps rotate in different directions so the parts have to be made accordingly. Refer to "Axial Piston Pump" Section 35, Chapter 4, for more information.

PRIORITY FLOW DIVIDER

The priority flow divider is part of the hydrostatic steering system receives oil from the upper CCLS axial piston pump circuit, 1. For more information on the hydrostatic steering system, see Section 41.

The steering priority flow divider valve, 3, maintains the steering flow on a priority basis from 0 - 34 L/min (0 - 9 GPM) and limits the maximum pressure to 165 + 6.9 - 0 bar (2400 + 100 - 0 PSI) for the 70 series, or 186 + 6.9 - 0 bar (2700 + 100 -0 PSI) for the 70A Series.

The priority flow divider is connected into the load sensing circuit with a special shuttle tee fitting, 2, so that the steering system can control the pressure flow compensation feature of the CCLS pump.




10

Priority Flow Divider Operation

When the steering circuit, 3, is demanding fluid, the priority valve spool, 1, will shift and direct the pump flow, 4, to the steering circuit. The spool position is controlled by the spring and load sense pressure coming into the spring cavity. This pressure will balance against steering circuit pressure which enters the right-hand end of the spool through the cross drilling.

When the steering circuit is not demanding oil, or is demanding an amount which is less than available pump flow, the spool, 1, will shift to the left and all or some of the pump flow, 4, will go to the remote valve circuit, 2.



11

If the steering load sense line pressure increases above 172 bar (2500 PSI) for the 70 series, or 186 bar (2700 PSI) for the 70A series, the relief valve, 5, will open and excess pressure will dump into the gear case assembly. This limits the maximum pressure in steering passage, 3. More information about the hydraulic steering system can be found in Section 41.

REMOTE CONTROL VALVES

Remote control valves are available to operate external hydraulic cylinders, motors, etc. Up to four remote control valves may be installed. The valves are located at the rear of the tractor.

Tractors with a standard hydraulic system can be equipped with two, three or four remote valves. MegaFlow tractors will be equipped with four remote valves.

The bottom control valve has absolute flow priority over the remaining valves.

STANDARD FLOW TRACTORS

After the number I valve has been satisfied, priority goes to the 3-point valve, then in a descending order to valves IV, III (if equipped), and to valve II last.

MEGAFLOW TRACTOR

After the number I valve has been satisfied, priority goes to valve II. The oil from the Megaflow pump satisfies the 3-point hitch valve, then in a descending order to valves IV and III.

Priority is greatly effected by the setting of the flow control valves. Make sure the flow controls are properly adjusted. See "Flow Control Adjustment" later in this section for more information.

Load checks are installed in the "extend" port of the lower two control valves.

The 70 Series tractor remote valves are operated by levers on the right-hand console with the remote valve flows being controlled by the flow control knob on the right hand console. The flow control knob is connected to the remote valves with a flow control cable.

NOTE: *The total system flow is not available to operate any one single hydraulic circuit. The maximum available flow from any one remote valve is 91 ± 8 L/min (24 GPM ± 2 GPM).*


The 70A Series tractor Electro-hydraulic remote valves are operated by finger controlled switches in the right hand console with the remote valve flow being controlled by the flow control knob on the switch pod. The flow control knob and the switches control the remote valve electronically.

NOTE: *The total system flow is not available to operate any one single hydraulic circuit. The maximum available flow from any one remote valve is 117 ± 8 L/min (31 ± 2 GPM).*

LOW-PRESSURE RETURN CIRCUIT

A low-pressure return circuit is available by removing the 1-1/16-12 ORB threaded plug, 1, and installing a coupler, 2. The coupler can be attached by using a steel O ring 12-12 hex nipple adaptor.

The use of the low-pressure return circuit will reduce back pressure in the remote hydraulic return line which will result in more efficient hydraulic motor operation. The low-pressure return circuit can also be used in applications where low return oil pressure is desired to improve implement operation such as with orbit motor case drain lines, or implement mounted hydraulic control valves.



12

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 2 - Low-Pressure System

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	3
	Hydraulic Pump Drive Assembly	3
	Tandem Gear Pump Assembly	4
	Tandem Gear Pump Fluid Supply	6
	Oil Filters	7
	Oil Reservoir	7
	Oil Cooler and Bypass Valve	8
	Low-Pressure Control Hydraulic Schematic	11
35 260	Removal and Disassembly	12
27 170	Hydraulic Pump Inlet Screen	12
27 170	Charge Pressure Regulator Valve	12
21 102	Filters	14
21 102	Filter Head	15
21 136	Cooler Bypass Valve	16
10 408	Hydraulic Oil Cooler	19
33 202	Accumulator	21
	Hydraulic Pump Driven Gear Case	22
	Repairing the Pump Drive Gear Case Bearings	23

SPECIFICATIONS

RESERVOIR

Capacity	
8670/8670A	117 L (31 gal)
8770/8770A, 8870/8870A, 8970/8970A	140 L (37 gal)
Change interval	900 hours (annually)
Oil type	M2C134D spec. hydraulic/transmission fluid F200 all season

FILTERS

Inlet screen	Stainless steel, 60 mesh
Transmission	102 mm (4″) spin-on
70 Series Standard flow (before serial number D419451)	102 mm (4″) spin-on
70 Series Standard flow (after serial number D419451), all 70A Series Standard Flow	127 mm (5″) spin-on
MegaFlow	127 mm (5″) spin-on
Change interval	900 hours (annually)
Bypass valve	3.5 bar (50 PSI)
Bypass sender	See Section 55 - Electrical System

TANDEM GEAR PUMP

Speed	2665 pump RPM (2100 engine RPM)
Low pressure control section	117 LPM (31GPM) 44.41 cm^3/rev (2.71 in^3/rev)
Typical operating pressure (70 Series)	17.2 -18.6 bar (250 - 270 PSI)
Typical operating pressure (70A Series)	16.5 -18.9 bar (240 - 275 PSI)
Charge pressure section	
Standard flow	151 LPM (40 GPM)
(1.750″ gear)	56.37 cm^3/rev (3.44 in^3/rev)
MegaFlow	261 LPM (69 GPM)
(3.000″ gear)	96.68 cm^3/rev (5.9 in^3/rev)
Typical operating pressure	1.0 - 2.1 bar (15 - 30 PSI)

CHARGE PRESSURE REGULATOR VALVE

Cracking pressure	0.7 ± 0.34 bar (10 PSI ± 5 PSI)

OIL COOLER BYPASS VALVE

Cracking pressure	6.9 bar (100 PSI)
Flow	95 L/min (25 GPM)

ACCUMULATOR

Precharge pressure	12.1 bar (175 PSI)
Displacement	0.07 L (5 in^3)


DRIVE GEAR CASE

Bearing end play	0.0254 - 0.0762 mm (0.001 - 0.003″)

DESCRIPTION OF OPERATION


HYDRAULIC PUMP DRIVE ASSEMBLY

The hydraulic pumps are mounted on a modular gear case assembly, 1, which is bolted on the right side of the rear axle center section. All of the pumps are mounted on SAE "B" drive pads, 2.



1


The hydraulic pump drive gears are driven by an idler gear, 1, which is driven from a live gear, 2, mounted on the PTO clutch drive shaft. The gears are cut with a 22° helical angle.



2

Standard Hydraulic Pump Drive


The standard hydraulic pump drive case assembly, 1, is shown in an exploded view. The pump driven gear, 2, is supported by tapered roller bearings, 3. The case components are splash lubricated. The pump drive shaft splines are pressure lubricated with oil from the charge pump input shaft.



3

MegaFlow™ Hydraulic Pump Drive

The MegaFlow or deluxe pump drive system uses all the features described in the standard flow system plus an extra gear, 2, that drives the second axial piston pump. The standard low- pressure pump and axial piston pump drive gear, 1, turn right-hand rotation at 2665 RPM with the engine at 2100 RPM. The optional MegaFlow pump driven gear, 2, turns left-hand rotation at 2100 RPM, the same as the engine speed.



4


MegaFlow Ready Option

The MegaFlow ready option is a factory-installed option which consists of the MegaFlow gear case assembly, MegaFlow charge pump, MegaFlow charge filter, and 38.1 mm (1.250") tubes.

The dealer must install the second pump, a new #II remote valve section, the plumbing required to connect the pump to the four-section remote valve assembly, and MegaFlow charge tube.

TANDEM GEAR PUMP ASSEMBLY

The tandem gear pump, 1, assembly has two separate pumping sections in it.



5

Low-Pressure Section

The smaller section, 1, near the input end supplies oil to the low-pressure circuit which includes the transmission clutch operation and lubrication. The low-pressure section is equipped with pressure balanced thrust plates, 2. The sections are aligned with dowels. The shafts are supported on bushings, 3.


Oil enters the inlet side and is carried in the spaces between the teeth as the spur gears rotate. The oil is forced out of the outlet port as the spur gears mesh together.

The low-pressure circuit also supplies flow for the differential lock, PTO clutch and brake, four-wheel-drive (FWD) clutch, and creeper (if equipped) which are all controlled by electric solenoids.

The service brake valve, oil cooler circuit, transmission lube, and PTO lube are also supplied by the low-pressure circuit.

For the 70 Series, the low-pressure section for the transmission is rated at 117 L/min (31 GPM) at 17.2 - 18.6 bar (250 - 270 PSI).

For the 70A Series, the low pressure section for the transmission is rated at 117 L/min (31 GPM) at 16.5 - 18.9 bar (240 - 275 PSI).



6


Charge Pressure Section

The larger section of the pump, 1, supplies oil to the CCLS pump charge system and brake cooling circuit (8670 after serial number D411605 and 8770, 8870, 8970 after serial number D411582, and all 70A Series). The section is a fixed clearance design and uses no thrust plates, 2.

Two different charge pump sections are used depending upon the type of high-pressure system used as shown in Figures 6 and 7.


The standard system has a gear width of 44.5 mm (1.750″), Figure 6; and the MegaFlow system has a gear width of 76.2 mm (3.000″), 3, Figure 7.

The standard charge pump is rated at 151 L/min (40 GPM). The MegaFlow charge pump is rated at 261 L/min (69 GPM).



7

The charge pump pressure is regulated by a charge pressure regulator valve, 1, that dumps the excess charge oil back to the gear pump inlet whenever the pressure exceeds 0.7 ± 0.34 bar (10 ± 5 PSI). The regulator valve maintains back pressure to the piston pump inlet so there is always a positive pressure at the inlet. Normal charge pressure at rated engine speed will be slightly higher.



8

TANDEM GEAR PUMP FLUID SUPPLY

The tandem gear pump assembly has a common supply tube, 1, which draws oil from the reservoir through a mid-mounted 60 mesh inlet filter screen, 2.


This mid-mount location allows the tractor to operate up to a 27° angle and to maintain proper oil flow in the inlet screen.

Cleaning the inlet screen during oil changes is recommended. The screen is made of steel; if it is damaged or plugged with contaminants. it should be replaced.

The screen can be removed from the right side of the tractor by removing the cover and valve assembly, 3. The screen is threaded onto a mounting stud, 4, and must be rotated counterclockwise to remove it.

An optional hydraulic reservoir oil heater may be installed in place of stud, 4.

Do not attempt to remove stud, 4, or heater while screen, 2, is attached as this may damage the screen.



9

OIL FILTERS


The oil is filtered after it leaves the tandem gear pump. Two spin-on filters are used; one for the transmission circuit, 1, and one for the CCLS axial piston pump charge circuit, 2.

The standard flow charge system and the MegaFlow charge system uses a 127 mm (5″) diameter filter, 2.

On the 70 Series, the standard flow charge system uses a 102 mm (4″) diameter filter, (2) prior to serial number D419451.

Both filters heads, 3, are equipped with a bypass valve that opens at 3.5 bar (50 PSI) and an electronic bypass indicator switch, 4.

The bypass indicators are connected to a single red filter indicator warning lamp in the electronic instrument cluster. The lamp will be illuminated steady when the charge pump filter is bypassing and will flash if the transmission filter is bypassing. Both of these alarms are non-critical. Filters should be changed as soon as possible, certainly within 1 hour of operation. Refer to "Electrical System" Section 55, Chapter 1 for additional information.




10

OIL RESERVOIR


The oil reservoir in the rear axle section contains 140 Liters (37 gal) in the large axle and 117 Liters (31 gal) in the small axle. Hydraulic transmission fluid specification M2C134D is used. For cold weather, use F200 "all season" hydraulic transmission fluid. The system will require about 129 Liters (34 gal) in the large axle and 102 Liters (27 gal) in the small axle for a regular oil change. The oil and filter service interval is 900 hours or annually.

The oil is drained from a plug, 1, located in the bottom of the rear axle center section.




11

The oil filler tube, 1, is located on the top cover at the rear of the tractor. The dipstick, 2, is located on the left rear side of the rear axle center section.



12


The optional immersion hydraulic transmission oil heater is installed in the oil reservoir, from the left side, inside the tandem gear pump inlet screen. The electric power cord, 1, is located on the left side of the tractor rear axle center section.



13

OIL COOLER AND BYPASS VALVE


The hydraulic oil cooler, 1, is mounted in front of the radiator and is part of the intercooler assembly, 2, on emissionized models. On non-emissionized models the intercooler is part of the air conditioning condenser. The cooler supply and return tubes, 3, connect to the cooler bypass valve which is mounted on the transmission control valve assembly.




14

The oil cooler bypass valve assembly, 1, is located on the powershift transmission control valve assembly.

The oil cooler flow comes from the transmission low-pressure control system. The oil cooler flow is 94 L/min (25 GPM) maximum. The bypass valve, 2, is pressure operated, spring loaded and cracks open at a 6.7 bar (100 PSI) pressure differential between the cooler supply and return circuits.



15


LOW PRESSURE HYDRAULIC CIRCUIT
HIGH PRESSURE
RETURN
SUCTION
LOAD SENSE
LOW PRESSURE
LUBRICATION / COOLER
CHARGE PUMP
TO POWER BRAKE VALVE
TO REMOTE VALVES, PILOT PRESSURE (70A ONLY)
TRANSMISSION FILTER
TRANSMISSION OIL COOLER
COOLER BYPASS VALVE
TO TRANS. LUBE
LUBE CIRCUIT RELIEF VALVE (40 PSI) (2.8 BAR)
PRESSURE REGULATING VALVE (240 - 275 PSI) (16.5 - 18.9 BAR)
TO TRANSMISSION CLUTCH CIRCUITS
CHARGE FILTER
CHARGE PUMP (40 GPM) (151 L/M)
TRANSMISSION PUMP (31 GPM) (117 L/M)
TO PTO LUBE
TO PTO BRAKE
CONTROL VALVE
STANDARD CCLS PUMP (31 GPM) (117 L/M)
INTAKE SCREEN
TO PTO FWD DIFFERENTIAL LOCK SOLENOIDS
TO BRAKE COOLANT
CHARGE PRESSURE REGULATING VALVE (10 - 15 PSI) (.69 - 1.03 Bar)
19980592

16

LOW-PRESSURE CONTROL HYDRAULIC SCHEMATIC


The low-pressure control hydraulic system circuit is shown.

1. Oil is drawn out of the reservoir and through the 60 micron mesh screen to the intake of the tandem gear pump.
2. Oil passes through the small section of the tandem pump and is forced out to the filter.
3. The filtered oil goes to the oil cooler valve and transmission pressure control valve assembly on the transmission.
4. A pressure regulating valve in the transmission valve body maintains pressure which forces oil into the transmission clutch operating circuit, low-pressure solenoid clutch circuit, the service brake circuit, and the remote valve pilot pressure on the 70A Series only.
5. A nitrogen charged accumulator is mounted on the brake supply line to stabilize the operation of the transmission regulating valve. The accumulator displaces 29 cm^3 (4.5 in^3) and is charged to 12.1 bar (175 PSI).
6. Excess oil flow not required by these circuits is routed out to the cooler and back into the valve assembly to be used as transmission lube oil and is maintained at 2.8 bar (40 PSI) maximum pressure. Any flow not needed by the lubrication circuit will return to the reservoir when the valve opens.
7. When the oil is cold and not flowing easily, a high back pressure might occur in the cooler bypass valve. If this pressure is above 6.9 bar (100 PSI), the cooler bypass valve will open and divert some oil directly to the transmission lubrication circuit.

REMOVAL AND DISASSEMBLY

HYDRAULIC PUMP INLET SCREEN AND CHARGE PRESSURE REGULATOR VALVE


1. Drain the fluid from the rear axle.
2. Remove the three attaching bolts, 1, that hold the cover, 2, in place.



17


3. Pull the end cover, 1, down until it is free of the coupler, 2.

NOTE: *Do not damage the O rings, 3, when removing the end cover.*




18

4. The charge pressure regulator valve, 1, can be removed by unthreading it from the port.
5. Clean or replace the valve and reinstall it in the end cover.




19

6. Remove the suction screen, 1, by turning it counterclockwise.
7. Clean the sump area.
8. Clean, then inspect, the suction screen and all O rings. Replace if damaged.
9. Install the suction screen. Turn it clockwise until hand tight, then turn it an additional 1/4 turn. Do not over tighten.
10. Install the O ring, 2, on the housing and lubricate with oil.
11. Oil the exposed O ring, 3, on the coupler.



20

12. Install the end cover, 2, and coupler. Do not damage the O rings.
13. Install the attaching bolts, 1, and torque to 95 N·m (70 ft lbs).
14. Refill the rear axle assembly with the correct amount of oil.




21

FILTERS

Transmission


1. To change the transmission filter, first clean the area around the filters.
2. Remove the filter, 1. Dispose of the filter properly.
3. Discard the O ring.
4. Clean the filter manifold seal surface, 3.
5. Coat the new O ring, 2, with clean oil.
6. Install the new filter and hand tighten securely.



22

Hydraulic

1. To change the hydraulic filter, first clean the area around the filters.
2. Remove the filter, 1. Dispose of the filter properly.
3. Discard the O ring.
4. Clean the filter manifold seal surface, 3.
5. Coat the new O ring, 2, with clean oil.
6. Install the new filter and hand tighten securely.



23


IMPORTANT: *Be sure to install the correct size filter.*

Filter	Dimension
70 Series Standard Flow (before SN D419451)	107 mm (4″) spin-on
70 Series Standard Flow (after SN D419451)	127 mm (5″) spin-on
70 Series Mega Flow	127 mm (5″) spin-on
70A Series Standard and Mega Flow	127 mm (5″) spin-on

NOTE: *If converting to the larger filter element on the 70 Series, a different filter head must be installed. The part number for the filter element and filter head is #86018757.*

FILTER HEAD


1. The filter head is equipped with a non-serviceable bypass valve. Arrows,1, on top of the filter head indicate the proper direction of fluid flow. This should be checked to ensure correct operation of the filter and the bypass valve. The filter head is attached to the mounting bracket with four cap screws.
2. Each filter head is equipped with a bypass switch, 2, which threaded into a 9/16-18 unf O ring port.



24

3. The bypass switches are identical on both filter heads. The high-pressure port, 1, and the low-pressure port, 2, are separated by an O ring, 3. The switch is sealed in the threaded port by an O ring, 4.

   The switch is normally closed, has an open set point at 2.76 ± 0.28 bar (40 ± 4 PSI) and resets at 1.79 bar (26 PSI).




25

COOLER BYPASS VALVE


1. To remove the cooler bypass valve assembly, position the tractor on a hard level surface and apply the park brake.
2. Remove the step, 1, and the battery box cover, 2. Disconnect the batteries.

NOTE: *When removing the cooler bypass valve assembly, the cooler ports in the main pressure regulating valve will be left exposed.*




26

3. Disconnect the charge pump oil tubes, 1, as required to gain access to the valve assembly.




27

4. Disconnect the low-pressure circuit supply tubes leading to the tractor PTO, 1; brake, 2; four-wheel drive engagement clutch, and lubrication circuits, 3.
5. If necessary, disconnect the tubes at the opposite ends or tie them out of the way to provide access and clearance during valve assembly removal.
6. Disconnect the cooler lines, 4, from the valve. If necessary, loosen or remove the tube to provide access.



28

7. Remove the five retaining bolts that hold the cooler bypass valve, 1, in place and remove the valve.




29

8. Lay the valve assembly on a clean workbench.
9. Use snap ring pliers to remove the snap ring, 1.

⚠ CAUTION ⚠


The spring is preloaded against the washer and the snap ring. Use extreme caution when removing the snap ring.



30


10. Remove the plunger, 2. Check it for scoring. Also check the bore in the valve body.
11. Clean the parts and coat them with clean hydraulic fluid.
12. Insert the plunger, spring, washer, guide, and snap ring. Make sure the snap ring is firmly locked in place.

13. Install new O rings on the valve assembly, and then install the cooler bypass valve assembly, 1. Torque the mounting bolts to 30 - 34 N·m (22 - 25 ft lbs).



31


14. Reinstall the hydraulic lines that were removed. Reconnect the batteries, start the tractor, and check for leaks. Finish assembly of the tractor.



32

HYDRAULIC COOLER


The oil cooler supply lines,1 , are routed from the connectors, 3, through the front main frame to the oil cooler, 2. The lines can be removed for repair as required.



33

Models 8670 (before serial number D411682) and 8770 (before serial number D408841) Tractors

1. The oil cooler, 3, on the Models 8670 (before serial number D411682) and 8770 (before serial number D408841) tractors is a separate assembly which is bolted to the tractor front frame. The cooler can be changed as a separate component. The air-conditioner condenser, 2, is bolted to the top of the oil cooler.
2. The external fins of the oil cooler can be cleaned as follows.
3. Use compressed air or a pressure washer not exceeding 6.9 bar (100 PSI).
4. Direct the air and water through each core from the back to the front. Make sure the radiator, 1, is also clean.
5. Straighten any bent fins.
6. If the cores are blocked with any oily substances, apply a detergent solution and remove it with water.
7. If the cooler is restricted internally due to contamination, THE COOLER SHOULD BE REPLACED. Do not attempt to clean and reuse a contaminated cooler. The cooler internal passages contains special baffles which stir the oil as it is flowing through the tubes. These baffles can trap small particles.



34

⚠ CAUTION ⚠


Wear eye protection and protective clothing during the cleaning process. Clear the area of bystanders so they are not struck by flying particles.

Models 8670 (after serial number D411682), 8770 (after serial number D408840), 8870, and 8970 and all 70A Series Tractors

1. The oil cooler, 1, is a part of the intercooler assembly which is bolted to the tractor front frame. If the cooler has to be changed, refer to the engine section of this manual for information about the intercooler.
2. The external fins of the oil cooler can be cleaned as follows.
3. Use compressed air or a pressure washer not exceeding 6.9 bar (100 PSI).
4. Direct the air and water through each core from the back to the front. Make sure the radiator, 3, is also clean.
5. Straighten any bent fins.
6. If the cores are blocked with any oily substances, apply a detergent solution and remove it with water.
7. If the cooler is restricted internally due to contamination, THE COOLER SHOULD BE REPLACED. Do not attempt to clean and reuse a contaminated cooler. The cooler internal passages contains special baffles which stir the oil as it is flowing through the tubes. These baffles can trap small particles.

⚠ CAUTION ⚠

Wear eye protection and protective clothing during the cleaning process. Clear the area of bystanders so they are not struck by flying particles.




35

ACCUMULATOR

1. The accumulator, 1, is non-serviceable, except for recharging. Recharging of the accumulator should be done by trained personnel.


   Precharge pressure is 12.1 bar (175 PSI).

2. Remove the accumulator by first depressing the brake pedal 8 - 10 times to dissipate any trapped hydraulic oil pressure.
3. Loosen the line fitting, 2, and remove the accumulator assembly.
4. Install new O rings on the fittings and reinstall the accumulator assembly. Torque the fittings as required.



36

HYDRAULIC PUMP DRIVE GEAR CASE



37

Standard Assembly

1. Bolt
2. Nut
3. Gasket
4. Bolt
5. Idler shaft
6. Bearing cup & cone
7. Retaining ring
8. Washer
9. Housing
10. Gasket
11. Housing cover
12. Bolt
13. Driven gear
14. Shim, 0.002″/0.003″/0.010″
15. Washer
16. Shim, 0.002″/0.003″/0.010″
17. Idler gear
18. Drive gear


1. The standard pump drive gear case uses one idler gear and one pump driven gear, 13, which are both supported on tapered roller bearings, 6.

   The MegaFlow case assembly is similar except it contains two pump driven gears.

NOTE: *The entire gear case does not have to be removed to overhaul the driven gear bearings. The gear case will have to be removed to repair the idler gear bearings.*

2. The long bolt, 1, and nut, 2, are used to stop the connecting gear, 18, on the PTO shaft inside from sliding rearward when the PTO shaft is removed.

HYDRAULIC PUMP DRIVE GEAR CASE




38

MegaFlow Assembly

1. Bolt
2. Nut
3. Gasket
4. Washer
5. Idler shaft
6. Cup and cone
7. Retaining ring
8. Bolt
9. Cover
10. O ring
11. Housing
12. Gasket
13. Cover
14. Bolt
15. Shim, 0.002″/0.003″/0.010″
16. Lower driven gear
17. Upper driven gear
18. Bolt
19. Washer
20. Shim, 0.002″/0.003″/0.010″
21. Idler gear
22. Drive gear

REPAIRING THE PUMP DRIVE GEAR CASE BEARINGS


1. Drain the oil from the rear axle center section. Remove the axial piston pump(s), 1 and 4, and the tandem charge pump, 2, if required.



39

2. Remove the rear cover plate, 1, from the gear case.
3. Remove and inspect the bearing cup(s) for damage.
4. Locate and mark the shims, 2, as removed.


NOTE: *The cups, 3, will slide out of the bore easily. This is normal.*



40


5. Remove and inspect the driven gear and bearings assemblies, 1. Use a bearing splitter to press the old bearing cones off of the gear.
6. Press new bearing cones on the gear assemblies.
7. Clean the gear case assembly as required to remove the debris.

NOTE: *Refer to "Hydraulic Pump Inlet and Charge Pressure Regulator Valve" earlier in this chapter for information about removing and cleaning the hydraulic pump inlet screen.*



41

8. This figure was used for front view clarity, refer to Figure 43 for more information.
9. Reach in to the gear case from the outside and attempt to move the idler gear, 1, to verify that the idler gear bearings feel operational.
10. If the idler gear, 1, feels EXTREMELY tight or has excessive side motion, then the gear case will have to be removed and the bearings inspected.




42

11. The gear case, 9, can be removed by loosening and removing all the bolts, 4, which hold the case to the rear axle center section. Use suitable lifting equipment to handle the weight of this case.
12. The idler gear bearings, 6, should also have 0.001″ - 0.003″ end play. Adding shims, 16, increases end play.


NOTE: *The bearings normally slide easily on the shaft, 5.*

13. Make sure the offset washer, 8, is properly seated during reassembly. These washers prevent shaft rotation.
14. To reinstall the case assembly, first install a new gasket, 3, lift the case back into place and torque the case mounting bolts, 4, to 98 N·m (72 ft lbs).
15. The long bolt, 1, and nut, 2, are used to stop the connecting gear on the PTO shaft inside from sliding rearward when the PTO is removed.




43

16. Install a new bearing cup, 1, in the housing. Make sure it is fully seated. The cup will normally slide easily into the bore.




44

17. Install the driven gear assemblies, 1, back into the gear case. The assemblies can be held in place by using a long bolt, 2, and a strap as shown.




45

18. Insert the same shim stack in the bearing bore that was removed.
19. Install new bearing cup(s) in the cover plate. The bearing cups may slide in very easily. Install a new gasket on the cover plate and temporarily reinstall the cover, 1.
20. Tighten the bolts, 2, to 54 N·m (40 ft lbs). Use an alignment stud to help hold the cover in place during assembly.




46

21. Install a dial indicator, 1, on the front side of the gear and check the end play. Correct bearing end play should be 0.001″ - 0.003″.
22. If the bearings are in a preloaded condition, remove the cover and remove a 0.002″ shim from behind the bearing cup and reinstall the cover. Recheck the end play.
23. Add shims if the bearings are in an end play condition.




47

24. Torque the cover, 1, mounting bolts, 2, to 54 N·m (40 ft lbs). Recheck bearing end play.




48

25. Reinstall the pumps. Check the O rings and replace any that are damaged.




49

26. Torque the inlet manifold adaptor plugs, 4, to 122 N·m (90 ft lbs).




50

27. Reinstall the hydraulic pumps, 1; 2; 4; back to the gear case, 3, as they were removed.



51

28. Change the transmission and hydraulic filters.
29. Make certain the drain plug is tight to 68 N·m (50 ft lbs).
30. Refill the rear axle center section with oil. See specification at the beginning of this chapter.
31. Install a flowmeter or loop lines in remote valve sections I (and IV if a MegaFlow unit) and start the tractor and allow the hydraulic system to purge the air from the closed center system.



52

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 3 - Tandem Gear Pump

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Operation	4
35 105	Disassembly and Repair	5
	Removal	5
	Disassembly	7
	Inspection of Parts	12
	Assembly	16
	Performance Testing	21
	Installation	22

SPECIFICATIONS


Type	Positive Displacement Spur Gear Pump
Rotation	CCW - 13 spline - SAE
Nominal System Pressure	
70 Series Transmission low-pressure system	17.2 -18.6 bar (250 - 270 PSI)
70A Series Transmission low-pressure system	16.5 -18.9 bar (240 - 275 PSI)
Standard hydraulic charge section	1.0 -1.4 bar (15 - 20 PSI)
MegaFlow (Deluxe) charge section	1.0 -1.4 bar (15 - 20 PSI)
Flow At Rated Engine Speed (2100 RPM)	
Transmission low-pressure system	117 L/min. (31 GPM)
Standard hydraulic section	148 L/min. (39 GPM)
MegaFlow (Deluxe) section	261 L/min. (69 GPM)
Pump Drive Speed At Rated Engine Speed	2668 RPM
Flow At Test Bench Speed (1800 RPM)	
Transmission low-pressure system	72 L/min. (19 GPM)
Standard hydraulic section	93 L/min. (25 GPM)
MegaFlow (Deluxe) section	165 L/min. (44 GPM)
Displacement	
Transmission low-pressure system	44.4 cm^3/rev (2.7 $in.^3$/rev)
Standard hydraulic section	56.4 cm^3/rev (3.4 $in.^3$/rev)
MegaFlow (Deluxe) section	96.7 cm^3/rev (5.9 $in.^3$/rev)
Torque Specifications	
End cover cap screws	79 N·m (58 ft lbs)
Mounting cap screws	75 N·m (55 ft lbs)

SPECIAL TOOLS

DESCRIPTION	TOOL NUMBER	USAGE
PD male quick coupler	FNH00533	Charge pressure test
PD female quick coupler	FNH00535	Charge pressure test
Adaptor	FNH00035	Connects test hose to PD coupler
Hose, test	FNH07099	High pressure hose with fittings
Gauge, pressure	FNH02027	41.4 bar (600 PSI) mechanical gauge
Gauge, pressure	FNH02026	6.9 bar (100 PSI) mechanical gauge
Adaptor, 1-7/16 - 12 ORFS female x 1-1/16 - 12 JIC male	FNH00110	Low-pressure pump flow test
Adaptor, 1-7/16 - 12 ORFS male x 1-1/16 - 12 JIC male	FNH00538	Low-pressure pump flow test
Hydraulic flowmeter	FNH02760	0 - 283 L/min (0 - 75 GPM)

DESCRIPTION OF OPERATION


The tandem gear pump assembly is a two-section, positive displacement spur gear pump that is available in two versions: standard flow, 1, and MegaFlow, 2. Both versions have the same front section, 3, with a displacement of 44.4 cm^3/rev (2.7 in^3/rev). The standard flow pump has a rear section displacement of 56.4 cm^3/rev (3.4 in^3/rev), and the MegaFlow pump has a rear section displacement of 96.7 cm^3/rev (5.9 in^3/rev).



1


For both pumps, the front section, 3, supplies fluid to the low-pressure circuit which includes the transmission, PTO, FWD, differential lock, brakes, creeper (if equipped), lubrication circuits, and oil cooler. The rear section, 4, of the pump supplies fluid to the CCLS piston pump charge system and brake cooling (after serial number D411582).

The front low-pressure section is equipped with pressure balanced thrust plates, 1. The rear charge section is a fixed clearance design and has no thrust plates, 2. Dowels, 3, are used to accurately align the shaft end housing and port end housings to ensure long seal and bushing life. A splined connecting shaft, 4, transmits torque from the front section drive gear to the rear section drive gear.



2

The MegaFlow pump has the same internal components as listed in the previous paragraph. Notice that the rear section, 2, is longer.




3

OPERATION


The pump is mounted on the hydraulic pump drive assembly and driven with a splined connection into the gear case. The pump rotation is counterclockwise meaning that the splined drive shaft rotates counterclockwise when looking at the front (input end) of the pump.

As the pump gears rotate, oil is carried in the spaces between the teeth from the inlet side to the outlet side. Oil enters the inlet side through a large 2-1/2" split flange port at the bottom of the pump, 1.



4

The low-pressure section fluid flow leaves the pump from the O ring port, 1, near the mounting flange. The charge pump section flow leaves from the O ring port, 2, near the back of the pump.




5

DISASSEMBLY AND REPAIR

REMOVAL


1. Clean the tractor thoroughly.
2. Remove the right rear wheel and block the tractor securely, 1. Wheel removal may not be required but is shown removed here for clarity.
3. Drain the fluid - approximately 117 Liters (31 gal) for the Models 8770/8770A, 8870/8870A, and 8970/8970A and 102 Liters (27 gal) for the Model 8670/8670A.

   If the tractor is parked level, it will not be necessary to drain the rear axle/hydraulic fluid. The fluid level will remain just below the pump. If the fluid must be drained for another reason, transfer the fluid into a clean holding barrel so that the fluid can be filtered and reused.



6

4. Use a wrench to remove the hardware which holds inlet tube, 1, to the bottom of the tandem pump.




7

5. Disconnect both outlet tube fittings, 1.


NOTE: *If the tractor has a megaflow pump, skip steps 6 & 7.*

6. On a tractor with a standard flow pump, remove the two cap screws, 2, which mount the pump to the drive gear case.
7. Remove the pump.




8

8. With a megaflow pump, pull the gear case, 1, (with all the pumps still attached) away from the tractor just enough to allow the megaflow pump to clear the transmission control valve as follows.



9

9. Remove the flow divider bracket by removing the two cap screws, 2, attaching the flow divider to the bracket. Remove the two cap screws, 1, attaching the bracket to the tractor. Support the flow divider and remove the bracket.



10

10. Disconnect all the hydraulic tubes or hoses connected to the pumps.
11. Support the gear case with a hydraulic floor jack.
12. Remove the bottom six of the eight cap screws holding the gear case to the tractor.

⚠ CAUTION ⚠


Be careful when removing the final two cap screws. Be sure the gear case and pumps are supported by the floor jack.

13. Remove the two top cap screws holding the gear case to the tractor.
14. Slide the gear case and pumps away from the tractor enough to clear the megaflow pump to transmission control valve.

NOTE: *Only use the proper gearbox gasket during assembly. This will keep the proper gear mesh.*

15. Remove the megaflow pump.


16. Cover the exposed ports with suitable plastic plugs, 1.



11

DISASSEMBLY

Tools Required:
5/16" socket wrench
Slip joint pliers
O ring pick
Prick punch
Screwdrivers (1/4" blade)
Seal installation tool
Petroleum jelly
Plastic or rubber hammer
Torque wrench




12

⚠ CAUTION ⚠


Do not grip on or near any machined surface during assembly or disassembly.

1. Punch-mark all sections, 1. Be sure to align these marks when reassembling.




13

2. Place the pump in a vise with the drive shaft pointing down.




14

3. Use a 5/16″ socket wrench to remove the four 3/8″ - 16 socket head cap screws, 1. Remove four washers, 2.



15


4. Lift off the end cover, 1. If prying is necessary, be careful not to damage the machined surfaces. Dowel pins, 2, will remain in either end cover or gear housing. DO NOT REMOVE.



16


5. Carefully remove the drive and driven gears, 1. Gears are a matched set; therefore, gears must be kept together. Examine and replace if necessary.

NOTE: *Mark the gears with indelible ink so the gears can be reengaged with the same teeth in contact.*




17

6. Remove the connecting shaft, 1.



18




19

7. Rotate the pump in the vise so that the drive shaft is pointing up.

⚠ CAUTION ⚠


Do not grip on or near any machined surface during assembly or disassembly.

8. Use a socket wrench to remove the four socket head cap screws and washers, 1.




20

9. Lift off the shaft end cover. If prying is necessary, be careful not to damage the machined surfaces. Avoid damaging the lip seal as you lift the cover over the drive shaft. Dowel pins will remain in either shaft end cover or gear housing. DO NOT REMOVE.



21


10. Remove the thrust plate, 1. Examine and replace if necessary. Refer to "Thrust Plates" later in this chapter.



22


11. Carefully remove the drive and driven gears, 1. Gears are a matched set; therefore, gears must be kept together. Examine and replace if necessary.

NOTE: *Mark the gears with indelible ink so the gears can be reengaged with the same teeth in contact.*




23

12. Remove the thrust plate, 1, from the bottom of the gear housing.



24

13. Remove input shaft seal, 1, from the end cover by pulling or prying the old seal out of the cover.
14. Wash all components in a suitable solvent and dry thoroughly.




25

INSPECTION OF PARTS

Bushings


If bushings, 1, are worn so it necessitates replacement, it would be practical to replace the entire pump.



26

Gears


Any scoring on gear hubs necessitates replacement. Nicking, grooving, or fretting of tooth surfaces also necessitates replacement.



27

Drive Shaft


Excessive wear in the shaft seal area indicates possible oil contamination or high inlet vacuums. If the input shaft spline shows excessive wear or damage, replace the shaft.



28

Thrust Plates


1. The thrust plates, 1, seal the gear section at the sides of the gears. Wear here will allow internal slippage; oil will bypass within the pump. A maximum of 0.05 mm (0.002") wear is allowable. Replace the thrust plates if they are scored, eroded, or pitted or show excessive wear.
2. Check the center of the thrust plates, 2, where the gears mesh. Erosion here indicates oil contamination.
3. Pitted thrust plates indicate cavitation or oil aeration.
4. Discolored thrust plates indicate overheating (probably insufficient oil) and must be replaced.



29

Dowel Pins

1. If either the dowel, 1, or dowel hole is damaged, the dowel or machined casting, or both, must be replaced.
2. If more than reasonable force is required to seat dowels, the cause may be a poorly deburred or dirty part, cocking of the dowel in the hole, or improper pin-to-hole fit.




30

Body


Inspect pump bodies for wear and damage. It is normal for gears to cut a light track on the inlet side of the body bore, 2, and, providing the depth of the track does not exceed 0.10 mm (0.004"), the body is reusable. Using an internal micrometer, measure the body at the bearing location and then at the track position to assess the track depth.

Seals and Gaskets

Replace all rubber and polymer seals including thrust plate channel seals, 1, shaft seal and section seals, 2.



31




32

1. Shaft seal
2. Mounting end cover
3. End cover seal
4. Thrust plate seals
5. Thrust bearing
6. Gear set, low pressure
7. Thrust plate
8. Thrust plate seal
9. End cover
10. Gear set, low pressure
11. End cover seal
12. Drive shaft
13. Center body

ASSEMBLY


1. Use a medium grit carborundum stone to polish any nicks on machined surfaces that might have occurred during disassembly. Rinse the parts in solvent and wipe clean.

2. Install a new lip seal, 1, into the shaft end cover. Before inserting the new seal, coat the outer edge of the lip seal with RTV silicone sealant or equivalent.




33

3. With the metal side of the lip seal up, 1, press or drive the seal into the mounting flange side of the shaft end cover.




34

4. Install the seal flush with the top of the lip seal bore. Be careful not to damage the lip of the seal. Wipe off excess sealant. Use a seal installation tool, 1, which measures 1-5/8″ OD x 1″ ID.



35


5. Install gear housing, 1, in vise with the low-pressure side pointing up.
6. Coat the new section seal, 2, with petroleum jelly and insert into the groove in the gear housing.



36


7. Assemble the channel seals, 1, into the grooves in the thrust plates, 2.

   Thrust plate, 1, is the outer thrust plate located nearest the input seal; thrust plate, 2, is the inner thrust plate located nearest the connecting drive shaft.




37

8. Install back-up seals, 1, so that the flat surface is out of the groove and the rounded surface fits into the channel seal. Coat all the seals with petroleum jelly first to ensure that they stay in the thrust plate grooves.




38

9. Gently slip the thrust plate, 1, through the gear housing and into place on the bottom of the housing. The channel seals should face the bottom of the gear housing. The square relief groove, 2, in the plate should face the outlet side of the pump.




39

10. Slide the front section gear set, 1, with the drive shaft pointing up through the gear housing and into the correct bushings. Both gears should rest on top of the thrust plate in the bottom of the gear bore. Squirt clean oil over the gears. Be sure to match the identification marks for proper gear mesh.




40

11. Slip thrust plate, 1, into the gear housing bore. The channel seal in the thrust PLATE SHOULD FACE UP. The square relief groove in the plate should face the outlet side of the pump, 2.




41

12. Position the shaft end cover, 1, over the gear housing so that the bushings receive the journals of the drive and driven gears and the drive shaft will slide through the lip seal. Be sure to line up the dowel holes over the dowel pins. Tap the shaft end cover lightly with a soft hammer to engage the dowel pins and to move the parts together. **NEVER USE A STEEL HAMMER.**




42

13. Install the four washers and four 3/8" - 16 socket head cap screws, 1, into the shaft end cover and gear housing. Torque the fasteners in a diagonal manner to 79 N·m (58 ft lbs).
14. Rotate the pump in the vise so that the drive shaft is pointing down.




43

15. Insert the connecting shaft, 1, in the spline of the drive gear.




44

16. Lubricate the new section seal, 1, with petroleum jelly and insert it into the groove in the gear housing.




45

17. Insert the rear section gear set, 1, through the gear housing and into the bushings. The drive gear of this gear set and the drive gear of the front gear set need to be placed "out of phase." The term "out of phase" means that the gear teeth in one section line up with the tooth spaces (valley)of the adjacent section. Look down through the inlet port past both gear sets to make sure the alignment is correct.




46

18. Position the port end cover, 1, over the gear housing so that the bushings receive the journals of the drive and driven gears. Be sure to line up the dowel holes over the dowel pins, 2. Tap the port end cover lightly with a soft hammer to engage the dowel pins to move the parts together. Check to be sure that the port end cover is assembled in the same orientation as before disassembly.




47

19. Install the four washers and four 3/8" - 16 socket head cap screws, 1, into the port end cover and gear housing. Torque the fasteners, 2, in a diagonal manner to 79 N·m (58 ft lbs).



48

20. Pour clean M2C134D or F200 hydraulic fluid into the pump inlet port and turn the pump a few revolutions. Cover all openings with suitable plastic plugs, 1.




49

PERFORMANCE TESTING

1. After a pump is rebuilt it can be tested on a **test bench** for correct operation before it is installed on the tractor. Testing conditions are the following:

   M2C-134D fluid
   49° C (120° F) oil temperature
   1800 RPM input shaft speed
   0 - 0.34 bar (0 - 5 PSI) inlet pressure
   20.7 bar (300 PSI) front section outlet pressure
   6.9 bar (100 PSI) rear section outlet pressure.

   Specified minimum flows are:
   72 L/min (19.0 GPM) for the front section
   93 L/min (24.5 GPM) for the standard rear section
   165 L/min (44.0 GPM) for the large rear section



50

2. If the front, 1, or rear, 2, section of a pump does not meet the minimum flow specification, the pump cannot be used. Further rebuild or replacement is required.


INSTALLATION

NOTE: *When attaching any hydraulic hose with an o-ring, always use a new o-ring.*


1. Install the pump on the tractor drive gear case. Use a new O ring, 1, and install cap screws.
2. Torque the two cap screws to 75 N·m (55 ft lbs).

NOTE: *If this is a standard pump, go to step 7.*

3. Slide the gearbox case and pumps back into position. Use a new gearbox case gasket to be sure of the gear mesh.
4. Torque the 8 capscrews holding the gearbox case to 91 N·m (67 ft. lbs.).
5. Connect all the hydraulic hoses or tubes to the pumps.
6. Install the flow divider bracket.
7. Install a new O ring on the bottom inlet flange of the pump, and then fasten the inlet tube, 1, back to the pump.




51




52

8. Refill the rear axle center section fluid reservoir if it was drained. Check the fluid level with dipstick, 1.
9. Pour 1 liter (1 qt) fluid down through the individual outlet ports.




53

10. Install new O rings on the fittings and tighten the outlet fittings, 1.




54

11. Remove the cover from the right side "B" pillar to get access to the main electrical distribution panel.
12. Remove the fuel solenoid relay, 1, (second from the bottom) from the main distribution panel. This will prevent the engine from starting.
13. Crank the engine for 20 seconds. Wait one minute. Repeat the procedure two more times. Reinstall the relay.



55


14. Install the loop line in the remote couplers, 1 and 2, for remote valve section I, green circuit.




56

15. Position the remote lever for green circuit, 2, to the flow position, 1 or 3. Start the engine and allow it to run at idle for 3-5 minutes to purge all the air from the low-pressure and charge system. Then operate the engine at full rated speed for 5-10 minutes to break in the pump and to check for fluid leaks.

NOTE: *70 Series art shown in Figure 57. 70A Series art shown in Figure 58.*




57



58

16. Reinstall the rear wheel and other components previously removed. Torque the rear wheel per the repair manual, and remove the safety stand, 1.



59

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 4 - Axial Piston Pump

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
35 106	Disassembly and Repair	16
	Removal	16
	Tools Required	17
	Disassembly	17
	Input Shaft Seal Replacement	17
	Seal Installation	18
	Compensator Valve Disassembly	20
	Main Pump Disassembly	24
	Swash Plate Removal	28
	Input Shaft	31
	Pump Reassembly	34
	Rotating Group Assembly	37
	Flow and Pressure Compensator Valves	41
	Pump Installation	43

SPECIFICATIONS

Type	Variable Displacement Axial Piston Pumps
Rotation	
Standard pump	CW - 13 spline - SAE
MegaFlow (deluxe) pump	CCW -13 spline - SAE
Pump Speed at Rated Engine Speed	
Standard pump	2688 RPM
MegaFlow (deluxe) pump	2100 RPM
Nominal System Pressure	
Low pressure standby* **(MegaFlow pump)**	19.0 ± 1.7 bar (275 ± 25 PSI)
70 Series High pressure standby	190 ± 3.4 bar (2750 ± 50 PSI)
70A Series High pressure standby	200 ± 3.4 bar (2900 ± 50 PSI)
Flow at Rated Engine Speed	
Standard pump	117 L/min (31 GPM)
MegaFlow (deluxe) pump	91 L/min (24 GPM)
Nominal Case Drain Leakage	
New pump	2 - 4 L/min (0.5 - 1 GPM)
Used pump	4 - 11 L/min (1 - 3 GPM)
Torque Specifications	
Mounting cap screws	79 N·m (58 ft lbs)
End cover cap screws	100 N·m (74 ft lbs)
Compensator valve mounting cap screws	12 N·m (9 ft lbs)

***Standard pump low pressure standby will be about 24.1 bar (350 PSI) due to a constant load sense signal from the dynamic bleed port in the steering flow divider.**


SPECIAL TOOLS

DESCRIPTION	TOOL NUMBER	USAGE
PD male quick coupler	FNH00534	Pump control valve pressure Load sense pressure
PD female quick coupler	FNH00535	Pump control valve pressure Load sense pressure
Adaptor 1/4 NTPF x 7/16 JIC	FNH00035	Connecting test hose to female coupler
Hose, test	FNH07099	
Gauge, pressure	FNH02028	Pressure test - mech. 344 bar (5000 PSI)
Gauge, pressure	FNH02027	Pressure test - mech. 41.4 bar (600 PSI)
Gauge, pressure	FNH02026	Pressure test - mech. 6.9 bar (100 PSI)
Adaptor	FNH00110	Axial pump flow tests
Hydraulic flowmeter	FNH02760	0 - 283 L/min (0 - 75 GPM)

DESCRIPTION OF OPERATION


The following repair information may be used for the inspection and repair of the variable displacement pressure-flow compensated axial piston pumps.

Two versions of the AA10V series 50 pressure-flow compensated axial piston pump are used. The pump model number AA10V45DFR/50R is for a clockwise rotation or right-hand application on the standard flow system, 1.




1

The pump, 2, model number AA10V45DFR1/50 is for a counterclockwise or left-hand rotation on the MegaFlow™ system.




2

When ordering replacement parts, make sure that the pump is identified correctly. The end cover, lens plate and swash plate are different due to the rotation of the pump. This product information is found stamped on a plate, 1, mounted on the pump body.



3

The axial piston pumps,1 and 4, are mounted on the hydraulic pump drive assembly and driven with a splined connection into the gear case, 3. The charge pump, 2, shares the same drive gear as the standard axial piston pump,1.




4

Pressure Control Valve

The variable displacement pump uses a two- spool control valve assembly. This assembly controls the low-pressure standby-flow compensation and high-pressure standby compensation modes of pump operation.

The control valve contains a low-pressure flow compensating spool, 2, and spring, 1. It also contains a high-pressure control spool, 3, and spring, 4. The control valves are factory set but are field adjustable if the valves need service.



5

Variable Displacement Pump

The axial piston pump operates due to the rotation of the drive shaft, 1, which causes linear piston movement as the piston shoe, 2, slides along the tilted swash plate, 3.


As the piston retracts in the cylinder bore charge oil fills the developing cavity. The inlet port, 4, in the valve plate directs charge pressure oil into the cylinder as long as the cylinder is in time with the port.

At maximum retraction of the piston, the shaft rotation has caused the cylinder, 5, to pass beyond the cylinder port. Continuing rotation causes the cylinder to come into phase with the discharge port, 6.

The pistons will start to slide up the tilted swash plate and force the oil from the cylinder bore out through the discharge port and into the pressure circuit.

The length of the piston stroke is controlled by the tilt angle of the swash plate cradle. The swash plate cradle can tilt through an angle of 0 -18 degrees. The swash plate cradle is tilted by a stroke control piston, 7, which is operated by hydraulic control pressure.

The swash plate cradle is mounted off center so that the spring, 8, can push the cradle into the tilted position. The swash plate cradle bushings are pressure lubricated by a oil hole drilled in the swash plate which index with a piston shoe as the cylinder rotates.



6

The rest of the pump is lubricated by oil that is a controlled leakage by the piston and slippers in the rotating group. A new pump will typically have approximately 3.8 L/min (1 GPM) case drain flow when operating at high pressure and normal operating temperature.


The standard CCLS pump will provide up to 119 L/min (31 GPM) to the hydrostatic steering and remote valve circuit.

NOTE: *The maximum available flow from any one remote valve section will be 119 L/min (31 GPM).*

The 70 Series high-pressure standby rating of the pump is 190 ± 3.4 bar (2750 ± 50 PSI).

The 70A Series high-pressure standby rating of the pump is 200 ± 3.4 bar (2900 ± 50 PSI).

The low-pressure standby rating of the pump is 19.0 ± 1.7 bar (275 ± 25 PSI).



7

Pump Operation - Tractor Not Running - Mode 1

1. Low-pressure flow compensating valve
2. High-pressure compensator valve
3. Stroke control piston
4. Swash plate
5. Rotating group
6. Inlet port
7. Discharge port
8. Load sense inlet


Variable Displacement Pump Operation

The pressure flow compensated variable displacement axial piston pump has five separate modes of operation.

NOTE: *The illustrations do not show the case drain port of the pump. The blue return oil will drain out of the case drain port and return to the reservoir during operation.*

1. Tractor not running:

When the tractor is not running and the hydraulic pump is not turning, the stroke control spring holds the swash plate, 4, at the maximum displacement angle.



8

Pump Operation - Low Pressure Standby - Mode 2

1. Low-pressure flow compensating valve
2. High-pressure compensator valve
3. Stroke control piston
4. Swash plate
5. Rotating group
6. Inlet port
7. Discharge port
8. Load sense inlet

2. Low-pressure standby:


When the hydraulic pump, 5, starts to turn, the pump will attempt to displace fluid out into the hydraulic circuit. If all the control valves are in neutral, the fluid will have no path to follow and the resulting back pressure will be felt in the pump discharge pressure port. 7.

This pressure will act against the low- pressure flow control compensating spool, 1. This spool will act against a spring and move to open up an oil port. When the pressure has reached 19.0 bar (275 PSI) fluid will go past the control spool land and enter the stroke control piston, 3, and tube.

The stroke control piston will destroke the pump by tilting the swash plate, 4, cradle back to the near neutral position. The pump and hydraulic system have reached a balance point at the time when this occurs. This balance point is called low-pressure standby.

The pump will continue to deliver enough flow to provide for pump and system leakage as the system operates in the low-pressure mode.

This mode is very efficient as it requires very little horsepower to operate the pump, is quieter and does not wear heavily on the parts. This mode also permits easy startup of the tractor because the hydraulic system is not pumping large amounts of fluid.



9

Pump Operation - Going Into Stroke - Mode 3


1. Low-pressure flow compensating valve
2. High-pressure compensator valve
3. Stroke control piston
4. Swash plate
5. Rotating group
6. Inlet port
7. Discharge port
8. Load sense inlet

3. Pump going into stroke:

When the operator actuates a hydraulic valve in the circuit, the system will respond by providing additional flow. The movement of the valve will cause a reduction of pressure in the pump output pressure port, 7, because the fluid has a path to follow.

This causes the low-pressure/flow compensator spool to shift which opens up a drain passage for the stroke control piston fluid. The spring forces on the swash plate forcing the swash plate to an increased angle which increases the pump displacement. The pump will then deliver a higher flow.

When the higher flow demand is met, the system back pressure will build up and the low-pressure spool will start to shift in an effort to reduce the displacement of the pump.



10

Pump Operation - Pressure Flow Compensator - Mode 4

1. Low-pressure flow compensating valve
2. High-pressure compensator valve
3. Stroke control piston
4. Swash plate
5. Rotating group
6. Inlet port
7. Discharge port
8. Load sense inlet

4. Pressure flow compensation:

When the operator moved the hydraulic control as mentioned in the previous paragraph, a load sensing signal was sent from the hydraulic control valve back to the load sensing port, 8, on the low-pressure compensating spool. This load sensing oil flow is a small portion of the oil that is actually leaving the remote control valve and going to the cylinder.

This signal enters the spring chamber and works with the spring to push the low- pressure spool, 1, back toward its seat.

NOTE: *The load sensing oil that enters this chamber is bled off through a bleed orifice that is connected to the tank port of the valve.*

As the spool travels toward its seat, the stroke control piston port is uncovered and the pump will go into a higher displacement mode. The pump will deliver enough oil into the circuit to keep the pump discharge pressure 19.0 bar (275 PSI) higher than the load sensing pressure.


This balance point is a result of the normal back pressure required to move enough flow into the system to do the work at the remote valve.

This allows the low-pressure flow compensating spool on the pump to control the pump displacement so that the pump discharge pressure reaches a balance point. The pump will then automatically adjust to the varying flow and pressure demands of the system.

NOTE: *The pump control valve has a stability orifice inserted in the stroke control passage. This orifice is used to regulate the response rate of the swash plate control piston. The orifice must be installed with the screwdriver slot parallel to the spool bores.*

IMPORTANT: *The compensating flow control located in each remote valve assembly should be adjusted so that any particular valve will not demand more flow than its work is requiring so that the pump can work most effectively.*

This allows the entire system to operate at a very efficient level because energy is not wasted by trying to produce excessive flow which would cause excessive back pressure. This excess back pressure will result in a higher horsepower requirement and will waste energy.



11

Pump Operation - High-Pressure Standby - Mode 5

1. Low-pressure flow compensating valve
2. High-pressure compensator valve
3. Stroke control piston
4. Swash plate
5. Rotating group
6. Inlet port
7. Discharge port
8. Load sense inlet

5. High-pressure standby:

When the oil flow completes its work, such as the cylinder is fully extended, the pump will go to high-pressure standby. The pump discharge fluid pressure will push the high- pressure control spool, 2, open far enough so that oil is ported to the stroke control piston fluid and the pump will destroke to a near neutral position.

The low-pressure flow spool, 1, will return to its seat because the pressure will equalize on both sides of the spool and the spring will push the spool.

The pump will maintain just enough displacement to overcome leakage and will maintain the (190 ± 3.4 bar [2750 ± 50 PSI] for the 70 Series, or 200 ± 3.4 [2900 ± 50 PSI] for the 70A Series) discharge pressure in the pump, 7, and the circuit.


When the operator returns the system control lever to neutral, the load sensing oil pressure is cut off and the low-pressure flow compensator spool will shift and uncover the stroke control port.

This allows the low-pressure spool to send oil to the stroke control piston and causes the pump to destroke even farther. The spring on the high-pressure spool will move the high pressure spool towards its seat. This will return the system to the low-pressure standby mode.

DISASSEMBLY AND REPAIR


REMOVAL

1. Clean tractor thoroughly.
2. Remove the right rear wheel and block the tractor securely. Wheel removal may not be required but is shown for clarity.
3. Drain fluid, approximately 117 Liters (31 gal). Transfer the fluid into a clean holding barrel so that the fluid can be filtered and reused.
4. Remove the load sense line, 1; inlet tube, 2; discharge tube, 3; and charge return manifold,4, on the standard pump.




12

5. Remove the two cap screws, 1, which hold the pump to the drive gear case. Remove the pump.
6. Cover the exposed ports with plastic caps as shown by the arrows.



13

7. The MegaFlow upper pump, 1, and lower pump, 2, are removed in a similar fashion. All of the inlet and outlet tubes, 3, must be removed to allow either pump to be taken off.




14

TOOLS REQUIRED

The following tools are required for disassembly and reassembly:


5 mm allen wrench
10 mm allen wrench
30 mm socket or end wrench
19 mm socket or end wrench
O ring pick
Prick punch
Plastic or rubber hammer
Internal retaining ring pliers (straight, 0.070″ tip)
Pencil magnet
Seal driver or a 1-1/4″ ID x 1- 1/2″ OD x 2-1/2″ long pipe
Screwdriver (1/4″ blade)
Torque wrench - 54 N·m (40 ft lbs) capacity
Petroleum jelly
Feeler gauge



15


DISASSEMBLY

1. Thoroughly clean the pump, 1, before any repairs are attempted. Mount the pump in a holding fixture like a soft jaw vise to assist in holding the pump for repair. Clean an area of the workbench and place clean shop towels on which to lay out the parts.
2. Mark the end cover, compensator valve assembly, and main body with a small punch mark to facilitate reassembly.




16

INPUT SHAFT SEAL REPLACEMENT




17

1. When replacing the input shaft seal, first clean the pump housing's mounting flange seal area thoroughly. Use the snap ring pliers, 1, to remove the input shaft seal retaining ring.



18


2. With the retaining ring removed, use a prick punch or similar tool, and carefully pierce the top of the lip seal. Using the prick punch, pry the seal from its bore.



19


SEAL INSTALLATION

1. Protect the inner lip of the new shaft seal, 1, lubricate and install the seal over the input shaft, 2, and into the pump housing.




20

2. Tap the shaft seal into the pump housing until it is just slightly below flush of the counterbore face. DO NOT SEAT THE SEAL AT THIS TIME.



21


3. Next, using the snap ring pliers, install the retaining ring, 1, on top of the shaft seal.



22

4. Use a seal driver, 1, such as a 1-1/4" ID 1-1/2" OD x 2-1/2" long pipe as shown here, to press both the retaining ring and shaft seal into the pump housing.


NOTE: *Press the retaining ring in just far enough that it snaps into the retaining ring groove machined into the pump housing.*



23


COMPENSATOR VALVE DISASSEMBLY

1. The following instructions may be used to disassemble the compensator valve assembly on the axial piston pumps. The compensator assembly, 1, contains two valves, springs, caps and related parts.




24

2. The small spring, 1, and valve assembly, 2, make up the flow compensator assembly which is also known as the low pressure standby valve. The larger spring, 4, and valve assembly, 3, are the pressure compensator which is also known as the high-pressure compensator.
3. Thoroughly clean the piston pump before any repairs are attempted.



25

4. To make the reassembly easier, measure and record the amount of threads sticking out of the adjusting caps prior to removing the assemblies, 1 and 2.




26

5. To disassemble the pump compensator valve, first position the pump in the input shaft down position. Next, using a 30 mm socket, or end wrench, remove the high- pressure adjustment cap assembly, 1, from the compensator housing, 2.

⚠ CAUTION ⚠

The valves will have to be adjusted after the assembly is put together. Any readjustments of this pressure compensator valve assembly above the system design specifications will void the warranty on the pump assembly.




27

6. Using a pencil magnet, or similar tool, remove the pressure compensator spool, 1, from the valve housing.


⚠ CAUTION ⚠

Do not use a strong magnet or apply the magnet to the valve for a long period of time. This will reduce the chances of magnetizing the valve which could cause sticky operation.




28

7. Remove the flow compensator/low pressure standby spool by first removing the adjustment cap assembly. Use a 19 mm socket or end wrench.
8. After removing this adjustment cap assembly, 1, remove the spring guide and spring from the valve assembly, 2.




29

9. Using a pencil magnet, or similar tool, remove the low-pressure spool, 1, from the valve housing, 2.



30


10. Remove the compensator housing by using a 5 mm allen wrench and remove the four allen screws, 1, that retain the assembly to the main body.




31

11. Remove the compensator housing, 1, from the pump assembly. Turn the compensator housing over and remove the three O rings, 2.

NOTE: *Be sure that the orifice adjusting screw, 3, is oriented fore and aft as shown.*



32




33

Exploded View of Main Pump

1. Housing
2. Control valve
3. Rod
4. Piston
5. Stroke limiting assembly
6. Shaft
7. Bearing
8. Backplate
9. O ring
10. Bearing
11. Spacer
12. Rotating group assembly
13. Swash plate
14. Spring
15. Bearings
16. Shaft seal
17. Snap ring


MAIN PUMP DISASSEMBLY

1. Using a 10 mm allen wrench, remove the four backplate retaining cap screws,1.




34

2. To remove the backplate assembly, after the retaining allen cap screws are removed, it may be necessary to place a screwdriver, 1, in the slots provided between the housing and backplate assemblies. With the screwdriver installed in the slots, pry downward to separate the components.
3. Carefully remove the backplate from the housing assembly.




35

4. Turn the backplate assembly over and remove the O ring and bronze lens (valve) plate. Two different plates are shown, one for the standard pump, 1, and one for the MegaFlow pump, 2.




36

5. Replace the lens plate if it is scored, nicked, warped or damaged by cavitation. Look for score marks or damage around the bearing surface area. Check the inlet and discharge port area for signs of contamination. This contamination may show as grooves starting in the feathering notch, 1.




37

6. Inspect the bearing cup, 1, and bore in the end plate for damage.




38

7. Remove the bearing cone, 1, from the drive shaft. The bearing should slide off easily. No puller is required.




39

8. Remove the bearing preload spacer, 1, from the drive shaft.




40

9. To remove the rotating group assembly from the housing assembly, first, carefully retain the rotating group assembly, 1, in the housing, and turn both assemblies over.




41

10. With the rotating group and housing assemblies in the input shaft up position, allow the rotating group assembly, 1, to slide down the input shaft assembly and out of the housing assembly.




42

11. With the rotating group assembly removed, remove the piston assemblies, 1, spider, and spider pivot, 2, from the piston block assembly, 3.




43

12. The rotating group assembly is shown disassembled for inspection: piston assemblies, 1; spider, 2; spider pivot, 3, and piston block assembly, 4. The piston block assembly usually requires no further disassembly unless the pins, 5, or block spring, 6, are damaged.




44

13. Inspect the block face, 1, for scoring or wear. Scratches that can be felt with your fingernail will require block replacement. DO NOT LAP THE FACE OF THE PISTON BLOCK. If any excessive wear or scratches are noted on the face of the piston block, the block assembly must be replaced.



45


14. Inspect the individual cylinder bores, 1, for scoring or wear.



46

15. Examine the piston and slipper assembly, 1, looking for scoring or loose-fitting slippers.


NOTE: *Excessive case pressure can cause the slippers to lift and the slipper edges to roll.*



47


SWASH PLATE REMOVAL

1. Remove the stroke control cover cap, 1.




48

2. Measure and record the distance, 1. DO NOT CHANGE THIS ADJUSTMENT.




49

3. Remove the stoke angle adjusting plug, 1. The stroke control piston, 2, can be seen down in the bore.




50

4. Slide the stroke control piston, 1, out of the bore.



51


5. Tilt the swash plate down so the stroke control push rod, 1, extends up into the bore.



52


6. Push the bottom end of the control push rod outward to disengage it from the socket and remove the push rod, 1.

NOTE: *The push rod is engaged in the socket by the rolled edges of the socket. Extreme care must be used to disengage the push rod from the socket by sliding it out of the end of the socket that is not rolled.*




53

7. Tilt the swash plate, 1, so that the pushrod socket is up and lift the swash plate out of the pump housing.




54

8. Remove the swash plate control spring, 1, and bronze saddle bearings, 2.



55


NOTE: *The bearing on the thrust or load side of the swash plate is pressure lubricated by a small hole, 1, drilled in the swash plate. The lubrication is provided when the hole in a piston slipper indexes with the hole in the swash plate.*



56


INPUT SHAFT

1. Remove the input shaft assembly, 1, by lifting it out of the housing assembly.




57

2. Inspect the input shaft, 1, and bearing cone, 2, assembly for damage such as worn splines, 3, or damaged bearing rollers.



58


3. Replace the bearing, 1, if required. Press the used bearing off and then press the new bearing on.
4. Use a pair of internal snap ring pliers to remove the shaft seal retaining ring, and remove the shaft seal from the housing assembly if it has not already been removed. See Figure 18.




59

5. Inspect the housing assembly. If the bearing cup, 1, or swash plate saddle bushing area, 2, has not been damaged, then there should be no reason to replace the housing.

NOTE: *When damage is noted, the housing assembly must be replaced.*



60



61


Exploded View of Main Pump

1. Housing
2. Control valve
3. Rod
4. Piston
5. Stroke limiting assembly
6. Shaft
7. Bearing
8. Backplate
9. O ring
10. Bearing
11. Spacer
12. Rotating group assembly
13. Swash plate
14. Spring
15. Bearings
16. Shaft seal
17. Snap ring

PUMP REASSEMBLY


Before reassembling the variable displacement axial piston pump, replace all worn and damaged parts and assemblies and all seals and O rings. Lubricate the seals and O rings with petroleum jelly to retain them during reassembly and provide lubrication to the dust and shaft seals.

1. Lubricate all finished part surfaces freely with clean hydraulic fluid, 1, to provide start-up lubrication between the rotating parts.




62

2. To reassemble, first position the housing assembly, 1, with the input shaft opening facing down on a suitable stand, 2.




63

3. Install a new input shaft bearing cup, 1.




64

4. Install the input shaft assembly, 1, into the housing assembly.



65


5. Install the swash plate control spring, 1, and new saddle bearings, 2.



66


6. Reassemble the swash plate, 1, into the housing by tilting the swash plate with the push rod socket up slightly and installing.

NOTE: *Caution must be used when installing the complete swash plate as not to dislodge the swash plate spring or the saddle bearings.*




67

7. Insert the push rod, 1, through the stoke piston bore and reengage the end of the tube into the swash plate socket.




68

8. Tilt the swash plate up and insert the push rod, 1, down and into the socket. Make sure the push rod is engaged in the socket correctly.




69

9. Install the stroke control piston, 2, in the bore. Screw the cover, 1, back on.



70


10. The stroke angle adjusting screw, 1, should be adjusted to the measurement taken during disassembly. Refer to Figure 49. If the screw is turned in past this point, the pump swash plate will not be able to tilt the full 18°.



71


ROTATING GROUP ASSEMBLY

1. Install the guide pins, 1, in the block spines.




72

2. Lubricate and install the pivot, 1, spider and piston assemblies, 2, on the pivot and into the block assembly.




73

3. Check bearing preload before installing the rotating group. Install bearing, 1, and spacer, 2, on the shaft.




74

4. Install rear cover, 1, tap it to seat it properly and measure the gap with a feeler gauge, 2.




75

5. The gap should be 0.00 - 0.05 mm (0.000 - 0.002″) as indicated, 1; grind spacer if required to achieve the proper clearance. Make certain there is no bearing end play. A dial indicator can be used to confirm this.



76


6. Remove the end cover, 1, bearing and spacer. Proceed with installation of the rotating group.
7. Turn the housing assembly over so that the input shaft drive end is up.



77


8. Hold the rotating group assembly, 1, in the upright position, and carefully install the rotating group assembly into the housing assembly. Make sure that the input shaft assembly splines are engaged correctly.

   EXTREME CAUTION must be used to ensure that all parts are in their proper position.
9. After the rotating group is installed, turn the housing assembly over so that the input shaft is down. Make sure the rotating group stays in place.




78

10. Install bearing, 1, and spacer, 2, on the end of the input shaft.




79

11. Install O ring in the small pressure passage, 1. Coat the O ring with petroleum jelly.




9 80

12. Install new O ring, 2, and the valve plate, 3, on the end plate, 1.
13. Install the end plate, making sure to align the punch marks made during disassembly.



81


14. Install the allen cap screws, 1, that retain the end plate and torque to 100 N·m (74 ft lbs).



82


FLOW AND PRESSURE COMPENSATOR VALVES

1. Lubricate and install the sealing O rings, 2, in the compensator housing, 1.
2. Make sure the orifice slot, 3, is positioned as shown.




83

3. Install the compensator housing on the pump body and torque the cap screws, 1, to 12 N·m (9 ft lbs).




84

4. Lubricate and install the low-pressure compensator spool, 1, into the compensator housing. Make sure the spool is inserted correctly.




85

5. Lubricate and install the spring and guide, 1, into the low-pressure compensator bore, 2. Install the low-pressure compensator adjusting screw and cap.




86

6. Lubricate and install the high-pressure compensator spool, 1, into the body assembly.




87

7. Install the high-pressure compensator adjustment cap, spring and guide assembly, 1, into the compensator housing, 2. Torque to 13.6 - 16.6 N·m (10 - 12 ft lbs).



88


8. Turn the adjusting screws, 1 and 2, so that the same amount of threads are showing that was measured before disassembly. INSTALL THE ANTI-TAMPER COVERS AFTER THE PUMP IS TESTED.
9. Plug all of the pump openings with protective covers until the pump is ready to be installed. The variable displacement axial piston pump is now ready for reinstallation and testing.



89


PUMP INSTALLATION

1. Install a new O ring on the pump mounting flange. Mount the pump to the drive gear case using two cap screws, 1. Torque the cap screws to 79 N·m (58 ft lbs).




90

2. Install the pump outlet fittings, 1 and 2.



91


3. Install the single or dual inlet manifold, 2: inlet elbow,1; and threaded inlet adaptor plugs, 4. Make certain that all O rings, 3, are in proper location. Torque the inlet adaptor plugs to123 N·m (90 ft lbs).



92

4. Reinstall the pump case drain line, 1; inlet supply tube, 3; discharge line, 2, and load sense line.
5. Fill the pump housing with hydraulic fluid.


   MegaFlow system shown.



93

6. Reconnect the lines, 1, 2 and 3.
7. Fill the pump housing with hydraulic fluid,


   Standard system shown.



94


8. Refill the rear axle center section with 117 Liters (31 gal) of M2C134D or F200 hydraulic fluid and check fluid level, 1. Add more fluid as required.

   The 8670/8670A tractor will hold about 102 Liters (27 gal).



95

9. Install flowmeters or loop lines in the quick couplers, 1 and 2, for the remote valves I "Green" and IV "Gray." Start the tractor and operate the control levers to purge the air from the high-pressure hydraulic system. Operate the pumps at low engine speed for 10 minutes to break the pumps in prior to any high-pressure testing.
10. Refer to Chapter 13 for instructions on pump flow and pressure testing.
11. Reinstall the rear wheel if it was removed. Torque the wheel bolts as instructed in Repair Manual.



96

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 5 - Flow Divider

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Description of Operation	3
	Priority Flow Divider	3
41 200	Disassembly and Repair	6
	Removal	6
	Teardown	7
	Assembly	8

SPECIFICATIONS

Relief valve pressure - 70 Series	172.4 bar (2500 PSI)
Relief valve pressure - 70A Series	186 bar (2700 PSI)
Flow	Up to 38.0 L/min (Up to 10 GPM)

DESCRIPTION OF OPERATION


PRIORITY FLOW DIVIDER

The steering priority flow divider, 3, provides both priority flow and maximum pressure control for the hydrostatic steering system.


The valve consists of a body, priority spool, and relief valve assembly.

The first function of the priority valve is to ensure that the steering circuit, 3, will get a demand priority flow from the pump circuit. This flow will be metered in a range from 0 - 38 L/min (0 - 10 GPM) and limits the maximum pressure to 165 + 6.9 - 0 bar (2400 + 100 - 0 PSI) for the 70 Series, or 186 + 6.9 - 0 bar (2700 + 100 - 0 PSI) for the 70A Series.

The amount of flow depends upon how fast the operator is turning the steering wheel.



1



2

1. Priority spool
2. Remote valve circuit
3. Steering circuit
4. Pump flow
5. Relief valve
6. Relief valve drain
7. Load sensing pressure

Only the flow required by the steering maneuver goes to the steering circuit, 3. Flow not required by the steering circuit is available for use in the remote valve circuit, 2.

When the operator turns the steering wheel, the priority spool, 1, will shift toward the right and cover the port which directs fluid out to the remote valve circuit, 2.

This action causes the pump flow, 4, to be directed to the steering circuit. If the pump flow is greater than the steering circuit requirement, the spool will shift back toward the left and the extra pump flow will go to the remote valve circuit.

The spring and pressure building up on the right-hand end of the spool cause this spool movement.

When the steering control valve is neutralized, the spool shifts all the way to the left and all the pump flow goes to the remote valve circuit.

The movement of the spool is controlled by load sensing pressure, 7, and the spring pressure balancing against the pump supply pressure built up on the right end of the spool.

The priority valve spool, 1, has two internal orifices which allow a small amount of fluid to transfer from the right end to the left end of the spool. This provides a dynamic bleed flow which keeps the spool positioned for fast response.

The second function of the priority valve is to regulate the maximum pressure of the steering circuit. This is accomplished by the relief valve, 5, in the load sense circuit, 7, which connects the steering control valve, priority valve, and implement pump together.

When the operator holds the steering wheel in a maximum turn, the pressure signal from the steering control valve is directed back to the load sensing port on the priority valve.

This pressure is directed into the pilot operated relief valve control passage. The pressure acts upon the relief valve plunger, which is opposed by a spring. When the pressure gets high enough, it will open the relief valve.


This allows the control pressure that is pushing on the main spool to bleed off. The main spool will shift to the left, and a reduced amount of fluid will be sent to the steering circuit. The priority valve spool will continue to shift until it reaches a balance point that allows just enough fluid to be sent to the steering circuit to keep the relief valve cracked open.

When the operator returns the steering wheel to neutral, the main passage in the steering control valve closes, and the load sense pressure is cut off. This causes the priority spool to shift, and close off the flow to the steering circuit.

The relief valve, 5, is factory set and is nonadjustable in the field. The internal setscrew is bonded with a thread-locking compound.

A new load sense line shuttle tee, part #86002299, 1, (replaced #9843574) was incorporated into production in January, 1996 to eliminate leakage across the shuttle tee seat. This "T" can be installed on earlier production tractors with slight modification (bending) of the tubes and with the addition of one #9993143 fitting.


NOTE: *The original shuttle tee can also contribute to steering wheel kickback if it is faulty.*



3

If the new load sense line shuttle "T" is installed on earlier units, the check fitting, 1, part #86505847, should be removed, discarded, and replaced with an adapter, part #9626421.

NOTE: *Another way to prevent steering wheel kick back is to install a check valve fitting in the inlet part of the steering control valve. See Section 41 for more information.*




4

DISASSEMBLY AND REPAIR

REMOVAL

To remove the flow divider, 3:


1. Clean the tractor. The right rear wheel should be moved outboard to improve access to the flow divider tubing, 1.



5

2. Loosen the five tubing connections on the flow divider, 1.
3. Loosen the two cap screws that attach the flow divider to the mounting bracket.


NOTE: *Use crowfoot wrenches or tubing wrenches whenever possible to loosen the tubing nuts.*



6

4. Remove the flow divider and cap all the hydraulic lines, 1 and 2, to prevent contamination.


NOTE: *Cab shown removed for clarity.*



7


TEARDOWN

1. Remove the orifice plug, 1, and O ring. Check the orifice. Spring, 3, will exert some force on the cap as it is removed. Remove the end plug, 6.
2. The spool, 4, should slide easily out of the body, 7.
3. Remove the relief valve, 9, and inspect the O ring, 8, and screen for damage.




8

4. Check the body, 1, and spool, 3, for scoring or nicks in the control land areas that could cause spool binding.
5. The orifices, 2 and 4, inside the spool are non-serviceable and should be tight. The orifice openings should be clean.
6. Orifice, 2, is 0.035″ inside diameter. Orifice, 4, is 0.025″ inside diameter.
7. Clean all parts with parts washing solution and allow to air dry.
8. Replace any damaged parts.




9



10


ASSEMBLY

1. Install new O rings on the plugs,1 and 2, and the relief valve, 3.
2. Coat the spool, 4, and the internal passages in the body with clean M2C134D hydraulic fluid and install the spool in the body.
3. Install the spring, 5, and the plugs, 1 and 2.
4. Install the relief valve, 3.




11

5. Loosely install the external fittings, 2, 3, and 4, with new O rings and check the mounting angle of the fittings.
6. Tighten the jam nuts to 54 - 68 N·m (40 - 50 ft lbs).
7. Torque adaptor, 6, to 8 -15 N·m (6 -11 ft lbs).
8. Reinstall the flow divider, 1, on the tractor.
9. Torque the tubing nuts, 5, to 126 - 170 N·m (93 - 100 ft lbs).
10. Torque the fitting, 7, to 13.5 - 16 N·m (10 - 12 ft lbs).



12

11. Install a flowmeter or loop line, 1, in the #I remote valve.
12. Start the tractor and engage the #I remote valve control lever to purge the system. Check for leaks.
13. Operate the steering wheel to purge air and oil through the priority circuit. Check for leaks.



13

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 6 - 70 Series Remote Valves

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Remote Valve Assembly	3
	Remote Valve Section (Series Logic)	9
	Remote Valve Section (Parallel Logic)	15
	Control Cables	21
	Return Tube	22
	Primary and Secondary Shuttles	22
	Order of Priority Operation	28

SPECIFICATIONS

Detent release valve pressure ..... 172.4 Bar (2500 PSI)

Flow ..... 0 - 91 L/min (0 - 24 GPM)

Torques

Tie bolts ..... 30 N·m (22 ft lbs)

Valve spool bonnet covers ..... 8 N·m (5 ft lbs)

Valve base mounting bolts ..... 237 - 270 N·m (175 - 200 ft lbs)

Remote coupler manifolds allen screws ..... 27 - 33 N·m (20 - 24 ft lbs)

Remote couplers ..... 68 - 75 N·m (50 - 55 ft lbs)

SPECIAL TOOLS

Remote coupler body removal tool FNH00095
(For cast aluminum couplers, before serial number D408953)

Tools Required

Standard wrenches including a 1-5/8″, 1-3/16″, and 1-7/8″ open end

Crowfoot wrenches 17mm, 7/8″

Allen wrenches, 1/8″, 7/32″ and 3/16″

Torque wrench with 9/16″ socket

Petroleum jelly for coating all O rings prior to installation


Flowmeter for testing system

DESCRIPTION OF OPERATION

REMOTE VALVE ASSEMBLY


The remote valve assembly is made up of two, three, or four remote control valve sections, 1, plus a three-point hitch/electronic draft control (EDC) section, 2, that can be stacked together to obtain the desired option configuration.

NOTE: *Three-point hitch valve, 2, is an option and is not on all tractors.*




1

Four remote valves, 1, are shown with the three-point hitch valve, 2.




2

The valve assembly is mounted on the outside of the rear of the cab on a mounting base which tilts it slightly toward the rear of the tractor.




3

The mounting base includes the oil inlet passage, 1, and the load sense outlet passage, 2.




4

The return oil passage, 1, from the remote valve assembly passes through the mounting base into the rear axle top cover.




5

The remote valve assembly mounting base is fastened to the rear axle housing top cover with four cap screws, 1. The top cover also contains a return oil passage, 2.



6



7

The sections have O rings, 2, and spacer shims, 3, between each section. The O rings are used to seal the fluid passages. The shims are required to provide proper preload on the O rings while the valve sections are heating and cooling during normal operation.


The valve sections are numbered from the bottom up. The #I valve section, 4, has absolute priority over the other sections due to a special casting and special flow control in the valve body.

The #II valve section, 5, is also a special casting and should be reinstalled in that position. Valve sections #III and #IV are the same and can be interchanged.

The MegaFlow™ remote valve assembly has a special #II remote valve section. The pressure oil passage is blocked between sections #II and #III. A plug, 1, is inserted in the pressure passage to isolate the pressure oil from the two CCLS axial piston pumps.

NOTE: *The remote control valves can be used for loader operation but do not have regenerative ability, and the operator may notice loader cylinder cavitation because of the spool port timing design.*

NOTE: *If used with a loader, #I and #II flow controls should be adjusted to maximum flow to prevent overrunning loads and subsequent jerky lowering operation due to the pilot operated (PO) check valve opening and closing.*



8


Series Logic Versus Parallel Logic Assemblies

A series logic or parallel logic valve assembly can be installed on the tractor. The main difference between the two valve assemblies is the internal porting of the valve assemblies. The main valve differences are discussed in this chapter.

The main identification between the two valve assemblies is the part number on the identification tag 1. Series valve assemblies can be identified by part numbers 9821338, 9821339, 9821344, 9821345, 9821346, 9821409 and 86002601. Parallel valve assemblies can be identified by part numbers 86018025 through 86018031.


Valve assemblies with HPL can also be identified by the HPL valve. The parallel assembly will not have the "A" port pressure regulator.

NOTE: *Some early model tractors with a series valve assembly may not have the "A" port pressure regulator.*



9


Individual valves can be identified by the number of ports drilled on the bottom side of the valve. Series valves will have only one port drilled in line with the secondary shuttle valve. Parallel valves will have two ports drilled in the bottom in line with the secondary shuttle and one will be closed with an expansion plug.



10


The individual valve are also stamped with a 3 digit number, 1, as follows:

Valve Section	Series	Parallel
#1	716	739
#2 (standard)	717	740
#2 (megaflow)	718	741
#3 and #4	364	379
EDC	727	742




11

Additionally the flow gain window in the flow control sleeve will be different. Figure 12 shows the flow gain window of the series valve and Figure 13 shows the flow gain window of the parallel valve.




DUAL SLOPE FLOW GAIN WINDOW

12



LINEAR FLOW GAIN WINDOW

13



14

Remote Valve - Cutaway View

REMOTE VALVE SECTION (Series Logic)


Valve assembly part numbers 9821338, 9821339, 9821344, 9821345, 9821346, 9821409, and 8600261.
A cross-sectional view of valve section #I is shown in the figure above. The cross-section of the valve sections used in #III and #IV is shown in Figure 15. The cross-section of valve section #II is similar to #I with a pressure compensating valve, 4, like those in valves #III and #IV.

The remote valve sections are load sensing, four-way, direct acting, with float and pressure detent release functions. Each valve has individual pressure compensating flow controls which also serve as load checks, 4.

The pressure compensating flow controls allow each section to independently control the flow. This helps to maintain proper flow in the respective valve section as the supply pressure changes.

This pressure compensation feature also helps to maintain smooth and easy movement of the control spool, 2, throughout the full range of spool movement and system pressure. This is accomplished by maintaining a 4.1 bar (60 PSI) pressure drop between the flow control and the main spool while fluid is flowing. The operator will not have to increase the effort to move a spool when the system is operating at 34.5 bar (500 PSI) versus 172 bar (2500 PSI).

The pressure detent release or kickout pressure is factory set at 155 bar (2250 PSI) and can be adjusted in the field by turning the adjusting screw, 5.




15

Remote Valve - Cutaway View

The adjustment range on the flow control is 4 - 91 L/min (1 - 24 GPM), 3. The flow control operation for the series valve assembly is non-linear throughout the control movement. The control movement for the flow range of 0 - 38 L/min (0 -10 GPM) is linear and then the movement is non-linear to the full open position. The control must be turned full counter-clockwise to obtain full flow operation.

The following drawings show the #I remote valve in the four different modes of operation - Neutral, Raise, Lower, and Float.

NOTE: *Do not restrain the valve spool and lever in the raise or lower detent position. The detent release system will develop a very loud hydraulic noise if the spool cannot snap back to neutral.*




16

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Neutral

Oil enters the valve through the port C, flows through the pressure compensating spool to passage E. Since oil in passage E is blocked by the control spool, no flow occurs, in valve section #I, to the coupler. Oil pressure on the stem end of the flow control piston shifts the piston, compressing the springs, allowing oil to flow from port C to port D supplying oil for valve sections #II, III, IV, and the three-point valve.



17

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock


Raise

When the control spool, 2, is pulled outward, oil from passage E is allowed to flow across the control spool into passages H and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 13, opening the valve and allowing oil in passage H to flow through to the extend coupler, 12.

Oil also flows to the primary shuttle, 7, which directs oil to the secondary shuttle and detent release adjusting valve. The secondary shuttle then directs oil to the spring end of the flow compensating valve and/or hydraulic pump pressure and flow compensating valve.

The flow control piston inside the flow control spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information on its operation.

Return oil enters the retract coupler, 1, then to passage K crossing over the spool to passage A where oil returns to sump.



18

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock


Lower

When the control spool, 2, is pushed inward one notch, oil from passage E is allowed to flow across the control spool into passages K and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 13, opening the valve and allowing return oil from the coupler to pass through the pilot operated check valve and into passage H. Oil in passage K flows to the retract coupler, 1, and out to the implement.

Oil also flows to the primary shuttle, 7, which directs oil to the secondary shuttle and detent release adjusting valve. The secondary shuttle then directs oil to the spring end of the flow compensating valve and/or hydraulic pump pressure and flow compensating valve.

The flow control piston inside the flow control spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information on its operation.

Return oil enters the extend coupler, 12, then to passage H crossing over the spool to passage A where oil returns to sump.




19

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Float

When the control spool, 2, is pushed fully inward, oil from passage E enters passage J moving the pilot operated line lock piston allowing free flow of oil through the line lock. Passages H and K are open to passage A, return to sump.



20

Remote Valve - Cutaway View

REMOTE VALVE SECTION (Parallel Logic)


Valve assembly part numbers 86018025 through 86018031.
A cross-sectional view of valves section #I is shown in the figure above. The cross-section of the valve sections used in #III and #IV is shown in Figure 21. The cross-section of valve section #II is the similar to #I with a pressure compensating valve, 4, like those in valves #III and #IV.

The remote valve sections are load sensing, four-way, direct acting, with float and pressure detent release functions. Each valve has individual pressure compensating flow controls which also serve as load checks, 4.

The pressure compensating flow controls allow each section to independently control the flow. This helps to maintain proper flow in the respective valve section as the supply pressure changes.

This pressure compensation feature also helps to maintain smooth and easy movement of the control spool, 2, throughout the full range of spool movement and system pressure. This is accomplished by maintaining a 4.1 bar (60 PSI) pressure drop between the flow control and the main spool while fluid is following. The operator will not have to increase the effort to move a spool when the system is operating at 34.5 bar (500 PSI) versus 172 bar (2500 PSI).

The pressure detent release or kickout pressure is factory set at 155 bar (2250 PSI) and can be adjusted in the field by turning the adjusting screw, 5.




21

Remote Valve - Cutaway View

The adjustment range on the flow control is 5.7 - 91 L/min (1.5 - 24 GPM), 3. The flow control operation is linear throughout the full adjustment range of the control movement. The control must be turned full counterclockwise to obtain full flow operation.

The following drawings show the #I remote valve in the four different modes or operation - Neutral, Raise, Lower and Float.




22

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Neutral

Oil enters the valve through the port C, flows through the pressure compensating spool to passage E and to the piston end of the flow control piston, 4, through the passage in the piston. Since oil in passage E is blocked by the control spool, no flow occurs, in valve section #I, to the coupler. Oil pressure on the stem end of the flow control piston shifts the piston, compressing the springs, allowing oil to flow from port C to port D supplying oil for valve sections #II, III, IV, and the three-point valve.



23

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Raise


When the control spool, 2, is pulled outward, oil from passage E is allowed to flow across the control spool into passages H and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 13, opening the valve and allowing oil in passage H to flow through to the extend coupler, 12.

Oil also flows to the primary shuttle, 7, which directs oil to the secondary shuttle, detent release adjusting valve and spring end of the flow compensating valve.

The secondary shuttle then directs oil to the hydraulic pump pressure and flow compensating valve.

The flow control piston inside the flow control spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information.

Return oil enters the retract coupler, 1, then to passage K crossing over the spool to passage A where oil returns to sump.



24

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock


Lower

When the control spool, 2, is pushed inward one notch, oil from passage E is allowed to flow across the control spool into passages K and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 13, opening the valve and allowing return oil from the coupler to pass through the pilot operated check valve and into passage H. Oil in passage K flows to the retract coupler, 1, and out to the implement.

Oil also flows to the primary shuttle, 7, which directs oil to the secondary shuttle, detent release adjusting valve and the flow compensating valve. The secondary shuttle then directs oil to the hydraulic pump pressure and flow compensating valve.

The flow control piston inside the flow control spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information on its operation.

Return oil enters the extend coupler, 12, then to passage H crossing over the spool to passage A where oil returns to sump.




25

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Float

When the control spool, 2, is pushed fully inward, oil from passage E enters passage J moving the pilot operated line lock piston allowing free flow of oil through the line lock. Passages H and K are open to passage A, return to sump.



26

CONTROL CABLES

The valves spools are operated by remote control cables, 1, which are connected to levers in the cab right-hand control console.


The control cables and levers permit movement of the spool to engage the detent up, detent down and detent float position.

The flow controls are operated by rotating cables, 2, mounted on the rear of the cab.

NOTE: *The flow control knobs and cables may be difficult to operate when the valve is in high-pressure operation. This difficulty is due to the fluid flowing through the flow control which places hydraulic loading on the flow control actuating stem.*

RETURN TUBE

The remote valve return oil flow exits the bottom of the valve assembly and enters the rear axle center section. A tube, 1, inside of this housing carries the oil back to the inlet screen area of the reservoir. This was done to reduce oil aeration when operating in high flow configurations.




27


PRIMARY AND SECONDARY SHUTTLES

Each remote valve section contains one primary, 1, and one secondary, 2, shuttle which is used to connect the "A" and "B" work ports to the load sensing circuit.

During system operation, the higher work port pressure is routed back to the primary shuttle where it seats a steel ball and closes off the other work port passage which has return oil pressure in it. The shuttle ball operation allows either work port to signal the load sense system. The pressure is then directed out to the secondary shuttle which allows the individual valve section to communicate in the load sense system.



28




29

1. Primary shuttle
2. Secondary shuttle
3. Flow control
4. Load sense oil to pump
5. Flow in from pump
6. Return oil
7. Control spool

Secondary Shuttles

The remote valve load sensing circuit is a series circuit which allows the secondary shuttles, 2, to communicate between the valve sections and the pump control valve. When a valve is operated, the load sense oil will enter the primary shuttle, 1, as described earlier and then enter the secondary shuttle, 2. The oil will also enter the flow control spring chamber, 3, and go out to the detent release piston area of the valve assembly.

The oil will seat the steel ball in the secondary shuttle, 2, and exit downward to the next shuttle where it will back seat the ball and go on to the next shuttle until the oil can exit the valve and go to the pump assembly. The secondary shuttle with the highest working pressure will override the shuttles and control the pump.



30

1. Remote coupler, - side
2. Control spool
3. Flow control stem
4. Flow control piston
5. Flow control sleeve
6. Secondary shuttle
7. Primary shuttle
8. Detent release adjusting valve
9. Orifice
10. Detent balls
11. Detent centering springs
12. Remote coupler, + side
13. Pilot operated line lock

Flow Control Operation

The flow control valve consists of a stem, 3, sleeve, 5, piston, 4, compensating springs, gain window, and oil supply port C. Flow is adjusted by rotating the flow control spool, controlling the amount of flow gain window opening in passage E. The flow control valve has two basic modes of operation to regulate the flow of oil to the coupler.

1. Remote valve control spool in neutral or float position:

With the remote valve control spool in neutral or float position oil fills the supply port C in the valve body, enters the sleeve ports and shifts the piston to open the gain window. There is also a port drilled in the center of the piston that applies pressure to the stem end of the piston, aiding in piston movement. Oil flows through the gain window to the control spool. With the control spool in neutral no load sense signal detected, no flow occurs through the flow compensator valve.

2. Remote valve control spool shifted to extend or retract:


When the remote valve control spool is shifted to the extend or retract position, pressure is directed through the primary shuttle to the secondary shuttle then to the spring end of the flow compensator valve. The system pressure on the stem end of the piston and spring pressure plus load sense pressure on the opposite end of the piston shifts the piston back and forth opening and closing the sleeve ports to adjust and maintain the flow through the coupler.

NOTE: *The amount of oil flow through the coupler is controlled by the amount of gain window opening into the control passage. The sleeve fits into a milled port that when the flow control knob is turned to the minimum setting, little or no flow is passed through the gain window. As the spool is turned the gain window increases, thus increasing flow to the coupler.*

When properly adjusted, an increase in system pressure due to a higher pressure demand from another valve, the piston shifts restricting the flow from passage C through the sleeve ports, thus maintaining flow to the coupler. Figure 30 shows the proper alignment of the flow control piston for the #I remote valve, when properly adjusted.

When improperly adjusted (flow control full open), maximum flow is being directed through passage E causing an increase in sense pressure on the spring end of the piston shifting the piston to the stem end, thus closing off the oil flow from port C to port D. When this happens valves II, III, IV, and three point do not receive any oil.

NOTE: *On series logic valves, the load sense pressure from the valve with the highest pressure demand will be on the spring end of each flow compensating spool. On parallel logic valves the load sense pressure from a valve requiring a higher pressure demand will not be on the spring end of each flow compensating spool.*



31

Three-Point Hitch Series Circuit Logic Priority


Valve assembly part numbers 9821338, 9821339, 9821344, 9821345, 9821346, 9821409, and 8600261.

The flow control chamber, 4, on the three-point hitch valve is ported differently than valve sections #II, #III, and #IV. This allows the three-point hitch valve to have pressure priority over these other valve sections. A high-pressure requirement in the three-point valve will cause the flow controls in the other valves to partially close down and direct higher pressure to the three-point hitch valve.

The flow control compensator also has different springs which assist in giving the three-point hitch valve priority operation.

If the #I valve section is deadheaded for any reason, the high pressure will enter the #I flow control chamber and stop oil flow from getting to the upper valve sections until the #I circuit is satisfied. This happens because of the load sensing oil flow pattern in the casting.

The MegaFlow remote valve system splits the remote valve load sensing circuit between the #II and #III valve sections with a special fitting, 5, fastened into the secondary shuttle port on the #II valve. This allows the upper valve sections to signal the MegaFlow pump and the lower valve sections to signal the standard pump through port 6. The plug, 9, blocks the pump inlet flows, 2, and 7.



32

Three-Point Hitch Parallel Circuit Logic Priority

Valve Assembly part numbers 86018025 through 86018031.
The flow control chamber, 4, on the three-point hitch valve is ported the same as valves #II, #III, and #IV. This allows all the valve sections to have equal priority after the #I valve. The valve section with the least restriction will gain flow priority over the other valves.

If the #I valve section is deadheaded for any reason, the high pressure will enter the #I flow control chamber and stop oil flow from getting to the upper valve sections until the #I circuit is satisfied. This happens because of the load sensing oil flow pattern in the casting.

The MegaFlow remote valve system splits the remote valve load sensing circuit between the #II and #III valve sections with a special fitting, 5, fastened into the secondary shuttle port on the #II valve. This allows the upper valve sections to signal the MegaFlow pump and the lower valve sections to signal the standard pump through port 6. The plug, 9, blocks the pump inlet flows, 2 and 7.

ORDER OF PRIORITY OPERATION FOR VALVE PART NUMBERS 9821338, 9821339, 9821344, 9821345, 9821346, 9821409, AND 86002601

These remote valves operate on a priority basis. The number I valve has complete flow priority. The remaining valves have a priority established in a descending order as shown in the tables.

If multiple hydraulic functions, such as dual orbit motors, are required, the most critical function motor should be connected to the #I valve. The second most critical motor must be connected to the #IV valve.

NOTE: *The power-steering flow divider has priority flow over all the flow from the upper pump.*

STANDARD HYDRAULICS (SINGLE PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch	2	Upper
IV	3	Upper
III	4	Upper
II	5	Upper
I	1	Upper

MEGAFLOW HYDRAULICS (DUAL PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch	1	Lower
IV	2	Lower
III	3	Lower
II	2	Upper
I	1	Upper

NOTE: *The #I valve flow control can block the flow to the downstream valves. Make sure it is adjusted properly.*

ORDER OF PRIORITY OPERATION FOR VALVE PART NUMBERS 86018025, TO 86018031

These remote valves operate on an equal priority basis with the number I valve having complete flow priority. The remaining valves share priority with flow going to the valve with least resistance.

If multiple hydraulic functions, such as dual orbit motors, are required, the most critical motor should be connected to the #I valve. The second most critical motor can be connected to any remaining valve.

NOTE: *The power-steering flow divider has priority flow over all the flow from the upper pump.*

STANDARD HYDRAULICS (SINGLE PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch, IV, III, and II	Valve with least resistance	Upper
I	1st	Upper

MEGAFLOW HYDRAULICS (DUAL PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch, IV, III, and II	Valve with least resistance	Lower
II	2nd	Upper
I	1st	Upper

NOTE: *The #I valve flow control can block the flow to the downstream valves. Make sure it is adjusted properly.*

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 7 - 70A Series Electro-Hydraulic Remote Valves

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Electro Hydraulic Remote Valves	3
	Control Switches	3
	Flow Control Adjustment	4
	Description of Operation	4
	Flow Control Operation	9
	Order of Priority Operation	14

SPECIFICATIONS

Timed Detent release	Operator Set
Flow	0 - 117 L/min (0 - 31 GPM)
Valve Solenoid Voltage	Extend and Retract Solenoid Resistance - 2.4 ohms Solenoids are 12 VDC pulse width modulated devices (PWM)

Torques

Tie bolts	30 N·m (22 ft lbs)
Valve spool bonnet covers	8 N·m (5 ft lbs)
Valve base mounting bolts	237 - 270 N·m (175 - 200 ft lbs)
Remote coupler manifolds allen screws	27 - 33 N·m (20 - 24 ft lbs)
Remote couplers	68 - 75 N·m (50 - 55 ft lbs)

Tools Required

Standard wrenches including a 1-5/8", 1-3/16", and 1-7/8" open end

Crowfoot wrenches 17mm, 7/8"

Allen wrenches, 1/8", 7/32" and 3/16"


Torque wrench with 9/16" socket

Petroleum jelly for coating all O rings prior to installation

Flowmeter for testing system

ELECTRO HYDRAULIC REMOTE VALVES

The electro-hydraulic remote control valves are similar to the mechanical remote control valves. The changes are primarily contained within the valve body. For assembly and mounting information use the appropriate section of the repair manual. In addition to the changes in the main body of the valve section, each valve section has two solenoids on both ends that control the main spool section of the valve.




1

CONTROL SWITCHES


The electro-hydraulic remote valves are operated by finger controlled switches in the right-hand console and are connected electronically to the remote valve solenoids. Each control switch is colored to correspond to the color on the remote valve. The numbers in these figures match up the control switches, remote valves and color coding.

1. Remote valve I (green) with load check
2. Remote valve II (blue) with load check
3. Remote valve III (brown) (if equipped)
4. Remote valve IV (gray) (if equipped)



2


1.	Control switch I	Green
2.	Control switch II	Blue
3.	Control switch III	Brown
4.	Control switch IV	Gray



3

FLOW CONTROL ADJUSTMENT

Each remote valve has a flow control knob, 1, to meter oil flow. The knob controls flow from 0 to 117 L/MIN (0 to 31 GPM). Turn the knob so the higher vertical decal stripe, 2, is visible to increase the rate of oil flow. Turn the knob so the lower vertical decal stripe, 3, is visible to decrease the rate of oil flow.



4

DESCRIPTION OF OPERATION

Pressure, Tank and Load Sense (same as manual valve) Standard Hydraulic System:

Flow from a single variable displacement pump enters the remote valve assembly thru the base plate (wedge) at the bottom of the valve stack. The fluid within the valve is on a priority basis to section #1. The remaining sections are on a parallel circuit so they can all share the fluid flow.

The return fluid leaves the remote valve assembly thru a hole in the bottom of the base plate that is manifold mounted to the rear axle section.

All of the remote valve functions can signal or control the variable displacement pump by load sensing signals sent to the control valve on the pump. This permits the system to respond to individual flow/pressure requirements. The valve stack has a shuttle network to resolve the load sense pressures of each work port so that the highest pressure is sent to the pump control. This is accomplished with primary and secondary shuttles in each section.

Megaflow (Deluxe) Hydraulic System:

Two variable displacement pumps provide flow to a Megaflow valve stack. A Megaflow valve stack has a special section #2, with machining to allow the pressure passage to be separated into two circuits by a spacer/disk inserted in the passage between sections 2 and 3. One pump provides flow thru the base plate (wedge) at the bottom of the valve stack to sections 1 & 2, where the flow is on a priority basis to section #1. The remaining sections (3, 4, and EDC) are on a parallel circuit that is supplied by the second pump.

The load sense signal for sections 1 and 2 is sent to the first pump thru a port on the base plate, the same as with a standard hydraulic system. The load sense signal for the remaining sections is sent to pump number 2 via a special fitting in place of the secondary shuttle on the cab-side of section #2.

Remote Valve Sections

The remote valve sections are load sensing, electro-hydraulic, four-position (Neutral, A-power, B-power, and Float), four-way (P, A, B, T). Each section has individual pressure compensators that also serve as load checks. Sections #1 and #2 have pilot-operated check valves (load holding) that are incorporated in the quick-coupler housings.

Main Spool Operation

The main spool of each section controls both the flow rate and direction. The spool is actuated by a solenoid-controlled pilot pressure applied to the housings on either end of the spool.

Pilot supply oil from the transmission circuit enters the valve assembly thru the top cover (thru a 100-micron filter fitting). The pilot oil is connected to all of the section solenoid valves in parallel. The solenoid valves are actually proportional pressure-reducing valves that received the pilot supply oil and then regulate the pressure applied to the main spool end in proportion to the pulse-width-modulated (PWM) current level applied to them by the programmable controller. Each solenoid cartridge valve has 3 hydraulic ports, Supply Pressure, Regulated Pressure, and Tank. The regulated pressure acts against the spool centering springs to move the spool a distance proportional to the current applied to the solenoid. With no current applied to the solenoid, the spool end is connected to the tank port of the solenoid cartridge. All of the solenoid cartridge tank ports are connected in parallel to the solenoid drain port at the top cover of the valve stack.

Flow Control


The flow control function is controlled by main spool position. The flow control thumb wheels in the tractor cab limits the maximum current that will be applied to the solenoids. Limiting the maximum current limits the maximum main spool stroke and flow.

Detent and Kickout (Detent Release)


The electro-hydraulic remote valve does not have mechanical detents or pressure detent release (kickout). Instead, the detents are a function of the control lever pods in the right hand console. The kickout is a timed function of the control electronics. (only operational in the "programmable" mode)

Electro-Hydraulic Pilot Line

The electro-hydraulic pilot line, 1, supplies transmission regulated pressure (16.5 to 19 bar, 240 to 275 psi at 1200 ERPM) to the remotes as pilot oil to assist up to 10 electro-hydraulic solenoids in shifting the remote valve main spools and EDC spool. The pilot line connects from the transmission main pressure port, 2, to the remote assembly valve cap. An inline screen helps protect the EHR pilot valves from contaminant.



5




6

Valve Solenoids

The main spools of the valve are controlled by pilot oil that is controlled by the valve solenoids. Each valve has two solenoids, one for extend (1) and one for retract (2). The solenoids are 12 VDC pulse width modulated devices (PWM). The solenoids have an internal resistance of 2.4 ohms.


The operation of the solenoids is accomplished with pulse width modulation which provides an accurate method for precisely controlling the movement of the valves. The current is modulated, switched on and off, from between 100 to 500 pulses per second. The operating voltage can be monitored with an analog voltmeter with a typical voltage in the 6 to 7 volt range.

The switching or modulation of the control current to the solenoids causes a dithering action to the pilot oil which in turn provides an accurate control of the main spool.



7


The wire connections to the solenoids will be labeled, 1, for each remote valve assembly. The top wire connections will not be labeled. They are for the three point hitch.



8


When the label is gone or not clear to read, the following will identify the wires going to the remote valve solenoids.

Look at the rear of the tractor, facing forward. All the wires going to the remote valve solenoids on the left side of the tractor are the B (extend) (1). All the wires going to the remote valve solenoids on the right side of the tractor are the A (retract) (2). Starting from the bottom solenoid and moving upward, the numbers go 1 through 4. The top wires are for the three point hitch (3). Re-label the wires before disassembly.



9


To remove a remote valve solenoid connector, squeeze the spring clip (1) and pull the connector off the solenoid.



10

Valve Section Identification
Each individual valve section is stamped, 1, with a five digit number for identification.


Valve	Identification
#1 Priority	2-6-004
#2 Standard	2-6-005
#2 Megaflow	2-6-007
#3 & 4	2-3-009
EDC Section	2-6-009



11

FLOW CONTROL OPERATION

The flow compensator spool, 3, consist of a piston, compensating spring, gain window, and oil supply port. Flow is adjusted by rotating the flow potentiometer located on the right hand control console by limiting the maximum current to the solenoids. Limiting the maximum current limits the maximum stroke and flow of the control spool, 2. Feeling the pressure of the two load sense parts thru the primary shuttle, 5, and the secondary shuttle, 4, the flow compensator spool moves side to side to control flow to the control spool.




12

1. Remote coupler, - side
2. Control spool
3. Flow compensator spool
4. Secondary shuttle
5. Primary shuttle
6. Remote coupler, + side
7. Pilot operated line lock

Neutral

Oil enters the valve through the port C, flows through the flow compensating spool to passage E. Since oil in passage E is blocked by the control spool, no flow occurs, in valve section #I, to the coupler. Oil pressure on the plug end of the flow compensator spool shifts the spool, compressing the springs, allowing oil to flow from port C to port D supplying oil for valve sections #II, III, IV, and the three-point valve.



13

1. Remote coupler, - side
2. Control spool
3. Flow compensator spool
4. Secondary shuttle
5. Primary shuttle
6. Remote coupler, + side
7. Pilot operated line lock


Raise

When the control spool, 2, is pulled outward by the electronically controlled pilot pressure, oil from passage E is allowed to flow across the control spool into passages H and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 7, opening the valve and allowing oil in passage H to flow through to the extend coupler, 6.

Oil also flows to the primary shuttle, 5, which directs oil to the secondary shuttle. The secondary shuttle then directs oil to the spring end of the flow compensating spool.

The flow compensator spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information on its operation.

Return oil enters the retract coupler, 1, then to passage K crossing over the control spool to passage A where oil returns to sump.



14

1. Remote coupler, - side
2. Control spool
3. Flow compensator spool
4. Secondary shuttle
5. Primary shuttle
6. Remote coupler, + side
7. Pilot operated line lock


Lower

When the control spool, 2, is partially pushed inward by the electronically controlled pilot pressure, oil from passage E is allowed to flow across the control spool into passages K and J. Oil in passage J applies pressure to the piston end of the pilot operated valve, 7, opening the valve and allowing return oil from the coupler to pass through the pilot operated check valve and into passage H. Oil in passage K flows to the retract coupler, 1, and out to the implement.

Oil also flows to the primary shuttle, 5, which directs oil to the secondary shuttle. The secondary shuttle then directs oil to the spring end of the flow compensating spool.

The flow compensator spool shifts back and forth maintaining coupler flow. See Flow Control Operation in this section for more information on its operation.

Return oil enters the extend coupler, 6, then to passage H crossing over the spool to passage A where oil returns to sump.




15

1. Remote coupler, - side
2. Control spool
3. Flow compensator spool
4. Secondary shuttle
5. Primary shuttle
6. Remote coupler, + side
7. Pilot operated line lock

Float

When the control spool, 2, is pushed fully inward by the electronically controlled pilot pressure, oil from passage E enters passage J moving the pilot operated line lock piston allowing free flow of oil through the line lock. Passages H and K are open to passage A, return to sump.



16

Three-Point Hitch Parallel Circuit Logic Priority
The flow control chamber, 4, on the three-point hitch valve is ported the same as valves #II, #III, and #IV. This allows all the valve sections to have equal priority after the #I valve. The valve section with the least restriction will gain flow priority over the other valves.

If the #I valve section is deadheaded for any reason, the high pressure will enter the #I flow control chamber and stop oil flow from getting to the upper valve sections until the #I circuit is satisfied. This happens because of the load sensing oil flow pattern in the casting.

The MegaFlow remote valve system splits the remote valve load sensing circuit between the #II and #III valve sections with a special fitting, 5, fastened into the secondary shuttle port on the #II valve. This allows the upper valve sections to signal the MegaFlow pump and the lower valve sections to signal the standard pump through port 6. The plug, 9, blocks the pump inlet flows, 2 and 7.

ORDER OF PRIORITY OPERATION FOR VALVE PART NUMBERS 86024149, 86024150, 86024152 AND 86024155

These remote valves operate on an equal priority basis with the number I valve having complete flow priority. The remaining valves share priority with flow going to the valve with least resistance.

If multiple hydraulic functions, such as dual orbit motors, are required, the most critical motor should be connected to the #I valve. The second most critical motor can be connected to any remaining valve.

NOTE: *The power-steering flow divider has priority flow over all the flow from the upper pump.*

STANDARD HYDRAULICS (SINGLE PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch, IV, III, and II	Valve with least resistance	Upper
I	1st	Upper

MEGAFLOW HYDRAULICS (DUAL PUMP)

Valve Location	Order of Priority	Pump
3-Pt. Hitch, IV, III, and II	Valve with least resistance	Lower
II	2nd	Upper
I	1st	Upper

NOTE: *The #I valve flow control can block the flow to the downstream valves. Make sure it is adjusted properly.*

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 8 - Remote Valve Couplers

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Coupler Mounting Block and Coupler Repair (70 Series BSN D408953)	3
	Coupler Mounting Block and Coupler Repair (70 Series ASN D408952)	9

SPECIFICATIONS

Rated Flow ..... 125 L/min (33 GPM)


Torques

Remote coupler manifold allen screws ..... 27 - 33 N·m (20 - 24 ft. lbs.)

Remote couplers ..... 68 - 75 N·m (50 - 55 ft. lbs.)


COUPLER MOUNTING BLOCK AND COUPLER REPAIR (70 SERIES BEFORE SERIAL NUMBER D408953)

1. The remote valves have a cast aluminum block, 1, fastened to the work parts on the valve sections. Remove the coupler mounting block, 1, from the valve body.




1

2. The coupler mounting block is retained by four allen screws, 1. Inspect and replace the O rings, 2, and replace as required.



2


3. Use the special tool FNH00095 to remove the couplers.



3

Valve sections #I and #II have a pilot operated (PO) line check valve assembly, 1, which locks oil in the "B" work port circuit. This stops oil leakage that would normally get past the internal spool land which can cause an implement to settle.


4. Reassemble the pilot-operated line lock coupler assembly, 1, and reinstall on the valve assembly. Torque the allen screws to 30 N·m (22 ft lbs).



4

5. The standard remote coupler manifold assembly, 1, is sealed with O rings, 2.
6. Remove the couplers, 1, from the manifold.
7. Reassemble the manifold assembly and attach to the valve body; torque the allen screws to 30 N·m (22 ft lbs).

NOTE: *Check the O ring ports for proper alignment. The manifolds are not interchangeable.*




5


NOTE: *The cast aluminum block couplers are not interchangeable with the cast steel block couplers. If a cast aluminum block coupler is to be replaced with a cast steel couplers, the remaining cast aluminum black couplers must also be replaced with steel couplers.*

8. The couplers are non-serviceable except for the seal rings, 2, and back-up washers, 1.

   Torque the couplers to 68 - 75 N·m (50 - 55 ft lbs) using special tool FNH 00095.



6



7


1. Body
2. Adaptor
3. Lock body
4. Lock sleeve
5. Lock body ball
6. Lock sleeve spring
7. Valve
8. Valve spring
9. Probe
10. Probe spring
11. Sleeve
12. Sleeve spring
13. Sleeve ball

These couplers can be coupled and uncoupled under pressure, as required. Four operating modes are possible:

1. Disconnected
2. Connecting under pressure on both the tractor and implement
3. Coupler pressure released. This is the same as coupling under pressure on the implement only.
4. Coupler pressurized - hydraulically connected.

Modes 1 and 4 always occur during normal couple and uncouple operation. Modes 2 and 3 can occur depending upon whether or not the oil under pressure is trapped in the tractor and/or in the implement circuit.


Both the valve, 7, and probe, 9, are held toward the right by spring pressure. Oil enters the coupler at the ports marked with the large arrows.



8

Mode 2: Connecting with pressure trapped on both the tractor and implement ends.

1. As the operator inserts the implement tip,1, the body moves forward in relation to the sleeve. This allows the sleeve balls to ride out and admit the implement tip.
2. The probe is forced forward at the same time. Spring pressure holds the lock sleeve rearward, allowing the lock body balls to ride toward the outside.
3. When the operator releases the forward pressure, the body springs rearward, forcing the sleeve balls into the groove on the implement tip and retaining the implement tip in the coupler.
4. At this point the mechanical coupling is complete.




70-400-606

9

Mode 3: Coupler pressure is released

1. If pressure is trapped in the tractor circuit, it must be released at this time by placing the remote lever into the FLOAT position.
2. Once pressure in the tractor circuit is released, the force of the probe spring overcomes the force of the valve spring , and the valve is moved into the forward, or open position.



70-400-607


10

Mode 4: Coupler pressurized

1. When pressure is supplied from the remote valve, the implement valve is opened and the probe is moved rearward by the force of the probe spring.
2. The tractor and implement are now coupled hydraulically.
3. Hydraulic pressure also causes the lock sleeve to move forward against the lock sleeve spring, forcing the lock body balls inward and maintaining the probe in the flow position.
4. When the remote valve is in the float position, the low back pressure within the system still provides enough force to overcome the lock valve spring and maintain the probe in the flow position.

COUPLER MOUNTING BLOCKS AND COUPLER REPAIR (70 SERIES AFTER SERIAL NUMBER D408952 AND 70A SERIES)


There are two leverless remote couplers, 1, secured using a retaining ring and garter spring. These 12.7 mm (1/2") female couplers will accept standard 1/2" SAE or ISO tips. The couplers components are not serviced separately except for replacement of sealing rings.



11

70 Series

The cast steel couplers (after serial number D408952) are fitted with a soft rubber dust cap. The left, 1, couplers are identified by an extended cylinder symbol containing an arrow pointing in the direction of cylinder travel and a "+" symbol molded on the tab. The right, 2, couplers are identified by a retracted cylinder symbol containing an arrow pointing in the direction of cylinder travel and a "-" symbol molded on the tab.




12

70A Series


Each control valve has a pair of self-sealing, leverless quick couplers to facilitate remote cylinder connection. These couplers also permit remote cylinder hoses to be pulled from the coupler if an implement should become disconnected from the tractor. The left couplers, 1, are identified by an extended cylinder symbol containing an arrow pointing in the direction of cylinder travel molded on the cover. The right couplers, 2, are identified by a retracted cylinder symbol containing an arrow pointing in the direction of cylinder travel molded on the cover. The covers pivot open by pressing on tab 3, to expose the quick coupler.

The covers are color coded (top) gray, brown, blue, green (bottom) to correspond to the control switches in the cab console.




13

The cast steel couplers contain a spillage port drain, 1, connected to a drain tube venting oil under the rear axle. The vent port, 2, connects to a tube venting oil back into the rear axle housing.



14

The spillage and vent coupler ports on the top coupler, are each sealed with port plugs, 1. O rings are used to seal between the couplers in the stack.




15

The remote valves have a cast steel block, 1, fastened to the work ports on the valve sections.

These blocks are grooved to accept a retaining ring, 1, and a garter spring, 2, used to retain the leverless hydraulic couplers. The passages between the coupler mounting block and valve body is sealed with O rings, 3. The drain passages between each coupler is also sealed with O rings.

NOTE: *The cast steel block couplers are not inter-changeable with the cast aluminum block couplers. If a cast aluminum block coupler is to be replaced with a cast steel couplers, the remaining cast aluminum block couplers must also be replaced with cast steel couplers.*

Valve sections #I and #II have a pilot operated (PO) line check valve assembly, 1, which locks oil in the "B" work port circuit. This stops oil leakage that would normally get past the internal spool land which can cause an implement to settle.




16

Coupler Mounting Block With Check Valve

To open this line check the engine must be running and the hydraulic system functioning normally. When the operator moves the control lever to the lower position, fluid pressure will pass through work port "A" and the oil pressure is also directed out to the pilot operated line check, 1, via a special internal drilled passage in the valve body.

When the line check opens, oil will be allowed to pass by the check valve, 2, and through the seat. The fluid will then enter the main body of the remote valve and return to the reservoir.

When the operator moves the control lever to the raise position, oil will leave the remote body and lift the line check, 2, off its seat. The oil will then go to the leverless coupler, 3.




17


Repair

1. Unscrew the four retaining allen screws, 1, and remove the coupler assembly (manifold assembly) from the spool valve assembly. Note that there are O ring seals between the coupler assemblies.

   Removal of intermediate coupler assemblies 2 or 3 will also necessitate the removal of coupler assemblies 1 or 4 respectively.
2. Remove the rubber dust caps, 2, by gently prying them out or their retaining groove.



18




19

3. Remove the garter spring, 1, through the coupler port, 2, then remove the retaining ring, 3.


4. Insert a screwdriver into the coupler port behind the garter spring retaining grove to loosen the coupler from the housing. Carefully slide the coupler out of the housing.
5. Re-assembly in the reverse order, ensuring that the garter spring is refitted and the O rings are correctly installed.

   Tighten the coupler assembly retaining allen screws to 27 - 33 N·m (20 - 24 ft lbs)




20

The couplers are fitted with snap-on plastic dust covers and drain hoses. The covers are indexed for left and right side installation. Make sure the covers are installed correctly by installing the + covers on the left and the - covers on the right. The drain passages between the covers are sealed with interlocking passages.




21

The couplers are threaded into the block and the oil passages are sealed with O rings, 1, and slipper seals, 2.



22



23


1. Body
2. Sleeve
3. Sleeve balls
4. Poppet
5. Piston
6. Spool

These couplers can be coupled and uncoupled under pressure, as required. Three operating modes ore possible:

1. Disconnected
2. Connecting with pressure trapped on both the tractor and implement ends.
3. Coupler pressurized

Modes 1 and 3 always occur during normal couple and uncouple operation. Mode 2 occurs when pressure is trapped in the tractor and/or in the implement circuit.


Both the poppet, 4, and piston, 5, are held toward the right by spring pressure. Oil enters the coupler at the points marked by the large arrows.



24

Mode 2: Connecting with pressure trapped on both the tractor and implement ends.

1. As the operator inserts the implement tip, 1, the body, 2, moves forward in relation to the sleeve, 3. This allows the sleeve balls to ride out and admit the implement tip.
2. The spool is moved at the same time. This releases the pressure in the tractor half.
3. When the operator releases the forward force, the body springs rearward, forcing the sleeve balls in the groove on the implement tip and retaining the tip in the coupler.
4. At this point the mechanical coupling is complete.



25

Mode 3: Coupler pressurized.

1. When pressure is supplied from the remote valve, the implement valve is opened.
2. Hydraulic pressure also causes the piston to move rearward. This holds the poppet in the flow position.
3. The tractor and implement are now coupled hydraulically.
4. When the remote valve is in the float position, the poppet springs have enough force to maintain the poppet in the flow position.

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 9 - Remote Valve Removal and Repair

CONTENTS

Section	Description	Page
35 000	Removal	2
	Remote Valve Removal	2
	Removing Individual Valve Assemblies	6
	Valve Reassembly	11
35 204	Teardown and Reassembly	16
	Individual Valve Section Disassembly	16
	Valve Section Overhaul (70 Series)	19
	Detent Release Overhaul (70 Series)	22


REMOVAL

REMOTE VALVE REMOVAL

NOTE: *70 Series art shown unless specified*


1. The remote valve assembly can be removed from the tractor in two different procedures.
2. The individual sections such as the three- point hitch control valve, 2, and the remote valve, 1, can be removed individually or as a group.

NOTE: *The recommended method is to remove the valve sections one at a time for individual repair unless the entire valve assembly is being removed for a complete overhaul.*




1

3. Remove the coupler covers and drain hoses. The covers are indexed for left and right side installation. The + covers go on the left side and the - covers go on the right side.



2

4. On the 70 Series, remove the complete valve assembly by disconnecting the control cables, 2; tubes, 3; and mounting bolts, 4. The front mounting bolts must be completely removed. Only loosen the rear bolts.



3


NOTE: *70A Series art shown in Figure 4.*

For the 70A Series, disconnect the wire connectors, 5, to the solenoids, the electro-hydraulic pilot line, 6, the tubes and mounting bolts the front mounting bolts must be completely removed. Only loosen the rear bolts.

5. Use a suitable hoist and sling assembly, 1, Figure 3, to lift the valve assembly, rotate it slightly to clear the mounting bolts, and lift it off the tractor.


⚠ WARNING ⚠

The valve assembly is very heavy. Do not try to lift the valve assembly without a suitable hoist.




4

6. Inspect the O ring seal face on the return port on the bottom of the valve assembly.




5

7. Inspect the mounting bolts, 1, and the O ring, 2.



6


8. The return oil is carried through the top cover into a tube, 2, which is fastened to the rear axle center section with bolts, 1 and 3.



7


9. Replace the O rings on the inlet fitting, 1, and the load sense fitting, 2.

NOTE: *Early tractors have a one-way check valve inside the fitting, 2. Make sure the check valve is clean and operating correctly.*




8

10. Loosely install the right rear mounting bolt, 1. Lubricate a new O ring with petroleum jelly and install it in the port, 2.



9

11. Use a suitable hoist and sling, 1, to reinstall the valve assembly.
12. Install the three remaining bolts, 4, and torque the mounting bolts to 237 - 271 N·m (175 - 200 ft lbs). Reinstall the hydraulic tubes, 3, and tighten the fittings.
13. Adjust the control cables, 2, as described later in this chapter. Start the tractor, check for leaks and correct operation.




10

REMOVING INDIVIDUAL VALVE ASSEMBLIES

NOTE: *70 Series art shown unless specified*


1. Remove light bracket, 1, and third link bracket, 2, on rear of tractor.



11

70 Series

2. Loosen the jam nuts, 2, and cap screws, 3. Remove the control cable bonnet covers, 1, from all of the remote valve sections that have to be removed from the tractor.




12

70A Series

NOTE: *70A Series art shown in Figure 13.*


Remove the remote valve solenoid connectors, 4, from all of the remote valve sections that have to be removed from the tractor



13

70 Series


3. Remove the roll pins, 1, which connect the cables to the spools. Use caution to not bend the spool as the pin is removed. Slide the valve spool, 2, all the way in the valve body to reduce strain on the spool when removing the roll pin.



14

70 Series


4. Loosen the allen screws, 3, and remove the flow control cables, 2, from the valve sections, 1.



15


5. Reach in behind the remote valve body assembly and disconnect the lower O ring face connection, 2, from the three-point lift relief valve.
6. Disconnect the four hoses from the three- point hitch shock relief valve and mark the hoses for proper reinstallation.

NOTE: *The right hoses, 1, can be removed at the cylinder, and the left hoses, 3, can be removed from the valve fittings.*



16

7. Remove the three nuts and lock washers, 1, which hold the end plate on the valve stack.




17

8. Remove the end plate, 1, and lift the relief valve assembly. Removal can be made easier by loosening the shock valve mounting bolt and nut, 2, with a 17 mm crow-foot wrench.


NOTE: *Make sure the three studs, 3, which hold the valve assembly together are screwed all the way down. This will provide more room at the rear of the cab.*

9. MAKE CERTAIN THAT ALL O RINGS, 4, AND STEEL SHIMS, 5, ARE KEPT IN PLACE FOR INSTALLATION. IMPROPER SHIMMING WILL CAUSE VALVE SECTION MALFUNCTION.




18

10. Remove the three-point hitch valve section.




19

11. Remove valve section IV if required. Keep O rings and shims in proper location.




20

12. Remove valve section III if required. Keep O rings and shims in proper location.




21

13. Remove valve section II if required. Keep O rings and shims in proper location.



22

14. The number II valve section on a MegaFlow valve assembly has unique parts. Make sure these parts are kept in place. Install the spacer/disc, 2; O ring, 3; and secondary shuttle/load sense adaptor, 1.




23

VALVE REASSEMBLY

NOTE: *70 Series art shown unless specified*


1. Install the number I and II valve sections on the stack assembly.

NOTE: *Make certain that the one steel shim is located on each stud bolt and all O rings are in place. Improper shimming will cause valve section malfunction.*




24

2. Reinstall the number III, IV, and three-point hitch valve sections with shims and O rings in the proper location. Reconnect the three-point hitch solenoid wires.



25


3. Check to be certain that all the shims, 2, and O rings, 1, are in place.



26


4. Reinstall the end plate assembly and cross torque the three nuts, 1, to 30 N·m (22 ft lbs).

NOTE: *Improper torque will cause valve section malfunction.*




27

5. On MegaFlow units, install the lower pump load sense line, 1, using a new O ring on the fitting.



28


6. Torque the load sense line to the remote valve adaptor elbow using a 7/8″ crowfoot wrench, 1.



29

7. Install the MegaFlow lower pump discharge line, 2. Reconnect the three-point hitch hoses, 4, to the lift relief valve.


   Torque the fittings.



30

70 Series


8. Synchronize the flow control adjustment by turning the shafts on the valves to the full open or counterclockwise (CCW) position and the knobs to the wide band position before tightening the setscrews.



31

70 Series


9. Reconnect the flow controls, 1, to the flow control cable, 2, in each valve and tighten two allen setscrews, 3.



32

70 Series


10. Reconnect the spools, 2, to the push/pull cables by inserting the roll pins,1.



33

70A Series

Reconnect the remote valve solenoid connectors, 3, and use the PDT tool to recalibrate the remote valves worked on. See Chapter 14 of this section.




34

70 Series

11. Adjust the cable bonnets with the hydraulic spools in neutral and the side console levers are centered in the lock gate, 1, neutral position.

70 Series

12. Tighten the jam nut and allen screws. Check each lever assembly to be sure that the spools move through all four positions - float, lower, neutral, and raise.
13. Paint all of the newly installed parts.




35

14. Install the flowmeter in the quick couplers for the #1 valve section and #4 valve section.
15. Start the tractor and operate the hydraulic lever to purge air from the high-pressure hydraulic systems. Confirm that both systems will reach proper flow and pressure.


NOTE: *Maximum available flow from any one set of couplers is 87 L/min (23 GPM) on the 70 Series, 117.3 L/min (31 GPM) on the 70A Series.*

16. Operate the three-point hitch to purge air from the cylinders.
17. Recheck the oil level in the rear axle.



36

TEARDOWN AND REASSEMBLY




37

INDIVIDUAL VALVE SECTION DISASSEMBLY

1. The studs, 1, are threaded into the bottom base assembly. The studs vary in length depending upon the number of valve sections in the assembly.
2. All valve sections' passages are sealed with O rings, 2. The valve sections are spaced apart with identical shims, 3.


NOTE: *Always mark each valve section, 4 and 5, so it can be reinstalled in the proper order. Be sure all shims and o-rings are reassembled in the proper locations. This prevents valve section malfunction.*

3. The standard remote valve assembly less three-point hitch uses four sections.
4. The I valve section, 1, is a unique casting and must always be in the I position.
5. The valve sections, 2, 3, and 4, are interchangeable in position except 2 is fitted with the pilot-operated line lock which is factory installed in the II position.




38

6. The MegaFlow assembly uses a special II valve section which must always be installed in the 2 position.
7. The three-point hitch section must always be installed in the 5 position next to the top cover, 6.




39



40

VALVE COMPONENTS (70 Series)


1. Remote coupler
2. Spool
3. Flow control shaft
4. Flow control spool
5. Flow control tube
6. Secondary shuttle
7. Primary shuttle
8. Detent poppet
9. Orifice
10. Detent balls
11. Centering springs
12. Remote coupler
13. Pilot-operated line lock



41

VALVE SECTION OVERHAUL (70 SERIES)

1. Remove the allen screws, 6, which hold the detent release cover, 7. Hold the spool, 3, in place and firmly unsnap the detent release cover from the spool. Refer to "Detent Release Overhaul" later in this chapter for detent overhaul instructions.
2. Depress the keeper which retains the centering springs, 8, and remove the centering springs.
3. Move the spool far enough to the right to expose the O ring, 1, and remove the O ring. Move the spool to the left and remove the O ring , 2.
4. Carefully remove the spool, 3, from the body without damaging the spool or body lands. Inspect the spool for scoring.
5. Remove the secondary shuttle and ball, 4.
6. Remove the primary shuttle, 5.
7. Remove the flow control assembly, Figure 18. Do not mix the flow control assemblies together because different lengths springs are used.



42

Flow Control Components


1. Flow control shaft
2. Retaining plug
3. Flow control spool
4. Flow control tube
5. Slot
6. Solid pin
7. Outer spring
8. Inner spring
9. Stationary roll pin
10. Rotating roll pin

8. Inspect the parts for wear, scoring, or damage. Repair damage by buffing with crocus cloth. If the damage cannot be repaired with the light buffing, then the valve spool and body must be replaced.
9. Clean the parts with clean parts solvent and coat with clean M2134D hydraulic oil.
10. Replace all O rings.

Valve reassembly


11. Install the flow controls making sure the slot, 5, in the flow control tube, 4, faces up toward the work ports. Index the roll pin, 10, so the slot faces up when the roll pin is turned fully counterclockwise.

NOTE: *If the tube is installed incorrectly, the flow control will not work through the entire range.*



43

12. Install the primary shuttle and secondary shuttle and ball. Torque the shuttles to 8 N·m (5 ft lbs).
13. Insert the spool far enough to the right to expose the O ring, 1, and install the O ring. Move the spool to the left and install the O ring, 2.
14. Install the centering springs, 8, and the spring keeper.
15. Install new O rings on the detent cover.
16. Hold the valve and spool in the vertical position and firmly snap the detent release cover, 7, into position. The detent balls should snap over the detent shaft. Install the allen screws, 7. Torque to 8 N·m (5 ft lbs).



44


1. Spacer
2. Detent housing
3. Balls
4. Spring, piston and seals
5. Snap ring and retaining washer

DETENT RELEASE OVERHAUL (70 SERIES)

1. Remove snap ring, 5; retaining washer; piston, 4; spring; centering detent balls, 3; and guide washer.
2. Remove detent adjustment nut; screw, 6; seal holder, 7; spring, 8; and poppet, 9.
3. Clean and lubricate parts.
4. Install spring, poppet, guide and adjusting screw and nut.
5. Install guide washer and eight 7/32″ detent balls in the body. Coat the balls with grease.
6. Install new seals and back-up washers on the piston. Install the piston in the housing.

NOTE: *The back-up washers are installed away from the center of the piston.*

7. Install the snap ring and retaining washer.




45

Valve Components (70A Series)

1. Remote coupler, - side
2. Control spool
3. Flow compensator spool
4. Secondary shuttle
5. Primary shuttle
6. Remote coupler, + side
7. Pilot operated line lock


VALVE SECTION OVERHAUL (70A SERIES)

If necessary to remove a solenoid, 1, turn the solenoid counter-clockwise.




46

Remove the solenoid housings, 1, by removing the allen head bolts.



47


Remove the spring assemblies,1, from each end of the main spool.



48


Remove the main spool plug, 1.

NOTE: *The end of the plug fits into a slot on the main spool and acts as a stop.*




49

Pull the main spool, 1, out of the valve.




50

Remove the plug, 1, for the flow compensator spool.




51

Remove the flow compensator spool, 1, and compensator springs, 2.




52

Remove the secondary shuttle, 1, and the ball bearing.



53

Remove the primary shuttle, 1.



54


Inspect all parts for wear, scoring, or damage. Repair damage by buffing with a crocus cloth. If the damage cannot be repaired with the light buffing, then the valve spool and body must be replaced.

Clean the parts with clean parts solvent and coat with clean M2134D hydraulic oil.

Replace ALL O-rings.

When installing the primary shuttle, secondary shuttle and ball bearing, torque the shuttles to 8 Nm (5 ft. lbs.)

When installing the main spool, the slot,1, on the end of the main spool must line up with the pin, 2, on the main spool plug.



55

When installing the solenoid housings, torque the allen head bolts to 8 Nm (5 ft. lbs.).

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 10 - Three-Point Hitch

CONTENTS

Section	Description	Page
35 000	Specifications	1
	Description of Operation	2
	Three-Point Hitch	2
	Three-Point Hitch External Linkage Components	15
	Quick Hitch	19
	Troubleshooting	20
	Disassembly and Repair	24
	Rockshaft Removal	24
	Seal and Bushing Replacement	26
	Rockshaft Installation	27
	Lift Cylinder Removal	29

SPECIFICATIONS

THREE-POINT HITCH

Control valve	
Pilot pressure (70 Series)	72.5 bar (500 PSI)
Pilot pressure (70A Series)	16.5 bar - 19 bar (240 - 275 PSI)
Solenoid voltage	Raise Solenoid Resistance - 2.4 ohms PWM voltage 4.2 V > 2.3V (40% > 26% duty cycle) Lower Solenoid Resistance - 2.4 ohms PWM voltage 3.6 V > 2.6 V (35% > 26% duty cycle)
Lift Circuit relief valve (70/70A Series)	207 bar (3000 PSI)
Lift relief valve (70A Series)	190 bar (2750 PSI) [High pressure standby, 200 bar (2900 PSI)]
Lift pressure (70 Series)	190 bar (2750 PSI) [High Pressure standby]

Cylinders	
Diameter	
8670 before serial number D409175	88.9 mm (3.5″)
8670 after serial number D409174/ 8670A	101.6 mm (4.0″)
8770/8770A, 8870/8870A	101.6 mm (4.0″)
8970/8970A	114.3 mm (4.5″)

Top Cover	
Top cover bore inside diameter	81.14 - 81.19 mm (3.1945 - 3.1965″)
Bushing bore inside diameter	76.26 - 76.40 mm (3.0025 - 3.008″)

	kg	**lbs**
Lift capacity (CAT III)		
8670 before serial number D409175	4536	10000
8670 after serial number D409174/ 8670A	5670	12500
8770/8770A, 8870/8870A	5670	12500
8970/8970A	6804	15000

Tightening Torques

Rockshaft retaining bolt torque	98 - 113 N·m (72 - 83 ft lbs)
Lift cylinder piston nut torque	163 - 176 N·m (120 - 130 ft lbs)
Lift cylinder head torque	319 - 407 N·m (250 - 300 ft lbs)


Special Tool

FNH00532	Rock Shaft Seal Installer

DESCRIPTION OF OPERATION

THREE-POINT HITCH

The three-point hitch lift control valve, 1, is shown. The system may also be referred to as the HYDRAULIC POWER LIFT (HPL) unit. The three-point lift control valve, 1, is a single-acting valve section equipped with an integral pilot operated line check valve. This valve is used to provide the basic position control feature of the three-point hitch.




1

This valve is operated by an electrohydraulic control system. The levers and switches in the right-hand console send signals to the right-hand module and chassis control module which sends pulsed DC current to the two pulse width modulated (PWM) solenoids on the valve assembly. The rate of raise and drop are not controlled by the internal flow control. The flow rates are controlled electronically by the chassis control module (CCM).

NOTE: *This valve cannot be made into a double-acting valve.*

The circuit has a 207 bar (3000 PSI), lift circuit relief valve to protect the cylinders and other components against excessive shock loads.

On the 70A Series the high pressure standby is 200 bar (2900 PSI), so a lift relief valve has been added to keep the three-point hitch left capacity to 190 bar (2750 PSI) like on the 70 Series.



2

Three-Point Hitch Circuit Schematic


The oil from the lift control valve "B" work port, 1, is directed to the base side of the lift cylinders, 5, to raise the three-point hitch rockshaft and linkage.

When the three-point hitch is lowered, oil from the base side of lift cylinders reenters through the "B" work port and is directed to the return circuit inside the remote valve assembly.

The pilot operated line check valve is opened by the internal oil pressure being developed at the "A" work port, 2, inside the valve . This pressure is directed against the bottom of the line check valve piston which causes it to open and allows the lift cylinder oil to reenter the valve.

The lift circuit relief valve, 3, is in the circuit to protect the components against extremely high shock loads. When the lift circuit relief valve opens, the excess pressure is dumped into the return line, 4, which is connected back to the top of the rear axle top cover.

On the 70A Series the high pressure standby is 200 bar (2900 PSI) so a lift relief valve, 6, has been added to keep the three point hitch lift capacity the same as the 70 series.



3

Three-Point Hitch Lift Control Valve

The main control spool, 1, is moved with pilot oil pressure that is controlled by two electric pulse width modulation (PWM) solenoids, 2. The main control spool is shifted to the right for raise and to the left for lowering operation. Pilot oil pressure from the solenoids travels via cross drillings to enter the chambers on the ends of the main spool body to operate the main spool.

A solenoid is located on each end of the valve body. The solenoid on the left side operates the raise cycle and the solenoid on the right operates the lower cycle. The solenoids are nominal 12 volt direct current and have a resistance of 2.4 ohms.

The operation of these solenoids is done with a PWM controlled current to provide the operator with a precise method and rate of raise and rate of drop control. This PWM current is a 12-volt current which is switched on and off 100-500 times a second by the chassis control module. The operating voltage can be monitored with an analog voltmeter and it will appear to be in the 6 - 7 volt range.

This switching or dithering of the solenoid current gives accurate pilot oil modulation so that the main spool movement can be controlled in a precise manner.

The lift control valve has a fixed flow control, 3. The (70 Series) series flow control assembly has a biased pressure compensation feature. This feature gives the lift control valve load sensing pressure priority over all the other remote valve sections except the number I valve section.

This ensures that the lift control valve on the series valve will always work first when the optional electronic draft control (EDC) or slip control is used. The biased pressure feature makes sure that the three-point hitch has an oil supply when other remote functions are operated simultaneously.


The 70 Series parallel valve does not have the biased pressure compensation feature eliminating the load sense priority over all valve sections except the number I valve section. When an adequate oil supply is available, the three point will operate with no effect on the valves #II, #III, or #IV.

The 70A Series valve operates the same as the 70 series parallel valve.

Three-Point Valve Pilot Pressure

70 Series


The pilot oil pressure used by the electric PWM solenoids is provided by a pressure regulating valve, 1, in the top cover plate, 2, of the remote valve assembly. The oil pressure is regulated to 34.5 bar (500 PSI). The oil is obtained from the high-pressure circuit within the remote valve assembly. The regulating valve assembly consists of a valve, spring and cap. The valve is nonadjustable.



4


70A Series

The pilot oil pressure used by the electric EDC solenoids is provided by transmission regulated pressure. The pilot pressure line connects to the transmission main pressure port, 2, and to the remote assembly top cap, 1. The pilot oil pressure is 16.5 - 18.9 bar (240 - 275 PSI). An inline screen helps protect the pilot valves from contaminants.




5

The oil is directed to the solenoids via internal passages, 1 and 2.




6

These passages are sealed with O rings, 1 and 2.




7

A #4 valve section fitting can be removed from the top cover plate and a pressure gauge can be installed to measure the solenoid operating pressure on the 70 Series. Pressure will change slightly while the PWM solenoids are operating as the hitch is being raised or lowered.



8

The 70A Series can be checked at transmission pressure port.




9

Lift Circuit Relief Valve


The lift cylinders and hitch components are protected from excessive shock loads by a 207 bar (3000 PSI) lift circuit relief valve, 1.

The rod side of the cylinders and the lift relief valve are connected to a tube, 2, which opens into the rear axle center section top cover. This allows the rod side of the cylinders to breathe.




10

The lift relief valve block assembly, 1, is mounted to the remote valve assembly. The relief valve cartridge, 2, is threaded into the block.



11

The circuit relief valve cartridge, 1, is factory preset and is nonadjustable.



12


Three-Point Hitch Options

The three-point hitch is offered in four different configurations.

1. Less three-point hitch.
2. Three-point hitch with electronic position control.
3. Three-point hitch with electronic position control and electronic draft control.
4. Three-point hitch with electronic position control, electronic draft control and slip control.

1. Less Three-Point Hitch

The top cover, 1, will have plugs, 2, over the rockshaft openings, and there will be no lift control valve in the remote valve assembly.




13

2. Three-Point hitch With Electronic Position Control

The basic external three-point hitch components, 1, will be installed. The rockshaft, lift arms and external cylinders are used to raise and lower the lift links and the draft arms. The rockshaft will pivot on bushings pressed into the top cover. The operator will have position control ability from the cab.


The feed back potentiometer and linkage, 2, are used to provide the chassis control module with a signal which shows the relative position of the rockshaft, 1, to the rear axle top cover.



14

The 70 Series three-point hitch lift position controls are in the cab located on the right-hand console. There is a lift control lever, 1; drop rate control knob, 2; height limit control knob, 3; and a fast raise/lower switch (not shown). The hitch-disabled light, 4, will illuminate if the hitch is disabled to operate the exterior switches, or if the tractor is started with the fast /raise switch in the forward position.

The light will flash if the control modules detect a fault condition.




15

The 70A Series three-point hitch lift position controls are in the cab located on the right-hand console. There is a lift control lever, 1, position/draft sensitivity control knob, 2 (if equipped), drop rate control knob, 3, height limit control knob, 4, slip limited control knob, 5 (if equipped).


The status light, 6, serves two purposes:

- Steady light signifies "hitch disabled". The "hitch disabled" warning is also duplicated on the instrument panel as an LCD symbol.
- Flashing light means that there is a malfunction in the 3-point hitch system circuits.



16


These controls send signals to the right-hand console module, 2, which communicates with the electronic instrument cluster, 1, and the chassis control module, 3, which are located inside the cab. These modules supply the pulse width modulated current flow to the solenoids on the three-point control valve. These microcomputer modules are nonserviceable except for software recalibration functions. The modules have self-diagnostic ability which can result in fault codes being displayed if the system malfunctions. Refer to Section 55 "Electrical System").



17


The tractor has lift, 1, and lower, 2, switches on each rear fender that can be used to position the hitch arms for attaching equipment.

NOTE: *Operation of the fender switches causes the hitch to move at a slower controlled rate.*



18

On 70 Series tractors before serial number D403821 the hitch must be disabled by pushing the lift control lever all the way forward in the quadrant and then the hitch-disable light, 1, will illuminate in the right-hand console. The hitch can be recaptured by slowly moving the lift lever rearward.




19

On tractors after serial number D403820 pressing the raise or lower switches will transfer control of the three-point hitch to the fender switches. The lift disabled symbol will be displayed and the hitch status light will be illuminated continually. To transfer control of the three-point hitch back to the lift control lever:

a. Cycle the FAST RAISE/WORK switch to the fast raise position (rear), then to the work position (forward).

b. Move the lift control lever fully forward then pull the lever slowly rearwards to capture the hitch.

NOTE: *See the operator's manual for more information about the safe operation of these switches.*




20

3. Three-Point Hitch With Electronic Draft Control (EDC)

The basic three-point hitch components are as previously described along with EDC draft load sensing pins.


The EDC pins are installed on the front pivot end of the lower draft arms as shown by the large arrow. These pins operate by providing a change in electrical resistance as the pins are distorted when a draft load is applied to the arms. The chassis control module measures this change in resistance and will raise or lower the three-point hitch arms as required to maintain the preset limit set by the operator with the position/draft sensitivity knob. Refer to the operator's manual and Section 55 - "Electrical System" of this manual for more information regarding calibration variables of the EDC draft sensitivity circuit.



21

Each load sensing pin consists of a hollow metal tube which contains a circuit board, 1, and a load sensing coil, 2. Located within the core are three coils which are supported by metal rods. The coils are energized by a 8.5 volt current from the control module which creates a stable pattern of magnetic flux within the pin.

The outer casing of the pin is made from a metal with unique electromagnetic properties. When the metal is subjected to a shear force, such as a draft load, the pin is distorted slightly and the natural magnetic forces in the pin change. This distorts the magnetic flux of the coils which changes the resistance slightly and a different voltage signal is sent out to the control module.




22

To work correctly, the load sensing pins, 2, must only sense draft loads in the horizontal position and must not sense implement weights in the vertical position. The pins are designed to be installed and indexed in the correct direction with a special clamp, 1.

NOTE: *The full position control is not recommended for soil engaging equipment.*

IMPORTANT: *Always select position control when attaching, detaching or installing equipment. Failure to do so may cause the equipment to drop suddenly when attaching, detaching or transporting equipment.*




23

The position draft/sensitivity knob, 1, is mounted in the right-hand console and is a variable potentiometer which is connected to the right-hand module and the chassis control module.

The position draft/sensitivity knob is used to select draft control, position control, or a combination of the two in order to make the system more or less sensitive to changes in draft loading.

Turn the knob counterclockwise to the full position control (position one) to decrease the system's response to a change in draft loading. The knob is detented in the full counterclockwise position.




24


4. Three-point hitch with EDC and slip limit control.

This slip limit control feature allows the operator to manually or automatically vary the three-point implement depth if the wheel slip exceeds certain limits.

The three-point hitch components as described in earlier sections are installed along with the optional radar gun. The Dickey Johns radar gun is mounted to a bracket on the underside of the tractor. The Vansco radar gun is mounted to a bracket that mounts to the side rail. The radar gun is powered with voltage from the EIC and emits a high-frequency microwave which is bounced off of the ground under the tractor. The radar wave is reflected back into the gun receiver and is converted to an alternating electrical current that is sent up to the EIC and to the control modules. The frequency or hertz of the radar gun signal increases as the speed of the tractor increases.




25



26

The slip limit control knob, 1, and slip override lamp, 2, are installed in the right-hand console. The control knob is a variable potentiometer which is connected to the right-hand control module and the chassis control module. The chassis control module is interconnected with the EIC tractor performance monitor to limit wheel slip. The modules calculate the relationship of the true ground speed from the radar gun and the indicated wheel speed from the transmission speed sensor to figure the percentage of wheel slippage.

The knob allows the operator to select a wheel slip limit above which the implement will raise until the wheel slip decreases below the limit. The slip override lamp, 2, is illuminated whenever the slip exceeds the preset threshold and remains on until the slippage is reduced. The knob is detented at the "OFF" position (fully counterclockwise) . A digital display of wheel slip and a slip alarm may be programmed into the EIC. If the slip limit control option is added to the tractor in the field, the tractor module equipment list will have to be reprogrammed. See the service manual (Section 55, Chapter 1, Mode 12) for more information.




27

THREE-POINT HITCH EXTERNAL LINKAGE COMPONENTS

The rockshaft pivots in bushings which are located in the rear axle top cover. The lift arms must be removed to remove the rockshaft. The top cover does not have to be removed from the tractor. The top cover rockshaft opening has oil seals, 1, in each end of the opening. These seals are installed with the garter spring lip seal facing inward.

The lift cylinders, 2, are different sizes to achieve the different lift capacities of the three-point hitches. Three different bore sizes are used, all the cylinders have the same stroke of 200 mm (7.88″).




28

The internal parts of the 88.9 mm (3.5″) and 101.6 mm (4.0″) cylinders are shown in Figure 29. The head is threaded on and can be removed by turning the head in a counterclockwise rotation.

The 88.9 mm (3.5″) cylinder is used on the Model 8670 tractor (before serial number D409175).


The 101.6 mm (4.0″) cylinder is used on the Models 8670 (after serial number 409174), 8670A, 8770/8770A, and 8870/8870A tractors.



29

The internal parts of the 114.3 mm (4.5″) cylinder are shown in Figure 30. The head is threaded on and can be removed by turning the head in a counterclockwise rotation.

The 114.3 mm (4.5″) cylinder is used on the Model 8970/8970A tractor.




30


The components of the basic CATEGORY II/III three-point hitch are shown in these figures.

1. Left lift rod
2. Top link
3. Top link transport hanger
4. Right lift rod
5. Right lift rod adjusting block/handle
6. Right lower link
7. Sway block
8. Left lower link
9. Left lift rod adjusting block/handle

Additional information and adjustment procedures can be found in the operator's manual.




31




32

The length of the vertical lift rod assemblies (before serial number D406366 and after serial number D417380) is adjustable by turning the threaded handles, 1.




33

Length adjustment of the vertical lift rod assemblies for tractors (after serial number D406365 and before serial number D417381) is obtained by turning handle, 3.



34

The length of the top link is adjusted by turning the handle, 1.




35

The lower link arms, 1, are equipped with flex link ends, 2, to ease hookup. The ends can be removed by removing the pin, 4.


NOTE: *The flex link and lock block, 5, must be installed with the tapered side facing toward the front of the tractor to prevent the flex link ends from pulling out under load.*

The sway of the arms is controlled by the adjustable guide blocks, 3.



36

The sway blocks, 1, which are fastened to the drawbar cage are moveable. Two positions are available, rigid and sway. Refer to the operators manual for more information regarding the adjustment of these blocks.




37

QUICK HITCH

The quick coupler hitch, 1, is optional on all models. This hitch is used to connect to three-point equipment without struggling with the attaching pins. The quick hitch moves the lower hitch points to the rear approximately 127 mm (5″).

This will reduce the total lift capacity of the hitch by a certain percentage because of the change in mechanical advantage.

A rule of thumb is that if the three-point hitch can lift the load to the maximum cylinder height extension height, then the load does not exceed the hitch capacity.




38

TROUBLESHOOTING

THREE-POINT HITCH WILL NOT RAISE

Perform these steps before proceeding to the following troubleshooting chart.


1. Verify that the three-point hitch valve controls are operating properly by reviewing the operator's manual instructions. Proceed with the troubleshooting if the system is not operating properly.
2. Retrieve all current and stored fault codes. Record the fault codes on the work order. Study the fault codes because a fault code in an unrelated area may offer a clue in troubleshooting the three-point hitch system.
3. Proceed to step 4 if relevant code(s) exists. Proceed to step 5 if no relevant code(s) exists.
4. Correct the relevant fault code(s) using diagnostic charts in Section 55, and recheck operation.
5. Does remote valve assembly #3 and #4 function normally? If so, then proceed to step 6; if not, then go to testing remote valve flow.
6. After performing the task in each of these boxes, attempt to operate the hitch. If it does not function, go to the next box.



THREE-POINT HITCH WILL NOT LOWER

Perform these preliminary steps before proceeding to the following troubleshooting chart.


1. Verify that the three-point hitch valve controls are operating properly by reviewing the operator's manual instructions. Proceed with the trouble-shooting if the system is not operating properly.
2. Retrieve all current and stored fault codes. Record the fault codes on the work order. Study the fault codes because a fault code in an unrelated area may offer a clue in troubleshoot-ing the hydraulic system.
3. Proceed to step 4 if relevant code(s) exists. Proceed to step 5 if no relevant code(s) exists.
4. Correct the relevant fault code(s) using the diagnostic charts in Section 55, and recheck operation.
5. Does remote valve assembly #3 and #4 function normally? If so, proceed to step 6; if not, then go to testing remote valve flow.
6. After performing the task in each of these boxes, attempt to operate the hitch. If it does not function, go to the next box.



THREE-POINT HITCH ELECTRONIC DRAFT CONTROL (EDC) WILL NOT FUNCTION

Perform these preliminary steps before proceeding to the following troubleshooting chart.


1. Verify that the three-point hitch and electronic draft controls are operating properly by reviewing the operator's manual instructions. Proceed with the troubleshooting if the system is not operating properly.
2. Retrieve all current and stored fault codes. Record the fault codes on the work order. Study the fault codes because a fault code in an unrelated area may offer a clue in troubleshooting the hydraulic system.
3. Proceed to step 4 if relevant code(s) exists. Proceed to step 5 if no relevant code(s) exists.
4. Correct the relevant fault code(s) using the diagnostic charts in Section 55, and recheck operation.
5. Does the three-point hitch valve assembly function normally? If so, then proceed to step 6; if not, then go to testing the remote valve flow.
6. After performing the task in each of these boxes, attempt to operate the hitch. If it does not function, go to the next box.



THREE-POINT HITCH SLIP CONTROL WILL NOT OPERATE

Perform these steps before proceeding to the following troubleshooting chart.


1. Verify that the three-point hitch and slip controls are operating properly by reviewing the operator's manual instructions. Proceed with the troubleshooting if the system is not operating properly.
2. Retrieve all current and stored fault codes. Record the fault codes on the work order. Study the fault codes because a fault code in a unrelated area may offer a clue in troubleshooting the slip control system.
3. Proceed to step 4 if relevant code(s) exists. Proceed to step 5 if no relevant code(s) exists.
4. Correct the relevant fault code(s) using diagnostic charts in Section 55, and recheck operation
5. Does three-point hitch valve assembly function normally? If so, then proceed to step 6; if not, then go to testing remote valve flow.
6. After performing the task in each of these boxes, attempt to operate the hitch. If it does not function, go to the next box.



DISASSEMBLY AND REPAIR

ROCKSHAFT REMOVAL

1. Cab does not have to be removed.
2. One wheel may have to be moved out to gain clearance for the rockshaft, which is 610 mm (24″) long.
3. Start the tractor and fully retract the three- point hitch cylinders.
4. Remove the third link, 3.
5. Vertical lift links, 1 and 4, must be disconnected at the top pivot pin.




39

6. The pivot pins (before serial number D405195) are retained by a grooved pin, 1, which is a tapered and hardened pin. These pins must be driven out backwards or in the opposite direction of installation. The pins are 6 mm (5/16″) diameter.

⚠ CAUTION ⚠


Do not attempt to drive the pins forward through the lift arms. This can cause severe damage to the components.



40


7. The pivot pins (after serial number D405194) are retained by a bolt, 1, that secures the plate, 2.

NOTE: *Tractors after serial number D412383 have a spacer and washer installed under the bolt.*



41


8. Disconnect the linkage rod, 1, at the lift arm pivot end.



42

Tractors before serial number D405195


9. Drive the groove pin, 1, out, and remove the pivot pin, 3.
10. Remove the retaining washer and bolt, 2.
11. Apply an index mark to the rockshaft, 4, and lift arm with paint pen.
12. Remove the retaining washer and bolt on the opposite end of the rockshaft.



43


Tractors after serial number D405194

13. Remove the bolt, 1, (including spacer and washer if after serial number D412383) then remove pivot pin.
14. Apply an index mark to the rockshaft, 4, and lift arm with paint pen.
15. Remove the retaining washer and bolt on the opposite end of the rockshaft.




44

16. Slide the rockshaft out of the bore, 1, taking care not to damage the seals.



45


17. Inspect the rockshaft for twisted or worn splines.



46


SEAL AND BUSHING REPLACEMENT

1. Remove the old seal, 1. The garter spring on the seal lip must face the inside toward the bushing.
2. Inspect the bushing, 2, for wear or damage. New bushings are pre-sized and should measure 76.26 - 76.40 mm (3.0025 - 3.008″) inside diameter when installed.
3. The bore in the top cover is 81.14 - 81.19 mm (3.1945 - 3.1965″) inside diameter.
4. Press the new bushing in place with a suitable driver.



47


5. Inspect the seal counter bore, 1. The left side of the top cover is shown in this illustration.



48

6. Install new seal, 2, using the special tool #FNH00532, 1.


NOTE: *Install the seal with the garter spring lip facing inward toward the center of the tractor.*



49

ROCKSHAFT INSTALLATION


1. Wrap the stepped spline area of the rockshaft with a layer of protective tape, 1. This is done to prevent damage to the seal lip as the shaft is installed. Apply grease to the shaft splines.



50


2. Install the shaft and remove the protective tape, 1.

NOTE: *Take care not to move the rockshaft from side to side after the tape has been removed.*



51

3. Install the left-hand upper lift arm, 1, onto the splines, aligning the index mark which was put on during installation.
4. Loosely install the retaining washer and bolt, 2.
5. Reinstall the right-hand lift arm, 1, making sure it is indexed correctly with the left-hand lift arm.
6. Make sure the rockshaft does not slide to the left and damage the seal.
7. Tighten the retaining bolt, 2. Torque the bolts to 98 - 113 N·m (72 - 83 ft lbs).
8. Reinstall the lift cylinder pivot pin and new grooved retaining pins on tractors before serial number D405195. On tractors after serial number D405194 reinstall the lift cylinder pivot pin, 3, and retaining bolt along with spacer and washer on tractors after serial number D412383.
9. Attach the rest of the lift link components. Adjust the hitch components as described in the operator's manual.



52

LIFT CYLINDER REMOVAL


1. Three different lift cylinder bore sizes are used:

   88.9 mm (3.5″) - 8670 before serial number D409175

   101.6 mm (4.0″) - 8670 after serial number D409174/8670A, 8870/8870A, 8870/8870A, 8870/8870A

   114.3 mm (4.5″) - 8970/8970A


   All the cylinders have the same stroke of 200 mm (7.88″).



53


2. The internal parts of the 88.9 mm (3.5″) and the 101.6 mm (4.0″) cylinders are similar, 1.

3. The cylinder head, 1, is threaded into the barrel and can be removed by turning the head counterclockwise. The 114.3 mm (4.5″) cylinder is shown at 2.



54

4. Lower the three-point hitch and remove any equipment that is mounted on the tractor.




55

Tractors before serial number D405195

5. Remove the grooved pin, 1, and the upper cylinder pivot pin, 2. Disconnect the hoses, 3, taking care to drain the oil into a suitable container.

⚠ CAUTION ⚠


Make certain all loads are removed from the three-point hitch before loosening the cylinder hoses.




56

Tractors after serial number D405194

6. Remove the retaining bolt, 1, and upper cylinder pivot pin, 2. Disconnect the hoses, 3, taking care to drain the oil into a suitable container.



57



58

88.9 mm (3.5") Bore Lift Cylinder (Model 8670 before serial number)


1. Wear ring
2. Piston seal
3. Wear ring
4. Seal
5. Cylinder assembly
6. O ring
7. Wear ring
8. Seal
9. Back-up seal
10. Dust seal
11. Rod assembly
12. Cylinder head assembly
13. O ring
14. Piston
15. Locknut
16. Clevis

Disassembly and Repair

NOTE: *Refer to the figure corresponding to the size cylinder being repaired.*

1. Install the clevis end, 16, of the cylinder securely in a vise.
2. Use a suitable tool to span the flats on the head, 12, and turn the cylinder head in the counterclockwise direction. The head is torqued to 319 - 407 N·m (250 - 300 ft lbs).

NOTE: *The 16-UN2B threads on the cylinder head have a light grade of thread- locking compound applied to the threads prior to factory assembly. Some heat may be required to relax this locking compound.*




59

101.6 mm (4.0") Lift Cylinder (Models 8670 after serial number D409174, 8670A, 8770/8770A, and 8870/8870A)

1. Wear ring
2. Piston seal
3. Wear ring
4. Seal
5. Cylinder assembly
6. O ring
7. Wear ring
8. Seal
9. Back-up seal
10. Dust seal
11. Rod assembly
12. Cylinder head assembly
13. O ring
14. Piston
15. Locknut
16. Clevis

3. Pull the head and rod assembly, 11, carefully out of the barrel, 5. Use caution when pulling the piston seals by the threaded area of the barrel.
4. Remove all the old seals and O rings, 1 through 4.
5. Remove the nut, 15, which holds the piston to the rod. The nut is torqued to 163 - 176 N·m (120 - 130 ft lbs).
6. Remove the cylinder head assembly, 12, from the rod assembly.
7. Clean the piston, 14, and barrel, 5. Inspect the parts for damage, such as scoring.
8. Install new seals, 7 through 10, as shown inside the cylinder head assembly. Coat the seals with clean hydraulic oil.



60

114.3 mm (4.5") Lift Cylinder (Model 8970/8970A)

1. Wear ring
2. Piston seal
3. Wear ring
4. Seal
5. Cylinder assembly
6. O ring
7. Wear ring
8. Seal
9. Back-up seal
10. Dust seal
11. Rod assembly
12. Cylinder head assembly
13. O ring
14. Piston
15. Locknut
16. Clevis

9. Reinstall the head assembly, 12, on the rod, then install the piston sealing O ring, 13.
10. Install the piston, 14, on the rod, and torque the nut to 163 - 176 N·m (120 - 130 ft lbs).
11. Install the seals, back-up washers and O rings, 1 through 4, on the piston. Coat the seals and O rings with clean hydraulic fluid.
12. Install a new O ring, 6, on the cylinder head. Apply a small amount of thread-locking compound to the threads.
13. Coat the piston seals with grease to protect them during installation. Use a piston seal insertion tool if one is available.
14. Carefully insert the piston and rod assembly, 11, back into the barrel, 5.

NOTE: *Take care not to damage the seals on the threads.*

15. Torque the cylinder head assembly to 319 - 407 N·m (235 - 300 ft lbs).
16. Reinstall the cylinders on the tractor and test for leaks by raising and lowering the three-point hitch without any load on the arms.

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 11 - Power-Beyond Applicators

CONTENTS

Section	Description	Page
	Special Tools	2
35 204	Power-Beyond Applications	3

SPECIAL TOOLS

FNH00110	Service Tool Adapter from 70 Series Special Tool Kit

POWER-BEYOND APPLICATIONS


Power-beyond hydraulic circuits on the 70 Series tractors are easily installed. The type of circuit connection and parts required will depend upon the type of hydraulic system fitted on the tractor (standard flow or MegaFlow system).

The external remote valve assembly that is being installed must be designed with closed center-load sensing with internal load sense drain back features.

The power-beyond installation will require that three hydraulic system connections be made.

The pump outlet flow, return oil flow, and load sense pilot line pressure connections can be made in several different locations as described in the following text.


1. **Pump Outlet Flow.** All remote valve mounting bases are equipped with a pressure test port, 1, that is 3/4-16 orb (1/2" tube). This port can be used to obtain a source of oil from the upper standard pump before the oil enters the remote valve.



1

2. The port, 1, is located on the left side of the base and is accessible above the three-point hitch rockshaft.
3. The size of the porting will only permit 1/2" couplers to be connected to the base which will limit the oil flow. The port can supply 45 - 57 L/min (12 - 15 GPM) for a power-beyond circuit. The port will free flow about 80 L/min (21 GPM), but the actual available flow is being rated on the conservative side.


NOTE: *The #I remote valve priority flow will not be maintained if the circuit is connected in this manner.*



2

4. Coupler parts


Ref. #	Description
1	Adaptor, 3/4" orb- 1/2" pipe
2	Female quick coupler, 1/2" pipe



3


5. **Top Cap Identification.**
On the 70 Series there are four basic top cap configurations available for the 70 series tractor, they are:
   - Standard flow hydraulics with HPL
   - MegaFlow hydraulics with HPL
   - Standard flow hydraulics less HPL
   - MegaFlow hydraulics less HPL

On the 70A Series the top cap is always power beyond ready.



4

6. There are two basic groups of top caps for use on the 70 series tractor, one for tractors with HPL and one for tractors less HPL. The difference between these two caps is the one w/HPL must have the pressure regulating valve, 1, in the top cover. Top covers with out this valve are for tractors less HPL, Figure 5.
7. On the 70 Series, within these combinations, the MegaFlow top cap has a port, 2, that allows for oil to enter the cap from the MegaFlow pump to enter the top of the valve stack. The Standard flow system does not have this port. The 70A Series always has port 2.
8. Units with HPL have a pressure regulating valve for regulating pressure to the PWM solenoids. Units less HPL do not have this valve.
9. On the 70 Series, additional ports that may be in the top cap include: load sense port, 3, load sense bleed, 4, and tank return port, 5. The factory installed caps do not have the load sense port or the load sense bleed. On the 70A Series, all these parts are present.
10. Setting up Power Beyond. When setting up power beyond hydraulics to a top cap without the load sense port and load sense bleed, you must "T" the power beyond sense line into the load sense line going to the pump. Additionally the valve must have a pilot drain to relieve the load sense pressure when the valve is in neutral.



5

11. Top caps with the load sense port and load sense bleed allow for the load sense line to be connected directly to the top cap. With these top caps the valve does not need the pilot drain.


12. Parts for 70 Series

    - Part #86013045 is for units with three-point-hitch (HPL). Contains load sense port and load sense bleed.
    - Part #86013046 is for units without three-point-hitch. Contains load sense port and load sense bleed.
    - Part #9821343 is the factory installed cap for the standard high-pressure hydraulic system with three-point-hitch.
    - Part #9845421 is the factory installed cap for the MegaFlow high pressure hydraulic system with three-point-hitch, less the load sense port and load sense bleed.

Part for all 70A Series is #86027560


13. Standard High-Pressure System. Use the following methods if full pump flow and/or # I remote valve priority flow is to be maintained during power-beyond operation.

14. Install a power-beyond kit which contains a new remote valve top cover section, shims, seals, and O rings. This provides an outlet out on the top of the remote valve stack with a 1-5/16 - 12 orb connection (1" tube size), 1. This will provide oil downstream from the steering priority flow divider and the number I remote valve priority circuit.



6


15. The oil can be taken from the elbow with a 1" tube ORF (1-7/16-12) to 3/4" hose (1-1/16-12) JIC adaptor. The special service tool adaptor #FNH00110 is shown in this illustration, 1.



7


16. Power-beyond kit

Ref#	Description
1	Top cover section
*	Shims
*	O rings (4)
*	O rings
*	O rings
*	O rings
2	Elbow, 90° orb-orf
3	"T" fitting, orb-orf



8

17. MegaFlow High-Pressure System. Remove the 90° elbow, # 390984-S36, from the remote valve top cover section (MegaFlow pump outlet to remote valve supply line).
18. Install a 391033- S36 tee fitting, 1, in place of the elbow. This tee fitting allows for a 1″ O ring face seal connection to be made which will allow the MegaFlow pump flow to be used for auxiliary remote valve operation.




9

19. The oil can be taken from the elbow with a 1″ tube ORF (1-7/16-12) to 3/4″ hose (1-1/16-12) JIC adaptor. The special service tool adaptor #FNH00110 is shown in this illustration, 1.


Description
"T" fitting, (orb on leg/orf on branches)

Adaptor, 1″ orf to 3/4″ or 1/2″ JIC
(from 70 series special tool kit)



10


20. **Return Oil Flow.** The return oil flow should be returned through the low-pressure return port as described in the Operator's Manual. Remove the plug ,1, and install the coupler, 2.



11


21. Return oil flow parts.

Ref#	Description
1	12-12 O ring connector
2	Coupler 3/4″ quick coupler
3	Male tip 3/4″ male tip
4	Cover



12

22. **Load Sense Circuit.** Connect into the pump load sense circuit by installing a hose into the port, 3.
23. This port, 3, directs oil into the secondary shuttle circuit and into the piston pump. This allows the auxiliary valve to signal the pump.
24. The auxiliary valve must be equipped with internal bleed back for the load sense circuit to function correctly if the top cover section does not have the load sense bleed, 4.




13

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 12 - Hydraulic Brake System

CONTENTS

Section	Description	Page
35 000	Closed Center Load Sensing (CCLS) Hydraulic Brake System	4
35 000	Operation of the European Trailer Brake System	4
	Operation of the 10 Bar (147 PSI) Trailer Brake System (Italian Market Only)	6
	Trailer Brake Valve Pilot Head Operation	9
	Trailer Brake Valve Operation	10
	Trailer Brake Valve	18
	Specifications	18
	Torques	18
	Special Tools	18
	Description	18
	Trailer Brake Valve Removal	19
	Trailer Brake Valve Disassembly	20
	Inspection and Repair	23
	Re-Assembly and Installation	23
	Bleeding the Brakes	24
	Bleeding Rear Axle Brakes	24
	Trailer Brake Valve Bleed Screws	25
	Trailer Brake Pressure Test	25



1

Component Layout

1. Trailer Brake Valve
2. Steering Priority Valve
3. Manifold
4. Trailer Brake Coupler
5. Switch #2 (Italy Only)
6. Switch #3 (Italy Only)
7. Long Solenoid (Italy Only)
8. Short Solenoid (Italy Only)
9. 10 Bar 147 Psi) Valve (Italy Only)
10. Manifold #2 (Italy Only)

***Callouts 5-10 are for the Italian 10 Bar (147 Psi) Trailer Brake System Only.**

CLOSED CENTER LOAD SENSING (CCLS) HYDRAULIC BRAKE SYSTEM


OPERATION OF THE EUROPEAN TRAILER BRAKE SYSTEM

The trailer brake valve is installed in the high pressure hydraulic circuit and located adjacent to the steering priority valve.

Sensing lines are connected from both the right and left hand tractor brake lines to the pilot head on the trailer brake valve.

When the tractor brakes are both applied, brake line pressure is used to activate the trailer brake valve and divert pump system pressure oil from the variable displacement piston pump to the trailer brake line. When only one tractor brake is applied, the trailer brake will not activate.


A special brake line quick release coupler is provided to connect the trailer brake hose to the tractor brake line.



2

Trailer Brake Socket and Coupling

European Trailer Brake System



50021963

3

OPERATION OF THE 10 BAR (147 PSI) TRAILER BRAKE SYSTEM (ITALIAN MARKET ONLY)

The Italian market brake system operates the same until the hydraulic oil exits the trailer brake valve.

When the hydraulic oil exits the trailer brake valve on the European brake system, the oil goes directly to the trailer brake coupler.

When the hydraulic oil exits the trailer brake valve on the Italian market brake system, the oil goes to a second manifold block before going to the trailer brake coupler.

Tractor Turned Off

With the tractor off, the trailer brake cylinder is applied mechanically by a spring inside the cylinder.

Tractor Operation with The Brakes Released

With normal tractor operation without activating the trailer brake, the 10 bar (147PSI) valve keeps a constant pressure at the trailer brake coupling. The pressure acts on the spring (inside the trailer brake cylinder) to release the mechanical actuation of the trailer brake cylinder. The trailer brake is not applied.

Tractor Operation with the Brakes Applied


While driving the tractor, the trailer brake is actuated by depressing both brake pedals. The trailer brake valve delivers high pressure oil to the trailer brake coupling. The pressure acts on a second spring (inside the trailer brake cylinder) to apply the trailer brake.

Tractor Turned on with the Parking Brake Applied

with the tractor running and the parking brake applied, the electronic switch connected to the brake lever is closed. This causes the solenoids on the #2 manifold to become energized and divert the oil back to the sump instead of the trailer brake coupling. The 10 bar (147 PSI) is no longer maintained at the trailer brake coupling and the mechanical spring (inside the trailer brake cylinder) is actuated to apply the trailer brake.


NOTE: *If pressure in the brake circuit drops below 3 bar (44 PSI), the switch on manifold #1 closes. This will energize the solenoids on the #2 manifold the same as the parking brake being applied.*

Italian Market Trailer Brake System



50021962

4




5

Pilot Head and Piston Assembly

1. Trailer Brake Valve Housing
2. Gasket
3. Seal
4. O Ring
5. Logic Head
6. Piston
7. Piston Housing
8. Pressure Relief Element

Pilot Head

1. Spring
2. Piston Seal
3. O Ring
4. Adaptor
5. Piston Assembly
6. Plunger
7. Piston Assembly
8. Bleed Screws
9. Pilot Head
10. Piston Seal




6

TRAILER BRAKE VALVE PILOT HEAD OPERATION

Brakes Not Applied

The pilot head assembly ensure that trailer braking only operates when both brake pedals are used together.

Sensing lines A and B are joined to the tractor hydraulic brake right and left hand lines.




7

Zero Brake Pressure - Brake Not Applied

Single Pedal Brake Application

If one brake is operated the tractor brake line pressure is sensed at port B (or A). The ball in the pressurized port seats and pushes the piston and brake plunger inward preventing tractor brake line pressure activating the pilot piston.




8

Brake Line Pressure - Brake Applied

Coupled Pedal Brake Application

When both tractor brake pedals are depressed, both sensing lines (and ports A/B) are pressurized. Both pistons are pushed inwards, the plunger unseats the check balls, tractor brake pressure is applied to the pilot piston to activate the trailer brake valve.



9

1. Piston
2. Bleed Screws
3. Piston
4. Ball
5. Pilot Piston
6. Plunger
7. Ball

TRAILER BRAKE VALVE OPERATION

Brakes Released


When the tractor brakes are in the release position, no pressure is being exerted in the tractor braking lines or on the pilot piston through ports 'A' and 'B' and the valve assumes the neutral position.

Oil from the hydraulic pump enters into trailer brake valve port 'D'. A small flow of oil passes from port 'D' through the restrictor in the center of the flow regulating valve to the control spool, which in the neutral position permits this oil to return to reservoir through port 'G'. The oil flow through the center of the regulating valve also has to pass through a small drilling which limits the volume of oil returning to reservoir through port 'G', against the spring pressure to permit flow of oil from the pump supply port 'd' to the tractor hydraulic system through port 'C'.

Additionally, in neutral the flow regulating valve while held against the spring pressure, prevents supply oil at port 'D' from flowing to the trailer brake check valve.

The flow of oil from the hydraulic pump on reaching the restrictor in the flow regulating valve generates a higher pressure on the pump supply side which ensures that in neutral the flow regulating valve is held.


The load sensing gallery 'E' is not pressurized when the valve is in neutral, but when subjected to pressure, signals the hydraulic pump to increase output.



10

Trailer Brake Valve Components

1. Check Valve
2. Flow Regulating Valve
3. Back Up Washer
4. Pressure Relief Valve Element
5. Retaining Collar
6. Seal
7. Washer
8. Plunger, Spool And Spring
9. Control Spool Sleeve
10. Check Valve Seat



11

Brakes Released

Pump System Pressure Oil

Return to Sump Oil

Zero Tractor Brake Line Pressure

1. Logic Head
2. Spring
3. Drilling
4. Flow Regulating Valve
5. Restrictor
6. Check Valve
7. Control Spool Sleeve
8. Control Spool Plunger
9. Pressure Relief Element
10. Pilot Piston

Oil Galleries

A Pressure from Right Hand Brake Line
B Pressure from Left Hand Brake Line
C Outlet Port for Hydraulic Circuit (Pump System Pressure)
D Inlet Port for Hydraulic Pump (Pump System Pressure)
E Load Sensing Gallery to Hydraulic Pump
F To Trailer Brakes
G Return to Sump


Brakes Being Applied

When both brake pedals are depressed simultaneously the pilot piston moves forward pushing against the pressure relief element. As the pressure relief element moves to the left the control spool and plunger similarly moves to the left.

As the control spool is moved to the left the flow of oil to reservoir through port 'G' is prevented in two stages. First the connection between the trailer brake line port 'G' is closed and secondly, oil passing through the center of the flow regulating valve is prevented from returning to reservoir through port 'G'. As oil from the hydraulic pump continues to pass through the flow regulating valve, the combination of rising oil pressure on the spring side of the valve and the spring pressure, moves the flow regulating valve to the left.

The flow regulating valve now begins to restrict the flow of oil to the tractor hydraulic system, but directs the pump supply oil to open the check valve and pass through port 'F' to supply the trailer brakes, also the variable flow sensing line is pressurized through port 'E' to control pump flow to the trailer brake valve.

The orifice located in the end of the flow regulating valve limits the rate at which oil can flow through the center of the flow regulating valve to the trailer brakes. The residual output from the pump is allowed to flow to the tractor hydraulic system.



12

Brakes Being Applied

Pump System Pressure Oil

Return Oil Flow

Return to Sump Oil

Tractor Brake Line Pressure

1. Logic Head
2. Spring
3. Drilling
4. Flow Regulating Valve
5. Restrictor
6. Check Valve
7. Control Spool Sleeve
8. Control Spool Plunger
9. Pressure Relief Element
10. Pilot Piston

Oil Galleries

A Pressure from Right Hand Brake Line
B Pressure from Left Hand Brake Line
C Outlet Port for Hydraulic Circuit (Pump System Pressure)
D Inlet Port for Hydraulic Pump (Pump System Pressure)
E Load Sensing Gallery to Hydraulic Pump
F To Trailer Brakes
G Return to Sump


Brakes Applied with Normal Pedal Pressure
As the pressure in the trailer brake line builds up to match the pressure applied to the tractor braking system, the increase in pressure acts on the end of the control spool plunger in opposition to that pressure applied on the pilot piston from the tractor brake pressure line.

When the trailer brake line pressure has increased in accordance with the pressure applied by the brake pedals, the control spool plunger moves to the right, allowing the oil trapped on the spring side of the flow regulating valve to return to reservoir through port 'G'. Assuming a constant brake pedal pressure is being maintained this movement of the plunger is not sufficient to allow the trailer brake line to connect with the dump port 'G'.

Because the oil on the spring side of the flow regulating valve is now open to reservoir, the valve moves to the right, preventing any further pump pressure oil from being directed over the check valve and into the trailer brake circuit. The oil in the trailer brakes is now trapped and maintains a constant braking pressure in accordance with the tractor brake pedal pressure.

Any increase in the pressure applied to the brake pedals will move the control spool and plunger to the left, causing the brake application cycle to be repeated until the pressure in the trailer brake circuit increases in accordance with the pressure being applied to the tractor brakes.

When the brake pedal pressure is decreased the control spool and plunger moves to the right allowing the trapped oil behind the flow regulating valve and the oil in trailer brake circuit to return to reservoir through port 'G'. The oil is allowed to escape to reservoir until the pressure in the trailer brake circuit once again matches the pressure applied to the brake pedals.



13

Brakes Applied with Normal Pedal Pressure

Pump System Pressure Oil

Return to Sump Oil

Tractor Brake Line Pressure

Trapped Oil

1. Logic Head
2. Spring
3. Drilling
4. Flow Regulating Valve
5. Restrictor
6. Check Valve
7. Control Spool Sleeve
8. Control Spool Plunger
9. Pressure Relief Element
10. Pilot Piston

Oil Galleries


A Pressure from Right Hand Brake Line
B Pressure from Left Hand Brake Line
C Outlet Port for Hydraulic Circuit (Pump System Pressure)
D Inlet Port for Hydraulic Pump (Pump System Pressure)
E Load Sensing Gallery to Hydraulic Pump
F To Trailer Brakes
G Return to Sump

Brakes Applied With Maximum Brake Pedal Pressure

If at any time the maximum permissible trailer braking pressure of 147 (2150 PSI) bar is reached, for example by pressing excessively on the tractor brake pedals, an increase in braking pressure is prevented by the pressure relief element.

As pressure in the trailer braking circuit increases to the maximum permissible limit, the trailer brake circuit oil pressure forces the control spool and plunger against the springs in the pressure relief element. As the pressure relief element springs are compressed the control spool plunger moves to the right, allowing the oil trapped behind the flow regulating valve to return to reservoir through port 'G'. The flow regulating valve can now move to the right and prevent any further pump system pressure oil from being directed over the check valve to the trailer brake circuit.

The pressure relief element is pre-set in manufacture by shims and must not be adjusted in service.



14

Brakes Applied with Maximum Brake Pedal Pressure

- Pump System Pressure Oil
- Return to Sump Oil
- Tractor Brake Line Pressure
- Trapped Oil

1. Logic Head
2. Spring
3. Drilling
4. Flow Regulating Valve
5. Restrictor
6. Check Valve
7. Control Spool Sleeve
8. Control Spool Plunger
9. Pressure Relief Element
10. Pilot Piston

Oil Galleries

A Pressure from Right Hand Brake Line
B Pressure from Left Hand Brake Line
C Outlet Port for Hydraulic Circuit (Pump System Pressure)
D Inlet Port for Hydraulic Pump (Pump System Pressure)
E Load Sensing Gallery to Hydraulic Pump
F To Trailer Brakes
G Return to Sump


TRAILER BRAKE VALVE

SPECIFICATIONS

Maximum Trailer Brake Pressure ..... 147 Bar (2150 PSI)

TORQUES

1. Check Valve End Cap
   14 - 19 N·m (10 - 14 ft.lbs.)
2. Logic Head Retaining Bolts
   10 - 13 N·m (8 - 10 ft.lbs.)
3. End Cap
   56 - 75 N·m (41 - 55 ft.lbs.)



15

SPECIAL TOOLS

DESCRIPTION

Adaptor Trailer Brake Coupling To Test Hose Test Hose - Pressure Testing Pressure Gauge 0-414 bar (0-6000 PSI) Adaptor - Pressure Gauge To Test Hose

** Use required items from pressure test kit #292870.*


Tool Number

NEW HOLLAND Part Number	V.L. CHURCHILL Tool Number
-	4ft-854
E1NN F493 AA	-
*	FNH 02028
*	FNH 0705

TRAILER BRAKE VALVE REMOVAL

1. Clean the area around the trailer brake valve.
2. Disconnect the left and right brake sensing lines (1 and 3) and cap disconnected pipes.


NOTE: *The logic head, 4, can be removed with the trailer brake valve in situ by removing the allen head bolts, 2.*



16

1. Left Brake Sensing Line
2. Logic Head Retaining Allen Head Bolts
3. Right Brake Sensing Line
4. Logic Head

3. Disconnect the pump sensing and brake coupler lines (3 and 4) and cap the disconnected pipes.
4. Plug all ports with plastic plugs.
5. Remove the mounting bolts, 2, and remove the trailer brake valve assembly, 1, from the tractor.




17

1. Trailer Brake Valve
2. Mounting Bolts (3)
3. Hydraulic Pump Sensing Line
4. Brake Coupler
5. Manifold

6. The trailer brake valve is located on a manifold, 1, attached by a plate, 5, to the rear axle housing.

   '0' Rings are located between the trailer brake valve, 2, and the manifold, 1.



18


1. Manifold Trailer Brake
2. Trailer Brake
3. Valve Mounting Bolts Brake
4. Elbow
5. Manifold Mounting Plate

TRAILER BRAKE VALVE DISASSEMBLY

Ensure the assembly is thoroughly cleaned externally before commencing disassembly.


1. Remove pilot head bolts. With reference to figure 20, remove the pilot head bolts and separate the pilot head, 5, and piston housing, 7, from the trailer brake valve housing, 1.

   The '0' ring, 4, piston seal, 3, and the gasket, 2, should be replaced.



19

1. Pilot Head
2. Piston Housing
3. '0' Ring
4. Trailer Brake Valve Housing




20

Pilot Head And Piston Assembly

1. Trailer Brake Valve Housing
2. Gasket
3. Piston Seal
4. '0' Ring
5. Logic Head
6. Piston
7. Piston Housing
8. Pressure Relief Element

2. Remove adaptor, 4, on the end of pilot head, 9, and remove components

   The '0' ring, 3, and both piston seals, 2 and 10, should be replaced.




21

1. Spring
2. Piston Seal
3. O Ring
4. Adapter
5. Piston Assembly
6. Plunger
7. Piston Assembly
8. Bleed Screws
9. Pilot Head
10. Piston Seal

3. Remove pressure relief element, 1, and control valve spool return spring, 2, from valve housing.

NOTE: *The spring, 4, and seal, 3, locate within the relief element. It is not necessary to disassemble the pressure relief element as this is serviced as a pre-set assembly.*




22

1. Pressure Relief Element
2. Spring
3. Seat
4. Return Spring

4. Remove collar, 3, retaining the control valve spool assembly, 1.

NOTE: *The retaining collar may be removed by placing a 14mm nut inside the locking ring. The nut should be of sufficient length to enable a socket spanner to be placed over the nut to allow the collar to be unscrewed.*

5. Use a suitable rod to push the control valve, 1, from housing.




23

1. Control Valve Spool
2. Back-Up Washer
3. Collar

6. Pull control valve spool assembly from spool sleeve, 9. Remove snap ring, 4, and disassemble spool and plunger assembly.

   The '0' ring, 1, and seal, 5, should be replaced.




24

1. O Ring
2. Spring
3. Plunger
4. Snap Ring
5. Seal
6. Washer
7. Locating Ring
8. Spool
9. Control Spool

7. Unscrew end cap, 3, and withdraw spring, 2, and flow regulating valve spool, 5. Remove snap ring, 1, and orifice, 6, from end of spool.

   The end cap '0' ring 4, should be replaced.




25

1. Snap Ring
2. Spring
3. End Cap
4. O Ring
5. Spool
6. Orifice
7. Snap Ring


8. Remove check valve end cap, 4, and withdraw spring, 3, and check valve, 6. If necessary unscrew and remove check valve seat, 2.

   The end cap '0' ring, 5, and check valve seat '0' ring should be replaced.



26

1. Trailer Brake Valve Housing
2. Check Valve Seat
3. Spring
4. End Cap
5. O Ring Seal
6. Check Valve
7. O Ring Seal



27

1. Check Valve
2. Flow Regulating Valve
3. Back-up Washer
4. Pressure Relief Valve Element
5. Retaining Collar
6. Seal
7. Washer
8. Plunger, Spool And Spring
9. Control Spool Sleeve
10. Check Valve Seat

INSPECTION AND REPAIR

1. Carefully examine all components.

   As only '0' rings and seals are serviced for the trailer brake valve, any worn or damaged valves will require the valve to be replaced as a complete assembly.

NOTE: *Two '0' ring seals are located inside the trailer brake valve body in the control valve bore. These seals must be carefully checked and if necessary replaced.*

RE-ASSEMBLY AND INSTALLATION

1. Re-assembly and installation follows the removal and disassembly procedure in reverse. On re-assembly observe the following requirements.
   - Ensure all oil seals and gaskets are renewed.
   - Lubricate all parts with clean hydraulic fluid.
   - Tighten all bolts and fittings to the correct torque.
2. Bleed the trailer braking system as described under the heading, "BLEEDING THE BRAKES".

BLEEDING THE BRAKES


Pre Bleeding

1. Attach transparent bleed pipes to both brake bleed screws and insert the open ends of the pipes into the transmission oil filter at the rear of the tractor.
2. Open both bleed screws half a turn.
3. Start the engine and set the engine speed to idle.
4. Pre-fill the brake system by depressing and holding down both brake pedals. Continue to hold the pedals in the depressed position for approximately 1 minute to expel most of the air from the system. Do not release the pedals until an assistant has closed the brake bleed screws.

BLEEDING REAR AXLE BRAKES

Open the left hand brake bleed screw and repeatedly depress the left hand brake pedal until no more air is expelled.

Close the bleed screw and repeat the procedure for the right hand brake.



28


TRAILER BRAKE VALVE BLEED SCREWS

Open left hand bleed screw on trailer brake valve and repeatedly depress brake pedal until no air is expelled.

Close bleed screw and repeat procedure for right hand brake.

Couple both brake pedals together. Open center bleed screw and repeat procedure by repeatedly depressing coupled brake pedals.

Test each brake pedal for satisfactory operation and road test tractor.




29

TRAILER BRAKE PRESSURE TEST

1. Install 0-414 bar (0-6000 PSI) pressure gauge to trailer brake coupling.
2. Set engine speed to 1500 rev/min.
3. Depress each brake pedal separately. There should be no reading on the pressure gauge.
4. Couple together and depress both brake pedals. The reading on the pressure gauge should increase as the brake pedals are depressed. The pressure should increase in proportion to pedal effort, until a maximum pressure of 147 bar (2150 PSI) is achieved.
5. Release brake pedals. Pressure should reduce to zero.
6. If trailer brake test not to specification:-

   Perform low and high pressure standby tests.

   Examine trailer brake valve.



30

1. Pressure Gauge 0-414 bar (0 - 6000 PSI) FNH 02028
2. Adaptor FNH 00705
3. Hose (7/16 JIC Female Swivel Ends)
4. Adaptor 4FT.854
5. Trailer Brake Coupler

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 13 - Pressure and Flow Testing

CONTENTS

Section	Description	Page
35 000	Specifications	2
	Special Tools	4
	Description of Operation	5
35 105	Low-pressure System Testing	6
	Testing Low-pressure System	6
35 106	High-pressure System Testing	9
	Axial Piston Pump	9
	Steering Flow Divider Relief Pressure	14
	Steering Flow Divider Flow Test	15
	Remote Valve	16
	Detent Release Operation	17
	Timed Detent Release Operation	18
	Three-point Hitch	19
	Three-point Hitch and Remote Valve Troubleshooting Aid Tool	24

SPECIFICATIONS

RESERVOIR

Capacity	
8670/8670A	117 L (31 gal)
8770/8770A - 8970/8970A	140 L (37 gal)
Change interval	900 hours (annually)
Oil type	M2C134D spec. hydraulic/transmission fluid F200 all season

FILTERS

Inlet screen	Stainless steel, 60 mesh
Transmission	102 mm (4″) spin-on
70 Series Standard flow (before serial number D419452)	102 mm (4″) spin-on
70 Series Standard flow (after serial number D419451), 70A Series Standard flow	127 mm (5″) spin-on
MegaFlow	127 mm (5″) spin-on
Change interval	900 hours (annually)
Bypass valve	3.5 bar (50 PSI)
Bypass sender	See Section 55 - Electrical System

TANDEM GEAR PUMP

Speed	2665 pump RPM (2100 engine RPM)
Low pressure control section	117 LPM (31GPM) 44.41 cm^3/rev (2.71 in^3/rev)
Typical operating pressure (70 Series)	17.2 -18.6 bar (250 - 270 PSI)
Typical operating pressure (70A Series)	16.5 -18.9 bar (240 - 275 PSI)
Charge pressure section	
Standard flow	151 LPM (40 GPM)
(1.750″ gear)	56.37 cm^3/rev (3.44 in^3/rev)
MegaFlow	261 LPM (69 GPM)
(3.000″ gear)	96.68 cm^3/rev (5.9 in^3/rev)
Typical operating pressure	1.03 - 2.07 bar (15 - 30 PSI)

CCLS AXIAL PISTON PUMP (0 - 2.77 in^3/rev)

Standard flow pump	
Speed	2665 pump RPM (2100 engine RPM)
Flow	117 LPM (31 GPM)
Low pressure	19.0 ± 1.7 bar (275 ± 25 PSI)
High pressure (70 Series)	190 ± 3.4 bar (2750 ± 50 PSI)
High pressure (70A Series)	200 ± 3.4 bar (2900 ± 50 PSI)
Case drain leakage	Less than 4 LPM (1 GPM)
MegaFlow pump	
Speed	2100 pump RPM (2100 engine RPM)
Flow	91 LPM (24 GPM)
Low pressure	19.0 ± 1.7 bar (275 ± 25 PSI)
High pressure (70 Series)	190 ± 3.4 bar (2750 ± 50 PSI)
High pressure (70A Series)	200 ± 3.4 bar (2900 ± 50 PSI)
Case drain leakage	Less than 4 LPM (1 GPM)

CHARGE PRESSURE REGULATOR VALVE

Cracking pressure	0.7 ± 0.3 bar (10 ± 5 PSI)

OIL COOLER BYPASS VALVE

Cracking pressure	6.9 bar (100 PSI)
Flow	95 LPM (25 GPM)

STEERING FLOW DIVIDER

Relief valve pressure ..... 172.4 bar (2500 PSI)
Flow ..... 38 LPM (10 GPM)

STEERING CONTROL VALVE TURNS LOCK TO LOCK

2WD ..... 4.1 turns 139.3 cm^3/rev (8.9 in^3/rev)
4WD ..... 4.3 turns 231 cm^3/rev (14.1 in^3/rev)
SuperSteer ..... 5.5 turns 231 cm^3/rev (14.1 in^3/rev)

STEERING CYLINDERS

2WD ..... one - 2.50″ X 10.00″ B/S
4WD ..... two - 2.25″ X 8.88″ B/S
SuperSteer ..... two - 2.25″ X 8.88″ B/S

REMOTE VALVE ASSEMBLY

2, 3, or 4 sections
- Flow control range (70 Series) ..... 0 - 91 LPM (0 - 24 GPM)
- Flow control range (70A Series) ..... 0 - 117 LPM (0 - 31 GPM)
- 70 Series has a detent release pressure ..... 172.4 bar (2500 PSI)
- 70A Series has a timed detent release ..... Operator set
- 70A Series valve solenoid voltage ..... Extend and Retract Solenoid Resistance-2.4 ohms
  Solenoids are 12VDC pulse width modulated devices (PWM).

THREE-POINT HITCH

Control Valve
- Pilot pressure (70 Series) ..... 72.5 bar (500 PSI)
- Pilot pressure (70A Series) ..... 16.5 - 19 bar (240 - 2750 PSI)
- Solenoid voltage ..... Raise Solenoid Resistance - 2.4 ohms
  PWM voltage 4.2V>2.3V (40%>26% duty cycle)
  Lower Solenoid Resistance - 2.4 ohms
  PWM voltage 3.6V>2.6V (35%>26% duty cycle)
- Lift circuit relief valve (70/70A Series) ..... 207 bar (3000 PSI)
- Lift relief valve (70A Series) ..... 190 bar (2750 PSI)
  [High pressure standby, 200 bar (2900 PSI)]
- Lift pressure (70 Series) ..... 190 bar (2750 PSI) [High pressure standby]

Cylinders
- Diameter
  - 8670 (before serial number D409174) ..... 88.9 mm (3.5″)
  - 8670 (after serial number D409173)/8670A ..... 101.6 mm (4.0″)
  - 8770/8770A, 8870/8870A ..... 101.6 mm (4.0″)
  - 8970/8970A ..... 114.3 mm (4.5″)

Lift capacity (CAT III)	**kg**	**lbs**
8670 (before serial number D409174)	4536	10000
8670 (after serial number D409173)/8670A	5670	12500
8770/8770A, 8870/8870A	5670	12500
8970/8970A	6804	15000

SPECIAL TOOLS


Tool Number	Description
FNH00110	Adaptor fitting for measuring the flow from the CCLS pumps and tandem gear pump
FNH00035	SAE to NPT adapters, used with FTC61682 (FNH02003) master hydraulic test kit
FNH00533	PD male test coupler
FNH00534	Special test port fitting used on CCLS pump
FNH00535	Female PD couplers
FNH00537	Plugs the high-pressure line when using FNH00110
FNH00538	Used for returning oil back into the circuit with special fitting FNH00110
FNH00539	Transmission limp home tool
FNH02003	Universal pressure test kit
FNH02755	Hydraulic tester 190 L/min (50 GPM)
FNH02760	Hydraulic tester 284 L/min (75 GPM)
FNH10419	Hydraulic in-line tester 114 L/min (1 - 30 GPM)
OEM1212	Quad gauge
OEM1250	Hydraulic in-line tester 38 L/min (1 - 10 GPM)
FNH00548	Tee fitting for PTO lube pressure
FNH00550	Wiring harness adaptor for three-point solenoid testing

DESCRIPTION OF OPERATION

The hydraulic system tests shown in this chapter are provided to assist in troubleshooting problems with the hydraulic system.

Wherever possible, special tools have been utilized to reduce the time required to set up and to conduct the test. The technician is expected to be familiar with the proper usage of hydraulic hoses, fittings, gauges and flowmeters.

Refer to technical training publications such as the Tech-Com video program or New Holland service training handouts for information regarding hydraulic system theory and system design concepts.




1

⚠ WARNING ⚠

Fluid under pressure can have sufficient force to penetrate the skin and cause serious personal injury. Always protect the skin and eyes from escaping fluid under pressure. If injured by escaping fluid, obtain medical assistance at once. Serious infection or reaction can occur if medical treatment is not administered immediately.

Before disconnecting lines, hoses, or fittings, be sure all pressure in the system has been relieved. Before applying pressure to a system, check to be sure all connections are tight and all fittings, lines, and hoses are not damaged. Never adjust relief valves to higher pressures than specified for the application. Higher pressures may result in failure of components in the system or machine damage.

Gauges, gauge fittings, and hoses must have operating pressure ratings at least 25% higher than the highest pressure of the system.




2

LOW-PRESSURE SYSTEM TESTING

IMPORTANT: *When performing hydraulic testing:*

1. Always park the tractor on a flat level surface. Engage the tractor park brake.
2. Connect the tractor exhaust pipe to an exhaust ventilation system.
3. Warn bystanders that hydraulic testing is taking place so they can take proper precautions.
4. Make sure test hoses are of proper design and for the pressure range being tested.
5. Bleed air from the test hoses.

NOTE: *Whenever possible, operate the hydraulic system to warm the fluid to 60° C (140° F) before conducting hydraulic testing to ensure accurate results. Use the portable diagnostic tool (PDT) data monitor feature to measure the transmission\hydraulic oil temperature.*


70-580-881

3


TESTING LOW-PRESSURE SYSTEM

Charge Pressure

1. Remove the SAE O ring plug at location, 1, and install a PD coupler special tool #FNH00533 in the test port.

NOTE: *It is not necessary to drain the fluid from the rear axle to install this plug. Very little fluid will be lost. Put a drain pan under the test port location prior to removing the plug.*

2. Install 4.1 bar (60 PSI) gauge and hose using PD female coupler special tool #FNH 00535.
3. Start the tractor engine and increase engine speed to 1900 RPM and record gauge reading.
4. Specification is 0.7 ± 0.34 bar (10 ± 5 PSI).



70-480-1574


4

Low-Pressure System Control Pressure (Transmission Main Regulator Valve)

NOTE: *70 Series art shown.*

1. Install 41.4 bar (600 PSI) gauge and hose using PD female coupler special tool #FNH 00535 to the male test port, 2, on the side of the transmission control valve, 1.
2. Start the tractor engine and increase engine speed to 1900 RPM and record gauge reading.
3. Specification is 16.5 - 18.9 bar (240 - 275 PSI).

NOTE: *Minor gauge fluctuation at 800 - 1200 RPM engine speeds will be normal. If the gauge needle continues to bounce aggressively, inspect the accumulator for proper dry nitrogen charge pressure of 12.1 bar (175 PSI).*



5


Flow Testing Tandem Gear Pump - Low- Pressure Section

1. Install hydraulic flowmeter, 3, special tool #FNH02760 in the circuit as shown using special tool fittings #FNH00110, 1, and #FNH00538, 2.

NOTE: *The circuit relief valve is downstream from the hydraulic flowmeter.*

IMPORTANT: *Make sure the flowmeter control valve, 4, is fully opened counterclockwise prior to starting the engine. Failure to do so will result in severe damage to the pump.*

2. Start the tractor engine and confirm that the flowmeter is working. Increase the engine speed to 2100 RPM and record the flow.
3. The specification is 117 L/min ± 10% (31 GPM ± 10%). The flowmeter reading may fluctuate at low engine speeds. The accumulator in the system is designed to absorb the energy of the flow changes.
4. Remove the test equipment, install new O rings and tighten fittings.



6


Flow Testing Tandem Gear Pump - Charge Pressure Section

1. This test applies to the standard flow hydraulic system only; the test fittings will not adapt to larger port sizes on the Megaflow charge pump.
2. Install hydraulic flowmeter, 3, special tool #FNH02760 in the circuit as shown using special tool fittings #FNH00110, 1, and #FNH00538, 2.

NOTE: *The circuit relief valve is downstream from the hydraulic flow meter.*

IMPORTANT: *Make sure the flowmeter control valve, 4, is fully opened counterclockwise prior to starting the engine. Failure to do so will result in severe damage to the pump.*

3. Start the tractor engine and confirm that the flowmeter is working. Increase the engine speed to 2100 RPM and record the flow.
4. The specification is 151 L/min ± 10% (40 GPM ± 10%) on a standard system.



70-480-1575


7

HIGH-PRESSURE SYSTEM TESTING

AXIAL PISTON PUMP

Low/High-Pressure Standby

1. Install special tool adapter #FNH00534, 1, in the test port on the pump control valve. Use a 4 mm allen wrench to remove the plug.
2. Take care not to lose the Uzit washer on the plug. Replace the Uzit washer with a new part when reinstalling the plug.
3. Remove the load sense line, 2, and plug the line with a special tool adapter #FNH00232 11/16" O ring face seal plug, 3. Install a suitable cap on the load sense fitting to prevent dirt entry.




8

4. Install gauge # FNH02028 and hose using PD female coupler special tool #FNH 00535 to the male test port, 1.
5. Position the hose so the gauge can be seen from the operator's seat.
6. Turn the high pressure adjustment screw, 2, all the way clockwise to back off the high pressure setting.
7. Start the tractor engine.
8. Increase engine speed to 1200 RPM and record the gauge reading.
9. Turn the low pressure screw, 4, all the way clock wise and reset the high pressure specs.

   70 Series 190 ± 3 bar (2750 ± 50 PSI).
   70A Series 200 ± 3 bar (2900 ± 50 PSI).
10. Turn the low pressure setting back out to desired spec. 16.5 - 18.9 bar (240 - 275 PSI).


NOTE: *After hooked up, the load sense may increase as much as 6.8 bar (100 PSI) because of the steering sense feedback.*



9

Load Sense Pressure

1. Install the special tool adapter #FNH00533, 1, in the 7/16" load sense port and a 345 bar (5000 PSI) gauge as shown.
2. Install 345 bar (5000 PSI) gauge and hose, 1, using PD female coupler special tool #FNH 00535 to the male test port, 2.
3. Position the hose so that the gauge can be seen from the operator's seat.
4. Start the tractor engine.
5. Move a hydraulic control lever to the raise position and hold it there. This provides a load sense signal to the pump.
6. An alternate method would be to turn the steering wheel and send a load sense signal from the steering flow divider.
7. Increase engine speed to 1200 RPM and record the gauge reading.
8. Specification is 190 ± 3.4 bar (2750 ± 50 PSI) MAXIMUM.
9. Load sense pressure will generally be 7 - 10 bar (100 - 150 PSI) less than the pump discharge pressure if oil is flowing through the remote couplers. When the remote flow is deadheaded, the load sense pressure will equalize to the pump discharge pressure.




10

Case Drain Flow

1. Install a flowmeter special tool #OEM 1249 flowmeter in the pump case drain line, 1.
2. Install a flowmeter tool #FNH10419 in the #I remote valve on a standard flow tractor and #IV on a MegaFlow™ tractor.
3. Start the tractor engine.
4. Move the hydraulic control lever to the raise position and hold it there. Make sure the flow control is open.
5. Increase engine speed to 2100 RPM.
6. Leakage specification:
   Less than 4 L/min (1 GPM) on a new pump
   Less than 12 L/min (3 GPM) on a used pump
7. These specifications are for reference only and should not be used to condemn a pump. Refer to the piston pump isolation flow test and determine if the maximum flow is also under specification before condemning the pump for replacement or repair.


NOTE: *Illustration shows the lower pump. The connections are similar on the upper pump.*



11

Axial Piston Pump Isolation Flow Test Standard Pump Flow Test

1. Install flowmeter inlet hose in the pump discharge port, 1, using special tool #FNH00110.
2. Install the return line from the flowmeter, 4, into the low-pressure return port at the rear of the tractor. Open the flowmeter control valve.
3. Disconnect the load sense line and cap it as instructed in the low pressure standby test.
4. Install special tool #FNH00537, 2, in the high-pressure discharge line.
5. Install gauge, 3, in the pump control valve as described in the high-pressure standby test.
6. Start the tractor engine and increase speed to 2100 RPM. Confirm that the pump will produce flow and pressure up to the low-pressure standby of 18.7 bar (275 PSI).



12

7. Remove the cover from the low-pressure flow compensator and screw the adjusting screw in fully (count the turns).
8. Start the tractor engine and increase the speed to 2100 RPM. Record the flow in steps as follows:


   34 bar (500 PSI) discharge pressure
   117 L/min (31 GPM)

   69 bar (1000 PSI) discharge pressure
   117 L/min (31 GPM)

   138 bar (2000 PSI) discharge pressure
   114 L/min (30 GPM)

   172 bar (2500 PSI) discharge pressure
   110 L/min (29 GPM)

   190 bar (2750 PSI) discharge pressure
   (high-pressure standby)
   0 L/min (0 GPM)
9. The variable displacement pump should de-stroke to zero flow @ 190 ± 3.4 bar (2750 ± 50 PSI).
10. Back out the low-pressure flow compensator, 4, and reset low-pressure standby. Confirm this pressure by closing the flowmeter control with the engine at low idle speed.
11. Remove the flowmeter and reconnect the lines after the test is completed.



13

Axial Piston Pump Isolation Flow Test
MegaFlow Pump Flow Test

1. Install flowmeter inlet hose in the pump discharge port, 1, using special tool #FNH00110. Refer to standard pump test.
2. Install the return line from the flowmeter into the low-pressure return port at the rear of the tractor. Open the flowmeter control valve.
3. Disconnect the load sense line, 3, and cap it as instructed in the low-pressure standby test.
4. Install special tool #FNH00537 in the high-pressure discharge line.
5. Install gauge in pump control valve, 2, as described in the high-pressure standby test.
6. Start the tractor engine and increase speed to 2100 RPM. Confirm that the pump will produce flow and pressure up to the low-pressure standby of 19.0 bar (275 PSI).
7. Remove the cover, 4, from the low-pressure flow compensator and screw the adjusting screw in fully (count the turns).
8. Start the tractor engine and increase the speed to 2100 RPM. Record the flow in steps as follows:

   34 bar (500 PSI) discharge pressure
   91 L/min (24 GPM)


   69 bar (1000 PSI) discharge pressure
   91 L/min (24 GPM)

   138 bar (2000 PSI) discharge pressure
   87 L/min (23 GPM)

   172 bar (2500 PSI) discharge pressure
   83 L/min (22 GPM)

   (70 Series)
   190 bar (2750 PSI) discharge pressure
   (high-pressure standby)
   0 L/min (0 GPM)


   (70A Series)
   200 bar (2900 PSI) discharge pressure
   (high-pressure standby)
   0 L/min (0 GPM)



14

NOTE: *The variable displacement pump should destroke to zero flow @ 190 ± 3.4 bar (2750 ± 50 PSI).*

9. Back out the low-pressure flow compensator and reset low-pressure standby, 4.
10. Specification is 19.0 ± 1.7 bar (275 ± 25 PSI).
11. Confirm this pressure, 2, by closing the flowmeter control with the engine at low idle speed.
12. Remove the flowmeter and reconnect the lines, 1 and 3, to the pump.




15

STEERING FLOW DIVIDER RELIEF PRESSURE


Quick Test

1. Install special tool adapter #FNH00534, 1, in the test port on the pump control valve. Use a 4 mm allen wrench to remove the plug.
2. Take care not to lose the Uzit washer on the plug. Replace the Uzit washer with a new part when reinstalling the plug.
3. Install 345 bar (5000 PSI) gauge and hose using PD female coupler special tool #FNH 00535 to the male test port,1.
4. Position the hose so that the gauge can be seen from the operator's seat.
5. Start the tractor engine and increase the engine speed to 1200 RPM.
6. Turn the steering wheel until the front wheels are fully turned and hold the wheel firmly in that position.
7. Record the gauge reading.
8. Specification for the valve cracking pressure is 172 + 6.9/-0 bar (2500 + 100/-0 PSI).
9. If pressure is within 165 - 172 bar (2400 - 2500 PSI) on the 70 Series , and 165 - 186 bar (2400 - 2700 PSI) on the 70A Series, the relief valve is okay. This **quick check method** is actually monitoring the pump pressure being delivered to the flow divider and steering control valve. A slight pressure drop will be seen using the quick check method.
10. If the quick check pressure is low, confirm the actual operating pressure by installing a gauge in one of the front axle steering cylinder supply hoses.



16

11. The relief valve cartridge, 1, is not easily field adjusted and **should be replaced** if the pressure is low.
12. The cartridge contains a setscrew, 2, which has been treated with a thread-locking compound.
13. This setscrew must be adjusted to change the spring rate. This setscrew must have thread-locking compound applied after adjusting the relief pressure. This is very difficult to do because the relief valve oil passes through the setscrew during the adjustment process.




17

STEERING FLOW DIVIDER FLOW TEST


Quick Test

1. Install a standard flowmeter, 1, in the #I remote valve coupler. Open the #I flow control fully in the counterclockwise direction. Turn the flowmeter control valve to the full open position.
2. Start the engine and set engine speed at 850 - 900 RPM.
3. Engage the #I remote control lever and note the flow reading on the flowmeter.
4. Turn the steering wheel very quickly from lock to lock and note the decrease in flow indicated on the flowmeter. The number of liters (gallons) that the flowmeter decreases is the amount of fluid being used by the flow divider to satisfy the priority steering circuit.
5. The steering flow divider is rated at 0 - 34 L/min (0 - 9 GPM) and is nonadjustable.



18

6. If the flow divider fails to respond correctly, check the operation of the shuttle ball fitting, 1, tee in the load sense line and also for a sticking flow divider spool, 3, Figure 17.
7. Remove the test equipment.




19


REMOTE VALVE

1. Install a standard flowmeter, 1, in the #I remote valve coupler. Open the #I flow control fully in the counterclockwise direction. Turn the flowmeter control valve to the full open position
2. Start the engine and set engine speed at 2100 RPM.
3. Engage the #I remote control lever and note the flow reading on the flowmeter.
4. Increase the system working pressure by turning the flowmeter control knob until the system pressure is indicating 172 bar (2500 PSI).
5. On the series valve sections (standard or megaflow ready) the flowmeter should indicate approximately 83 L/min (22 GPM). Two or more valves need to be activated at the same time to see 117 L/min (31 GPM).
6. On the parallel valve sections (standard or megaflow ready) only one valve needs to be activated to see 117 L/min (31 GPM).
7. The valve sections #III & #IV will pass 8 L/min (2 GPM) more than valve sections #I & #II due to the internal restrictions of the pilot-operated line locks.

   On the Megaflow systems, (series or parallel, valve section 1 & 2 will share a total of 117 L/min (31 GPM). Valve sections 3 & 4 will share a total of 91 L/min (24 GPM).
8. In series valve sections, a single remote valve section will not handle the total flow capacity of the piston pump. Remote valves will have to be tested in parallel, 1, to read total pump capacity through the remote valves.
9. Remove the test equipment.



20




21


DETENT RELEASE OPERATION

70 Series

1. Install a standard flowmeter, 1, in the remote valve couplers to be tested. Open the flow control fully in the counterclockwise direction. Turn the flowmeter control valve to the full open position
2. Start the engine and set engine speed at 1200 RPM.
3. Engage the remote control lever.
4. Increase the system working pressure by turning the flowmeter control knob until the system pressure is indicating 172 bar (2500 PSI).
5. The detent release system in the remote valve section should release and allow the valve, cable and lever to shift back to neutral.
6. If adjustment is required, loosen the jam nut, 2, and turn the adjusting screw, 1, clockwise to raise the release pressure.
7. Turn the adjusting screw out counterclockwise to lower the release pressure.
8. To lock the lever in detent, turn the adjusting screw fully in counterclockwise until it is seated and tighten the jam nut.
9. Remove the test equipment.



22




23

TIMED DETENT RELEASE OPERATION

70A Series

NOTE: *Primarily used for cylinder applications.*

1. Connect the implement of choice or a standard flow meter, 1, in the remote valve couplers to be tested. Adjust the flow control knob on the pod to maximum flow. If using a flow meter, turn the flow meter control valve to the full open position.
2. Start the engine and set the engine RPM to 2100 (working RPM). Checking or programming the control switches with the engine and hydraulic flow off is possible, however, accuracy of actual operation will be marginal. Whenever a hydraulic application is changed, the control switches should be reprogrammed to start the new operation.
3. Engage the remote control switch in either the extend or retract position (depending upon hydraulic hook-up) should the control switch be moved to the float position, no timed program is possible and the control switch must be returned to neutral manually.
4. If the remote control switch does not return to neutral in the desired time, reprogramming of the switch is needed. The timed operation sequence only begins once the switch is put into detent.




24

THREE-POINT HITCH

Pilot Control Pressure (70 Series)


1. Remove the SAE O ring plug at location, 1, and install a PD coupler special tool #FNH00533 in the test port.
2. Install 41.4 bar (600 PSI) gauge and hose using PD female coupler special tool #FNH 00535. Install the gauge so it can be seen from the operator's seat.
3. Start the tractor engine and increase engine speed to 1200 RPM. Raise or lower the three-point hitch.
4. Record the gauge reading. Some gauge needle fluctuation is normal.
5. Specification is maximum of 34.5 bar (500 PSI) as the hitch is moving. When the hitch arms are not moving, the pilot pressure will drop down to the normal low-pressure standby setting of the pump.
6. The pressure will remain higher for about 8-10 seconds if the three-point system was fully lowered. This is due to the operation of the pilot-operated line lock and the time-out feature in the EDC module.



25

Pilot Control Pressure (70A Series)

1. Check the pilot control pressure at the transmission pressure port.
2. Specification is 16.5 - 18.9 bar (240 - 275 PSI).




26

Three-Point Hitch Lifting and Lowering Pressure


⚠ WARNING ⚠

Remove all three-point hitch implements before conducting this test.


1. Install special tool adapter #FNH00534, 1, in the test port on the pump control valve. Use a 4 mm allen wrench to remove the plug.
2. Take care not to lose the Uzit washer on the plug. Replace the Uzit washer with a new part when reinstalling the plug.
3. Install 345 bar (5000 PSI) gauge and hose using PD female coupler special tool #FNH 00535 to the male test port, 1.
4. Position the hose so that the gauge can be seen from the rear of the tractor.
5. Start the tractor engine and increase engine speed to 1200 RPM.
6. Move the hitch position control lever to the "EXTERNAL" (fender switch) position and leave it there, on tractors before serial number D403821.
7. Stand clear of the three-point hitch attachments. Use the left side fender switch, 1, to raise and lower the hitch.
8. Full raise pressure specification is 190 ± 3.4 bar (2750 ± 50 PSI).
9. This is the high-pressure standby rating of the pump.
10. Lowering pressure specification is 131 bar (1900 PSI).



27



28




29

11. This pressure is required to hold the pilot-operated line lock, 1, open and controlled by the design of the valve spool.
12. The lowering pressure is not adjustable in tractors built from September, 1993 until July, 1994.
13. Tractors built after July, 1994 have an externally adjustable relief valve, 2, in the "A" port which is factory set and should require no field adjustment.
14. Tractors with parallel logic (valve assembly part numbers 86018025 through 86018031) do not have an externally adjustable relief valve in the "A" port.
15. Remove the test equipment

Lift Relief Valve


Quick Test

1. Test the three-point hitch raise pressure as shown in the previous test, then deadhead a remote valve lever.
2. The maximum pressure should remain the same at the test port, 1, 190 ± 3.4 bar (2750 ± 50 PSI).



30

3. If the three-point hitch pressure does not go to maximum, remove the lift relief cartridge, 2, and replace it. Repeat the test.
4. The lift relief cartridge is factory adjusted to open at 207 bar (3000 PSI).
5. The lift relief assembly, 1, may be removed and bench tested with a hydraulic tester. The specifications are the same.




31

Three-Point Hitch Pulse Width Modulation (PWM) Solenoid Valve Operation

1. The electrical circuit to the solenoids can be checked by using a voltmeter. A digital or analog d/c voltmeter, 2, will indicate the **average voltage readings** which is also stated as a % duty cycle. The voltmeter built into the portable diagnostic tool (PDT) also works in this application.
2. There is a test meter, 2, available from FLUKE (model #87 True RMS meter) which is a very good tool to test the operation of a PWM circuit. This meter will test hertz, average voltage, and duty cycle all at the same time.
3. The voltmeter connections probing into the wiring harness connector must be secure while testing the circuit. All the testing must be done with the connector plugged into the solenoid.


NOTE: *If the solenoids are disconnected while the key is turned on, the hitch will require recalibration before the test can be continued.*

4. Use special tool #FNH00550, 1, to probe inside the rear of the wire harness connector to make the testing easier. The lowering solenoid is on the right, and the raise solenoid is on the left.
5. Turn ignition key on, but **DO NOT START** the tractor engine.
6. Solenoid voltage frequency is 500 Hz using the chassis control module system voltage of 12 volts.
7. Move the position control lever to the external control (fender switch) position, on tractors before serial number D403821.



32


8. Operate both fender switches, 1, in the up and down position. Both solenoids should indicate at 26% (2.3 - 2.5v) duty cycle.
9. Turn ignition key on; start the tractor engine.
10. Capture the hitch by moving the position control lever toward the raise position.
11. Move the lever toward the lowering position and record the voltmeter reading.
12. The lowering solenoid in **fast** (rabbit) full lower starts at 42% (4.6v) and ramps down to 26% (2.5v) as hitch approaches end of stroke.



33

13. Lowering solenoid in **slow** full lower (turtle) starts at 35% (3.6 v) and ramps down to 26% (2.6 v) as indicated on the voltmeter, 2, as hitch approaches end of stroke.
14. Move the lever to the full raise position and record the voltmeter reading.
15. The raise solenoid, 1, in fast full raise starts at 40% (4.2 v) and ramps down to 26% (2.3 v) as hitch approaches end of stroke.

NOTE: *The duty cycles and voltages are not absolute values but reasonably accurate. The important thing to remember is that the values will change as the Chassis Control Module controls the duty cycle and as the input voltage to the Chassis Control Module changes.*




34

THREE-POINT HITCH AND REMOTE VALVE TROUBLESHOOTING AID TOOL

A three-point hitch troubleshooting aid tool, 1, OTC #NH01375, is available through OTC. The harness adapts the transmission limp home tool #FNH00539 to the three-point hitch solenoids.

This tool combination allows operation of the three-point hitch by bypassing the tractor operating system. The adapter supplies a regulated voltage and current to the raise and lower solenoids.



35

To use this tool combination:

1. Connect in the four leads labeled Clutch B, Clutch 2, Clutch Rev, and Clutch F1 of the three-point troubleshooting aid tool to the corresponding leads on the transmission limp home harness, 2.
2. Attach the two leads, 3, labeled raise and lower, to the three-point raise and lower solenoids. (The Raise solenoid is on the left, connector C165, the lower solenoid is on the right, C164).
3. Connect the limp home harness to the 3-pin implement plug behind the right-hand operator's console.
4. Start the tractor and use the forward button of the limp home switch to raise the hitch and the reverse button to lower the hitch.

IMPORTANT: *Repeated continuous cycling of the hitch with the limp home harness may cause electrical failure in the adapter harness.*

The troubleshooting aid tool can be used to troubleshoot the electrohydraulic remote valves by connecting the harness from the transmission limp home tool #FNH00375 to the extend and retract solenoids of the remotes.

Start the tractor and use the forward and reverse button of the limp home switch to extend and retract the remote valve.

SECTION 35 - HYDRAULIC SYSTEMS

Chapter 14 - EHR Calibration, Diagnostics and Hydraulic System Troubleshooting

CONTENTS

Section	Description	Page
35 000	Calibration of the Electro-hydraulic Control System (EHR)	2
	Functions of the PDT	2
	Set Up	3
	Start Calibration	7
	Set Defaults	8
	Deadband	9
	Calibration of the Pod Levers	10
	Set Currents	13
	Setting the Flow Control Potentiometer	17
	Changing the Lever Deadband	18
	Diagnostics of the Electro-hydraulic Remote Valve Control System	19
	Solenoid Errors	19
	Lever Errors	20
	System Errors	20
	Other Screens	21
	Troubleshooting Electro-hydraulic Self Test	22
	Troubleshooting Hydraulic System	23
	Hydraulic System Quick Checks	28

CALIBRATION OF THE ELECTRO-HYDRAULIC CONTROL SYSTEM (EHR)

IMPORTANT: *READ THESE INSTRUCTIONS COMPLETELY BEFORE BEGINNING TO CALIBRATE THE EHR REMOTES.*

This information applies to the EHR remote valves on the 70A tractor.

This information DOES NOT apply to the EDC section.

When an electronic hand control (pod or components) on the right hand console are repaired/replaced, both levers will require calibration.

When remote valves or solenoids are repaired/replaced, the lever for that valve only will require calibration.

When the wire harness or the EHR control module are replaced, the complete EHR system will require calibration.

NOTE: *Repairs of hydraulic remote couplers will not require calibration. Repairs involving seal replacement between valve sections should not require calibration.*

Calibration is accomplished with the use of a PDT #NH00500, a calibration/diagnostic cable (#380000199), and a flash cartridge #NH01405, (#297644EUR) loaded with the EHR calibration software.

After repairing or replacing a mentioned component, proceed as follows:


FUNCTIONS OF THE PDT

The refresh rate of the PDT screen, 1, may take several seconds, (30 seconds or more for some functions). During this time, the screen may go blank. Wait for the next screen to appear. DO NOT repeat commands as this may lock-up the PDT. If the PDT does lock-up, go back to the beginning of "Set-Up" in this section.

Pressing the MODE key, 2, on the keypad will scroll the display to the previous screen.

Pressing the ENTER key, 3, on the keypad will save the setting and go to the next screen.


When instructed to press a key, use the keypad, 4.



1


SET UP

1. Connect the two leads, 1, of the diagnostic cable to the PDT.




2

2. Insert the DC power plug, 1, from the PDT into the cigarette lighter receptacle on the upper right front corner of the cab.




3

3. Connect the cable diagnostic connector, 1, from the PDT to the appropriate EHR diagnostic connector, 2, from the EHR controller located behind the tractor seat. The connectors are labeled. If the components of the EHR system for the remote valve 1 or 2 were repaired/replaced, connect to the diagnostic connector labeled 1. If the components of the EHR system for the remote valve 3 or 4 were repaired/replaced, connect to the diagnostic connector labeled 2.



4


When the labels are gone or not legible, look at the EHR controller behind the operator's seat under the floor mat. Diagnostic connector one is connected to the wire lead on the right side of the tractor, 1. Diagnostic connector two is connected to the wire lead on the left side of the tractor, 2.



5

4. Press the EHR engagement switch, 1, to the OFF position. Turn the tractor ON and run the engine at idle.

   The timer switches, 2, MUST be in the OFF position and not illuminated.




6

5. Connect an in-line hydraulic flow/pressure tester #FNH02760, 1, (or comparable tester), to the remote valve being calibrated or tested. Place the tester in a position to be read clearly.


NOTE: *When using an in-line hydraulic flow/pressure tester, be sure to connect it correctly. Most in-line flow/pressure testers will only measure flow in one direction. For the opposite direction, disconnect and reconnect the tester to the corresponding couplers.*

6. Warm the hydraulic oil to full working temperature before any calibration or test functions. The hydraulic oil is warm enough when reasonable resistance can be applied and not lose any GPM flow, 3. To help warm the hydraulic oil, turn the knob, 2, and apply reasonable resistance on the hydraulic flow/pressure tester. When the oil is warm, decrease ALL the resistance with the knob, 2.




7

7. Insert the flash cartridge (#NH01405), 1, loaded with the EHR calibration software, into the PDT.




8

When the PDT "wakes up", two vertical rows of red lights, 1, will light up followed by two horizontal bar segments, 2. The display will automatically change.



9


The cartridge version screen appears. The display will automatically change.



10


8. The select a function screen appears. If the 70A EHR is displayed behind the # 1, press the # 1 key.

   If there are multiple functions on the cartridge and the 70A EHR is not displayed behind the #1, refer to the "re-mapping instructions" in the NH01376 flash cartridge download kit.




11

   The copyright and software version screen appears. The display will automatically change.




12

9. The "turn ignition on" screen appears. Pull the EHR engagement switch to the ON position. After the switch is on, the display will change.



13

The version screen appears. The display will automatically change.




14

On the initial operation menu screen, there are three options. (Do not select any options at this time.)

Pressing the F1 key followed by the # 1 key "Config/Cal" is for calibration of the EHR system.

Pressing the F2 key followed by the # 1 key "Diags" is for troubleshooting the EHR system.


DO NOT PRESS HELP on the keypad. When HELP is pressed, the PDT goes into a mode not used on the 70A tractor. If "HELP" is selected, press MODE.



15

START CALIBRATION

1. On the initial operation menu, press F1 followed by the #1 key (Config/Cal).



16


On the configuration/calibrate screen, there are four options. (Do not select any options at this time.)

Pressing the #4 key "Set Defaults" returns ALL settings to the factory settings.

Pressing the #3 key "Deadband" sets the amount of movement in a lever before hydraulic oil flow begins.

Pressing the #2 key "Cal Levers" electronically locates the lever position through movement.

Pressing the #1 key "Set Currents" sets the optimum performance of the remote valves.




17

SET DEFAULTS

2. "Set Defaults" if there is no flow of hydraulic oil, or if any EHR electrical or hydraulic component was repaired/replaced, press the # 4 key.


NOTE: *The default settings are ONLY a starting point.*



18

3. On the default screen, press ENTER to reset ALL the settings to factory (default).


   To by pass this step and NOT reset the settings to factory (default), press F1 followed by the #3 key



19

DEADBAND


4. On the configure/calibrate screen, press the #3 key (Set Deadband).



20

5. On the deadband menu screen, selection #1 and #2 are for changing the amount of lever movement (free play) from the neutral position (either direction) before hydraulic oil flow begins. Do not press #1 or #2 key at this time. If changing the lever deadband is desirable, do it AFTER all calibrations and flow checks are complete. See "Changing the Lever Deadband" on page 34 of this section.


   Press the #3 key (Deadband N 0).



21

6. On the deadband N screen, there MUST be a 0 displayed, 1. Use the up and down arrow keys to change the display.

   Press ENTER.



22


7. On the deadband menu screen, press #4 to display the enable/disable screen, 1. Use this screen to disable lever 2 on a pod that has no remote valve connected to it. This is only required on pod 2 (remotes 3 and 4), when the tractor is equipped with only 3 remotes. This eliminates false error codes from the EHR module.

   0 = enable
   1 = disable

   To disable lever 2,use the up and down arrow to change the # 0 to a # 1, 2.

   Press ENTER.


   Press MODE.



23

CALIBRATION OF THE POD LEVERS

8. On the configure/calibrate screen, press the #2 key (Cal Levers).




24

9. On the calibrate lever selection screen, press the #1 or #2 key to calibrate the levers. The following steps allow the software to know the different lever positions electronically.

   Lever 1 used for an example.


   Press the #1 key.



25


10. Place the lever in the float position (fully forward), allow enough time for the setting, 1, to change, press ENTER. The setting will change when the pod lever is moved to the next instructed position. The number on the display might not be the same as the figure.

NOTE: *In ALL the lever calibration steps, allow enough time for the setting, 1, to change before pressing ENTER.*




26

11. Hold the lever in the max A (retract) feathering position, (just before forward motion detent), wait, and press ENTER.




27

12. Place the lever in the mid (neutral) position,wait, and press ENTER.



28


13. Hold the lever in the max B (extend) feathering position,(just before detent), wait, and press ENTER.



29

The communication error screen will appear. IGNORE the message and place the lever to the mid (neutral) position to save the calibration. The calibrate lever screen will appear.


NOTE: *This is the only step this communication error can be ignored.*



30

14. To calibrate lever 2, press the # 2 key and repeat lever 1 example.

    When completed with both lever calibrations and the calibrate lever selection screen appears, press MODE.



31

SET CURRENTS


NOTE: *The symbol "I" on the PDT display means "currents". (Do not press any keys at this time.)*

NOTE: *Set the flow control potentiometer, 1, to maximum flow.*

15. Use "Max" current to establish maximum oil flow through a remote valve.


    Use "Min" current to establish oil flow through a remote valve at lever activation. The lower the "Min" value, the lower the amount of oil flow at the initial activation of a lever.

    Use "Flow" ADJUST" to eliminate the lower end deadband (free play) on the flow control potentiometer, 1.




32

16. On the configure/calibrate screen, press the #1 key (Set Currents).



33

17. On the currents menu screen, press the #4 key (Flow adjust).




34

18. adj 1a = lever 1 retract
    adj 1b = lever 1 extend
    adj 2a = lever 2 retract
    adj 2b = lever 2 extend

    Flow adj 1a used for an example.

    On the flow adjustment menu screen, press the #1 key (Flow adj 1 a).




35

    On the flow set up screen, the value MUST be 100, 1, before the "Min/Max" calibration can start. Use the up and down arrow keys to set the value to 100.

19. Press ENTER.


NOTE: *Repeat this step for selections 2,3, and 4.*

20. Press MODE.



36


21. On the currents menu screen, press the #2 key (I Float 1).



37

22. On the float 1 screen, the float value MUST be 200, 1. Use the up and down arrow keys to set the float value to 200.


    Press ENTER.



38

23. On the currents menu screen, DO NOT PRESS the # 3 key, 1. The 70A series tractor does not have float in the extend position.

    Press the #1 key (I Min Max).




39

24. Axis 1A = lever 1 retract
    Axis 1B = lever 1 extend
    Axis 2A = lever 2 retract
    Axis 2B = lever 2 extend

    Axis 1A used for an example.


    On the currents axis screen, press the #1 key (I Axis 1 A).



40

25. On the currents minimum screen, use the up and down arrow keys to set the "I min" value to 117, 1.


    Press ENTER.



41

26. On the currents maximum screen, use the up and down arrow keys to set the "I max" value to 150, 1.


    Press ENTER.



42

27. Set the engine RPM to 2100. Be sure the hydraulic oil is normal working temperature.
    - Hold the selected lever to max feathering position.
    - Record the maximum flow.
    - Display the currents **maximum** screen. To pass over the minimum screen setting of 117, press ENTER.
    - Increase the value in increments of 5 and press ENTER.
    - Hold the lever to max feathering position.
    - Record the maximum flow.
    - Repeat this until there is no increase in flow, 1.
    - Then, decrease the value in increments of 3, recording each value until flow is reduced by a small amount. Then increase the value by one.

NOTE: *The final value MUST be the lowest number that produces the maximum flow.*




43

On the currents axis screen, press MODE.


SETTING THE FLOW CONTROL POTENTIOMETER

28. On the currents menu screen, press the #4 key (Flow adjust).



44


29. On the flow adjustment menu screen, press the #1 key (Flow adj 1 a).



45

30. On the flow set up screen, change the value, 1, to 80 by using the up and down arrow keys.

    Press ENTER.



46

31. Set the flow control potentiometer, 1, to the minimum setting and place the lever, 2, into the retract detent position.

    While watching the flow meter, turn the potentiometer slowly and observe the flow controlled by the movement.


    If flow is delayed when the potentiometer moves off the minimum setting, increase the FLOW ADJUST value in increments of one and re-test.

    If flow is present when the potentiometer is in the minimum setting, decrease the FLOW ADJUST value in increments of one and re-test.


    If maximum flow occurs before the potentiometer reaches full movement, the "I MAX" value may be too high. Repeat the "I MAX" calibration.

    - **Go to the "FLOW ADJUST" menu. Record the value and change it to 100 before starting the "I MAX" calibration.**
    - **Go to the "I MAX" calibration and lower the valve by one.**
    - **Return your "Flow Adjust" to your recorded valve and retest the potentiometer. If satisfied, the procedure is complete. If more calibrating of the potentiometer is needed, repeat the three steps.**

    When calibration is complete, if desirable the lever deadband can be changed.



47



48

CHANGING THE LEVER DEADBAND


32. On the deadband menu screen, press the #1 or #2 key to change the lever deadband,(free play) (Deadband ax 1 or 2).

    ax 1 = lever 1
    ax 2 = lever 2

    To increase the deadband (free play), increase the value, 1. To decrease the deadband (free play), decrease the value, 1. Use the up and down arrow keys.

    Press ENTER.


    For the other lever, repeat the last two steps.



49

DIAGNOSTICS OF THE ELECTRO-HYDRAULIC REMOTE VALVE CONTROL SYSTEM

1. On the initial operation menu, press F2 followed by the #1 key (Diags).



50

On the diagnostic menu screen, there are four options. (Do not select an option at this time.)


Pressing the # 1 key, "Solenoid errs", is for a solenoid malfunction.

Pressing the #2 or # 3 key, "Lever errs", is for a lever malfunction.

Pressing the # 4 key, "System errs", is for a software or a calibration problem.

NOTE: *On any selected diagnostic screen:*

0 = no error
1 = short to ground
2 = short to power




51

SOLENOID ERRORS

2. On the diagnostic menu screen, press the #1 key.
3. On the solenoid error screen, solenoid malfunctions for the A (retract or float) or B (extend) are seen, 1.

   Press MODE.




52

LEVER ERRORS

4. On the diagnostic menu screen, press the #2 or #3 key.

   Lever #1 used for an example.


   Press the # 2 key.



53

5. On the lever error screen, lever malfunctions in the "pot" (neutral), "act" (lever movement between detents), "ff" (detent A, retract or detent B, extend) and "flt" (float). are seen, 1.

   Press MODE.




54

SYSTEM ERRORS

6. The system error screen is for establishing a software or calibration problem.

   On the diagnostic menu screen, press the #4 key.




55

7. On the system error screen, an eprom (software chip inside the module) or calibration error are seen, 1.

   0 = no error.

   1 = error.

   Press MODE twice.



56


OTHER SCREENS

There are numerous other screens on the PDT tool using this software. If the screens are not described in the previous calibration procedures or diagnostics, then they are not for the 70A series tractor hydraulic application and should be ignored unless otherwise directed by New Holland NA.

TROUBLESHOOTING ELECTRO-HYDRAULIC SELF TEST

The Electro-hydraulic remote valve controller has selftest and diagnostic capabilities. A detected fault by the EHR controller is indicated by a flash pattern on the 1st and 3rd manual/programmable operation switches, 1. The fault code flashes will be consecutive, followed by a pause, and then the flashes will start again. It will continue this sequence until the fault is corrected. Count the number of continuous flashes between the pauses and refer to the fault code table below.

NOTE: *Only switches 1 and 3 indicate fault codes with flashing lights. Faults for remotes 2 and 4 will flash on switches 1 and 3.*



57

No. of Flashes	Description of Fault	Remedy
1	No fault	No action required.
2	EEPROM inconsistent	Remove and replace EHR controller.
3	Solenoid 1A (extend) open	1. Check solenoid harness for continuity. 2. Replace solenoid.
4	Solenoid 1B (retract) open	1. Check solenoid harness for continuity. 2. Replace solenoid.
5	Solenoid 2 A (extend) open	1. Check solenoid harness for continuity. 2. Replace solenoid.
6	Solenoid 2 B (retract) open	1. Check solenoid harness for continuity. 2. Replace solenoid.
7	Lever 1 flow control potentiometer open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
8	Lever 1 flow control potentiometer short to power	1. Replace switch control pod.
9	Lever 1 feathering positions (both directions) open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
10	Lever 1 feathering positions (both directions) short to power	1. Replace switch control pod.
11	Lever 1 detent position (both directions) short to power	1. Replace switch control pod.
12	Lever 1 float position open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
13	Lever 1 float position short to power	1. Replace switch control pod.
14	Lever 2 flow control potentiometer open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
15	Lever 2 flow control potentiometer short to power	1. Replace switch control pod.
16	Lever 2 feathering positions (both directions) open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
17	Lever 2 feathering positions (both directions) short to power	1. Replace switch control pod.
18	Lever 2 detent position (both directions) short to power	1. Replace switch control pod.
19	Lever 2 float position open or short to ground	1. Check harness for continuity or short to ground. 2. Replace switch control pod.
20	Lever 2 float position short to power	1. Replace switch control pod.

TROUBLESHOOTING HYDRAULIC SYSTEM

NOTE: *Electrohydraulics for 70A Series Only.*

PROBLEM	POSSIBLE CAUSE	CORRECTION
Complete hydraulic system does not operate	Low oil level	Fill system
	EHR engagement switch in "OFF" position.	Pull to "ON" position
	Restricted hydraulic filter	Replace hydraulic filter
	Restricted charge pump suction screen	Clean screen
	Quick coupler flow checking	Replace male tip and or female coupler
	Low oil level	Fill system
	Valve spool not moving	Connect linkage and make correct cable adjustment
	Low pressure sensing circuit * *This can sometimes occur on just one valve section, other valve sections will still function.	Restricted sense line hose or passage, blown O ring on secondary shuttle
	Pump defective	Troubleshoot pump
	Pump not turning	Check hydraulic pump drive gear case
	Malfunctioning hydraulic system	See "Hydraulic System Quick Checks" later in this chapter
Hydraulic oil overheats	Oil level low or high	Adjust oil level
	Low hydraulic oil temp setting	Software
	Oil cooler or radiator plugged	Clean oil cooler and radiator
	Restricted oil flow through the cooler	Clean oil cooler, lines and check bypass valve operation
	Blocked oil filter element	Replace filter
	Excessive leak in transmission circuitry	Refer to Section 21
	Flow control improperly adjusted	Adjust flow control to lower flow position
	3-Pt Hitch not adjusted properly	Calibrate/adjust/software
	Hydraulic load or orbit motor not matched to tractor	Review the operator's manual
	Extra orifices in hydraulic lines	Remove all orifices when adding external motors or valves.
Hoses will not couple	Incorrect male connectors	Replace connectors with ISO-1/2" standard connectors available from your authorized dealer

PROBLEM	POSSIBLE CAUSE	CORRECTION
Mechanical detent disengages prematurely	Detent release pressure set too low	Adjust detent pressure
Electrical detent times out prematurely	Not adjusted properly	Adjust time out time
Electrical detent time out does not cancel	Incorrect timing procedure used	Redo timing procedure
Remote attachment operates too fast or too slow	Flow control not properly adjusted	Adjust flow control
Remote attachment does not operate	Hoses not completely connected	Attach hoses correctly
	Electrohydraulics not properly calibrated.	Recalibrate electrohydraulics
	Flow checking in couplers	Cycle remote levers. If problem persists, replace male couplers.
	Load exceeds system capacity	Reduce load or use correct size cylinder
	Flow control at minimum	Set flow control to maximum
	Lock gate restricts control lever movement	Reposition lock gate
New installed power-beyond remote valves will not work	Improper connection to the load sense circuit	See "Power-Beyond Applications" later in this chapter
Only steering system works	Stuck priority flow divider	Repair flow divider
	Load sense shuttle "T" malfunction	Inspect/test/replace
	Low hydraulic pump flow (standard pump)	Check pump and repair as required
	Primary/secondary shuttle seal	Inspect and replace
	Low oil level in the reservoir	Add oil
All low pressure functions and steering functions okay, NO high pressure flow	Stuck shuttle tee ball in sense line	Clean shuttle tee fitting
	Failed O ring in secondary shuttle	Replace O rings
All low pressure functions okay, NO high pressure functions	Stuck flow compensator valve on main pump	Clean or replace pump compensator
	Failed pump drive	Rebuild pump drive
Low transmission oil pressure	Low oil level	Fill reservoir with oil
	Restricted transmission oil filter	Replace the filter
	Electrical system	Refer to Section 55
	Excessive leak in transmission circuitry	Refer to Section 21

PROBLEM	POSSIBLE CAUSE	CORRECTION
Low-pressure system is noisy	Low oil level	Fill reservoir with oil
	Worn/damaged pump	Repair the pump
	Air entering system	Check O ring seals on inlet tube
	Lines and tubes contacting tractor frame or cab	Check lines for debris buildup
	Restricted cooler lines	Check lines for obstruction
	Gears of tandem pump, transmission and charge sections in phase	Offset gear timing of transmission and charge sections
Low charge pressure	Restricted hydraulic filter	Replace filter
	Malfunctioning charge pressure regulator	Replace charge pressure regulator.
	Worn/damaged pump	Repair the pump
MegaFlow system valve III, IV, and three-point hitch do not work	Stuck flow compensator valve spool on MegaFlow pump	Clean compensator valve
	Leaking spacer/disc between valve II and III	Replace spacer/disc #86500481
	Failed O ring in secondary shuttle	Replace O ring
	Electrohydraulics not calibrated properly	Recalibrate electrohyraulics
	Failed MegaFlow pump	Repair pump
	Module/Pod Malfunction	Repair/replace
	Leaking #2 shuttle plug	Replace shuttle plug
MegaFlow system valves I and II do not function	Stuck shuttle tee ball in sense line	Clean tee fitting
	Leaking spacer/disc between valve II and III	Replace spacer/disc #86500481
	Electrohydraulics not calibrated properly	Recalibrate Electrohydraulics
	Failed O ring in a secondary shuttle	Replace O rings
	Module/Pod Malfunction	Repair/replace
	Leaking #2 shuttle plug	Replace shuttle plug
Only a single remote valve will not function	Flow control spool stuck	Repair flow control spool
	Electrohydraulics not calibrated properly	Recalibrate Electrohydraulics
	Male/female coupler mismatched or disconnected	Replace coupler
	Primary/Secondary shuttle	Inspect/test/replace
	Module/Pod Malfunction	Repair/replace
	Pressure not released from coupler after hooking up pressure	Move hydraulic levers

PROBLEM	POSSIBLE CAUSE	CORRECTION
Only steering will not function	Stuck priority flow divider spool	See Section 35, Chapter 5
	Block load sense orifice of steering motor	Remove blockage
	Stuck steering relief valve	See Section 35, Chapter 5
	Load sense shuttle "T" malfunction	Inspect/test/replace
	No load sense signal from steering control valve	Repair steering control valve
Tractor is hard to steer	Low power steering relief pressure	Check the pressure
	Spindles won't turn	Grease the spindles
	Limited slip differential won't release	Add limited slip oil additive
	Sticking flow divider spool	Check the spool for scoring
	Defective shuttle ball tee	Replace shuttle tee fitting
	Excessive load on the front end	Reduce front end load
Steering hangs up momentarily	Flow divider spool not shifting	Check flow divider and shuttle tee fitting in load sense line restricted orifice in the spool
	Sense line orifice at steering valve plugged	Check sense line orifice
Only three-point hitch will not function	Work/transport switch in transport position	See Section 35, Chapter 7
	Lift arms wedged against swayblocks in raised position	Adjust swayblocks per operator's manual
	Failed solenoid coil or coils	Replace parts
	Low pilot oil pressure	Check pressure reducing valve
	Failed lift relief valve	Repair lift relief valve
	Failed cylinder packings	Repair cylinder
	Low Transmission Pressure	Check, reset

PROBLEM	POSSIBLE CAUSE	CORRECTION
Loud high-pitched noise coming from remote valves after oil gets warm	Detent release poppet is opening	Return remote lever to neutral and adjust detent release mechanism to lock valve in detent. DO NOT RESTRAIN THE LEVER WITH THE ROTARY LOCK GATES.
	3-Pt. hitch calibration	Recalibrate 3-Pt. hitch
Only the #I remote valve functions, other valves do not work	#I flow control improperly adjusted	Turn flow control toward low flow position
	#I valve circuit is deadheaded	Return #I valve to neutral position
	#I valve continuous operating pressure too high	Lower operating pressure on the #I valve to 125 bar (1800 PSI)
Insufficient flow from valve sections when using multiple functions	Too much flow to a particular valve	Adjust individual flow to minimum required to function properly
	Total flow exceeds maximum pump flow	Reconsider the application
Inadequate hydraulic flow	Quick coupler flow checking	Replace male tip
	Flow control	Readjust flow control
	Low-pressure sensing circuit	Restricted sense line hose or passage, blown O ring on secondary shuttle
	Electrohydraulics not calibrated properly	Recalibrate electrohydraulics
	Pump defective	Troubleshoot pump
	Pilot operated line check	Repair or replace line check
Low system pressure	Low pressure sensing	Stuck flow compensator spool, restricted sense line or passage, blown O ring on secondary shuttle
	High-pressure compensator	Adjust high-pressure compensator
Noisy hydraulic system	Air in system	Change hydraulic filters
	Pressure detent release valves	Raise detent release pressure
	Lines touching cab floor	Isolate - Relocate line
Slow response of hydraulic pump	Shuttle ball T-fitting in implement valve sense line not seating	Replace shuttle ball T-fitting
	Low pressure sense line restricted	Relocate line/replace line

HYDRAULIC SYSTEM QUICK CHECKS

1. What works and what doesn't?
   a. Transmission
   b. FWD
   c. Diff-lock
   d. PTO
   e. Brakes
   f. Steering
   g. Three-point hitch
   h. Remote #I
   i. Remote #II
   j. Remote #III
   k. Remote #IV

2. Separate the systems (low-pressure systems vs. high-pressure systems). Remember, low-pressure circuits are supplied by the tandem pump, while high- pressure circuits are supplied by the piston pump(s).
   a. Do ALL low-pressure systems work? (refer to question 1, items a. through e.)
   b. If all low-pressure systems do not work, which ones are not working?
   c. Do ALL high-pressure systems work? (refer to question 1, items f. through k.)
   d. If all high-pressure items do not work, which ones are not working?

3. Determine if system is standard or MegaFlow.

4. Separate the systems (standard vs. MegaFlow). Remember, on MegaFlow systems the top hydraulic pump supplies oil to steering priority and #I and #II remote valves; bottom hydraulic pump (MegaFlow) supplies oil to three-point hitch and remote valves #III and #IV.
   a. Do ALL high-pressure standard systems work? (refer to question 1, items f. through k.)
   b. If all systems do not work, which ones are not working?
   c. Do ALL high-pressure MegaFlow systems work? (refer to question 1, items f, i., and j.)
   d. If all high-pressure systems are not working, which ones are not?

5. Separate the systems again (hydraulic vs. electrical problem).
   a. Use the service manual, Section 55 - Electrical Systems, Chapter 1, to enter and check various low-pressure and high-pressure solenoids through Modes 6 and 7. If the circuit functions as it should when in these test modes, the problem is usually electrical. If the circuit does not function even when in these tests, the problem is often, but not always, hydraulic in nature.
   b. Is an error code also generated? Use the service manual, Section 55 - Electrical Systems, Chapter 2, and follow the flow chart for the fault.
   c. Electrohydraulic error codes. See this Section and Section 55.

SECTION 41 - STEERING

Chapter 1 - Hydrostatic Steering

CONTENTS

Section	Description	Page
41 000	Specifications	2
	Minimum Hardware Tightening Torques	3
	Description of Operation	5
	Steering System Control Valve	7
	Steering Control Valve Types	11
	Steering Cylinders	12
	Troubleshooting	13
	Removal and Disassembly	18
	Steering Control Valve	18
	Parts Inspection	23
	Assembling the Steering Control Unit	24
	Installing the Steering Control Valve	29

SPECIFICATIONS

Power steering oil		ESN-M2C134-D
Power steering oil capacity		Integral with hydraulic reservoir
Steering wheel turns (lock to lock)	2 WD	4.1
	4 WD	4.3
	SuperSteer	5.5
Relief valve setting 70 Series		172.4 bar (2500 PSI)
Relief valve setting 70A Series		186 bar (2700 PSI)
Flow requirement		38 L/min (10 GPM)

Torques		**N·m**	**Ft. Lbs.**	**In. Lbs.**
Check ball seat setscrew		11		100
Gerotor cap screw	pre-torque	17		150
	final torque	33		275
Steering control valve mounting nuts and cap screws		Use hardware torque charts on following pages		
Hydraulic fitting		21	15	

MINIMUM HARDWARE TIGHTENING TORQUES

IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

INCH HARDWARE AND LOCKNUTS

NOMINAL SIZE	SAE GRADE 2		SAE GRADE 5		SAE GRADE 8		LOCKNUTS		NOMINAL SIZE
	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	UNPLATED or PLATED SILVER	PLATED W/ZnCr GOLD	GR.B w/GR5 BOLT	GR.C w/GR8 BOLT	
1/4	55* (6.2)	72* (8.1)	86* (9.7)	112* (13)	121* (14)	157* (18)	61* (6.9)	86* (9.8)	1/4
5/16	115* (13)	149* (17)	178* (20)	229* (26)	250* (28)	324* (37)	125* (14)	176* (20)	5/16
3/8	17 (23)	22 (30)	26 (35)	34 (46)	37 (50)	48 (65)	19 (26)	26 (35)	3/8
7/16	27 (37)	35 (47)	42 (57)	54 (73)	59 (80)	77 (104)	30 (41)	42 (57)	7/16
1/2	42 (57)	54 (73)	64 (87)	83 (113)	91 (123)	117 (159)	45 (61)	64 (88)	1/2
9/16	60 (81)	77 (104)	92 (125)	120 (163)	130 (176)	169 (229)	65 (88)	92 (125)	9/16
5/8	83 (112)	107 (145)	128 (174)	165 (224)	180 (244)	233 (316)	90 (122)	127 (172)	5/8
3/4	146 (198)	189 (256)	226 (306)	293 (397)	319 (432)	413 (560)	160 (217)	226 (306)	3/4
7/8	142 (193)	183 (248)	365 (495)	473 (641)	515 (698)	667 (904)	258 (350)	364 (494)	7/8
1	213 (289)	275 (373)	547 (742)	708 (960)	773 (1048)	1000 (1356)	386 (523)	545 (739)	1

NOTE: Torque values shown with * are inch pounds.

IDENTIFICATION
CAP SCREWS AND CARRIAGE BOLTS




SAE GRADE 2



SAE GRADE 5




SAE GRADE 8



REGULAR NUTS




SAE GRADE 5 HEX NUTS



SAE GRADE 8 HEX NUTS

LOCKNUTS



GRADE IDENTIFICATION

GRADE A NO NOTCHES

GRADE B ONE CIRCUMFERENTIAL NOTCH

GRADE C TWO CIRCUMFERENTIAL NOTCHES




GRADE IDENTIFICATION

GRADE A NO MARKS

GRADE B THREE MARKS

GRADE C SIX MARKS

MARKS NEED NOT BE LOCATED AT CORNERS



GRADE A NO MARK
GRADE B LETTER B
GRADE C LETTER C

GRADE IDENTIFICATION

MINIMUM HARDWARE TIGHTENING TORQUES


IN FOOT POUNDS (NEWTON-METERS) FOR NORMAL ASSEMBLY APPLICATIONS

METRIC HARDWARE AND LOCKNUTS


NOMINAL SIZE	CLASS 5.8		CLASS 8.8		CLASS 10.9		LOCKNUT CL.8 W/CL8.8 BOLT
	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	UNPLATED	PLATED W/ZnCr	
M4	15* (1.7)	19* (2.2)	23* (2.6)	30* (3.4)	33* (3.7)	42* (4.8)	16* (1.8)
M6	51* (5.8)	67* (7.6)	79* (8.9)	102* (12)	115* (13)	150* (17)	56* (6.3)
M8	124* (14)	159* (18)	195* (22)	248* (28)	274* (31)	354* (40)	133* (15)
M10	21 (28)	27 (36)	32 (43)	41 (56)	45 (61)	58 (79)	22 (30)
M12	36 (49)	46 (63)	55 (75)	72 (97)	79 (107)	102 (138)	39 (53)
M16	89 (121)	117 (158)	137 (186)	177 (240)	196 (266)	254 (344)	97 (131)
M20	175 (237)	226 (307)	277 (375)	358 (485)	383 (519)	495 (671)	195 (265)
M24	303 (411)	392 (531)	478 (648)	619 (839)	662 (897)	855 (1160)	338 (458)

NOTE: Torque values shown with * are inch pounds.


IDENTIFICATION
HEX CAP SCREW AND CARRRIAGE BOLTS
CLASSES 5.6 AND UP



HEX NUTS AND LOCKNUTS
CLASSES 05 AND UP



DESCRIPTION OF OPERATION




1

The hydrostatic power steering system is made up of the closed center high-pressure pump, 4; priority valve, 1; steering control valve, 2; lines and cylinders, 3, on the front steering axle. The closed center implement pump is discussed in Section 35.

The steering system fluid is supplied from the priority valve, 1, mounted on top of the rear axle center housing. This priority valve receives fluid from the variable displacement hydraulic pump, which is mounted on the side of the rear axle center housing.

The priority valve has three high-pressure lines and two load-sensing lines connected to it. These lines include pressure in from the pump, out to the steering control valve, and out to the remote valve circuit. The load-sense lines come in from the steering control valve and exit to the special shuttle ball "T" fitting, which directs load sense fluid to the pump.



2


The steering control valve, 1, starting at serial number D408436 has an inlet check valve in the inlet port, 2. This check valve opens at 0.2 - 0.34 bar (3 - 5 PSI).

This prevents instances of steering wheel kick back at full lock when a remote valve or the EDC is operated.

The check valve can be retro-fitted to tractors built prior to serial #D408436 and is available from P & A.


The steering control valve directs fluid to the steering cylinders located on the front axle. The steering cylinders are double acting. The two-wheel drive tractor uses one cylinder, and the FWD uses two cylinders. The fluid is carried to the cylinders by steel tubing and rubber hoses which are mounted on the tractor main frame. The line connections are all O ring faced seal fittings (ORFS).

The return fluid from the steering control valve is directed back to the reservoir, via a return line, which enters below fluid level.



3


The hydrostatic steering control lines, 1 and 2, are connected to the main tractor circuit lines at a location under the removable cab floor plate. The line connections points are staggered for easy access.



4


STEERING SYSTEM CONTROL VALVE

The steering system control valve is a closed center load-sensing fixed displacement valve. Closed center means that when the steering valve is in the "NEUTRAL" position, the pump port is blocked off at the spool sleeve. The return port remains open.




5

The steering control valve is bolted, 1, to the outside front fire wall of the cab for sound isolation. The valve can be removed by gaining access to the front of the cab fire wall. Removal of the left and right side panels is required. Muffler and rear hood supports can be left in place.




6

The valve is operated by a splined shaft, 2, from the steering column. The steering column, 1, has both tilting and telescoping features.



7



8

The major components of the steering control valve are:

1 Control spool which is splined to the steering column.
2 Rotary sleeve assembly which fits around the spool and is joined to it by centering springs.
3 Main housing.
4 Mechanical drive.
5 Gerotor (star and ring) metering section assembly.

For steering control operation, the spool opens the porting for fluid flow from the pump port through the sleeve, rotary spool valve, and the metering section, to the steering cylinder, and back to the tank port.

The metering unit gerotor gear set outer ring is fixed in position as part of the housing. The inner star moves in a small circular orbit, within the outer ring, to pump or displace fluid. The star is coupled to the sleeve and spool, by the mechanical drive, which rides between t he ID of the star and the centering pin. In this way, the movement of the steering wheel and the sleeve directly controls the amount of fluid displaced by the star.

The spool also contains porting to direct the load sensing fluid back to the shuttle "T" fitting and on to the load sense control on the CCLS pump. This load sensing fluid is a sample of the working pressure going to the steering cylinder.


Steering Control Valve Operation

Neutral

In neutral or straight ahead driving, the control unit is maintained in the power "OFF" position by the centering springs.

In this position, porting in the spool and sleeve are closed in the "IN" housing port so there is no hydraulic oil flow. There is no oil flow out the load- sense port and back to the load-sense circuit.

The non-load reactive control valves will also have the left- and right-turn ports blocked from each other. The partially load-reactive valves will have the left and right ports slightly open to each other.



9

Left and Right Turn


When the steering wheel is turned, the control spool also revolves. Centering pin holes in the spool are elongated enough to allow the spool to turn about 1/16" in either direction.

However, the sleeve, which is anchored by the entering springs, pin, and to the metering unit, tends to not move because of tractor front-end turning resistance. This resistance is hydraulically coupled to the metering unit and thus to the sleeve.


These opposite forces cause the leaf centering springs to bend. The spool revolves in the sleeve so the porting within the two parts are aligned. Incoming pressurized fluid is then directed to the metering unit. Fluid is displaced by the metering star and directed to the appropriate steering cylinder port, via the spool and sleeve.

When the operator stops turning the steering wheel, centering springs return the spool and sleeve to the "NEUTRAL" position. Fluid flow to the metering unit is shut off, which stops the turning movement of the tractor's front wheels.

Port "L" delivers fluid to power a left turn, and port "R" delivers power to power a right turn. During the turn operation, fluid being returned to the opposite port from the steering cylinder is ported within the control unit and sent back to the reservoir.



10



11


Manual Turning

Limited emergency manual steering is available when the hydraulic pump flow is interrupted. The control unit automatically reverts to manual operation. In this condition, the metering section becomes a rotary hand pump and directs fluid to move the steering cylinder in either direction when the steering wheel is turned.

A check valve inside the control valve allows recirculation of oil within the control circuit and the steering cylinder system. This check valve is closed during normal operation and opens during manual operation.

⚠ WARNING ⚠


The torque required to turn the steering wheel in this emergency steer condition is very high. This system should only be used to steer the tractor long enough to get it safely stopped and moved off the roadway.



12

STEERING CONTROL VALVE TYPES

There are four different versions of steering control valves. The type used depends upon the front axle option used and market specifications. The control valves have different gerotor sizes, non-load and partially load reactive porting. One model is also equipped with crossover reliefs.



13

70 Series Part #86507484
70A Series Part #86026868
International Sales Organization (ISO) cabs, 14.1 cubic inch in nonreactive with crossover relief. Model #2634137081.

70/70A Series Part #9821416
North American cabs on two-wheel drive tractors 8.9 cubic inch. The partially load reactive gives some road feel back to the steering wheel. Identified with a red paint dot on the gerotor section, 1.

70 Series Part #9823774
70A Series Part #86026836
North American units with standard mechanical front axle, partially load reactive 14.1 cubic inch. Identified by a blue paint dot on the gerotor section, 1.

70/70A Series Part #9849239
North American units with SuperSteer, articulated front axle steering non-load reactive 14.1 cubic inch. Identified by a green paint dot on the gerotor section, 1.

These non-load reactive valves are used because the FWD steering axle can give some feedback, causing the tractor to self-steer while the FWD clutch is being engaged and disengaged.

STEERING CYLINDERS


The type of steering cylinder used depends upon the front axle option used.

Two-Wheel Drive Steering Cylinder

The two-wheel drive front axle uses one double-acting balanced cylinder, 1.

The cylinder is balanced with a rod sticking out both ends of the barrel to give equal cylinder displacement in both directions. This gives the cylinder equal movement in both directions as fluid is displaced from the steering control valve. This gives the cylinder equal size working areas so the equal steering effort can be generated when turning in both directions.

Refer to Section 44, Chapter 1, for additional details regarding the front steering cylinder.




14

Front-Wheel Drive Steering Cylinders

The front-wheel drive (FWD) axle uses two double-acting cylinders, 1. These two cylinders provide the additional force required to steer a tractor with the FWD axle. The two steering cylinders are connected so the base end of one cylinder and the rod end of the other cylinder are working together to turn the tractor. This allows the cylinders to develop equal effort when turning in both directions.

Refer to Section 25, Chapter 1, for additional information regarding the steering cylinders on the front axle.



15

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Slow steering, hard steering, or loss of power assist.	Worn or malfunctioning pump	Replace pump
	Stuck flow divider piston	Replace flow divider
	Worn pump compensator allowing the system pressure to be less than specified	Replace pump and compensator
	Malfunctioning relief valve allowing the system pressure to be less than specified	Replace the relief valve
	Overloaded steer axle	Reduce load
	If load-sensing system: 1. Leaking or kinked load-sensing signal line	Correct
	2. Malfunctioning priority valve	Check spring and sticking piston. Check damping orifices in both ends of main bore. Check system pressure at pump discharge test port for proper system pressure. If not correct, replace priority valve relief cartridge.
	Worn or damaged motor and stator assembly.	Inspect and replace
	Damaged valve spool	Install new steering motor
	Jammed valve spool	Clean thoroughly. Install new steering motor if necessary
	Worn or damaged bearings	Inspect steering column bearings. Inspect bearing and bearing surfaces in the steering motor. Install new bearings if necessary
	Front axle binding	Inspect and repair

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Wander - Vehicle will not stay in a straight line	Air in the system, due to low level of oil, cavitating pump, leaky fitting, pinched hose, etc.	Correct
	Worn mechanical linkage	Repair or replace
	Bending of linkage or cylinder rod	Repair or replace
	Loose cylinder piston	Repair or replace
	Leaky crossover relief or anti-cavitation valve in cylinder lines	Repair or replace the accessory valve
	Severe wear in steering control unit	Replace the steering control unit
	Leakage past valve spool	Inspect spool for wear, or damage. Install new assembly if necessary
	Damaged motor seals	Inspect and install new seals particularly rotor seal and O rings
	Leaking steering cylinder	Inspect and repair
Drift - Vehicle veers slowly in one direction	Single rod end cylinder slowly extends without turning the steering wheel	A small rate of extension may be normal on a closed center system
	Worn or damaged steering linkage	Replace linkage and align front end
Slip - A slow movement of steering wheel fails to cause any movement of steered wheels	Leakage of cylinder piston seals or accessory valve between cylinder lines or ports	Replace seals or accessory valve
	Worn steering control unit meter	Replace steering control unit
Temporary hard steering or hand-up	*Thermal shock	Check unit for proper operation and cause of thermal shock

*Thermal shock - A condition caused when the hydraulic system is operated for some time without turning the steering wheel so fluid in the reservoir and system is hot and the steering control unit is relatively cool (more than 10° C (50° F) temperature differential). When the steering wheel is turned quickly, the result is temporary seizure and possible damage to internal parts of the steering control unit. The temporary seizure may be followed by total freewheeling.

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Erratic steering	Air in system due to low level of oil, cavitating pump, leaky fitting, pinched hose, etc.	Correct condition and add fluid
	Loose cylinder piston	Replace cylinder
	*Thermal shock damage	Replace steering control unit
	Sticking flow control spool	Replace flow control valve
Excessive noise	Air in system	Check for loose connections or damaged tubing. Purge air from system
	Broken spool spring	Install new spring
	Hydraulic lines contacting tractor	Wrap hydraulic lines with tape
Spongy or soft steering	Air in hydraulic system. Most likely air trapped in cylinders or lines	Bleed air out of system. Placing ports on top of the cylinder will help prevent air trapping
	Low fluid level	Add fluid and check for leaks
Freewheeling - Steering wheel turns freely with no feeling of pressure and no action on steered wheels	Steering column upper shaft is loose or damaged	Tighten steering wheel nut
	Lower splines of column may be disengaged or broken	Repair or replace column
	Steering control unit meter has a lack of oil. this can happen on start-up, after repair, or long periods of non- use.	Usually starting engine will correct problem
	No flow to steering unit can be caused by: 1. Low fluid	Add fluid and check for leaks
	2. Ruptured hose	Replace hose
	3. Internal steering control unit damage due to *thermal shock	Replace the unit

*Thermal shock - A condition caused when the hydraulic system is operated for some time without turning the steering wheel so fluid in the reservoir and system is hot and the steering control unit is relatively cool (more than 10° C (50° F) temperature differential). When the steering wheel is turned quickly, the result is temporary seizure and possible damage to internal parts of the steering control unit. The temporary seizure may be followed by total freewheeling.

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Freewheeling - Steering wheel turns with slight resistance, but results in little or no steered wheel action	Leaking crossover relief or anti-cavitation valve in cylinder lines	Repair or replace the accessory valve
	Piston seal blown out	Determine cause. Correct and replace seal
Excessive free play at steering wheel	Loose steering wheel nut. Steering column shaft worn or damaged. There should be very little free play in the unit itself	Repair or replace steering wheel connection or column
Excessive free play at steered wheels	Broken or worn linkage between cylinder and steered wheels	Check for loose fitting bearings and anchor points in steering linkage between cylinder and steered wheels.
	Leaky cylinder seals	Replace cylinder seals
Binding or poor centering of steering wheel	Binding or misalignment in steering column or splined input connection	Align column pilot and spline to steering control unit
	High back pressure in tank line can cause slow return to center. Should not exceed 300 PSI	Revise circuit return line
	Large particles can cause binding between the spool and sleeve	Clean the unit and filter the oil. If another component has failed generating contaminants, flush the system while bypassing the steering control unit
Steering unit locks up	Large particles in meter section	Clean the unit
	Insufficient hydraulic power (unit over 15 in^3)	Check hydraulic power supply
	Severe wear and/or broken pin	Replace the unit
	*Thermal shock	Replace the unit


*Thermal shock - A condition caused when the hydraulic system is operated for some time without turning the steering wheel so fluid in the reservoir and system is hot and the steering control unit is relatively cool (more than 10° C (50° F) temperature differential). When the steering wheel is turned quickly, the result is temporary seizure and possible damage to internal parts of the steering control unit. The temporary seizure may be followed by total freewheeling.

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Steering wheel oscillates or turns by itself	Parts assembled wrong. Steering unit improperly timed	Correct timing
	Lines connected to wrong ports	Reconnect lines correctly
Steering wheel turns in wrong direction when operator activates steering wheel	Lines connected to wrong cylinder ports	Reconnect lines correctly
Steering wheel kicks at start of steering	No inlet check valve on steering control unit	Install a check valve
Instability - Load-sensing systems hoses jump	Air in lines	Check pump inlet Bleed sensing lines
	Harmonic system	Add hose or an accumulator
	Plumbing	Bleed all lines Pilot lines should be tuning Lines to cylinder should be tubing If two pilot lines are used, go to 1
	Relief setting	Pump relief should be 21 bar (300 PSI) above priority relief
	Priority valve	Bleed by holding against top for thirty seconds on models with built-in relief only
		Decrease damping orifice by adding small wire
		Increase spring rate (this will raise the standby pressure)
	Load sensing pump	Compensator sticky Increase standby pressure
Steering wheel kicks while operator is holding the tractor in a full turn while operating a remote hydraulic lever.	Pressure spike in the high-pressure flow divider system	Install check valve on inlet port of steering valve (see Figure 3 for inlet port location.
		Check load sense line shuttle "T"
Low load sense signal pressure seen by pump - implement stack valve test much higher	Leakage across line shuttle "T" seat	Replace line shuttle "T"

REMOVAL AND DISASSEMBLY


STEERING CONTROL VALVE



16


Removal

1. Remove left side panel door, 5, and trim panel, 4. Loosen the hinge bar, 1, at the top, and pivot it down out of the way.
2. Remove the clamp holding the receiver/ drier, 3, and move the drier out of the way.
3. Remove the hood release lever pivot bolt, 2, and bushing assembly. Move the lever out of the way.



17

4. Remove the right side panel door, 4, and trim panel, 2. Loosen the hinge bar, and pivot it down out of the way.
5. Loosen the exhaust pipe clamp, 3, and the mounting bolts, 5. Remove the exhaust pipe.



18

6. Use crowfoot wrenches to loosen the five hydraulic connections.

NOTE: *Avoid loosening the brake line, as this will require brake bleeding after reassembly.*

7. Cap the fittings to prevent contamination.
8. Remove the four cap screws, 1, and pull downward on the steering control valve to remove it from the drive shaft. Remove the control valve out through the opening on the left side (opposite the brake valve).
9. Remove the four cap screws which secure the mounting plate, 2, to the steering control valve.
10. If the four pressure fittings on top are to be removed, mark the installation angle so the fittings can be installed the same way.
11. The upper two fittings are short 90° fittings, and the lower two fittings are long 45° fittings.

Disassembly

⚠ CAUTION ⚠

Do not sand, file or repair the spool, sleeve, or housing in any way. The unit may malfunction, causing loss of control of the tractor resulting in personal injury.

Tools Required:


Screwdriver 10 cm-15 cm x 3 mm
(4″ - 6″ long, 1/8″) flat blade
5/16″ socket
Breaker bar wrench
Torque wrench 1.6 bar 33 N·m (275 in. lbs. capacity)
Plastic or rubber hammer
1/4″ allen wrench
1/8″-24 machine screws, 1-1/2″ long
Needle-nose pliers

Cleanliness is very important when repairing a steering control unit. Work in a clean area, such as a room specifically made for diesel pump service. Before disconnecting any of the hydraulic lines attached to it, clean any dirt and foreign material from the complete control unit. Use a wire brush to clean joint areas of the steering control unit.

NOTE: *Although not all drawings show the unit in a vise, it is recommended the the unit be kept in a vise during disassembly. Follow the clamping procedures explained.*


Meter (Gerotor) End

1. Clamp the unit in a vise, meter end up. Clamp lightly on the edges of the mounting area. Use protective material, 1, on the vise jaws. Do not over tighten the jaws.



19

2. Remove the 5/16" cap screws, 1, which hold the end cap, 2, and remove the seal from the end cap, 3.




20

3. Remove the meter (gerotor), 1, and the seal, 2, from the meter.


NOTE: *Be careful not to drop the star from the meter.*

4. Remove drive spacer, 3.



21


5. Remove the drive, 2.
6. Remove the spacer plate, 1, and the seal from the housing, 3.



22


Control End

7. Remove the housing from the vise. Place the housing on a clean soft cloth to protect the surface finish. Use a thin-bladed screwdriver to pry the retaining ring, 1, from the housing.



23


8. Rotate the spool and sleeve until the pin is horizontal. Push the spool and sleeve assembly forward with the thumbs, just far enough to free the gland bushing from the housing. Remove the bushing, 1.



24


9. Remove the quad ring seal from the seal gland bushing.
10. Use a thin-bladed screwdriver to pry the dust seal from the seal gland bushing. Do not damage the bushing.

NOTE: *Later model steering valves may use a one-piece seal design.*



25


11. Remove two bearing races, 1, and the needle thrust bearing, 2, from the spool and sleeve assembly.



26

12. Remove the spool and sleeve assembly from the 14-hole end of the housing.


NOTE: *The inner spool, sleeve, and housing are not replaceable separately because the parts are fitted at very close tolerances. If the problem with the steering control unit is with the spool, sleeve, or housing, replace the control assembly or take it to an authorized Char-Lynn service center for rebuilding and testing.*




27

13. Push the pin, 1, from the spool and sleeve assembly.
14. Push the spool partially from the control end of the sleeve, then remove the six centering springs from the spool, carefully, by hand.
15. Push the spool back through and out the sleeve. Rotate the spool slowly when removing it from the sleeve.

16. Remove the seal, 1, from the housing.
17. Remove the setscrew, 2, from the housing.
18. Screw a 1/8"-24 machine screw into the end of the check ball seat, 3. Then, by pulling on the screw with a pliers, lift the seat out of the housing.
19. Remove the two seals, 4, from the check valve seat.
20. Tip the housing to remove the check ball, 5, and the check ball retainer, 6.



28



70-400-1824

29

Ref. No.	No. Used	Description
1.	1	Pump housing
2.	7	12-point head, special cap screw
3.	1	End cap
4.	1	Gear set
5.	1	Spacer
6.	1	Spacer plate
7.	1	Drive shaft
8.	1	Control spool
9.	1	Control sleeve
10.	6	Spring
11.	1	Pin
12.	1	Special setscrew
13.	1	O ring
14.	1	Check ball seat
15.	1	O ring
16.	1	Check ball
17.	1	Check ball retainer
18.	1	Control parts assembly (Includes Ref. Nos. 1, 8-11, and 16)
19.	2	Bearing race
20.	1	Needle thrust bearing
21.	1	Seal
22.	1	Seal
23.	1	Retaining ring
24.	1	Bushing
25.	1	Seal
26.	3	O ring

PARTS INSPECTION

1. Check all O rings for obvious cuts and nicks.
2. Check the fit and finish of the inner spool sleeve and housing.

NOTE: *The inner spool, sleeve, and housing are not replaceable separately because the parts are fitted to very close tolerances. If the problem with the steering control unit is with the spool, sleeve, or housing, replace the control assembly or take it to an authorized Char-Lynn service center.*

3. Check the bearing and race for damage.

ASSEMBLING THE STEERING CONTROL UNIT

NOTE: *The inner spool, 8; sleeve, 9; and housing, 1, are not replaceable separately because the parts are fitted at very close tolerances. If the problem with the steering control unit is with the spool, sleeve, or housing, replace the control assembly, 18, or take it to an authorized Char-Lynn service center.*

⚠ CAUTION ⚠

Do not sand, file, or repair the spool, sleeve, or housing in any way. The unit may malfunction, causing loss of control of the tractor resulting in serious personal injury.


Check all mating surfaces. Replace any parts that have scratches or burrs that could cause leakage. Clean all metal parts in clean solvent. blow dry with air. Do not wipe dry with cloth or paper towels, because lint or other matter can get into the hydraulic system and cause damage. Do not use a coarse grit or try to file or grind these parts.

NOTE: *Lubricate all seals (with the exception of the new quad ring seal) with clean petroleum jelly such as Vaseline®.*

Do not use excessive lubricant on the seals for the meter section.


Replace all oil seals with new seals.

1. Use a needle-nose pliers to lower the check ball retainer, 4, into the check valve hole of the housing. Make sure the retainer is straight (not tilted on the edge) in the housing.
2. Install the check ball, 3, in the housing.
3. Lubricate the 15.8 mm (5/8″) diameter seal and 11 mm (7/16″) diameter seal. Install seals on the check ball seat, 2.
4. Lubricate the check ball seat and seals thoroughly before installing the seat in the housing. When installing the seat, do not twist or damage the seals. Install the check ball seat in the housing, insert the open end of the seat first. Push the check ball seat to the bottom of the hole.
5. Install the setscrew, 1. Use a 5/16″ allen wrench to torque the setscrew to 11 N·m (100 in. lbs.) To prevent interference, make sure the top of the setscrew is slightly below the housing mounting surface.




30

6. Assemble the spool and sleeve carefully, so the spring slots, 1, line up at the same end. Rotate the spool while sliding the parts together. Some spool and sleeve sets have identification marks; align these marks, then test for free rotation. The spool should rotate smoothly in the sleeve with finger tip force applied at the splined end.




31

7. Bring the spring slots of both parts in line, and stand the parts on the end of a bench. Insert the spring installation tool through the spring slots of both parts, 1.



32

8. Compress the extended end of the centering spring set, and push it into the spool sleeve assembly, withdrawing the installation tool at the same time.
9. Center the spring set in the parts so they push down evenly and flush with the upper surface of the spool and sleeve.
10. Install the pin, 1, through the spool and sleeve assembly, until the pin becomes flush at both sides of the sleeve.




33

11. Position the spool and sleeve assembly so the splined end of the spool enters the 14-hole end of the housing first.


NOTE: *Be extremely careful the parts do not tilt out of position while inserting. Push the parts gently into place with a slight rotating action. Keep the pin nearly horizontal. Bring the spool assembly entirely within the housing bore until the parts are flush at the meter end or 14-hole end of the housing.*

Do not pull the spool assembly beyond this point to prevent the cross pin from dropping into the discharge groove of the housing. With the spool assembly in the flush position, check for free rotation within the housing by turning with light fingertip force at the splined end.




34

12. Place the housing on a clean, lint-free cloth. Install a 54 mm (2-1/8″) diameter seal, 3, in the housing.
13. Install the two bearing races, 1, and the needle thrust bearing, 2, in the order shown.



35


14. Install a 32 mm (1-1/4″) diameter dust seal, 1, in the seal gland bushing. The flat or smooth side of the seal must face down toward the bushing.



36


15. Install the dry quad ring seal, 1, in the seal gland bushing. Smooth the seal in place with your finger. Do not use any seal that falls freely into the pocket of the bushing.
16. Install the seal gland bushing, 2, over the spool end with a twisting motion. Tap the bushing in place with a plastic or rubber hammer. Make sure the bushing is flush against the bearing race.
17. Install the retaining ring, 3, in the housing. After install the ring, tap on the ring end, or pry with a screwdriver around the entire circumference of the ring to properly seat the ring in the groove.
18. Clamp the housing in a vise. Clamp lightly on the edges of the mount area. Do not over tighten the jaws.

NOTE: *Make sure the spool and sleeve are flush, or slightly below, the 14-hole surface of the housing. Clean the upper surface of the housing by wiping it with the palm of a clean hand. Clean each of the flat surfaces of the meter section parts in a similar way when ready for reassembly. Do not use cloth or paper to clean the surfaces.*




37

19. Install a 76 mm (3″) diameter seal, 1, in the housing.
20. Install a spacer plate, 2. Align the bolt holes in the spacer plate with the tapped holes in the housing.




38

21. Rotate the spool and sleeve assembly, 1, until the pin is parallel with the port face. Install the drive, making sure the drive is engaged with the pin. To insure proper alignment, mark the drive. Note the relationship between the slotted end of the drive to the splined end of the drive when marking.




39

22. Install a 76 mm (3″) diameter seal, 1, in the meter.




40

23. Reinstall the housing in the vise. With the seal side of the meter toward the spacer plate, align the star valleys, 1, on the drive, 2. Note the parallel relationship of the reference lines, 3, 4, 5 and 6. Align the bolt holes without disengaging the meter from the drive.




41

24. Install the drive spacer, 1, in the meter.
25. Install a 3″ diameter seal, 2, in the end cap.
26. Install the end cap, 3, on the gerotor, and align the holes.
27. Install the seven dry cap screws, 4, in the end cap.



42

28. Pre-tighten the screws to 17 N·m (150 in. lbs.), then torque the screws to 33 N·m (275 in. lbs.) in the sequence shown.




43

INSTALLING THE STEERING CONTROL VALVE

1. Install new O rings on the five pressure fittings and reinstall the fittings in the steering control valve.
2. Install the long 45° fittings in the lower ports, 1. The shorter 90° fittings should be in the top two ports, 2.
3. Tighten the jam nuts on the fittings if the installation angle was marked before disassembly. Otherwise, leave the jam nuts finger tight.
4. Install the steering control valve to the mounting plate and secure the four cap screws.
5. Align the steering column drive shaft and insert the steering control valve into the mounting cavity on the front of the cab fire wall. Put the control valve in from the left side of the tractor.

NOTE: *An assistant may be required to rotate the steering wheel to achieve drive shaft engagement.*




44

6. Install the four cap screws, 1, into the threaded holes.

NOTE: *When attaching the steering control unit, be sure the mounting plate, 2, is situated so that binding or end loading on the steering control unit is not experienced.*

IMPORTANT: *If binding or end loading of the steering control unit occurs, problems with steering chatter or hard steering may result.*




45

7. Install new O rings on the face fittings and install the lines in a pattern which will allow for proper alignment and tightening of the jam nuts and fitting cap nuts. Torque the cap nuts to 15 ft lbs.


IMPORTANT: *Failure to attach the lines to the proper ports will result in incorrect steering operation or hydraulic component damage.*

8. Loosely install the exhaust pipe, 1.
9. Start the tractor and allow the engine to idle for two minutes so the load sense circuit can self-bleed through the internal passage. CHECK FOR LEAKS.
10. Check for correct steering operation by slowly turning the steering wheel fully in both directions. Perform this operation several times to bleed the air from the steering cylinder circuit.
11. If the system still acts like there is air in the circuit, loosen a fitting down at the steering cylinders and bleed the air/oil mixture into a clean container. CHECK FOR LEAKS.
12. Tighten the exhaust pipe, 3, clamps and reinstall the right side trim panel and door.



46

13. Reinstall the hinge bar, 1; hood latch pivot bolt assembly, 2; and receiver/drier, 3.
14. Reinstall the left side trim panel, 4, and door, 5.



47

SECTION 44 - TWO-WHEEL DRIVE AXLE AND WHEELS

Chapter 1 - Two-wheel Drive Front Axle

CONTENTS

Section	Description	Page
44 000	Specifications	2
	Special Tools	2
	Description of Operation	3
	Two-wheel Drive Front Axle	3
	Troubleshooting	6
	Adjustments	7
	Front Wheel Track Spacing	7
	2WD Axle Adjustment	9
	Front Wheel Position	10
	Front Wheel Toe-in	11
	Disassembly and Repair	13
	Axle Removal	13
	Axle Installation	17
	Axle Center Beam Bushing Replacement	21
	Axle Extension Installation	21
	Spindle Removal and Disassembly	21
	Axle Extention/Spindle Bushing Replacement	22
	Spindle Reassembly	22
	Front Wheel Bearing	23
	Steering Cylinder	25
	Center Steering Arm	30
	Steering Rod	32

SPECIFICATIONS

Toe-in	6 - 13 mm (0.250 - 0.500″)
Spindle bushing recess	4 mm (0.157″)
Center steering arm bushing recess	5 mm (0.196″)
Center steering arm clearance	10 mm (0.42″)
Axle center section pivot pin end play	0.25 - 2 mm (0.010 - 0.078″)
Axle center section end play	1.5 mm (0.059″)
Axle center section bushing inside diameter	50.23 - 50.33 mm (1.977 - 1.981″)

Tightening Torques

Wheel bearing nut	20 N·m	(15 ft lbs)
Wheel mounting bolt	204 N·m	(150 ft lbs)
Tie rod through bolts	68 N·m	(50 ft lbs)
Tie rod ball joint nut	170 - 210 N·m	(125 - 155 ft lbs)
Tie rod adjusting nut	170 - 210 N·m	(125 - 155 ft lbs)
Axle pivot pin retaining bolt	55 N·m	(41 ft lbs)
Axle pivot pin mounting block bolts	576 N·m	(425 ft lbs)
Axle extension mounting bolts	576 N·m	(425 ft lbs)
Steering cylinder ball joint nut	150 - 170 N·m	(110 - 125 ft lbs)
Steering cylinder piston rod nut	150 - 170 N·m	(110 - 125 ft lbs)
Steering cylinder mounting bolt	690 N·m	(510 ft lbs)
Steering cylinder ball joint clamp	35 - 40 N·m	(25 - 30 ft lbs)

SPECIAL TOOLS


Engine splitting stand	FTC50817
Transmission support stand	FTC60296
Engine stand adapter	FNH00530
Torque wrench extension	506570

DESCRIPTION OF OPERATION

TWO-WHEEL DRIVE FRONT AXLE

The two-wheel drive axle is an adjustable width axle assembly which consists of a hollow center beam, 1, with telescopic sections, 2, on each end.


The axle track spacing is adjustable in 101.6 mm (4") increments to six positions. The adjustment is accomplished by removing bolts and sliding the outer axle sections in the center beam until the correct width is achieved.



1


The axle mounting pivot allows for 8.5° - 12° of oscillation. The pivot pin, 1, is located above the axle center line. The oscillation is limited by blocks, 2, attached to the front bolster casting.

The pivot pin is fastened to the tractor front bolster casting.




2

The front axle pivots on replaceable bushings, 1, which are located inside the center axle beam.




3

The front axle pivot pin assembly consists of pin, 1; two blocks, 2; and six shim washers, 3. The pin is bolted to the block at location 4, and slips into the block on the other end. The shim washers, 3, are used to adjust free play when the pin is installed in the axle center beam.




4

The steering linkage is operated by one double-acting steering cylinder, 4, which rotates the center pivot, 2, which in turn moves the tie rods,1.




5

The tie rod assemblies, 4, are adjustable to allow for toe-in adjustments when the axle width is changed. The axle extension bolts, 1, and tie rod clamp bolts, 2, and clamps, 3, are used to make the width changes.




6

The tie rod assemblies are connected to steering arms, 1, which are splined to the spindles assemblies, 4. The spindle assemblies rotate in two replaceable bushings, 2. The vertical load of the front axle spindle is carried by the thrust bearing, 3. The wheel hubs, 6, are mounted on tapered roller bearings, 5.



7

Three different sizes of front rims, 1, are used. The front rims are attached to the hubs with eight wheel bolts. The wheel disc centers are offset. The two smaller rims can be reversed to change the wheel track.




8

TROUBLESHOOTING

PROBLEM	POSSIBLE CAUSE	CORRECTION
Tractor is hard to steer	Spindles will not rotate in axle extensions	Grease the bushings and thrust bearings
	Low power steering pressure	Check power steering operation (see Section 41)
Tractor wanders on ridged roads/rough fields	Toe-in set incorrectly	Adjust toe-in
	Loose steering linkage	Replace worn parts
	Air in the cylinder	Bleed the cylinder hoses
	Steering cylinder seals worn	Rebuild steering cylinder
	Worn tires or low tire pressure	Replace tires/check tire pressure for the load
	Worn steering control valve	Troubleshoot steering control valve (see Section 41)
Oil leaks from steering cylinder	Worn steering cylinder seals	Rebuild/replace the steering cylinder

ADJUSTMENTS



9

FRONT WHEEL TRACK SPACING


1. The track spacing is adjustable in 102 mm (4″) increments to six positions.
2. Both telescopic sections of the axle must be extended so the same number of adjustment holes are showing.

⚠ WARNING ⚠

70 SERIES tractors are produced with lights which meet applicable lighting regulations for operating on or traveling on public highways. If the wheel track setting is adjusted beyond the original factory position, the lights may have to be readjusted or auxiliary lights may have to be fitted to comply with legal requirements.

Additionally, ensure that the overall tractor width does not exceed the maximum width permitted in your locality.

3. Track adjustment can also be adjusted by installing the front wheels with the offset disc facing in, 1, or out, 2. The 16.5L-16.1 tires and wheels must be installed with the offset facing out, 2.
4. The following table lists the available track adjustments. The spacing dimensions indicate the distance between the center point of the tread measured at the ground contact point.
5. The track width dimensions shown may vary from your actual measurements depending upon the specific wheel and tire combinations and the tire manufacturer.



10


⚠ WARNING ⚠

Tractor wheels are very heavy. Handle with care and ensure when stored that they cannot fall and cause injury.

AXLE POSITION	1		2		3		4		5		6	
RIM DISC POSITION	In	Out	In	Out	In	Out	In	Out	In	Out	In	Out
	mm (in.)		mm (in.)		mm (in.)		mm (in.)		mm (in.)		mm (in.)	
Tire Size												
11.00 - 16.0	1550 (61″)	1753 (69″)	1651 (65″)	1854 (73″)	1753 (69″)	1956 (77″)	1854 (73″)	2057 (81″)	1956 (77″)	2159 (85″)	2057 (81″)	2261 (89″)
16.5L - 16.1	N/A	1727 (68″)	N/A	1829 (72″)	N/A	1930 (76″)	N/A	2032 (80″)	N/A	2134 (84″)	N/A	2235 (88″)
14L - 16.1	1575 (62″)	1702 (67″)	1676 (66″)	1803 (71″)	1778 (70″)	1905 (75″)	1880 (74″)	2007 (79″)	1981 (78″)	2108 (83″)	2083 (82″)	2210 (87″)

N/A = Not available

2WD AXLE ADJUSTMENT



11

Front Axle Adjustment

1. Park the tractor on a level surface and position the front wheels straight ahead.
2. Apply the park brake and place blocks at the front and rear of the rear wheels.
3. Jack up the front axle and place jack stands under the center section of the axle.
4. Remove two bolts, 1, from both of the axle extensions.
5. Remove the tie rod clamp bolts, 2, and clamps, 3, from both of the tie rods.
6. Slide both of the axle extensions to the desired position.

NOTE: *Both axle extensions must be extended so the same number of holes are exposed on both extensions.*

7. Install the axle extension bolts, 1, and torque to 576 N·m (425 ft lbs).
8. Position each tie rod end, 4, so the same number of holes are exposed as are exposed in the axle extension.
9. Install the tie rod clamps, bolts and nuts. Torque the nuts to 68 N·m (50 ft lbs).
10. Check and, if required, adjust the toe-in.

FRONT WHEEL POSITION


Use the following procedure to change the front wheel track by reversing the front wheel offset, 1.

1. Park the tractor on a level surface and position the front wheels straight ahead.
2. Apply the park brake and place blocks at the front and rear sides of the rear wheels.
3. Jack up the front axle and place on jack stands.
4. Remove the wheels.
5. Reverse the wheel offset and reinstall the wheels.
6. Torque the wheel bolts in a diagonal pattern to a torque of 204 N·m (150 ft lbs).

NOTE: *Torque the wheel bolts as specified. Operate for 200 m (218 yds) and retorque. Repeat the torque check after one hour and then at 10 hours or at daily intervals until the bolt torque remains constant. Check torque at 50-hour intervals thereafter.*

⚠ WARNING ⚠


Never operate the tractor with a loose wheel rim or disc. Always tighten hardware to the specified torque and at the recommended intervals.



12

FRONT WHEEL TOE-IN

The correct toe-in is 6 - 13 mm (1/4 - 1/2″).



13

Checking Toe-In

1. Raise the front axle so that both wheels are off the ground and the steering is free to turn through a full right-hand and left-hand turn. Support the axle with jack stands. Make sure the rear wheels are blocked.
2. Place a mark on the inside front of the front rims where the tire and rim meet. Place the marks at hub height.
3. Measure the distance, 1, between the marks.
4. Rotate both front tires 180° until the marks are at the rear.
5. Measure the distance, 2, between the marks.
6. Subtract the front measurement,1, from the rear measurement.
7. If the toe-in is 6 - 13 mm (1/4 - 1/2″) and the right tire does not contact the end of the cylinder rod in a full right turn, the toe-in is correct and no adjustment is needed.


NOTE: *If toe-in is not as specified, proceed to step 8.*

Adjusting Toe-In

8. Measure the distance, 1, between the inner, 2, and outer tie rods ends, 4, on both tie rods. Adjust the tie rods to achieve equal measurements. This will ensure that both wheels track evenly.
9. Loosen the jam nut, 3, on each tie rod.
10. Remove the outer tie rods ends, 4, from each spindle, 5.
11. Adjust each tie rod equally to achieve the 6 - 13 mm (1/4 - 1/2") toe-in.
12. Install each outer tie rod end, 4, and torque the retaining nut, 6, to 170 - 210 N·m (125 -155 ft lbs). Install a new cotter pin on each tie rod end.
13. Tighten the jam nut, 3, on each tie rod.
14. Recheck the toe-in adjustment.
15. Perform a full right-hand turn and ensure that the tire does not contact the steering cylinder.

⚠ WARNING ⚠

Maintain all steering components in a reliable and satisfactory condition to ensure safe operation and to comply with legal requirements.




14

DISASSEMBLY AND REPAIR


AXLE REMOVAL

1. Park the tractor on a level surface and position the front wheels straight ahead.
2. Apply the park brake and place blocks at the front and rear of the rear wheels.
3. Disable the tractor by removing the fuel injection pump solenoid relay #16 as described in Section 55, Chapter 3.
4. Jack up the front axle and install the engine splitting stand adaptor, 1, special tool #FTC 50817, and adapter FNH00530, as shown. Place a jack stand, 2, under the center section of the transmission as shown.




15

5. Remove the front wheels.




16

6. Install the transmission support stand, 1, special tool # FTC60296, under the front axle center beam. Secure the axle to the support stand with a chain or strap.




17

7. Disconnect and cap the hydraulic power steering right turn, 1, and left turn hoses, 2. Mark the hoses left and right for identification during reinstallation.




18

8. Remove the two cap screws, 1, that retain the front pivot pin mounting block, 2, to the front frame.




19

9. Remove the two cap screws, 1, that retain the rear pivot pin mounting block, 2, to the front frame.



20

10. Lower the screw jacks on the support stand until the front axle mounting blocks, 1, clear the front frame.




21

11. Carefully roll the front axle, 1, and support stand assembly, 2, clear of the tractor.


⚠ CAUTION ⚠

The front axle will rest on the support stand but it should be secured to the stand if it is to be serviced or moved.




22

12. Slide the pivot pin front mounting block, 1, and shim washers, 2, off the pivot pin.




23

13. Slide the pivot pin assembly, 1, and the shims, 2, out of the rear of the axle.



24


14. Inspect the pivot pin shaft, 1, and mounting blocks, 2, for wear or damage. Replace parts as required.



25

15. Inspect both of the pivot bushings, 1, for wear or damage. Replace if required.


    New bushing inside diameter is 50.23 - 50.33 mm (1.977 - 1.981").



26


AXLE INSTALLATION

1. Lubricate the bushings, 1, and pack grease (grease specification ESE-MIC75-B) into the bore area between the bushings.




27

2. Reinstall pivot pin assembly, 1, and shim washers, 2, from the rear side. If the rear block was separated from the pin, then torque the cap screw to 55 N·m (41 ft lbs).




28

3. Reinstall the front mounting block, 1, and shim washers, 2, on the pin assembly.




29

4. Roll the axle assembly, 1, back under the tractor.




30

5. Raise the axle assembly with the support stand screw jacks until the mounting blocks, 1, fit back into the holes in the front frame of the tractor.



31


6. Insert the cap screws, 1, through the front mounting block, 2, and loosely install the cap screws, 1.



32


7. Insert the cap screws, 1, through the rear mounting block, 2, and torque the front and rear cap screws to 576 N·m (425 ft lbs).

NOTE: *Check for excessive axle end play by trying to insert another shim washer in between the stack of washers on the shaft. If it does not fit, then end play is not excessive.*




33

8. Install new O rings on the fittings and connect the steering cylinder hoses,1 and 2.
9. Torque the fittings to 27 N·m (20 ft lbs).




34

10. Remove the axle support stand, 1.



35


11. Install the front wheels, 1, and torque the cap screws in a diagonal pattern to 204 N·m (150 ft lbs).
12. Check the axle toe-in as previously described in "Front Wheel Toe-In."
13. Use a hydraulic jack to hold up the front of the tractor and remove the engine support stand, 2, and jack stand, 3. Lower the tractor to the floor.
14. Lubricate all the pivot points of the front axle as described in the operator's manual.
15. Reinstall the engine fuel solenoid relay that was removed to disable the tractor.
16. Start the tractor engine and cycle the steering in full left and right turns to check for correct steering linkage operation and to purge the air from the steering cylinder circuit.



36

AXLE CENTER BEAM BUSHING REPLACEMENT

(Axle removed from tractor)
Remove old bushings, 1, and clean the bore. Install new hardened bushings, 1, into the axle center beam making sure that the bushings are recessed slightly. The bushings do not require machining after installation.




37

AXLE EXTENSION INSTALLATION

(Axle removed from tractor)
If the extensions have been removed, install as follows:

1. Install the axle extension, 3, into the axle beam,1. Install the four bolts and washers, 2, through the axle beam into the four nuts, 4.
2. Tighten the bolts to 575 N·m (425 ft lbs).


NOTE: *Make sure that the same number of bolt holes are exposed on both sides of the axle center beam assembly.*



38

SPINDLE REMOVAL AND DISASSEMBLY

1. Remove the cotter pin, 2, and hex nut, 1, from the tie rod ball joint at the steering arm, 5.
2. Remove the ball joint from the steering arm, 5.
3. Remove the bolt, 3, and washer, 4, from the steering arm.
4. Mark the steering arm, 5, and the spindle, 8, for correct alignment during assembly.
5. Remove the steering arm, 5, from the spindle, 8.
6. Remove the spindle, 8, from the axle extension, 6.
7. Remove the thrust bearing, 9, from the spindle, 8.




39

AXLE EXTENSION / SPINDLE BUSHING REPLACEMENT

1. Use a suitable puller and remove the bushings, 1, from the axle extension.
2. An alternate method of removal would be to use a chisel to split the bushing and drive it out.


⚠ WARNING ⚠

Always wear proper safety equipment when using a chisel.



40


3. Use a suitable driver and install the bushings, 1, into both ends of the axle extension so the open end of the oil groove, 2, in the bushing faces the inside of the axle extension.
4. Press the bushings into the axle extension so they are recessed 4 mm (0.157") below the axle extension inside diameter, 3.



41


SPINDLE REASSEMBLY

1. Install the thrust bearing, 9, on the spindle, 8.
2. Install the spindle, 8, into the axle extension.
3. Align the marks on the spindle, 8, and the steering arm, 5. Install the steering arm on the spindle.
4. Apply Loctite 242 (FP219) on the threads of the steering arm mounting bolt, 3.
5. Install the flat washer, 4, and bolt, 3, on the spindle.
6. Install the tie rod ball joint into the steering arm, 5.
7. Install the hex nut, 1, on the ball joint. Tighten the hex nut to a torque of 170 - 210 N·m (125 - 155 ft lbs).
8. Install the cotter pin, 2, through the hex nut. If the cotter pin holes do not line up, tighten the nut further until they do line up, then install the cotter pin.



42

FRONT WHEEL BEARING



43

Disassembly

1. Remove the front wheel or wheels.
2. After front wheel or wheels are removed, proceed to pry the hub cap, 11, from the hub, 7.
3. Remove the cotter pin, 12; hex nut, 10; washer, 9; and bearing cone, 8, from the spindle.
4. Remove the hub, 7, from the spindle, 1.
5. Remove the seal retainer, 4, and bearing cone, 5, from the hub.
6. Pull the bearing cups, 6, from the hub.
7. Remove the seal, 3, and dust shield, 2, from the spindle.
8. Wash all the parts in a safe parts washing solvent and allow parts to air dry.

⚠ WARNING ⚠


Do not spin dry bearings with compressed air.

Inspection

Inspect the bearing cups and cones. Replace any parts that are worn or damaged. Replace the wheel seals, 3, and dust shields, 2, and seal retainer, 4.

Reassembly

1. Install the new dust shield, 2, on the spindle so the outer flange of the dust shield points toward the hub and the open section of the dust shield is on the bottom.
2. Install new hub seal, 3, on the spindle so the metal face of the seal is toward the hub, 7.
3. Press the two new bearing cups, 6, into the hub until cups are seated in the hub.
4. Pack both the bearing cones with wheel bearing grease. Install the inner bearing cone, 5, into the hub. See the operator's manual for grease recommendations.
5. Install new seal retainer,4, into the hub until the outer flange of the seal retainer contacts the hub, 7.
6. Install the hub, 7, on the spindle, 1, so the seal retainer enters the dust shield.
7. Install the outer bearing cone, 8; washer, 9; and hex nut, 10, on the spindle.
8. Rotate the hub and tighten the nut to a torque of 20 N·m (15 ft lbs). Back off the hex nut until the first slot where the cotter pin, 12, can be installed is aligned with the hole in the spindle.
9. Install the cotter pin, 12, in the spindle. Press the hub cap, 11, in place in the hub.
10. Install the wheel and tire on the hub. Tighten the wheel mounting bolts to a torque of 204 N·m (150 ft lbs).
11. Lubricate the assembly through the grease fitting, 13, on the hub and check the toe-in.



44

STEERING CYLINDER

NOTE: *For trunnion bushing removal only go to step 4. The steering cylinder does not have to be completely removed from the machine to change the trunnion bushings. All work can be done with the steering cylinder and its related plumbing attached to the machine.*

Removal


1. Disconnect the steering lines from the steering cylinder, 2.
2. Loosen the ball joint clamp bolt, 1.
3. Using a wrench on the flat end of the piston rod, 5, turn the piston rod out of the ball joint, 1.
4. Remove the cylinder mounting bolts, 3 and 6, and washers from the cylinder.
5. Remove the cylinder, 2, from the center steering arm, 4.
6. Remove the trunnion caps, 7, from the cylinder.

Installation


1. Install the trunnion caps, 7, in the cylinder bushings.
2. Install the cylinder, 2, in the center steering arm, 4.
3. Apply Loctite® 242 to the new M20 x 60 trunnion bolts, 3 and 6. Install the washers and bolts on the cylinder. Tighten the bolts to a torque of 690 N·m (510 ft lbs).

NOTE: *For the top trunnion bolt, use torque wrench extension 506570. Use the formula, 1, and tighten the bolt to specification.*

IMPORTANT: *The bolts must be tightened to specifications.*




45



46


4. Turn the cylinder piston rod into the ball joint using a wrench on the flat end of the rod, 5. Tighten the rod to a torque of 170 N·m (125 ft lbs).
5. Tighten the ball joint clamp bolt, 1, and nut to a torque of 40 N·m (30 ft lbs).
6. Install the steering lines, 1 and 2, on the steering cylinder.
7. Start the engine and turn the steering wheel to a full left turn and then a full right turn several times to purge air from the system.




47

Disassembly


1. Remove steering cylinder, 1, from the tractor and drain the oil from the barrel.
2. Locate the hooked end of the retaining ring, 13, on the threaded rod end of the barrel.
3. Hold the end of the retaining ring with pliers, and rotate the cylinder head, 12, with a spanner wrench to force the retaining wire out of the barrel.
4. Pull the rod, 7, piston, 2, assembly out of the barrel.
5. Remove the cylinder head, 6, on the opposite end of the barrel by removing the retaining wire, 5, out through the slot while rotating the cylinder head with a spanner wrench.
6. Make a note of how all the seals, 8 and 11, and O rings, 3 and 4, and backup washers, 9 and 10, are installed and remove them.
7. Clean all the parts in parts washing solvent and inspect the cylinder barrel for damage.
8. If the cylinder barrel is scored deeper than light scratching, it must be replaced. If the barrel is lightly scratched, then use a small flex hone to clean it.



48



49



50

Reassembly

1. Lubricate the rod seals, 8, with petroleum jelly. Install one rod seal into the inner inside groove of each cylinder head.
2. Lubricate the rod wiper, 11, with petroleum jelly. Install one rod wiper into the outer inside groove of each cylinder head. The flush side of the wiper enters the cylinder head first and is pressed fully into the cylinder head.
3. Install one back-up washer, 9, into the wide outer groove of each cylinder head.
4. Install one O ring, 4, into the wide outer groove of each cylinder head. The O ring goes between the back-up washer and the cylinder head toward the smaller end of the cylinder head.

   Compress the O rings and back-up washers with a smooth hose clamp or a ring compressor to return them to the original size.
5. Install the O ring, 3, into the groove of the piston, 2.
6. Install the piston seal, 10, in the groove of the piston on top of the O ring. Compress the seal with a smooth hose clamp or ring compressor.

7. Install the piston rod, 7, into the cylinder so the threaded end of the piston rod is at the end of the cylinder with the pivot mount.


NOTE: *The left-hand piston rod is 442 mm (17.4") long, and the right-hand piston rod is 480 mm (18.9") long. Do not reverse the piston rods ends.*

8. Inspect the piston seal for damage during installation.
9. Install the cylinder heads, 12 and 6, over the piston rod and into the cylinder.
10. Turn the cylinder heads, 12 and 6, so the small hole in the cylinder head appears in the hole at the end of the cylinder.
11. Install the hooked end of the retaining ring, 13, through the hole of the cylinder, into the hole of the cylinder head, 12. Using a spanner wrench on the cylinder head, turn the cylinder head to pull the retaining ring fully into the cylinder. Repeat for cylinder head, 6, and ring, 5.
12. Install the cylinder assembly back on the front axle as described in this chapter.

CENTER STEERING ARM

Removal

1. Steering cylinder, 4, and steering rods, 1, must be removed to remove the steering arm, 2. The axle assembly can remain on the tractor.
2. Remove the roll pin, 3, which retains the pivot pin and pull the pivot pin out.
3. Pull the steering arm out of the axle boss area; locate all of the shim washers and tag them so they can be installed in the same location.




51

Inspection

Clean the parts in a part washing solvent and inspect the pivot pin and bushings for wear. Replace worn parts.


Reassembly

1. Press the two bushings, 2, into the center steering arm, 1, so they are 5 mm (0.196") below the surface of the center steering arm. Install grease fitting, 3.




52

2. Install the pivot pin, 7, through the bottom boss of the axle center section.
3. Lubricate the two O rings, 2 and 4, with petroleum jelly. Install the two O rings in the top and bottom recess of the center steering arm.
4. Install the center steering arm, 3, between the upper and lower boss of the axle center section, 1.
5. Install two 3.96 mm (0.156″) thickness flat washers, 5, between the bottom of the steering center arm and the lower boss of the axle center section.
6. Install the pivot pin, 7, through the center steering arm.
7. Install one 3.96 mm (0.156″) thickness flat washer and one 1.06 mm (0.042″) thickness flat washer, 5, between the center steering arm and the upper boss of the axle center section.
8. Check the clearance between the upper washer and the axle center section. The gap must be no greater than 1.06 mm (0.042″).
9. Add or subtract washers at the top of the steering center arm to adjust the clearance.
10. Install the roll pin, 6, through the center steering arm pivot pin. Grease the center steering arm assembly.



53


STEERING ROD



54

Removal and Disassembly

1. Remove the cotter pin, 6, and hex nut, 3, from the ball joint in the center steering arm, 4.
2. Loosen the locknut, 8, on the ball joint.
3. Remove the ball joint, 7, and boot, 5, from the center steering arm.
4. Remove the cotter pin, 15, and hex nut, 1, from the drag link.
5. Remove the drag link, 14, and boot, 16, from the steering arm.
6. Remove the nuts, 10; clamps, 11 and 12; and bolts, 13, from the tie rod and drag link.
7. Remove the ball joint, 7, from the tie rod.
8. Pull the drag link, 14, from the tie rod.
9. Repeat steps 1 through 8 for the other tie rod assembly.



55

Reassembly and Installation

1. Slide the drag link into the unthreaded tie rod end, 4.
2. Install the bolts, clamps and nuts through the tie rod and drag link holes once the proper assembly width has been decided.
3. Tighten the bolts and nuts to a torque of 70 N·m (50 ft lbs).
4. Install the locknut, 3, on the ball joint.
5. Install the ball joint into the tie rod.
6. Install the inner ball joint, 2, in the steering arm. Tighten the hex nut to a torque of 136 N·m (100 ft lbs).
7. Install the cotter pin through the hex nut. If the cotter pin holes do not line up, tighten the nut further until they do line up and then install the cotter pin.
8. Install the outer ball joint, 4, into the outer steering arm, 5.
9. Install the hex nut, 6, and tighten to a torque of 170 - 200 N·m (125 - 155 ft lbs).
10. Install the cotter pin through the hex nut. If the holes for the cotter pin do not line up, tighten the hex nut further until they do line up and then install the cotter pin.
11. Check for 6 -13 mm (1/4 - 1/2") toe-in, 1, and adjust the toe-in if required. See "Adjusting Toe-in" earlier in this chapter.

SECTION 44 - TWO-WHEEL DRIVE AXLE AND WHEELS

Chapter 2 - Four Wheel Drive (FWD) Front Axle Track Spacing

CONTENTS

Section	Description	Page
44 520	Specifications	2
	Four Wheel Drive (FWD) Front Axle Track Spacing	3
	Four Wheel Drive Track Adjustment	3
	Front Wheel Positions	4

SPECIFICATIONS

Tightening Torques

Disc to hub (Carroro axle)	803 N·m (592 ft lbs)
Disc to hub (Dana axle)	340 N·m (250 ft lbs)
Disc to rim	345 N·m (255 ft lbs)

FOUR WHEEL DRIVE (FWD) FRONT AXLE TRACK SPACING

FOUR WHEEL DRIVE TRACK ADJUSTMENT

Four wheel drive (FWD) tractors have fixed axle assemblies. However, the track width is adjustable to eight different settings by changing the wheel rim relative to the center disc, the rim and/or disc relative to the axle hub or by interchanging both front wheels.









Figure 1 shows the track spacings available by changing the wheel rim and disc positions relative to the hub.

Each drawing represents either a left-hand wheel viewed from the rear or a right-hand wheel viewed from the front.

IMPORTANT: *When the track adjustment is changed, the steering stops must be adjusted to maintain turning diameter and to provide clearance between the tractor and the tires and, when installed, fenders.*

NOTE: *(Dana axle only) A special FWD offset wheel disc kit is available for SuperSteer axles. This kit contains two wheel discs and two steering stops. The special 2" offset wheel disc can be used to achieve a 1531 mm (62") track setting, which is used with the special steering stops to provide a reduced turnaround diameter.*

NOTE: *Fixed-position fenders will have to be removed to achieve minimum turn diameters.*

Track Setting	Disc/Rim Position
1525 mm (60")	
1625 mm (64")	
1727 mm (68")	
1829 mm (72")	
1930 mm (76")	
2032 mm (80")	
2134 mm (84")	
2235 mm (88")	

1


FRONT WHEEL POSITIONS

Use the following procedure to position the front wheels to obtain the desired track adjustment:

1. Position the front wheels straight ahead.
2. Apply the park brake and place blocks at the front and rear of the rear wheels.
3. Jack up the front axle and place on jack stands.

⚠ WARNING ⚠

With a front wheel on a four wheel drive tractor supported on a stand, never attempt to rotate the wheel or start the engine. This may cause the rear wheels to move, resulting in the tractor falling from the stand. Wheels should always be supported such that the tires are only just clear of the ground.



2

4. Remove the front wheel.
5. Position the wheel disc and rim as required to achieve the desired track adjustment.
6. Reinstall the wheel and torque the hardware in a diagonal pattern to the following:

   Disc to hub (Dana axle), 1. - 340 N·m (250 ft lbs)

   Disc to hub (Carraro axle), 1. - 803 N·m (592 ft lbs)


   Disc to rim, 2. - 345 N·m (255 ft lbs)

NOTE: *Torque all rim, disk and wheel bolts as specified. Operate for 200 m (218 yds) and retorque. Repeat torque check after one hour, then at 10 hours or daily intervals until bolt torque remains constant. Check torque at 50-hour intervals thereafter.*

NOTE: *When interchanging left- and right-hand wheel assemblies, ensure the "V" of the tire tread remains pointing in the direction of forward travel.*

7. Check the front wheel toe-in and steering stops for correct adjustment.

NOTE: *(70 Series only) During a full turn, check for possible interference between the SuperSteer front tires and the tie-down brackets, 1.*



3

SECTION 44 - TWO-WHEEL DRIVE AXLE AND WHEELS

Chapter 3 - Rear Wheel Track Spacing

CONTENTS

Section	Description	Page
44 000	Specifications	2
	Special Tools	2
	Rear Wheel Track Spacing	3
	Introduction	3
	Model 8670/8670A Tractors	5
	Model 8770/8770A, 8870/8870A and 8970/8970A Tractors	6
	Rear Wheel Track Adjustment	7
	Adjusting Rear Wheels	8
	Dual Rear Wheels	10

SPECIFICATIONS


Tightening Torques

Disc to hub bolts, 1, (steel disc wheels)	800 N·m (590 ft lbs)
Disc to rim nuts, 2, (cast disc wheels)	596 N·m (440 ft lbs)
Wedge to disc bolts, 3, (cast disc wheels)	407 N·m (300 ft lbs)
Wedge to hub bolts, 4, (steel disc wheels)	407 N·m (300 ft lbs)
Dual Wheels: Wedge to hub bolts (six wedge bolts)	407 N·m (300 ft lbs)
Wedge to hub bolts (four wedge bolts)	407 N·m (300 ft lbs)
Rear weight retaining bolts	258 N·m (190 ft lbs)

After installing rear hardware, tighten to specifications using a torque multiplier or torque wrench:

NOTE: *Check the torques listed in this manual against the torque values listed in the operator's manual. Repair manual torque values should be used if there is a difference.*

NOTE: *Check hardware torque after driving the tractor for 200 m (218 yds), after 1 hour and 10 hours operation, and thereafter at the 50-hour service intervals.*




1

SPECIAL TOOLS

Description	Tool Number	Usage
Wheel adjusting tool	#NH29RT96	Move wheel assembly on the bar axle.

⚠ WARNING ⚠

Never operate the tractor with a loose wheel or rim. always tighten the bolts to the specified torque and check them frequently.



2

REAR WHEEL TRACK SPACING

INTRODUCTION

NOTE: *Read this section completely before adjusting track width.*


NOTE: *The track width dimensions (width from tire center to center) shown may vary from your actual measurements depending on specific wheel and tire combination and tire manufacturer.*

Tractors are factory equipped with either 2438 mm (96″) or optional 2844 mm (112″) rear axles. 3048 mm (120″) axles are available on the 8770/8770A, 8870/8870A and 8970/8970A tractors.

Two different diameter axle shaft and wheel styles are used as indicated in the following table:

Model	Axle Diameter	Style Wheel
8670/8670A	92 mm (3-5/8″)	Pressed steel (one piece)
8770/8770A 8870/8870A 8970/8970A	105 mm (4-1/8″)	Cast center (two piece)


Model 8670/8670A tractors are equipped with one piece pressed steel wheels, 1. All other models equipped with 710/70 tires use pressed steel wheels.



3

Models 8770/8770A, 8870/8870A and 8970/8970A tractors are equipped with steel disc wheels, 2, with a cast center, 1.

Refer to the track spacing chart that corresponds to your model and tire size.



4





REAR WHEEL TRACK SPACING

The rear wheel track spacings are shown in the following charts. Each drawing represents either a left-hand wheel viewed from the rear or a right-hand wheel viewed from the front.

At each disc to rim position, a range of track settings are available by moving the wheel assembly in or out on the axle shaft.





Spacing dimensions indicate the distance between the center points of the tire tread.

MODEL 8670/8670A TRACTORS

Track Setting Hub and Wheel Placement	Tire Size	Minimum Track Setting All	Maximum Track Setting 96″ Axle (2438 mm)	Maximum Track Setting 112″ Axle (2844 mm)
	18.4 20.8 420/80 14.9 710/70 30.5	(1524 mm) 60″ (1601 mm) 63″ (1524 mm) 60″ (1524 mm) 60″ (1727 mm) 68″ (1829 mm) 72″	(1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″	(2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″
	All tires	(1880 mm) 74″	(2134 mm) 84″	(2540 mm) 100″
	All tires	(2133 mm) 84″	(2463 mm) 97″	(2870 mm) 113″
	All tires	(2490 mm) 98″	(2718 mm) 108″	(3150 mm) 124″

5

MODEL 8770/8770A, 8870/8870A, 8970/8970A TRACTORS

Track Setting Hub and Wheel Placement	Tire Size	Minimum Track Setting All	Maximum Track Setting 96″ Axle (2438 mm)	Maximum Track Setting 112″ Axle (2844 mm)	Maximum Track Setting 120″ Axle (3048 mm)
	18.4 20.8 420/80 14.9 *710/70	(1524 mm) 60″ (1601 mm) 63″ (1524 mm) 60″ (1524 mm) 60″	(1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″ (1854 mm) 73″	(2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″ (2260 mm) 89″	(2464 mm) 97″ (2464 mm) 97″ (2464 mm) 97″ (2464 mm) 97″
	All tires	(1829 mm) 72″	(2134 mm) 84″	(2540 mm) 100″	(2743 mm) 108″
	All tires	(2083 mm) 82″	(2337 mm) 92″	(2743 mm) 108″	(2946 mm) 116″
	All tires	(2387 mm) 94″	(2642 mm) 104″	(3048 mm) 120″	(3251 mm) 128″

6


* Refer to Figure 5 for spacing. This tire is mounted on a pressed steel wheel.

REAR WHEEL TRACK ADJUSTMENT

Adjustment of track spacing is achieved by sliding the complete wheel assembly on the axle shaft and/or by changing the rim and disc position.

To reposition the wheel on the axle shaft or to completely remove the wheel, block the front wheels, front and rear, jack up the rear of the tractor until both rear wheels are off the ground. Support the rear of the tractor with blocking or stands. Position wheels with hole in the rim at the top.


Loosen the two center wedge bolts, 1, about 12 mm (1/2"). Remove the four outer wedge bolts, 2.



7

Clean the bolts and threaded holes in the wedges before lubricating and installing the outer wedge bolts at 1, for pushing the wedges. Tighten the outer wedge bolts evenly until the wedges loosen on the axle shaft. The wheel assembly will now be free to slide in or out on the axle shaft.

IMPORTANT: *Do not use a torque greater than 407 N·m (300 ft lbs) on the pusher bolts. The use of penetrating oil between the wedge and axle shaft will be of benefit. If difficulty is experienced, place a shaft protector over the end of the axle shaft and strike with a hammer to "shock" the wedge free.*




8

⚠ WARNING ⚠

Take suitable precautions, including the use of safety glasses, against the possibility of flying metal particles.

An optional wheel adjustment tool #NH29RT96 is available to move the loosened wheel in or out as required. To use the tool, slide the stepped end, 1, into the notch, 2, between the wedges. Attach the block, 3, to the axle with one of the removed wedge bolts, 4. Turn the adjusting bolt, 5, in or out to move the wheel assembly.



9

Set the wheel to the desired position on the shaft. Remove the pusher bolts and replace them in the outer holes, 2, Figure 8.

Tighten the six wedge retaining bolts in increments of 68 N·m (50 ft lbs) until a final torque of 407 N·m (300 ft lbs) is achieved.

IMPORTANT: *The wedges must be pulled tight evenly.*

Repeat the procedure on the other wheel, making sure that both rear wheels are the same distance from the ends of the axle shafts.

NOTE: *Check the torque of all six wedge retaining bolts on each wheel after driving the tractor for 200 m (218 yds), after 1 hour, and 10 hours operation and thereafter at the 50-hour service intervals.*

ADJUSTING REAR WHEELS

⚠ WARNING ⚠

Tractor wheels are very heavy. Handle with care and make sure, when stored, that they cannot fall and cause injury.

NOTE: *When changing from one track width setting to another, it may be necessary to interchange the left- and right-hand wheel assemblies. If so, be sure that the "V" of the tire tread remains pointing in the direction of forward travel.*

Rear wheel track adjustment is effected by changing the position of the disc, and/or wheel rim, relative to the rear axle.

In each position, a range of track settings may be achieved by moving the wheel assemblies in or out on the axle shafts.


To change wheel position, follow all steps outlined in "Rear Wheel Track Adjustment", in this chapter.

Adjusting Pressed Steel Wheel

After the rear axle is jacked up and blocked, remove the disc to hub bolts, 1. Using a suitable lifting device, remove the wheel and store the wheel and tire where it won't fall over. Repeat the procedure on the opposite wheel and install where the first wheel was removed.

Torque the disc to hub bolts to 800 N·m (590 ft lbs) in 68 N·m (50 ft lbs) increments using a diagonal pattern.

NOTE: *Check bolt torque after driving the tractor for 200 m (218 yds), after 1 hour, and 10 hours of operation and thereafter at the 50-hour service intervals.*



10

Adjusting Cast Center Wheel


After the rear axle is jacked up and blocked, remove the disc to rim attaching hardware, 1. Remove the wheel using a suitable lifting device and store where it won't fall. Repeat this procedure on the opposite rim and install on the first disc. If the discs, 2, are to be switched, remove wheel weights first, then position discs as required.

Reinstall the rim and weights and tighten all bolts and nuts.

Repeat the procedure on the other wheel.

Tighten the rim to disc retaining nuts uniformly in an alternate pattern, 68 N·m (50 ft lbs) at a time, until a torque of 596 N·m (440 ft lbs) for Grade 8, is obtained.

NOTE: *Check hardware torque after driving the tractor for 200 m (218 yds), after 1 hour, and 10 hours operation and thereafter at the 50-hour service intervals.*



11

DUAL REAR WHEELS

⚠ WARNING ⚠

Tractor wheels are very heavy. Handle with care and make sure, when stored, that they cannot fall and cause injury.

NOTE: *Dual rear wheels may only be installed on tractors with 2845 mm (112″) or 3048 mm (120″) rear axles.*

The outer wheel track spacing can be adjusted to a maximum of 3251 mm (128″) and the inner wheel to a minimum of 1524 mm (60″). Position the wheels on the axle to achieve the desired track spacing. See "Outer Wheels" and "Inner Wheels" in this section.

Dual rear wheels may be installed on tractors equipped with the 2845 mm (112″) or 3048 mm (120″) axle.

Figure 12 shows dual wheel configuration for the Model 8670/8670A tractor and models 8870/8870A and 8970/8970A tractors with 710/70 duals.

Figure 13 shows dual wheel configuration for Models 8770/8770A, 8870/8870A and 8970/8970A tractors.

Outer Wheels

The outer wheels, 1, are pressed steel wheels. They are bolted to extension hubs, 2, that are clamped to the axle shafts using wedges, 3, in the same manner as Model 8670/8670A pressed steel single wheels.

The hub to wedge attaching hardware can be installed in either of two positions to make removal easier depending on wheel spacing.


Option 1

Install six 76 mm (3″) long wedge to hub bolts from the wedge side as shown in 4, Figures 8 and 9. Torque bolts to 407 N·m (300 ft lbs).

Option 2


Install four 178 mm (7″) long wedge to hub bolts from the hub side as shown in 5, Figures 8 and 9. Torque bolts to 407 N·m (300 ft lbs).

IMPORTANT: *These 178 mm (7″) long bolts are included in the optional dual wheel kit available through your authorized dealer. Do not use the standard (shorter) wedge bolts.*




12

1. Wheel disc
2. Hub
3. Wedges
4. Six wedge to hub bolt position (option 1)
5. Four wedge to hub bolt position (option 2)



13

A minimum clearance of 102 mm (4") must be maintained between the sidewall of the tires measured at the closest point, 1. The tractor should be properly ballasted and the implement attached to accurately measure the tire clearance.



14

Wheel Removal/Installation
To remove the outer wheel, proceed as follows:

- Block the front wheels, front and rear, then jack up and support the rear axle.

⚠ WARNING ⚠

Before removing a wheel, make sure it is securely supported.

- Remove the ten wheel disc to hub bolts from the wheel and lower the wheel to the ground using a suitable lifting device. Repeat on the other wheel.

When reinstalling the outer wheels, torque the disc to hub bolts in an alternate pattern to 800 N·m (590 ft lbs).

Inner Wheels
The manual adjust inner wheels can be adjusted in the same way as manual adjust single wheels. However, due to interference between inner and outer tires or between the inner tires and the fenders, limited track settings may be achieved.

To adjust the inner wheels, first remove the outer wheels as described under "Outer Wheels."

Follow the instructions under "Rear Wheels Track Adjustment" in order to adjust the track width of the inner wheels.

NOTE: *Check wheel hardware torque after driving the tractor for 200 m (218 yds), after 1 hour, and 10 hours of operation and thereafter at the 50-hour service interval.*

SECTION 44 - TWO-WHEEL DRIVE AXLE AND WHEELS

Chapter 4 - Rear Wheel Removal/Replacement

CONTENTS

Section	Description	Page
44 520	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	3
	Removal	3
	Installation	5

SPECIFICATIONS


Tightening Torques

Disc to hub bolts, 1, (steel disc wheels)	800 N·m (590 ft lbs)
Disc to rim nuts, 2, (cast disc wheels)	596 N·m (440 ft lbs)
Wedge to disc bolts, 3, (cast disc wheels)	407 N·m (300 ft lbs)
Wedge to hub bolts, 4, (steel disc wheels)	407 N·m (300 ft lbs)
Dual Wheels: Wedge to hub bolts (six wedge bolts)	407 N·m (300 ft lbs)
Wedge to hub bolts (four wedge bolts)	407 N·m (300 ft lbs)
Rear weight retaining bolts	258 N·m (190 ft lbs)

After installing rear hardware, tighten to specifications using a torque multiplier or torque wrench:

NOTE: *Check the torques listed in this manual against the torque values listed in the operator's manual. Repair manual torque values should be used if there is a difference.*

NOTE: *Check hardware torque after driving the tractor for 200 m (218 yds), after 1 hour and 10 hours operation, and thereafter at the 50-hour service intervals.*




1

SPECIAL TOOLS

Description	Tool Number	Usage
Wheel adjusting tool	#NH29RT96	Move wheel assembly on the bar axle.

⚠ WARNING ⚠

Never operate the tractor with a loose wheel or rim. always tighten the bolts to the specified torque and check them frequently.



2

DESCRIPTION OF OPERATION


The rear wheels and dual wheels are attached to the rear bar axles with cast hubs and wedges. Removal of the rear wheels is required to repair the rear axle and may be advantageous to gain access to other areas of the tractor such as the hydraulic pumps.

DISASSEMBLY AND REPAIR

REMOVAL


IMPORTANT: *Prior to removing the wheel, make sure the vehicle is properly supported and the front wheels are blocked front and rear. Removal of the rear wheel weights at this time will reduce the overall weight of the assembly.*

1. Position the tractor on a level, hard surface. The surface should be hard enough to support jack stands without allowing them to sink.
2. Raise the rear of the tractor with a jack. Place heavy-duty axle stands under the tractor in an area where the tractor will be firmly supported but will not interfere with the components to be removed.
3. Position the wheel so the slot, 1, is at the top. Use the slot when a chain is used to lift the wheel.



3


4. Remove snap ring from the grove at end of axle.
5. Loosen the two center wedge bolts, 1, about 12 mm (1/2"). Remove the four outer wedge bolts, 2.



4

6. Clean the four outer wedge bolts and threaded holes in the wedges before lubricating and installing the wedge bolts at 1. These bolts will push the wedge from the hub.
7. Tighten the outer wedge bolts evenly until the wedge is loosened on the axle shaft. When loose, the wheel assembly will be free to slide out on the axle shaft.

IMPORTANT: *Do not use a torque greater than 407 N·m (300 ft lbs) on the pusher bolts. The use of penetrating oil between the wedges and axle shaft will aid removal. If difficulty is experienced in loosening the wedges, place a shaft protector over the end of the axle shaft and strike it with a hammer to shock the wedges free.*



5


⚠ WARNING ⚠

Take suitable precautions, including the use of safety glasses, against the possibility of flying metal particles.

8. Install the optional wheel adjustment tool to move the loosened wheel to the end of the axle shaft.

   To use the tool, slide the stepped end, 1, into the notch, 2, between the wedges.

   Attach the block, 3, to the axle with one of the removed wedge bolts, 4. Turn the adjusting bolt, 5, out to move the wheel assembly to the end of the axle. Then remove the adjusting tool.




6

9. Remove the wheel from the axle using a suitable lifting device.

⚠ WARNING ⚠

Tractor wheels are very heavy. use appropriate tools to lift and handle the wheels. Store the wheels so they cannot fall and cause injury.



7


INSTALLATION

IMPORTANT: *Before reinstalling the rear wheels and duals, carefully inspect the axle, inner hubs and wedges for wear and damage. Check also for damaged bolts.*

1. Install the rear wheels in the reverse order of removal.
2. Set the wheel to the desired position on the shaft, then install the center wedge bolts, 1, and the outer wedge bolts, 2.
3. Tighten the six wedge retaining bolts in increments of 68 N·m (50 ft lbs) until a final torque of 407 N·m (300 ft lbs) is achieved.

IMPORTANT: *The wedges must be pulled tight evenly.*

4. Refer to the specification section for wheel torques and frequency at which they should be checked.
5. Install snap ring in grove at end of axle.
6. Reinstall the rear wheel weights if previously removed. Torque the bolts to 258 N·m (190 ft lbs).




8

SECTION 50 - CLIMATE CONTROL

Chapter 1 - Climate Control Systems

CONTENTS

Section	Description	Page
50 000	Introduction	2
	Specifications	3
	Tightening Torques	5
	Description of Operation	6
	Air Conditioning System Components	10
	Troubleshooting and Servicing Air Conditioning System	25
	Primary Troubleshooting and Testing	27
	Diagnosis Chart	28
	A/C System Performance Test and Diagnosis Chart	37
50 000	Component Removal and Installation	54



1

INTRODUCTION

Prompted by environmental concerns, Ford New Holland is now producing equipment with non-chlorofluorocarbon (non-cfc) air-conditioning systems. The new refrigerant used is R-134a. R-134a is a hydrofluorocarbon that has no chlorine molecule, which destroys the atmosphere's ozone layer.

The prior refrigerant, R-12, is a cloroflourocarbon, which contains a chlorine atom. The 70 Series tractor air-conditioning system contains refrigerant R-134a. R-134a systems function in the same manner as R-12 except for minimal operating pressure differences and component variations.

NOTE: *Follow all local and governmental regulations regarding the handling of HFC materials before performing any work on systems using HFC compounds.*

⚠ CAUTION ⚠

This air-conditioning system uses R-134a refrigerant. Use only R-134a refrigerant and R-134a compatible lubricants in this system. R-134a and R-12 lubricants are not compatible with each other. They must be handled separately and not mixed.

Vehicles with R-134a air-conditioning components such as the 70 series tractor are distinguished from vehicles which use R-12 by an I.D. tag mounted on the vehicle chassis close to the compressor mounting location, as well as by the service ports.

SPECIFICATIONS

CAB AIR CONDITIONING SYSTEM PERFORMANCE

System Capacity BTU's	
Heating	44,000 BTU/hr.
Cooling	22,600 BTU/hr.
Cab Pressurization (high fan speed)	3/8" to 1/2" water column
Annual Refrigerant Loss	118 grams (0.26 lbs.)/ year
Maximum Centrifugal Fan Flow	400 CFM (cubic feet per minute)

ELECTRICAL

Voltage	12
Blower Motor Current Draw	
Low	3.5 amps
Medium	7.2 amps
High	12.4 amps
Compressor Clutch Current Draw	4.5 amps

REFRIGERANT

Type	HFC-134a (R-134a) ESA-M17B2-A Suva Trans A/C
Total System Capacity	2.26 kg (5.0 lbs.)

REFRIGERANT OIL

Type	PAG (Polyalkylene Glycol)
Union Carbide UCON	Refrigeration Lubricant 6290
Viscosity	505 SUS
Total System Capacity	334 cc (11.3 fl. oz.)

SYSTEM OPERATING PRESSURE

Normal System Pressure at 43° C (110° F) Ambient	
High side	16.9 bar (245 PSI)
Low side	1.0 bar (14 PSI)
High-Side Operating Range	10 to 22.4 bar (145 to 325 PSI)
Low-Side Operating Range	0.4 to 2.0 bar (6 to 30 PSI)

SYSTEM PRESSURE SWITCH SETTINGS

High/Low (binary) Pressure Switch Settings:	
High circuit opens on rising pressure	22.4 bar (325 PSI)
High circuit closes on descending pressure	15.9 bar (230 PSI)
Low circuit opens on descending pressure	1.6 bar (22.5 PSI)
Low circuit closes on rising pressure	2.8 bar (40 PSI)
Low Pressure Switch Settings (+/- 0.3 bar [5 PSI]):	
Circuit opens on descending pressure	1.0 bar (15 PSI)
Circuit closes on rising pressure	2.3 bar (35 PSI)

COMPRESSOR

Type	Sanden SD7H15 (Model KCA3BF)
Number of Cylinders	7
Bore and Stroke	29.3 mm x 32.8 mm (1.15" x 1.29")
Displacement	154.9 cc/rev. (9.5 cu.in./rev.)
Operating Speed	4000 to 6000 RPM
Continuous Maximum Permissible Speed	4000 RPM
Operating Pressures	
Maximum discharge	25.2 bar (366 PSI)
Minimum suction	0.4 bar (6 PSI)
Weight	8.07 kg (17.8 lbs.)
Lube Oil Quantity (new compressor)	270 cc (9.3 fl. oz.)

COMPRESSOR CLUTCH

Type	8V Polygroove
Magnetic Clutch Air Gap	0.25 mm-1.0 mm (0.010"-0.040")
Voltage	12
Compressor Clutch Current Draw	4.5 amps

COMPRESSOR DRIVE BELT

Type	8V Polygroove
Tensioning System	Automatic spring-loaded

RECEIVER/DRIER

High Pressure Relief Valve Opening Pressure	31 bar - 38 bar (450 PSI - 550 PSI)
Initial Oil Fill (new drier)	29.5 cc (1 fl. oz.)
Moisture Indicator Color:	
Blue	Dry (normal)
Pink	Wet (system service required)

TIGHTENING TORQUES


DESCRIPTION	WRENCH SIZE	FT LBS	N·M
Compressor Mounting Bracket Retaining Bolts	9/16"	32	43
Compressor to Mounting Bracket Retaining Bolts	9/16"	32	43
Compressor Clutch Hub Retaining Nut	14 mm	12	16
Compressor Clutch Pulley Retaining Nut	14 mm	65	88
Compressor Clutch Hub Cover Plate Retaining Screws	8 mm	6	8
Compressor Inlet (Suction) Hose Connector	1-1/16"	21-27	39
Compressor Outlet (Discharge) Hose Connector	7/8"	15-20	35
Condenser Inlet Hose Connection	3/4" & 7/8"	15-20	35
Condenser Outlet Hose Connection	3/4"	11-13	17
Receiver/Drier Mounting Bracket Retaining Bolts	13 mm	16	22
Receiver/Drier Inlet and Outlet Couplings	3/4"	11-13	17
Evaporator Housing Cover Retaining Screws	5/16"	1	1.5
Evaporator Outlet Tube to Outlet Coupling	3/4"	29	39
Expansion Valve Outlet Coupling	7/8"	21-27	34
Expansion Valve Inlet Coupling	5/8"	11-13	18
Heater Hose Retaining Clamps	5/16"	3	4
Heater Hose Retaining Clamps	5/16"	3	4
Thermostatic Switch Retaining Nut	5/16"	1.8	2.4

DESCRIPTION OF OPERATION

GENERAL

NOTE: *70 Series art shown in Figure 2.*

The function of the air climate control is to improve the operator's comfort by raising or lowering the air temperature in the cab, reducing the humidity level and removing dust and pollen from the air within the cab compartment.




2

CONTROLS


There are three operator controls for the heating system and air conditioning

1. The air-conditioning mode switch, 1, controls the activation of the air-conditioner. Depress the switch to activate the air-conditioner compressor.
2. The temperature control, 2, is used to modulate the flow of engine coolant through the heater core. It is a rotary-type control that uses a control knob and mechanical linkage that is attached to a control cable, which connects to the water valve. Rotate the knob fully clockwise for maximum heat and fully counterclockwise for less heat and for maximum cooling when the air conditioning is activated. This control is used to regulate cab temperature, regardless of whether or not the air-conditioner is activated.
3. The fan speed switch, 3, controls the blower speed which regulates air flow in the system. Power is supplied to the fan speed switch from a fused source. It then flows to the blower motor resistor, and from there to the blower motor. There are three "on" positions (low, medium and high), and no "off" position. As the fan speed switch is moved from low, medium and high speeds, the power supply is routed to different terminals on the resistor. This action, in turn, changes the amount of voltage being supplied to the blower motor, thereby controlling the operating speed. If the A/C switch is turned on, power is also provided from the fan speed switch to activate the A/C system.




3

The climate control system draws outside air in from the air intake grill on the left side of the tractor cab through the filter, across the evaporator coil and through the heater core before entering the cab through the louvered openings.




4

To provide optimum cab dehumidification and pressurization, the outside and recirculated air blend is fixed. 70% of the air is automatically recirculated.



5



6

AIR CONDITIONING PROCESS

Refrigerant is drawn into the compressor as a cool, low-pressure vapor, is compressed and then moves out as a hot, high-pressure vapor to the condenser.

As the hot, high-pressure vapor passes through the condenser core, it gives off heat to the cooler outside air being drawn past the fins by the radiator cooling fins.


The vapor is condensed to a liquid by giving off heat to the outside air. This liquid moves to the receiver/dryer under high pressure.

Hot, high-pressure liquid is stored in the receiver/dryer until it is released to the evaporator by the expansion valve.

The liquid refrigerant passes through a metered orifice in the expansion valve and into the evaporator coil. As the refrigerant passes through the orifice in the expansion valve, the refrigerant changes from a high-pressure liquid to a low-pressure atomized liquid. Then, when it reaches the evaporator coils, it begins to cool, absorbing heat from the air drawn across the coils and fins by the blower. The refrigerant now changes from a cold low-pressure liquid to a cool low-pressure vapor and leaves the evaporator outlet moving to the suction (low-pressure) side of the compressor to repeat the cycle.

As the heat loss is taking place, moisture (humidity) in the air will condense on the outside of the evaporator and drain off as water through the drain hoses attached to the evaporator drain pan, thereby reducing the humidity level of the cab. Also, dust or pollen not removed by the cab filters will collect on the wet evaporator fins and coils and will be washed off with the condensed moisture.

In summary, the heat in the cab is removed by the refrigerant in the evaporator and is transferred from the refrigerant to the outside air by the condenser unit.



7

AIR CONDITIONING SYSTEM COMPONENTS

- **A.** Heater Inlet Shut Off Valve
- **B.** Temperature Control Valve
- **C.** Expansion Valve and Evaporator
- **D.** Receiver-Drier
- **E.** Compressor and Service Ports (70 Series)
- **F.** Condensor (70 Series)
- **G.** Heater Return Shut Off Valve
- **H.** High End Compressor Service Port (70A Series)
- **I.** Low End Compressor Service Port (70A Series)

AIR CONDITIONING SYSTEM COMPONENTS

DESCRIPTION AND OPERATION

All components in an air conditioning system are connected together by hoses through which refrigerant circulates. To ensure the system cools the cab properly, each component must be in good operating condition.


COMPRESSOR

NOTE: *70 Series shown in Figure 8.*

The tractor air conditioning unit has a compressor mounted inside the engine compartment and is belt driven by the crankshaft pulley.

The compressor separates the low and high pressure sides of the system and is basically a pump which has two functions:

1. It raises the refrigerant temperature and pressure by compression.
2. As a pump to circulate the required volume of refrigerant and refrigerant oil around the system.




8

COMPRESSOR - OPERATION

The compressor has an electromagnetic clutch attached to it. The function of this clutch is to engage or disengage the compressor as required in the operation of the air conditioning system.

The clutch is of stationary coil type and forms an integral part of the compressor pulley assembly. It is belt driven from the engine crankshaft, and when energized engages the pulley assembly to the compressor.


When the clutch is de-energized, the pulley and the compressor are disengaged.



9

CONDENSER


The condenser, 2, is situated in front of the radiator, 1, and above the oil cooler, 3, on models 8670 (BSN D411682) and 8770 (BSN D408841).



10

The condenser, 1, is situated in front of the intercooler, 2, on Models 8670 (ASN D411681), 8770 (ASN D408840), and all model 8870 and 8970. The condenser consists of a number of turns of continuous coil mounted in a series of thin cooling fins to provide a maximum of heat transfer in a minimum amount of space.


The condenser receives the hot, high-pressure refrigerant vapor from the compressor. The hot vapor passes through the condenser coils. Outside air is pulled through the condenser by the engine fan. Heat moves from the hot refrigerant vapor into the cooler outside air flowing across the condenser coils and fins.



11

When the refrigerant vapor reaches the pressure and temperature that will induce a change of state, a large quantity of heat is transferred to the outside air and the refrigerant changes to a high-pressure warm liquid and moves on to the receiver/drier.


The condenser on all 70A Series tractors are at the same location as the 70 Series. The high pressure port, 1, has been relocated to the top of the condenser.



12

RECEIVER/DRIER

The receiver/drier, 1, is located on the left side of the engine and is a storage tank which receives the high pressure, warm liquid refrigerant from the condenser through an inlet line and delivers the refrigerant through an outlet line to the thermostatic expansion valve.



13


The receiver stores the liquid refrigerant to be sure a steady flow to the thermostatic expansion valve is maintained under widely different operating conditions.

The receiver/drier consists of several components:

The drier section contains a desiccant to absorb any moisture within the system and a filter prevents the entry of foreign particles.

The high-pressure relief valve provides protection for the system.

A sight glass, 1, and moisture indicator, 2, are located on top of the receiver/drier, 3, The moisture indicator is normally blue in color. It will turn pink when moisture is present.



14

NOTE: *Any moisture in the air conditioning system is extremely harmful. Moisture not absorbed by the dehydrator will circulate with the refrigerant, and droplets may collect and freeze in the thermostatic expansion valve orifice. This action will block the refrigerant flow and stop the cooling action. Moisture will also react with refrigerant R-134a to form a corrosive hydrochloric acid.*

The desiccant can only absorb a limited amount of moisture before reaching saturation point, and the ability to retain the moisture is dependent upon temperature. As the temperature increases, the ability to absorb decreases. This explains why an air conditioning system may operate satisfactorily when outside temperatures are low but stop cooling when ambient temperatures increase and the saturated desiccant releases moisture into the system.

SIGHT GLASS

The sight glass normally shows a solid column of refrigerant.

The sight glass is used to observe the condition of the refrigerant as follows:

Clouded - Desiccant is escaping from the dehydrator and circulating through the system. The dehydrator and receiver must be replaced and the system purged (refrigerant replaced).

NOTE: *At high ambient temperature, above 38° C (100° F), a cloudy sight glass does not indicate abnormal operation.*

Oil Streaks, Foam or Bubbles - Insufficient refrigerant in the system. (Occasional bubbles during initial operation is normal.)


Clear - A correct charge, an over-charge or a complete lack of refrigerant. (An over-charge is indicated when test gauge readings are above normal.)

EXPANSION VALVE

The expansion valve, 1, is located on the pressure line leading into the evaporator and performs the following functions:

1. METERING ACTION - A metered orifice changes the liquid refrigerant from a high to a low pressure.
2. MODULATING ACTION - A thermostatically controlled valve within the expansion valve body controls the volume of liquid refrigerant passing through the orifice and makes sure the refrigerant is fully vaporized within the evaporator. Liquid refrigerant can damage the compressor.
3. CONTROLLING ACTION - The valve responds to changes in the cooling requirements. When the heat load on the system increases, the valve opens to increase the refrigerant flow and, when less cooling is required (or increased compressor volume due to increased engine speed), the valve closes and decreases the refrigerant flow.

NOTE: *Access to the expansion valve will vary between the metal and plastic air conditioning housings used in the cab roof.*




15

EXPANSION VALVE - OPERATION

All of the needed temperature and pressure sensing functions are consolidated into this basic unit and no external tubes are required for these purposes.

The block, or "H" type expansion valve gets its name from the cross-sectional view of the valve.

There are two refrigerant passages which form the legs of the "H." One passage is in the high pressure refrigerant line, 7, from the receiver/dryer to the evaporator inlet. The other passage is in the low pressure refrigerant line, 4, from the evaporator to the compressor.



16

The expansion valve contains a "thinking," or master segment, which is coupled to the "slave" segment that actually accomplishes the desired action. The "master" segment is on the evaporator outlet line, where pressure and temperature are monitored. The "slave," or actual control valve, is located on the evaporator inlet line.

During manufacture of the expansion valve, refrigerant is permanently sealed in a chamber, 1, above the diaphragm, 2. A metal pin, 3, acts as an internal temperature sensing probe, and conducts evaporator outlet heat to the sealed refrigerant above the diaphragm. Evaporator outlet pressure acts on the underside, 8, of the diaphragm. Diaphragm movement is transmitted to the ball-and-spring valve, 5, via the push rod, 6.


Liquid refrigerant flow is controlled by the opposite forces of the push-rod forcing the ball off its seat and the valve spring exerting pressure on the ball to keep it on its seat.

During air conditioning "off" condition, the pressure on the bottom of the expansion valve diaphragm rises above the pressure on the top of the diaphragm, allowing the valve spring to close the valve.

When the system is started, the low-side pressure on the bottom of the diaphragm drops rapidly, allowing the valve to open and meter liquid refrigerant to the evaporator, where it begins to vaporize as it absorbs cab heat.

The compressor suction draws the vaporized refrigerant out of the evaporator, where it passes the internal temperature sensing probe. The probe conducts the reduced heat to the trapped refrigerant above the diaphragm. As the trapped refrigerant cools, the pressure, and thus the force, are reduced and the spring forces the ball, push-rod, and diaphragm upward, reducing refrigerant flow.


When heat from the cab is absorbed by the refrigerant, that heat is conducted by the internal temperature sensing probe to the trapped refrigerant above the diaphragm. As the trapped refrigerant is warmed, the pressure, and thus the force, increases. This forces the diaphragm and push-rod down, further opening the ball valve and allowing increased refrigerant flow.



17

The bottom of the pressure sensing diaphragm internally senses the evaporator outlet pressure through an internal passage. As evaporator pressure is increased, due to high refrigerant flow through the ball-and-spring valve, the diaphragm flexes upward, pulling the push-rod away from the ball seat of the expansion valve. The valve spring forces the ball toward the seat, and the liquid refrigerant flow is reduced.


As pressure is reduced, due to restricted refrigerant flow, the diaphragm flexes downward, opening the valve to provide additional refrigerant flow.



18


EVAPORATOR COIL

The evaporator is located inside the pressurizer assembly to the rear of the heater core in the roof of the cab. Like the condenser, the evaporator coil consists of numerous copper tubes mounted in a series of thin aluminum cooling fins. The fins and tubing are designed to transfer heat from the cab air to the cold refrigerant liquid as it moves through the evaporator tubing.



19

The cool refrigerant inside the tubing cools the fins on the evaporator making them colder than the cab air. Therefore, moisture in the air blown across the coil condenses on the fins. The moisture forms into droplets and drains into a tray, 1, at the bottom of the pressurizer housing and out of the cab through one of four drain tubes, 2.




20

To ensure moisture flows freely from the drip tray, drain hoses are located in the "A" pillars, 1, and "B" pillars, 2.

Dust and other airborne particles may also be trapped in the condensed moisture droplets. In this way, the A/C system dehumidifies, filters and cools the air in the vehicle cab.

NOTE: *It is very important to keep the fresh and re-circulation air filters clean and properly installed. Otherwise, the evaporator will become clogged with dust and debris which will dramatically reduce system performance.*




21

The coil temperature is controlled by the operation of the thermostatic switch, which prevents the moisture collected on the evaporator fins from freezing and possibly blocking the air flow. It is very important that the coil temperature be maintained to achieve maximum cooling without freeze-up.

HEATER CORE

The heater core is an assembly of metal tubing and fins used to exchange heat from the engine coolant to the air in the cab.

Engine coolant is pumped through the core by the engine water pump. As it passes through the core, heat energy is transferred to the cab air, being circulated by the blower motor assembly.



22

AIR CONDITIONING ELECTRICAL CONTROLS

Details on connector, fuse, and relay location can be found in Section 55 (Electrical) of the Repair Manual.

Electrical power flow through the climate control system is as follows:

The key switch is supplied with power through the MFP-2 50A fuse in the Main Fuse Panel, and the 10A key switch fuse (MDP-F26) in the Main Distribution Panel.

With the key switch in the "Accessory/Ignition" position, control power is supplied to the Auxiliary #2 Relay (MDP-R10), found in the Main Distribution Panel. The load circuit of the Auxiliary #2 Relay is powered by the 40A Main fuse MFP-6.

From the Auxiliary #2 Relay, power flows through the 25A Climate Control Fuse (MFP-F2), found in the Main Distribution Panel.

Power is delivered to the pressurizer assembly through pin 4 on the C020 connector on the right-hand side of the pressurizer assembly via wire CM245. From the connector, power flows to both the blower switch, and the load circuit of the Compressor Relay.

The blower switch is a 2-pole, meaning that it has two moving contact points, or legs. One leg supplies power to the blower motor, via a resistor assembly. Depending on the speed setting of the blower switch, power is supplied to the blower motor through two, one or no resistor windings.


The second leg of the blower switch powers the A/C Mode Switch. The A/C Mode Switch controls power to the compressor by powering the control circuit of the Compressor Relay. In the Compressor Relay control circuit, power flows from the A/C Mode Switch through the Thermostatic Switch to the coil of the relay. The relay coil circuit is completed to ground through the High/Low, and Low side, pressure switches.

Power is delivered from the Compressor Relay to the clutch by way of connectors C020 Pin 7, C005 Pin 7, C008 Pin D, and C100 via wires CM244, RM244, and FM244.

BLOWER FAN

The blower fan, 1, is located ahead of the heater core, 2, and evaporator, 3, and draws air across the outside and recirculation filters, evaporator coil and heater core. The conditioned air is then blown through the louver outlets and into the cab. The blower motor is controlled by a three-speed switch.


The blower always runs (low speed minimum) with the key switch on, so that cab pressure is always maintained.



23


AIR FILTRATION

There are two air filters on the climate control system. The fresh air filter, 1, is a paper element, located under the cab roof on the left-hand side.



24


The recirculation filter, 1, is a foam element, located in the cab headliner, above the operator's area.



25

AIR-CONDITIONER THERMOSTATIC CONTROL SWITCH

The thermostatic switch, 1, consists of a bellows-type thermostat and capillary sensor tube, 2, filled with refrigerant. The bellows are attached to a frame which pivots to open or close a set of contact points. The capillary tube is inserted about five inches deep into the evaporator coil, 3, between the fins and tubing.



26


The thermostatic switch controls the electrical circuit that supplies power to the compressor clutch. It has a fixed operating range, and will automatically open and close in order to maintain the evaporator coil temperature between 0° C - 3° C (32° F- 38° F).

It maintains the evaporator coil temperature by cycling the compressor clutch off and on, thereby controlling the flow of refrigerant through the A/C system. When the evaporator has a change in temperature (either warmer or cooler), the refrigerant in the thermostatic capillary tube will expand or contract. This causes the switch points to open or close, controlling the operation of the compressor clutch. The capillary tube is inserted into the evaporator core, in such a manner that it senses the temperature of the evaporator core. Because the temperature of the refrigerant in the tube directly affects the pressure in the capillary tube a pressure signal is sent to the thermostatic switch.

When the evaporator coil cools down sufficiently, a pressure signal from the capillary tube acts to trip the thermostatic switch and shuts the power off to the compressor clutch. For a period of time, the compressor remains idle and the refrigerant flow stops. When this occurs, the evaporator core warms up and causes the capillary tube to detect this new (higher) temperature. Again the pressure signal sent to the thermostatic switch by the capillary tube trips the switch to activate the compressor clutch. This cycling of the compressor clutch will continue throughout the operation of the air conditioning system.

BLOWER MOTOR RESISTOR

The blower motor resistor, 1, regulates power from the fan speed switch to the blower motor assembly and acts as a voltage dropping device.




27

RELAY SWITCH

The relay, 1, is installed in the electrical circuit and provides low current flow through all electrical switches in the system by supplying high amperage current directly to the compressor as it is engaged.

NOTE: *The mounting and location of the relay switch will vary between the metal and plastic air conditioning housings used in the cab roof.*



28

HIGH/LOW-PRESSURE CUTOUT SWITCH

NOTE: *70 Series art shown in Figure 29.*

The binary pressure cutout switch, 1, and low-pressure cutout switch, 2, are located respectively on the #6 high inlet and #12 low outlet pressure hose fitting at the expansion valve.

The binary pressure cutout switch monitors the operating pressures on the (liquid) high-pressure side of the A/C system. The primary function of this switch is to prevent the compressor from operating under the following conditions:


1. The pressure on the high side exceeds the pre-set operating limits.
2. The pressure on the high side is below the pre-set limits (i.e., a loss of refrigerant, or low ambient temperature).

When either of the above conditions occur, the switch automatically opens the electrical contacts in the switch and the circuit to the clutch. The switch is non-adjustable and opens at 22.4 bar (325 PSI).

The purpose of the low-pressure cutout switch is to prevent the compressor clutch from engaging if the system pressure is too low.

This switch is responsible for monitoring the operating pressures on the low-pressure side. If the pressures drop below the preset operating range, it opens the electrical circuit to the clutch. When the pressure rises back up to the preset value, it closes the electrical circuit and cycles the clutch. The switch is non-adjustable and opens at 1.0 bar (15 PSI). See "Specifications" later in this chapter for additional pressure switch settings.

On the 70A Series, to increase the length of the air conditioning "ON" cycle time, the low pressure switch, 2, in the roof has been eliminated. The binary low and high pressure switch remains in the roof.



29


WATER VALVE

The water valve, 1, is mounted on the heater core though a connecting hose at the inlet of the heater core.

The purpose of the water valve is to control the flow of engine coolant into the heater core. This is accomplished by adjusting the temperature control knob that is mechanically attached to the water valve via the control cable. The flow of coolant is modulated as the temperature control knob is moved from the hot to cold position.

The operation of the water valve is important in both the heater and air conditioning modes. In the A/C mode, it is opened or closed allowing coolant to flow through the heater core, thereby warming the air exiting the evaporator core. If it becomes too cold, this is controlled by the operator, who will adjust the temperature control knob to achieve the desired temperature.


NOTE: *It is very important that the water valve be closed and operating properly when maximum A/C system performance is required.*



30

ENGINE COOLANT SHUTOFF VALVES


The engine coolant shutoff valves are located on the right-hand side of the engine. The heater inlet (hot), 1, is located between ports 5 and 6 of the intake manifold.



31

The heater return (cool), 1, is located behind the thermostat housing at the front of the engine.

The purpose or the shutoff valves are to shut off the flow of coolant from the engine block. This is necessary when servicing the heater components to prevent losing coolant from the engine.




32

LUBRICANTS

The refrigerant R-134a and the lubricant used with it were developed as a system. R-134a uses a lubricant made from polyalkylene glycol (PAG). This lubricant is **NOT** compatible with the mineral oil used with R-12. R-134a mixed with the mineral oil used in an R-12 system will cause the mineral oil to become chemically unstable.

Likewise, the hoses, bearing shaft seals, and O rings used in R-12 systems are not compatible with lubricants used in this system. Hardening, swelling or cracking of these rubber parts when used with incompatible lubricants will also lead to early failure of the system.

The lubricants used with R-134a are far more aggressive to rubber parts than the mineral oils. When servicing this air conditioning system, be certain that the rubber parts you are installing are approved for use with R-134a and its oil.



70-610-1188


33

REFRIGERANT - R-134A

To achieve the absorption and the release of heat which is, in essence, the function of an air conditioning system, requires the use of a suitable "refrigerant" - a liquid that has a relatively low temperature boiling point, plus certain desirable safety and stability features.

⚠ WARNING ⚠

Be sure to use the correct and dedicated equipment for testing and working on this system containing R-134A. Read and understand all of the following information before continuing or working on this system.



70-610-1189

34

TROUBLESHOOTING AND SERVICING AIR CONDITIONING SYSTEM

GENERAL SAFETY AND SERVICE PRECAUTIONS

All refrigerants have potentially dangerous physical and chemical properties. All refrigerants are stored under relatively high pressure as a liquid, and all of them are chemicals which can be harmful or fatal if not treated properly. When not used as directed you could be exposed to physical injury, frostbite, blindness, possible poisoning and/or death by asphyxiation, or cardiac arrest. In addition, some of the new refrigerants including R-134a have been found to be flammable under certain conditions.

The following safety warnings are generally recognized as minimum precautions that must be observed when servicing air conditioning systems.

1. Read, understand, and follow the instructions provided by the manufacturer of all the service equipment with which you will be working and operation of the tractor.
2. Wear safety goggles at all times when servicing an air conditioning system, extraction or recycling equipment, or otherwise handling refrigerant. Liquid splashed in the eye can cause frostbite and/or irritation.

   Wear appropriate rubber gloves and other protective clothing. Extreme care should be used when handling R-134a in order to prevent contact with skin and other body parts. This is to prevent freezing of body tissues. Liquid R-134a boils at -18° C to -11° C (0° F to 12° F). Read and follow the information in the material safety data sheet provided by your refrigerant supplier regarding the proper handling of refrigerant.

⚠ CAUTION ⚠

Avoid breathing A/C refrigerant and lubricant vapor or mist. Exposure may irritate eyes, nose, and throat. To remove R-134A from the A/C system, use service equipment certified to meet the requirements of SAE J2210 (R-134A recycling equipment). If accidental system discharge occurs, ventilate work area before resuming service. Additional health and safety information may be obtained from refrigerant and lubricant manufacturers.

3. Never mix R-134a with air for leak testing. In general, it should not be used or allowed to be present with high concentrations of air above atmospheric pressure. It has been determined that pressurized, air rich mixtures of R-134a and air can undergo combustion when exposed to an ignition source.
4. Never perform operations other than routine maintenance on your extraction or recycling equipment without first consulting the manufacturers' authorized personnel. Removal of fittings and filters can cause refrigerant under pressure to escape. Use the proper safety equipment, including safety goggles.
5. Never service or maintain extraction or recycling equipment while it is plugged in unless proper service procedures direct you to do so.
6. Always transfer refrigerant to cylinders or tanks specifically approved for refilling by the U.S. Department of Transportation. The designations "DOT 4BW" or "DOT 4BA" indicate such approval. Use no other containers.
7. Never overfill a refrigerant container. There must be vapor space left in the cylinder in order to accommodate temperature-induced changes in pressure and liquid volume. SAE recommends filling tanks for shop use with liquid to no more than 60% of their gross weight rating.
8. Ensure that containers are never heated to over 52° C (125° F). Even a correctly filled container becomes an explosive hazard if its temperature exceeds 52° C (125° F).
9. Recycling equipment may create sparks or arcs in internal switches or other systems. Because of the fire and explosive hazard that may be present, always use recycling equipment in locations with forced ventilation having at least four air changes per hour.
10. Extension cords are a known cause of fires and equipment malfunction. Their use is not recommended. In circumstances where their use is unavoidable, the shortest cord with 14 gauge or larger conductors must be used. If your service equipment requires a ground circuit (third prong), make sure that the extension cord is so equipped and that the ground circuit is intact. Avoid cords that are worn, frayed, or otherwise damaged.
11. Perform work in well-ventilated areas. Some refrigerants can accumulate in low areas such as service pits. Breathing concentrated refrigerant vapors could result in asphyxiation or other health hazards, including cardiac arrest.

CLEANLINESS

Many failures in all types of systems can be traced to dirt. The cleaner your work, the longer your customers' systems will last, and the less need there will be for maintenance operations that will potentially release refrigerant into the atmosphere.

Dirt, even microscopic particles, in hose connections can create enough clearance for the refrigerant to escape.

PRIMARY TROUBLESHOOTING AND TESTING

The most important factor in heater air conditioning troubleshooting is verification of the problem by observing the system operation and isolating the problem area.

Operational Checks - Heating

1. Check that both engine coolant shutoff valves at the engine block are open.
2. Check that the heater inlet hose at the rear of the engine block is warm.
3. Check that the engine coolant temperature is at least 76° C (170° F), indicated by at least 6 bars displayed on the instrument cluster.
4. Check the cab air filter to check that it is clean and free from obstruction to air flow.
5. Check the recirculation filter to see that it is clean and free from obstruction to air flow.

Operational Checks - A/C

First start the engine and set the throttle at 1500 RPMs. Run the engine for ten minutes with the air conditioner set at maximum cooling and the blower on high speed.

1. Check to make sure that the A/C mode switch is pushed in, the temperature control knob is on cold, and the blower is on full.
2. Check that the air conditioning systems are operating, such as:

   Compressor clutch engages when the A/C mode switch is pushed from"OFF" to "ON" position.

   Engine cooling fan is operating at full speed.

   Blower fan is operating at all speeds.
3. Check the compressor drive belt for slippage.
4. Check the cab air filter to ensure it is clean and free from obstruction to air flow.
5. Check the evaporator fins. Be sure they are not plugged or excessively dirty causing insufficient air flow across the evaporator coil.
6. Check the recirculation filter to ensure that it is clean and free from obstruction to air flow.
7. Check the condenser core to ensure it is clean and free from obstruction to air flow.

NOTE: *If the compressor clutch fails to engage by operating the air conditioning mode switch when the engine is first started, it may indicate an electrical problem or a malfunction of the electric drive clutch on the compressor. Review the electrical diagram in this section for proper diagnosis.*

If the compressor clutch engages but cuts out prematurely, the system may be either very low on refrigerant charge or have a malfunction of the expansion valve causing the low-pressure and high pressure switches to operate. Troubleshoot the system by conducting the System Performance Tests described later in this section.


DIAGNOSIS CHART

PROBLEM	POSSIBLE CAUSE	CORRECTION
No Cooling	A/C mode switch not on.	Turn mode switch on.
	Temperature control switch not rotated fully counter-clockwise towards the blue index.	Rotate temperature control counterclockwise.
	Loose or broken compressor drive belt.	Check belt and tension. Replace as required.
	Loss of refrigerant.	Check sight glass. Recharge and test.
	Compressor clutch does not engage.	Perform electrical checks - Refer to electrical part of this Section. Defective clutch - Overhaul clutch.
	Insufficient air flow through evaporator.	Check air filter. Check evaporator core and clean if required. Check blower motor operation. Defective blower fans.
	Faulty expansion valve operation.	Conduct "System Performance Test" - replace as needed.
	Faulty compressor.	Conduct "System Performance Test" - repair as needed.
Insufficient Cooling	Dirty evaporator coil and/or filter.	Visual inspection - clean.
	Temperature control switch not rotated fully counter-clockwise towards the blue index.	Rotate Temperature switch counterclockwise.
	Dirty condenser core.	Visual inspection - clean.
	Low refrigerant charge.	Visual inspection of sight glass and perform system tests - recharge.
	Water valve partially open.	Visual inspection.
	Compressor drive belt slipping.	Visual inspection - replace or adjust as needed.
	Evaporator icing up.	Perform system tests.

PROBLEM	POSSIBLE CAUSE	CORRECTION
Insufficient Cooling (Cont'd)	Faulty thermostatic switch.	Visual inspection of capillary tube to outlet tube. Perform system tests - replace if needed.
	Faulty expansion valve.	Visual inspection of capillary tube to outlet tube. Perform system tests - replace if needed.
	Faulty blower fan.	Visual inspection of fan rotor and fastening to motor shaft. Repair or replace.
	Plugged or restricted receiver/drier.	Perform system tests - replace if needed.
	Moisture in the system.	Visually inspect moisture indicator on receiver/drier Perform system tests - evacuate and recharge. Replace receiver/drier
	Faulty compressor.	Perform system tests - overhaul if needed.
Noisy System	Loose panel in cab plenum.	Visual inspection.
	Faulty compressor clutch.	Replace Clutch Assembly
	Noise in compressor.	Replace Compressor
	Excessive charge in system.	Perform system test and adjust charge.

TEST PROCEDURE - STABILIZING THE SYSTEM

NOTE: *70 Series art shown in Figure 35.*



35

Test Ports

On the 70 Series tractor, the test ports are located on the high- and low-pressure hoses where they connect to the compressor. On the 70A Series tractors, the high pressure test port is located on the high pressure hose where it connects to the condenser. The low pressure test port is located on the low pressure hose where it connects to the compressor. The fittings conform to SAE J2197 standards.

After the manifold gauge set has been connected and before pressure tests can be made, the system must be stabilized as follows:

1. Set the parking brake, be sure the Powershift lever is in neutral, start the engine and close the cab windows and doors.
2. Start the engine and run at fast idle speed (approximately 1000 - 1200 RPM).
3. Make sure the A/C mode switch is on.
4. Operate the system at maximum cooling, with the blower fan at high speed, for 10 minutes to stabilize all components.
5. Check that the manifold low-pressure gauge reading is within the specified range of approximately 0.28 - 2.48 bar (4 - 36 PSI).
6. Check the manifold high-pressure gauge reading and compare the reading to the pressure indicated on the following pressure temperature charts.

PRESSURE/TEMPERATURE RELATIONSHIPS

Ambient Temperature		High-Pressure Gauge Reading	High-Pressure Gauge Reading	Low-Pressure Gauge Reading	Low-Pressure Gauge Reading
°F	°C	PSI	bar	PSI	bar
70	21	114 -- 134	7.86 -- 9.24	3.0 -- 4.2	0.21 -- 0.29
75	24	126 -- 146	8.68 --10.07	3.6 -- 4.8	0.25 -- 0.33
80	26	141 -- 161	9.72 --11.10	4.8 -- 6.0	0.33 -- 0.41
85	29.5	159 -- 179	10.96 --12.34	5.3 -- 6.5	0.37 -- 0.45
90	32	179 -- 199	12.34 --13.72	6.1 -- 7.3	0.42 -- 0.50
95	35	186 -- 206	12.82 --14.20	7.5 -- 8.7	0.52 -- 0.60
100	38	209 -- 229	14.41 --15.79	8.1 -- 9.3	0.56 -- 0.64
105	40.5	227 -- 247	15.65 --17.03	9.3 --10.5	0.64 -- 0.72
110	43	260 -- 280	17.93 --19.31	12.0 --13.2	0.83 -- 0.91
115	46	297 -- 317	20.48 --21.86	15.1 --16.3	1.04 -- 1.12
120	49	341 -- 361	23.51 --24.89	16.9 --18.1	1.17 -- 1.25

CHECK FOR LEAKS FIRST

The A/C system should not leak. "Topping off" a leaky air conditioning system perpetuates the escape of refrigerant to the atmosphere. The proper service procedure is to locate and then correct the leak before putting any refrigerant into the system.

IMPORTANT:

- *Any refrigerant introduced into the system for the purpose of finding leaks must also be recovered from the system.*
- *Always use the same type of refrigerant for checking leaks as was originally installed. On the 70 Series tractor use R-134a.*
- *Never use compressed air to detect system leaks. The introduction of air into the system may create a fire or explosion hazard, may overload the desiccant with moisture, and could contaminate the system with dirt and improper oil.*

A small amount of refrigerant leakage is normal. Much of the normal leakage comes from the slow seepage of refrigerant through the flexible hoses. Other common sources of leaks are at joints between the flexible hose and metal tubing or at threaded hose connections. These are usually much larger leaks than the natural seepage through the walls of the hose and are almost always repairable. When servicing them it is important that leakage be minimized.

Be certain to use an electronic leak detector, Tool # OEM 1486 or equivalent, for detecting R-134a.

REFILLING

Refilling the air conditioning system must be done by the weight method. The lubricants used in R-134a tend to layer onto the walls of the refrigeration system. This layering obscures the view through the sight glass. Visual methods of refilling R-134a systems will result in improper system charging. For this reason, the old practice of "topping off" a partially discharged air conditioning system using the sight glass is no longer recommended. The 70 Series tractors air conditioning system has a capacity of 2.27 kg (5.0 lbs) of R-134a refrigerant.

CONTAMINANTS

No mobile air conditioning system can operate for long without picking up some contaminants in the refrigerant. The flexible hoses, for example, allow moisture and air to migrate into the refrigerant from the outside atmosphere. Moisture and non-condensable gasses (air) are the most common contaminants found in mobile air conditioning systems.

Lubricant and refrigerant that remains in service equipment can be a contaminant. The lubricant may have absorbed some refrigerant, moisture and air that has migrated into the air conditioning system. Some of the lubricant is captured by and carried along with the refrigerant. When you recover a refrigerant, a certain amount of lubricant will be captured by the extraction or recovery equipment as well. This lubricant will be drained into a catch bottle or reservoir for measurement and proper final disposal.

Lubricant that has come out of an air conditioning system should never be reused. Re-using this oil may result in contamination of the air conditioning system with the refrigerant, moisture and air that has been temporarily absorbed into the oil. Instead the A/C system should be refilled with the same amount of correct fresh oil that was removed in the service operation. The used oils must be disposed of in a manner which complies with federal, state and local disposal requirements.

To avoid contamination between systems using dissimilar refrigerant, service equipment MUST be dedicated to a single refrigerant.

PREVENT MIXING OF SERVICE EQUIPMENT

Refrigerants must not be mixed. For this reason, service fittings are different for refrigerants R-12 and R-134a. Systems using R-134a have quick couple service connections while R-12 systems use screw threads. The intent of this is to prevent the use of the same tools for different refrigerants, thereby avoiding mixing of refrigerants in the service equipment.

Incompatible lubricants and other contaminants can be left behind on air conditioning service manifolds, gauges, hoses and fittings. Even small amounts of refrigerant and lubricant left behind can be harmful to the performance and durability of a system designed to use another refrigerant.

If refrigerants are mixed the thermodynamic and chemical characteristics will change resulting in excessive pressure and poor lubrication, leading to failure of the compressor, desiccant and other system components. Mixtures of R-12 and R-134a can result in a 25% over pressure resulting in system failure

To help avoid a mix-up of service equipment and refrigerants, equipment hoses designed for use with each refrigerant is easily identified. New service hoses compatible with R-12 will carry the designation "SAE J2196". Service hoses used with R-134a must have a black stripe along the entire hose length and carry the designation "SAE J 2196/R-134a."

REFRIGERANT RECOVERY AND RECYCLING EQUIPMENT

Both "recovery" and "recycling" equipment are in use and available to service technicians. Both types of equipment will remove the refrigerant from an air conditioning system. However, recovery equipment only pulls the refrigerant from the air conditioning system and stores it in an appropriate container. Recovery equipment does not clean the refrigerant. Its only purpose is to recover the refrigerant from an air conditioning system prior to disassembling and servicing it.

It is important that recovered refrigerant is recycled or reclaimed before it is put back into an air conditioning system. During service operations involving a partial recharge or while the A/C system is in use, refrigerant can pick up moisture, lubricants, microscopic metal chips, and other potential contaminants. In many cases, these contaminants contribute to or are the primary cause of the system failure. To put used uncleaned refrigerant back into an air conditioning system may well result in poor system performance. Re-use of refrigerant that has not been recycled or reclaimed will void the warranty.

Equipment that removes refrigerant from a mobile air conditioning system (usually called "recovery" equipment) may allow the service technician to put the used refrigerant back into the system without first cleaning it to minimize performance.

If you want to remove, clean, and reuse R-134a refrigerant at your shop, you must use a machine that both extracts and recycles refrigerant from mobile air-conditioning systems and dedicate that machine to be used only with R-134a.

Recycling equipment meeting SAE standards J1990 and J2210 is designed to extract and recycle refrigerants that have been in a mobile air conditioning system only. R-134a refrigerant can also be used in a non-mobile air conditioning system or refrigeration system. Non-mobile systems may introduce contaminants to the refrigerant that equipment meeting SAE J1990 and J2210 cannot remove. This equipment is not intended to deal with non-mobile systems.

USING RECOVERY EQUIPMENT

Recovery equipment is relatively small and easily portable. It is best used in situations where a shop must service vehicles such as agricultural or off-highway equipment that cannot easily be brought into a shop. It is also convenient for shops that must deal with a variety of different refrigerant types and exchange recovered refrigerant for reclaimed refrigerant at some central location.

Recovery equipment must be used for those refrigerants for which it was designed. The lubricants, hoses and seals in this equipment have been designed to work with only one refrigerant.

USING RECYCLING EQUIPMENT

Recycling equipment is defined as equipment that both extracts and removes common contaminants from refrigerants. Recycling equipment designed and certified to meet SAE standards can make refrigerant recovery from mobile air-conditioning systems suitable for reuse in automotive A/C systems. Like recovery equipment, SAE standards require that each piece of recycling equipment be dedicated to a single refrigerant.

Note that only equipment capable of recovering and cleaning R-134a to meet SAE J2099 purity levels can be certified as meeting SAE standards. Recycling equipment capable of purifying R-134a to SAE J2099 purity levels will carry a label which contains the phrase "Design certified by Underwriters Laboratories, Inc. for compliance with SAE J2099." Note that the Underwriters Laboratories label which certifies that the machine is free of reasonable shock or other safety hazards to the user is NOT an indication of compliance with SAE standards. The UL label must specifically state that the machine is "designed certified" to the applicable SAE standard.

RECYCLED VERSUS RECLAIMING

Recycled refrigerant is refrigerant that has been recovered from a mobile air conditioning system and which is cleaned to meet J2099 for R-134a by the same shop that recovered it. The equipment designed to recycle refrigerant in the shop environment is intended to remove only those types of contaminants that are picked up during the operation of a mobile air conditioning system.

Reclaimed refrigerant has been recovered from a variety of different shops and possibly even different types of air conditioning systems, and has then been reprocessed to the same standards of purity as virgin refrigerant. Reclamation to such standards of purity requires equipment that is normally not affordable by an average shop. Hence, reclamation of refrigerant is usually done by independent companies established for that purpose.

The following is intended as a guide to servicing mobile air conditioning systems in a way that minimizes the potential for losing refrigerant to the atmosphere. Following the procedures in this section will help you ensure compliance with SAE J2211 for R-134a systems.

⚠ CAUTION ⚠

Fire or explosion hazard exists with R-134A under certain conditions. R-134A has been shown to be nonflammable at ambient temperature and atmospheric pressure. However, tests under controlled conditions have indicated that, at pressures above atmospheric and with air concentrations greater than 60% by volume, R-134A can form combustible mixtures. While it is recognized that an ignition source is also required for combustion to occur, the presence of combustible mixtures is a potentially dangerous situation and should be avoided.

R-134A service equipment or vehicle A/C systems should not be pressure tested or leak tested with compressed air. Some mixtures of air/R-134A have been known to be combustible at elevated pressures. These mixtures are potentially dangerous and may result in fire or explosion causing injury or property damage. Additional health and safety information may be obtained from refrigerant and lubricant manufacturers.

REFRIGERANT RECOVERY PROCEDURE

1. Ensure that all service equipment hose lines are fitted with shutoff valves or check valves within 30 cm (12") of their ends. This will ensure that only minimal quantities of refrigerant escape to the atmosphere when the equipment is disconnected from the A/C system, and that only small amounts of moisture and other contaminants can enter the system.
2. Be sure that all equipment including the connecting hose lines and manifold are compatible with the refrigerant in the system with which you are going to work, and that your equipment has been previously used only with the refrigerant you are about to recover.
3. Be sure that all shutoff valves are tight before connecting them to the A/C system.

⚠ CAUTION ⚠

Shutoff valves should be closed at all times unless they are connected to a vehicle's A/C system, a refrigerant storage container, or another piece of service equipment containing the same refrigerant. this prevents refrigerant from escaping into the atmosphere, damaging the environment and contaminating the equipment.

4. Connect the extraction or recovery equipment to the A/C system in accordance with the instructions supplied by the equipment manufacturer.
5. Start the recovery process by turning on the recovery equipment and extracting the refrigerant from the A/C system in accordance with the equipment manufacturer's instructions.
6. Continue to extract refrigerant until the A/C system has been brought under a vacuum and there is no refrigerant remaining in the vehicle system.
7. Verify that there is no refrigerant remaining in the system by:
   a. Shutting off the recovery unit and observing the system pressure level.
   b. Waiting five minutes and observing the system pressure again. If the system pressure has not risen above atmospheric pressure (0 gauge pressure), all the refrigerant has been removed and you may proceed to step 8.

      If, after five minutes, the system pressure reading has risen above atmospheric pressure (0 gauge pressure), the extraction/recovery process must be repeated until the pressure reading remains at or below atmospheric for at least two minutes with the recovery equipment shut off before proceeding to step 8.
8. Close the shutoff valves in the service lines.
9. Remove the service lines from the vehicle system. If the recovery equipment has automatic closing shutoff valves, verify that they are operating properly and do not leak.
10. Determine the amount of lubricant removed from the A/C system during the refrigerant recovery process. Replenish the A/C system with an equal volume of new, correct lubricant.

    Dispose of the used lubricant in accordance with applicable federal, state and local requirements.
11. The system is now ready to be serviced or repaired.

FLUSHING

Some service or repair operations have been flushing A/C systems to remove dirt or other debris. It has been common practice to use another CFC, usually R-11, for this purpose. The Clean Air Act prohibits the use of any CFC for such a purpose where the CFC may be released into the atmosphere. Methychloroform, a popular flushing agent, is also prohibited.

⚠ CAUTION ⚠

Flushing should never be done with shop or other compressed air. certain mixtures of air and R-134A are combustible. The use of air to flush R-134A systems could result in combustion. Shop air also contains moisture which would contaminate the system.

IMPORTANT: *Never use CFC-11, R-11, CFC-12, R-12, CFC-113, R-13 or any substance to flush an R-134a system. To do so would result in breakdown of the lubricant and system corrosion.*

Use of other flushing solvents may cause other problems. If a vacuum pump does not remove the solvent, it could affect the chemical stability of the refrigerant and lubricant.

Flushing the system is not recommended. In the event of a major compressor failure replacing the compressor output pressure line and receiver/drier should collect most of the debris.

RECHARGE/REFILLING

Recharge the system only with the proper virgin refrigerant or recycled refrigerant purified to meet SAE purity standard (J2099 for R-134a). Use the weight method to determine the proper amount of refrigerant. Tractor uses 2.27 kg (5.0 lbs.) of R-134a refrigerant.

USE OF A MANIFOLD GAUGE SET

When using a manifold gauge set to diagnose, recharge or service the tractor air conditioning system.

1. Ensure that all equipment hose lines are fitted with shutoff valves or check valves within 30 cm (12″) of their ends and that the valves are closed. This will ensure that only minimal quantities of refrigerants escape to the atmosphere, and that only small amounts of moisture and other contaminants can enter the system.
2. Be sure that all equipment including the connecting hose lines and manifolds are:
   - Compatible with the refrigerant in the A/C system.
   - Free of all contaminants.
   - Used only for the same type of refrigerant in the system.
3. Be certain that all shutoff valves are shut tight before connecting them to the A/C system or charging source.
4. Connect the manifold gauge set to the unit according to the instructions supplied by the gauge set manufacturer.
5. Perform the desired diagnostic and service operation.
6. Close the shutoff valves on the service hoses.
7. Disconnect the hoses from the system.

NOTE: *When the manifold gauge set is disconnected from the air conditioning system and you want to empty it of refrigerant, or when the center hose is to be moved to another device which cannot accept refrigerant pressure, the hoses should be attached to recovery equipment or recycling equipment to remove the refrigerant, lubricant and contaminants from the hoses.*

CHECKING REFRIGERANT FOR EXCESS AIR

At times you may question whether or not a container of refrigerant has been recycled. One check which can be done in the shop is to determine if there is excess air mixed in with the refrigerant. This check is a simple comparison of the container pressure with theoretical pressure at a known temperature. If the pressure is equal to or less than a theoretical value established for R-134a of usable purity, the contents of the container does not contain excess air.

IMPORTANT: *Using R-134a with excess air will result in higher system operating pressures and may cause damage to the A/C system.*


This check can be done in the following manner:

1. Store the container for at least 12 hours at a known temperature of 18.3° C (65° F), or higher. The container must not be in direct sunlight or under the influence of any other direct source of heat.

   Carry out all the next steps in the same area in which the container has been stored, as it is very important that the temperature of the container is stable.
2. Attach an appropriate pressure gauge to the container. This pressure gauge should read in increments of 6.9 kpa (1 PSI).
3. Use a calibrated thermometer to measure the air temperature within 100 mm (4″) of the container surface.

4. Use this table for R-134a to compare the pressure in the container with the pressure shown for the temperature of the tank. If the pressure in the container is equal to or less than the pressure in the table, the refrigerant in the container meets the requirements for excess air.

Temperature vs. Pressure Chart



If the pressure is greater than shown in the table, you may still be able to use it by proceeding to step 5.

5. If the pressure exceeds that of the table, connect the tank to recovery or recycling equipment in such a way as to allow you to continue to monitor tank pressure.
6. Bleed a small amount of vapor from the tank into the recovery or recycling equipment until the tank pressure is below that shown in the table for the temperature at which the tank was stored. Close the shutoff valves in the recovery/recycling equipment service hose.

NOTE: *This process may cause the temperature of the tank to drop.*

7. Allow the tank temperature to re-stabilize at the temperature of the storage room by shaking it and allowing it to sit in the same spot for up to another 12 hours.
8. After making certain that container temperature has again stabilized to room temperature, repeat step 4 above.

If the pressure exceeds that in the table for the storage temperature you measured, the refrigerant in the tank has too much excess air to be used and must be recycled or reclaimed.

If the refrigerant being checked has been contaminated with other refrigerant, such as R-12, the tank pressure may indicate it contains air. If the tank is vented and the pressures still indicate a high reading, and you think there is a possibility of the R-134a refrigerant being contaminated with R-12, the container must be sent to a reclaim facility.

CONTAINERS FOR THE STORAGE OF RECYCLED REFRIGERANT

Recycled refrigerant must be stored only in DOT CFR Title 49 or UL containers approved for such use. The container must be specifically marked for the refrigerant type you are storing. The use of unmarked containers must be avoided as it can lead to mixing of refrigerants and consequent A/C system failure.

Disposable refrigerant containers should not be used for the storage or recovery of used or recycled refrigerant. Disposable containers are the type of containers in which virgin refrigerant is often sold.

Any container of recycled refrigerant that has been stored or transferred must be checked prior to its use in accordance with the temperature/pressure check described in the previous paragraphs, "Checking Refrigerant for Excess Air."

New storage tanks must be evacuated to at least 635 mm (25") of mercury prior to use. Otherwise, excess air may be introduced to the refrigerant.

TRANSFER OF REFRIGERANT

To transfer refrigerant in portable containers, you must make sure that:

1. The container meets DOT CFR Title 49 requirements and is UL-approved for such use.
2. The container is free of contaminants and air.
3. Container filling operations are controlled by weight. In the shop, containers must be filled **NO MORE THAN 60%** of their gross weight rating. This will prevent overfilling and possible explosion if the container is exposed to higher temperatures.

DISPOSAL OF EMPTY OR NEAR EMPTY DISPOSABLE CONTAINERS

Improper scrapping of disposable containers can release some refrigerant into the atmosphere. This must be avoided by removing any of the remaining contents with a recovers or recycling machine as follows.

1. Attach the service hose of your recovery or recycling machine to the container.
2. Open the container valve and the recovery/recycling equipment shutoff valve and evacuate the container just as you would a mobile air conditioning system.
3. When the maximum stable vacuum has been achieved, close the container valve and the service hoses valves, allowing the vacuum to be in the container.
4. Mark the container "empty" and dispose of it properly.

APPLICABLE SAE STANDARDS

J639 Safety and containment of refrigerant for mechanical vapor compression systems used for mobile air conditioning systems.

J1989 Recommended service procedure for the containment of R-12.

J1991 Standard of purity for use in mobile air conditioning systems.

J2099 Standard of purity for recycled R-134a for use in a mobile air conditioning system.

J2196 Service hose for automotive air conditioning.

J2197 R-134a service hose fittings for automotive air conditioning service equipment.

J2211 Recommended service procedure for the containment of R -134a.

J2219 Committee draft: Concern to the mobile air conditioning industry.

RELATED SAE STANDARDS:

J1990 Recovery and recycle equipment for mobile air conditioning systems.

J2209 R-12 recovery equipment for mobile air conditioning systems.

J2210 R-134a recycling equipment for mobile air conditioning systems.

These and other SAE standards may be obtained from:

SAE Customer Service
400 Commonwealth Drive
Warrendale, Pa 15096-0001

A/C SYSTEM PERFORMANCE TEST AND DIAGNOSIS CHART

PROBLEM	POSSIBLE CAUSE	CORRECTION
Gauge Readings: Low-Pressure - Low High-Pressure - Low Evaporator air not cold	Low refrigerant charge.	Perform leak tests and repair Evacuate system Charge system, retest system
Evaporator air warm	Extremely low refrigerant charge.	Same as above
Evaporator air cool but not sufficiently cold. Expansion valve inlet tube surface shows considerable condensation or frost.	Expansion valve not permitting sufficient flow Stuck valve	Check expansion valve as follows: 1) Set at maximum cooling Spray CO_2 or other gas on valve head or sensing bulb Low-pressure gauge should then show a vacuum reading Retest 2) If expansion valve is defectiveas determined in step 1, or if the valve inlet tube shows heavy condensation or frost, proceed as follows: Recover the system refrigerant R-134a Replace expansion valve Evacuate system Charge system Retest


PROBLEM	POSSIBLE CAUSE	CORRECTION
Gauge Readings: Low-Pressure - High High-Pressure - High Evaporator air warm Liquid line hot (condenser outlet to expansion valve tube)	Improper operation of condenser	Inspect for dirty condenser restricting air flow and cooling
Bubbles in sight glass	Overcharged with refrigerant	Check operation of engine cooling fan. Repair as needed. Check for overcharge as follows: Recover the system refrigerant R-134a Remove condenser assembly, flush and clean thoroughly Replace receiver/drier Evacuate the system Replace any oil lost during recovery Charge the system with 2.27 kg (5.0 lbs) of R-134a refrigerant Retest
Evaporator air not cold	Air and moisture in the system	Discharge the system Replace receiver/drier Evacuate the system Charge the system Retest
Evaporator air warm. Evaporator and hose to condenser shows considerable moisture	Expansion valve allowing too much refrigerant to flow through the evaporator	Check expansion valve Set for maximum cooling Spray liquid CO_2 on expansion valve head Low-pressure gauge should show vacuum reading If the expansion valve is defective, proceed as follows: Discharge the system Replace the expansion valve Evacuate the system Charge the system Retest

PROBLEM	POSSIBLE CAUSE	CORRECTION
Evaporator air warm. Evaporator and hose to condenser shows considerable moisture (Cont'd)	Expansion valve allowing too much refrigerant to flow through the evaporator (Cont'd)	If the above test shows expansion valve operating properly, proceed as follows: Recover the system refrigerant R-134a Replace the receiver/drier Inspect all lines and tubing from the compressor outlet to the expansion valve. Replace if needed Evacuate the system Charge the system Retest
Gauge Readings: Low-Pressure - low High-Pressure - high Insufficient cooling	Restriction in liquid line	Discharge the system Replace the receiver/drier Inspect all lines and tubing from compressor outlet to expansion valve. Replace if needed. Evacuate the system Charge the system Retest
Gauge Readings: Low-Pressure - high High-Pressure - low Evaporator air not cold	Internal leak in compressor. (reed valves, gasket, worn or scored piston rings or cylinder)	Recover the system refrigerant R-134a Replace the compressor Evacuate the system Charge the system Retest

PROBLEM	POSSIBLE CAUSE	CORRECTION
Gauge Readings: Low-Pressure - High High-Pressure - Normal Insufficient cooling, Low-pressure reading does not fluctuate with manual operation of the A/C mode switch (pressure should drop until compressor cycles).	System low on charge	Perform leak test Recover the system refrigerant R-134a Repair leaks
Evaporator air not cold.	Air or moisture present in system	Replace receiver/drier Evacuate system Charge the system Retest
Insufficient cooling during hottest part of day. Low-pressure reading does drop to vacuum during test (normal). High pressure reading drops when low pressure reading shows vacuum. Evaporator air is sufficiently cold until low-pressure reading drops to vacuum, then it becomes warm.	Excessive moisture in system. Receiver/drier saturated and releases moisture when outside air temperature is high. Moisture freezes in expansion valve preventing refrigerant flow	Discharge system Replace receiver/drier Evacuate the system Retest
Gauge Readings: Low-Pressure - Normal High-Pressure - Normal Compressor cycles "on" and "off" too frequently	Defective temperature control (thermostatic) switch	Stop engine and shut off A/C Replace temperature control switch Retest system and check compressor cycling

MANIFOLD GAUGE READINGS AND INTERPRETATIONS

NOTE: *70 Series art shown in Figure 36.*



36

Test Ports

On the 70 Series tractor, the test ports are located on the high- and low-pressure hoses where they connect to the compressor. On the 70A Series tractors, the high pressure test port is located on the high pressure hose where it connects to the condenser. The low pressure test port is located on the low pressure hose where it connects to the compressor. The fittings conform to SAE J2197 standards.

Normal manifold gauge readings on the low side gauge are 1.0 - 2.0 bar (15 - 30 PSI). The high-pressure gauge readings used in the gauge reading examples that follow are for an ambient temperature of 35° C (95° F). However, as outside air temperature increases or decreases, so will the pressure readings. Refer to the Pressure/Temperature Relationships chart below for equivalent readings.


Test Conditions

1. Tractor engine speed set at full RPM.
2. System fully charged.

NOTE: *Ambient air temperature readings are taken 50 mm (2") in front of the condenser.*

PRESSURE/TEMPERATURE RELATIONSHIPS

Ambient Temperature		High-Pressure Gauge Reading	High-Pressure Gauge Reading	Low-Pressure Gauge Reading	Low-Pressure Gauge Reading
°F	°C	PSI	bar	PSI	bar
70	21	114 -- 134	7.86 -- 9.24	3.0 -- 4.2	0.21 -- 0.29
75	24	126 -- 146	8.68 --10.07	3.6 -- 4.8	0.25 -- 0.33
80	26	141 -- 161	9.72 --11.10	4.8 -- 6.0	0.33 -- 0.41
85	29.5	159 -- 179	10.96 --12.34	5.3 -- 6.5	0.37 -- 0.45
90	32	179 -- 199	12.34 --13.72	6.1 -- 7.3	0.42 -- 0.50
95	35	186 -- 206	12.82 --14.20	7.5 -- 8.7	0.52 -- 0.60
100	38	209 -- 229	14.41 --15.79	8.1 -- 9.3	0.56 -- 0.64
105	40.5	227 -- 247	15.65 --17.03	9.3 --10.5	0.64 -- 0.72
110	43	260 -- 280	17.93 --19.31	12.0 --13.2	0.83 -- 0.91
115	46	297 -- 317	20.48 --21.86	15.1 --16.3	1.04 -- 1.12
120	49	341 -- 361	23.51 --24.89	16.9 --18.1	1.17 -- 1.25



37

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 1

Problem:
Little or no cooling.

Cause:
Refrigerant slightly low.

CONDITIONS*


1. Low side pressure too low. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too low.
3. Evaporator air not cold.

CORRECTIVE PROCEDURES

1. Leak test the system.
2. Repair leaks. (Discharge and recover the refrigerant from the system; replace lines or components).
3. Replace any oil lost during recovery with new oil. Be sure to use oil compatible with the tractor system.
4. Evacuate the system.
5. Charge the system.
6. Performance test the system.

DIAGNOSIS: System refrigerant is low. May be caused by a small leak.

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



38

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 2

Problem:
Insufficient cooling.

Cause:
Refrigerant excessively low.

CONDITIONS*


1. Low side pressure very low. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too low.
3. Evaporator air warm.

CORRECTIVE PROCEDURES

1. Leak test the system.
2. Recover the refrigerant from the system.
3. Repair leaks.
4. Replace any oil lost during recovery with new oil. Be sure to use oil compatible with the tractor system.
5. Evacuate the system.
6. Charge the system.
7. Performance test the system.

DIAGNOSIS: System refrigerant is extremely low. A serious leak is indicated.

***Note:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



39

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 3

Problem:
Insufficient cooling.

Cause:
Air in system.

CONDITIONS*


1. Low side pressure reading does not change when compressor cycles "on" and "off."
2. High side pressure slightly high or slightly low.
3. Evaporator air not cold.

CORRECTIVE PROCEDURES

1. Check the moisture indicator on the receiver/drier
2. Leak test the system. Give special attention to the compressor seal area.
3. Recover the refrigerant from the system.
4. Repair leaks.
5. Replace the receiver/dryer.
6. Check compressor oil to ensure no loss.
7. Evacuate the system.
8. Charge the system.
9. Performance test the system.

DIAGNOSIS: Non-condensables (air or moisture) present. System not fully charged.

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



40

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 4

Problem:
Insufficient cooling.

Cause:
Compressor malfunction.

CONDITIONS*


1. Low side pressure too high. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too low.
3. System fully charged
4. Evaporator air not cold.

CORRECTIVE PROCEDURES

1. Replace the compressor.

DIAGNOSIS: Internal leak in compressor caused by worn or scored pistons, rings, or cylinders.

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



41

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 5

Problem:
Insufficient or no cooling. Engine overheats in some cases.

Cause:
Condenser not functioning properly.

CONDITIONS*

1. Low side pressure too high. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too high.
3. Liquid line hot.
4. Evaporator air warm.

CORRECTIVE PROCEDURES

1. Check belt tension. Loose or worn drive belts could cause excessive pressures in the compressor head.
2. Look for clogged passages between the condenser fins and coil, or other obstructions that could reduce condenser air flow.
3. If engine overheating is a symptom, check radiator fan and pressure cap for proper operation.

(At this point, operate the system and check its performance. If still unsatisfactory, proceed as follows.)

4. Check for overcharge of refrigerant, and correct as follows:
   a. Discharge and recover the refrigerant.
   b. Add new refrigerant.


(Operate the system and recheck the performance. If the gauge readings are still too high, proceed as follows.)

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*

5. Recover the refrigerant from the system.

6. Remove the condenser; if it appears dirty or plugged, replace it.
7. Replace the receiver/dryer.
8. Evacuate the system, and recharge it.
9. Performance test the system.

DIAGNOSIS: Lack of cooling caused by pressure that is too high on the high side, resulting from improper operation of condenser. (Refrigerant charge may be normal or excessive.)



42

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 6

Problem:
Insufficient cooling during hottest part of hot days.

Cause:
Moisture in the system.

CONDITIONS*


1. Low side pressure reading normal 0.2 - 2.0 bar (3 - 30 PSI), but drops to a vacuum reading during testing.
2. High side pressure reading normal but drops when low side reading shows a vacuum.
3. Evaporator air sufficiently cold until low side pressure gauge shows a vacuum, then it becomes warm.

CORRECTIVE PROCEDURES

1. Recover the refrigerant from the system.
2. Replace the receiver/dryer.
3. Evacuate the system.
4. Charge the system.
5. Performance test the system.

DIAGNOSIS: Excessive moisture in system. Drying agent in receiver/dryer is saturated and releases moisture during high outside air temps. This moisture collects and freezes in the expansion valve, preventing a flow of refrigerant through the evaporator.

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



43

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 7

Problem:
Insufficient or no cooling.

Cause:
Large amount of air in system.

CONDITIONS*


1. Low side pressure too high. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too high.
3. Evaporator air not cool.

CORRECTIVE PROCEDURES

1. Recover the refrigerant from the system.
2. Replace the receiver/dryer.
3. Evacuate the system.
4. Charge the system.
5. Performance test the system.

DIAGNOSIS: Air in system. This, and the moisture in the air, is contaminating the refrigerant, causing the system to operate improperly.

***NOTE:** *Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



44

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 8

Problem:
Insufficient or no cooling.

Cause:
Improper operation of thermostatic expansion valve (stuck open)

CONDITIONS*


1. Low side pressure too high. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too high.
3. Evaporator air warm.
4. Evaporator and suction hose (to compressor) surfaces show considerable moisture.

CORRECTIVE PROCEDURES

1. Check for sticking expansion valve:
   a. Operate the system at maximum cooling
   b. Check the low side gauge. The pressure should drop slowly.
2. If the test indicates that the expansion valve is defective, proceed as follows:
   a. Recover the refrigerant from the system.
   b. Replace the expansion valve.
   c. Evacuate the system.
   d. Charge the system.
   e. Performance test the system.

DIAGNOSIS: Thermostatic expansion valve is allowing too much refrigerant to flow through the evaporator coils. Valve may be stuck open.

***NOTE:** *Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



45

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 9

Problem:
Insufficient cooling.

Cause:
Improper operation of thermostatic expansion valve (stuck closed).

CONDITIONS*


1. Low side pressure too low (0 PSI or vacuum). Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure low.
3. Evaporator air cool, but not sufficiently cold.
4. Evaporator valve inlet pipe surface shows considerable moisture or frost.

CORRECTIVE PROCEDURES

1. Place finger on expansion valve inlet. If too cold to touch, proceed as follows:
   a. Operate the system at maximum cooling.
   b. Check the low side gauge. The pressure should drop slowly.
2. If the expansion valve inlet surface shows frost or heavy moisture, proceed as follows:
   a. Discharge and recover the refrigerant from the system.
3. If the corrective procedure outlined in step 1 shows that the expansion valve is defective, proceed as follows:
   a. Evacuate the system.
   b. Charge the system.
   c. Performance test the system.

DIAGNOSIS: Expansion valve is not permitting a sufficient flow of refrigerant. May be caused by valve stuck in restricted or closed position.

***NOTE:** *Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



46

1. Low side low
2. High side low
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 10

Problem:
Insufficient cooling.

Cause:
Restriction in high side of system.

CONDITIONS*

1. Low side pressure too low. Gauge should read 0.2 - 2.0 bar (3 - 30 PSI).
2. High side pressure too low.

NOTE: *A normal or high reading of the high side pressure gauge under these conditions indicates the system is overcharged or the condenser is restricted.*


3. Evaporator only slightly cool.
4. Liquid line and receiver/drier are cool to touch and show frost or considerable moisture.

CORRECTIVE PROCEDURES

1. Discharge and recover the refrigerant from the system.
2. Replace the liquid lines, receiver/drier, or other obstructed components.
3. Evacuate the system.
4. Charge the system.
5. Performance test the system.

DIAGNOSIS: Restriction in the liquid line and/or receiver/drier resulting in a "starved" evaporator (compressor removing refrigerant from the evaporator faster than it can enter).

NOTE: *Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*



47

1. Low side gauge
   Compressor cycles on at 2.3 bar (34 PSI)
   Compressor cycles off at 1.9 bar (28 PSI)
2. High side normal
3. High side hand valve closed
4. High side hose connected to high side service connector
5. Not used
6. Low side hose connected to low side service connector
7. Low side hand valve closed

GAUGE READINGS AND INTERPRETATIONS

EXAMPLE 11

Problem:
Compressor cycles (cuts in and out) too rapidly.

Cause:
Thermostatic switch defective.

CONDITIONS*

1. Low side pressure readings too high during both "on" and "off" compressor cycles and between cycles. Readings should be:
   a. 0.2 - 1.0 bar (3 - 15 PSI) - cycle "off"
   b. 2.5 - 2.7 bar (36 - 39 PSI) - cycle "on"
   c. 1.6 - 1.9 bar (24 - 28 PSI) - between cycles
2. High side pressure normal.

CORRECTIVE PROCEDURES

1. Stop the engine and shut off air conditioning system.
2. Replace thermostatic switch.
3. Make sure the switch's temperature sensing line is installed in the same position and depth (in evaporator core) as previous bulb.

⚠ CAUTION ⚠

Line is filled with refrigerant under pressure. Do not kink or bend it too sharply.

4. Performance test the system.

DIAGNOSIS: Defective thermostatic switch.

***NOTE:** Test procedure based upon ambient temperature of 35° C (95° F). For proper high side gauge reading for other ambient temperatures, refer to the Pressure/Temperature Relationships chart.*


COMPONENT REMOVAL AND INSTALLATION

WHEN PERFORMING SERVICE OPERATIONS TO COMPONENTS LOCATED IN THE CEILING-MOUNTED HEATER/AIR CONDITIONER, GAIN ACCESS BY REMOVING THE CAB ROOF TO EXPOSE THE SECONDARY ROOF PANEL. PROCEED AS FOLLOWS:

Tool Requirements:
10 mm socket
5/16" socket
21 mm socket
15 mm socket
5 mm allen-head wrench

CAB ROOF REMOVAL


1. Remove bolts, 1, securing roof to tractor cab.
2. Grasp roof and pull up exerting controlled pressure. Roof will lift off providing access to the secondary inner roof panel. To allow complete roof removal, disconnect radio antenna wire and ground strap. Also, disconnect beacon light socket harness, if so equipped.



48


FRONT INNER ROOF PANEL REMOVAL

1. Remove fifteen bolts, 1, securing front inner roof panel.




49

2. Remove panel to expose heater/air conditioning unit.



50


NOTE: *Two different heater/air conditioner unit housings (metal and plastic) are used in the cab roof. Refer to the appropriate manual section when servicing the unit.*



51


A/C UNIT COVER REMOVAL
BSN D410005

1. Remove tape securing wire harness to unit cover.




52

2. Loosen and reposition wire harness routed across unit.




53

3. Remove twelve 5/16" hex bolts securing inspection cover to unit housing.



54


4. Remove cover.



55


A/C UNIT COVER REMOVAL
ASN D410004

1. Remove wiring harness, 1, from tie straps, 2, on front of cover.




56

2. Remove heater control cable, 1, from tie straps, 2, on top cover. Remove bolts securing inspection cover to unit housing.



57

3. Remove cover.




58

EXPANSION VALVE REPLACEMEN
BSN D410005

Tool Requirements:
5/8" open end wrench
5/16" socket
7/8" open end wrench
10 mm socket
3/4" crowfoot
Flat-head screwdriver


Removal

1. Discharge air conditioning system.




59

2. Remove refrigerant delivery line, 1, (5/8" hex).




60

3. Remove return line (7/8″ hex) to expansion valve. After removal, seal open A/C line connections to minimize system contamination.




61

4. Remove forward and bottom 5/16″ hex bolts securing sheet metal expansion valve cover to unit housing.




62

5. Final removal of expansion valve cover is achieved by loosening four 10 mm hex bolts that secure fresh air entry ring to unit housing.




63

6. Remove 7/8" hex nut securing evaporator outlet (upper) tube to expansion valve.




64

7. Remove hex nut securing evaporator inlet (lower) tube to expansion valve utilizing 3/4" crowfoot due to space constraints.



65

8. Remove the 7/16" retaining bolt through the center of the expansion valve.




66

Installation

1. Prior to installation of new expansion valve, replace the O ring on the evaporator plumbing and apply a liberal coat of PAG oil.
2. Proceed to install replacement valve by reversing steps one through eight.

SERVICE NOTE:

1. Any time the system is opened and discharged, the receiver/dryer must be replaced.
2. Seal all A/C line connections after removal to minimize system contamination.




67

EXPANSION VALVE REPLACEMENT ASN D410004


Removal

1. Discharge air conditioning system.
2. Remove the A/C unit cover. (See A/C unit cover removal for more information.)
3. Remove refrigerant delivery, 1, and return line, 2, from expansion valve, 3. Seal open line connections to minimize system contamination.
4. Remove bolt, 4, retaining expansion valve to housing.




68

5. Remove evaporator coil from housing (see Evaporator replacement for more information.)



69

6. Remove insulated shield covering expansion valve, 4. Remove bolt, 3, securing plate, 5. Remove lines, 1 and 2, from the expansion valve.



70

Installation

1. Prior to installation of new expansion valve, replace the O ring on the evaporator plumbing and apply a liberal coat of PAG oil.
2. Proceed to install replacement valve by reversing steps one through six.

SERVICE NOTE:


1. Any time the system is opened and discharged, the receiver/dryer must be replaced.
2. Seal all A/C line connections after removal to minimize system contamination.

EVAPORATOR REMOVAL
BSN D410005

Tool Requirements:
5/8" wrench,
7/16" socket
7/8" wrench
Flat-head screwdriver
1-1/8" wrench
10 mm socket
5/16" socket


Removal

1. Discharge air conditioning system.




71

2. Remove refrigerant delivery (5/8″ hex) and return (7/8″ hex) lines, 1, to expansion valve. Seal open line connections to minimize system contamination.




72

3. Remove insulated shield covering expansion valve, remove both forward and bottom 5/16″ hex bolts securing shield to unit housing. Loosen both forward mounting bolts (10 mm) that secure fresh air entry ring to unit housing.




73

4. Remove expansion valve support bracket bolt (7/16″ hex) located on valve body. Loosen both delivery (3/4″ hex) and return (7/8″ hex) solid plumbing tubes, 1, and remove the valve.




74

5. Remove thermostat capillary tube, 1, from evaporator, 2.




75

6. Remove spring clips located on evaporator core header flanges captivating evaporator core to evaporator retainer.



76

7. Remove evaporator core from unit housing.



77

Installation

1. Proceed to install replacement evaporator by reversing steps one through seven.

SERVICE NOTE:


1. Replace receiver/drier.
2. Insert thermostat probe into evaporator per the factory specification outlined below:

   Locate probe 6" from looped end of evaporator (opposite end from expansion valve) and insert between first and second rows of tubes closest to heater core - total probe depth 5".

EVAPORATOR REPLACEMENT
ASN D410004


Removal

1. Discharge air conditioning system.
2. Remove the A/C unit cover. (See A/C unit cover removal for more information.)




78

3. Remove refrigerant delivery, 1, and return line, 2, from expansion valve, 3. Seal open line connections to minimize system contamination.
4. Remove bolt 4, retaining expansion valve to housing.




79

5. Remove thermostat capillary tube, 1, from evaporator core, 2.



80


6. Remove spring clips, 1, located on evaporator core header flanges captivating evaporator core to evaporator retainer.



81

7. Remove evaporator core and expansion valve from unit housing.

   Remove the expansion valve from the evaporator core.



82

Installation

1. Proceed to install replacement evaporator by reversing steps one through eight.

SERVICE NOTE:

1. Replace receiver/drier.
2. Insert thermostat probe into evaporator per the factory specification outlined below:


   Locate probe 6″ from looped end of evaporator (opposite end from expansion valve) and insert between first and second rows of tubes closest to heater core - total probe depth 5″.

HEATER CORE REPLACEMENT

Tool Requirements:
5/16″ socket
Flat-head screwdriver


Removal

1. Adjust cable operated water valve to fully closed position to minimize coolant loss.




83

2. Close engine coolant shutoff valves on the right side of the engine.
3. Disconnect heater inlet and outlet hose.
4. Drain residual coolant into drain pan.




84

5. Loosen hose clamps (5/16″ hex) located on inlet and outlet plumbing of heater core. Do not remove heater hoses at this point.




85

6. Remove spring clips (located on core header flanges) that captivate heater core to core retainer.
7. Remove thermostat capillary tube from evaporator to prevent interference during heater core removal.



86

8. Remove heater core from unit housing. Fully remove core once heater hoses have been disconnected from core.




87

Installation
Proceed to install replacement core by reversing steps one through eight.

SERVICE NOTE:

To ensure optimum A/C performance, insert thermostat probe into evaporator per factory specifications as previously described.




88

MOTOR BLOWER REPLACEMENT

Tool Requirements:
3/8" socket

Removal


1. Disconnect motor power and ground lead wires from unit wire harness.



89

2. Remove bolts, 1, retaining blower motor and fan assembly.


NOTE: *The number and location of bolts will vary according to type of A/C housing (metal or plastic).*



90

3. Remove motor.

Installation
Proceed to install replacement motor by reversing steps one through three.



91

SERVICE NOTE:


The motor blower is an internally balanced assembly and must be replaced as an entire unit. Do not attempt to replace individual components.

THERMOSTAT REPLACEMENT

Tool Requirements:
3/8" socket

Removal


1. Locate and remove thermostat capillary tube, 2, from evaporator core, 3.
2. Remove clear protective tubing from thermostat capillary and retain for use on replacement thermostat.
3. Disconnect two-way electrical connector, 1, from thermostat.



92

4. Remove two hex nuts from mounting studs located on either side of thermostat.

NOTE: *The location of the thermostat will vary according to the type of A/C housing (metal or Plastic).*




93

Installation
Install protective tubing over new thermostat capillary tube and proceed to install by reversing steps one through four.

SERVICE NOTE:

Thermostat probe must be inserted into evaporator core per the factory specification as previously described.




94

FAN SPEED RESISTOR REPLACEMENT

Tool Requirements:
5/16" socket


Removal

1. Disconnect electrical connection by grasping three-way molded connector and applying even upward force.




95

2. Remove two retaining bolts at either end of resistor card holder and remove resistor. Retain resistor cage.



96

3. Proceed to install replacement resistor by reversing steps one and two, directing special attention to alignment of male and female termination points located between resistor and mating connector. Failure to do so may result in unnecessary damage to resistor card holder and terminal wedge points due to misalignment.



97


CABLE OPERATED WATER VALVE

(Removal of Unit Inspection Cover, Not Required)

Tool Requirements:
1/4" socket
5/16" socket


Removal

1. Close engine coolant shutoff valve, 1, (outlet). Drain coolant from outlet heater hose.




98

2. Loosen the hose retaining bracket.




99

3. Blower harness may require easing through the pressurizer casing to allow access to lower hose clamps.




100

4. Loosen water valve inlet and outlet hose clamps (5/16" hex) and remove coolant lines from water valve. Protect headliner area under water valve to prevent possible damage from residual coolant leakage.



101

5. Remove 1/4" hex bolt securing cable retainer to water valve.
6. Remove spring clip and disconnect control cable from water valve control arm.



102

Installation

1. Proceed to install replacement valve by reversing steps one through six.

SERVICE NOTE:

1. To assure optimum A/C performance, proper water valve adjustment is required. Proceed as follows:
2. Place temperature control knob in cab on full cold position. Manually place water control arm in fully closed position and tighten cable retainer screw to ensure positive water shutoff is achieved.


A/C RELAY

Removal

1. The relay, 1, is located on the outside of the A/C housing behind the water valve.

NOTE: *The mounting location and position will vary according to the type of A/C housing (metal or plastic).*

2. Remove the retaining bolt, 2, and disconnect the relay from the harness. On units with the plastic housing it may be necessary to remove the tie strap, 3, retaining the electrical connector and harness.



103

Installation

Proceed to install by reversing removal procedure.


THE FOLLOWING COMPONENTS ARE LOCATED IN THE TRACTOR CAB. ACCESS IS ACHIEVED BY REMOVING THE OVERHEAD CONSOLE. TO SERVICE, PROCEED AS FOLLOWS:

A/C MODE SWITCH, TEMPERATURE CONTROL SWITCH OR BLOWER SWITCH REMOVAL

Tool Requirements:
10 mm socket
9/16" deep socket
Phillips-head screwdriver


Removal

1. Remove two mounting bolts (10 mm hex) securing left-hand pillar post cover to the tractor cab frame member.




104

2. Release fasteners securing right-hand pillar post cover over the main distribution panel and remove.




105

3. Remove recirculation air filter facia panel, 1, located on overhead console by removing two Phillips-head screws located on either side of facia panel.




106

4. Remove overhead console by extracting two each Phillips-head screws and mounting bolts (10 mm hex) located on either side of recirculation cutout.




107

5. Carefully dislodge overhead console providing access to electrical connections on back side of A/C switch.




108

6. Remove serrated bezel nut that secures A/C mode switch to overhead console.



109


7. Remove three-way electrical connector on rear of A/C mode switch.



110

Installation

Proceed to install replacement switch by reversing steps one through seven.



111


THE FOLLOWING COMPONENTS ARE LOCATED IN THE ENGINE COMPARTMENT OF THE TRACTOR. TO SERVICE, PROCEED AS FOLLOWS:

RECEIVER/DRIER REPLACEMENT

Tool Requirements:
1/2" socket
5/8" wrench
3/4" wrench
1/2" wrench


Removal

1. Discharge air conditioning system.




112

2. Remove two bolts (1/2" hex) securing receiver/drier mounting strap to hood release bracket.
3. Partially rotate drier to clear hood release bracket and route downwards for easy access to inlet and outlet fittings.




113

4. Remove 5/8" hex inlet fitting from drier and seal A/C line connection.




114

5. Remove 3/4" hex outlet fitting from drier and seal A/C line connection.



115

Installation
Proceed to install replacement drier by reversing steps one through five.



116

SERVICE NOTE:


1. Replace the receiver/drier.
2. Seal all A/C line connections after removal to minimize system contamination.

COMPRESSOR REPLACEMENT

Tool Requirements:
13 mm socket
1-1/16" wrench
9/16" wrench
13 mm wrench
7/8" wrench,
1/2" socket
9/16" socket


Removal

1. Discharge air conditioning system.
2. Remove three 13 mm hex bolts securing fan shroud screen located on right-hand side of radiator.




117

3. Remove compressor belt utilizing 1/2" flex end driver on spring-loaded idler pulley to relieve belt tension.




118

4. Remove and cap the 1-1/16" hex suction line fitting from compressor.




119

5. Remove and cap the 7/8″ hex discharge line fitting from compressor.




120

6. Note the O rings, 1, on the high- and low-pressure fittings.




121

7. Plug both the high- and low-pressure lines, 1, once removed to prevent contamination.



122

8. Remove four 9/16" hex bolts securing compressor to engine mount bracket.
9. Disconnect two-way electrical connector, 1, from clutch coil.




123

Installation
Proceed to install replacement compressor by reversing steps one through nine.

SERVICE NOTE:

Seal all A/C line connections after removal to minimize system contamination.




124

COMPRESSOR CLUTCH


Disassembly

1. All clutch servicing should be done with the compressor removed from the vehicle.




125

2. Remove the clutch cover retaining screws and remove the cover.




126

3. Support the compressor. If using a vise, do not hold on to the housing.




127

4. Insert the clutch holder pins into two of the threaded holes on the front plate. Remove the retaining nut from the end of the shaft.




128

5. Remove the clutch front plate with the puller.




129

6. Remove the shims from the drive shaft.




130

7. Remove the key.




131

8. Remove the dust seal.




132

9. Remove the pulley retaining snap ring and bearing snap ring (where fitted).




133

10. Remove the pulley, using a universal puller as shown.



134

11. Loosen the cable clip on the compressor housing.




135

12. Remove the field coil retaining snap ring and field coil.

Reassembly


1. Reassembly is the reverse of assembly with the following differences.
2. Using a suitable adaptor that rests firmly on the outer diameter of the bearing, tap the pulley assembly into position. Care must be taken to ensure correct alignment.
3. Replace the retaining nut and tighten to a torque of 38 N·m (28 ft. lbs.).



136

4. Check the clearance between the clutch front plate and pulley. This should be consistent around the circumference and be between 0.4 mm and 0.8 mm (0.016" and 0.031").
5. Consistency is achieved by gently levering up the plate at minimum variation and tapping down at maximum.
6. If the clearance is not within specification, add or subtract shims and repeat step four above.

NOTE: *New shims are available in sizes 1.0 mm, 0.5 mm and 0.13 mm (0.040", 0.020" and 0.005").*




137

CONDENSER REPLACEMENT MODELS 8670 BSN D411682 AND 8770 BSN D408841

Tool Requirements:
7/8" wrench
13 mm socket
3/4" wrench
13 mm wrench


Removal

1. Discharge air conditioning system.
2. Disconnect 7/8" hex inlet fitting line from condenser with the condenser swung out.




138

3. Disconnect 3/4" hex outlet fitting line from condenser.




139

4. Remove the 13 mm hex bolt that secures canister air filter inlet scoop to top condenser frame and remove the scoop if necessary.




140

5. Remove the 13 mm bolt, 1, connecting the condenser to the radiator.



141

6. Remove two 13 mm hex bolts located on either side of the lower condenser frame.




142

Installation

Proceed to install the replacement condenser by reversing steps one through six.

SERVICE NOTE:

Seal all A/C line connections after removal to minimize system contamination.



143


CONDENSER REPLACEMENT MODELS 8670 ASN D411681, 8770 ASN D408840, 8870, 8970 AND 70A SERIES

NOTE: *70 Series art shown.*

Tool Requirements:
3/8″ socket
7/8″ wrench
12mm socket
3/4″ wrench,
12mm wrench


Removal

1. Discharge air conditioning system.
2. Remove 3/8″ hex bolt securing refrigerant hose hold-down clamp to top section of condenser mounting frame.




144

3. Disconnect 7/8″ hex inlet fitting line from condenser and seal.




145

4. Disconnect 3/4″ hex outlet line from condenser and seal.




146

5. Release both rubber hold-down straps located on right-hand side of condenser.



147


6. Remove two 12 mm hex bolts securing the hinge arrangement, located on left-hand side of condenser.



148

Installation

Proceed to install replacement condenser by reversing steps one through six.



149

SERVICE NOTE:

Seal all A/C line connections after removal to minimize system contamination.

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 1 – Electronic Instrument Cluster (EIC) and System Overview

CONTENTS


Section	Description	Page
55 418	Specifications	3
	Description of Operation	4
	Main Distribution Panel	7
	Service Diagnostics	9
	Electronic Instrument Cluster (EIC)	11
	Central LCDs	12
	Tractor Performance Monitor	12
	Automatic Engine Shutdown	13
	70 Series Indicator, Warning Lamps and Audible Alarm	14
	70A Series Indicator, Warning Lamps and Audible Alarm	15
	Air Filter Restriction	17
	Differential Lock	17
	Cold Start Assist (Ether)	18
	Cold Start Assist (air inlet)	18
	Coolant Level Low	19
	Alternator Charge Indicator	19
	Intercooler Overheated	20
	Transmission Pressure Low	20
	Transmission, Rear Axle/Hydraulic Oil Temperature	20
	Hydraulic/Transmission Filters Restricted	21
	PTO Engaged	22
	Programmable Up Shift	22
	Programmable Down Shift	22
	70 Series FWD On	23
	FWD Auto	23
	70A Series FWD On	23
	FWD Auto	23
	Four Wheel Drive (FWD) Switch (if equipped)	23

Headlight High Beam 24
System Status 24
Parking Brake 24
Bar Graph Displays (LCD) 25
Stop and Audible Alarm Conditions 26
Central Display (LCD) 29
Lower Selectable Display 31
Electronic Instrument Cluster - Tractor Performance Monitor (TPM) 33
Automatic Display Information 34
Selectable Display Information 35
EIC Lighting Display 39
Troubleshooting and Diagnostics 40
EIC Harness Tool 41
MODE 1, Operator Calibrations 41
MODE 2, View Stored Fault Codes 50
MODE 3, All Module Input Parameters 53
MODE 4, EIC Output Diagnostics 56
MODE 5, RHC Output Diagnostics 57
MODE 6, EDC Output Diagnostics 58
MODE 7, ETC Output Diagnostics 59
MODE 8, EIC Full Display Test 60
MODE 9, Hardware/Software Revision Level 61
MODE 10, Transmission Calibration Review and Programming 63
MODE 11, 3-Point Hitch and EDC Calibration 66
MODE 12, Tractor Features Configuration 69
MODE 13, Steering Angle Sensor Operation/Calibration (70A Series) 72

SPECIFICATIONS

COMPONENT	LOCATION	GENERAL SPECIFICATIONS
Fuses	Main fuse panel (MFP) right side of floor	8 main fuses, 40 and 50 AMP
	Main distribution panel (MDP) right “B” post	30 fuses, (70 Series) 32 fuses, (70A Series) 5 to 25 AMP
Relays	Main distribution panel (MDP) right “B” post	17 relays (70 Series) 20 relays (70A Series)
Electronic transmission control (ETC) module	Part of chassis control module (CCM)	16 BIT micro-controller with application memory and non-volatile calibration memory
Electronic draft control (EDC) module (optional)	Part of chassis control module (CCM)	16 BIT micro-controller with application memory and non-volatile calibration memory
Electronic instrument cluster (EIC) module	Tractor dash	8 BIT micro-controller with application memory and non-volatile calibration memory
Right-Hand controls (RHC) module	Part of right-hand console	8 BIT micro-controller with application memory and non-volatile calibration memory
Speed sensors	Engine speed front trans. housing	2500 OHMS resistance digital engine speed
	Ground speed center trans. housing	2500 OHMS resistance digital ground speed
EHR module	Behind operators seat on top of the CCM.	EPROM processor (microcontroller MHVD8-8)

DESCRIPTION OF OPERATION



1

1. Electronic instrument cluster (EIC)
2. Main fuse panel (MFP)
3. Main distribution panel (MDP)
4. Right-hand controls module (RHC)
5. Chassis control module (CCM) (ETC and EDC)
6. Diagnostic and maintenance connector (DAM)
7. Electro-hydraulic remote module (EHR) (70A Series only)

The 70/70A Series tractors use the latest technology in electronics to provide excellent reliability and serviceability. The system uses a wiring harness with both color and letter identifiers on each wire.

All 70/70A Series tractors are equipped with the same Electronic Instrument Cluster (EIC).

- The EIC is one of five microprocessors on the tractors.
- The second processor is located in the Right-Hand Controls (RHC) module, and it is mounted in the right side console. It controls many of the tractor functions initiated by the operator.
- The third and fourth processors are located in the Chassis Control Module (CCM) which is secured to the cab floor behind the operator's seat. The Electronic Transmission Control (ETC) module and the Electronic Draft Control (EDC) module, if the tractor is equipped with 3-point hitch, are the two modules housed inside of the CCM.

The fifth processor (70A Series only) is the Electro-hydraulic Remote (EHR) module and is located on top of the CCM. The EHR module controls the hydraulic functions of the electro-hydraulic remotes.

All of the modules except the EHR module (70A Series only) communicate information from tractor sensors, switches and operator controls to each other and to displays or actuators as directed. The operator instructs the electronic modules what to do, the modules interpret the commands and direct the tractor subsystems to complete the functions as required.

The EHR module has one independent wiring harness that connects the module, remotes and control pods to each other.

The three control modules are fitted with connectors. The connectors are not identified on the modules. The wiring diagrams identify the connectors as J1, J2, and J3 and harness connectors C001, C002, C006, C007, C010, and C011.

All modules, 1, except the EHR module (70A Series only) communicate information on two signal wires, 3, using a communications network technology known as Controller Area Network (CAN). This technology allows modules to perform many functions through the use of shared input and output resources, thus minimizing sensors and wiring components. In addition, modules check for faults and display or store this information as required for reference in servicing.


The tractor electrical system is equipped with 13 service diagnostic modes to allow the technician to do most troubleshooting without disconnecting connectors or modules. An additional feature of the electronic system is a Diagnostic and Maintenance (DAM) connector, 2, which permits a hand-held Portable Diagnostic Tool (PDT) to be used for more detailed testing, programming or calibration.

Six harnesses are used to power all circuits. The Cab Main (CM), Cab Roof (CR), Front Main (FM), Front Light (LT), Right-Hand console (RH) and the Rear Main (RM) harness. All connectors are identified by the letter “C,” and three digits such as C007.


On the 70A Series only, a seventh EHR harness is added. The connectors are identified the same as the other six harnesses.

NOTE: *70 Series art shown in Figure 3.*

The Cab Main (CM) harness utilizes a Main Fuse Panel, 1, between the Main Distribution Panel (MDP), 2, and the two 950 CCA batteries.



2



3


On the 70 Series, the main fuse panel (MFP), 1, houses 7 large fuses to protect the Main Distribution Panel (MDP) with a spare fuse in position #1. Release clips, 2, to remove the MFP cover, 3.

On the 70A Series, the main fuse panel (MFP) now uses fuse position #1 for a 40 amp fuse that supplies power to the electro-hydraulic remotes and the trailer light circuit.

The MDP contains fuses and relays. It is attached to the side of the cab in the right “B” post and is covered with a protective cover. The cover is held in place with over center latches.


The Main Fuse Panel fuse identification is shown below.

The wiring harness diagram is designed to show power flow from its source on the top of the diagram through appropriate circuits to ground on the bottom. An index is provided to locate specific components. All switches, controls and actuators are shown in each circuit. See Section 55, Chapter 6 “Wiring Diagrams,” for additional information.



4

Fuse No.	Rating	Color	Circuit
1 (70)	–	–	Spare
1 (70A)	40A	Orange	Main electro-hydraulic fuse
2	50A	Red	Main fuse I
3	40A	Orange	Main transmission fuse
4	50A	Red	Main road lamp fuse
5	50A	Red	Main work lamp fuse
6	40A	Orange	Main accessory fuse
7	40A	Orange	Main fuse II
8	40A	Orange	Main implement socket fuse



5

Main fuse locations

MAIN DISTRIBUTION PANEL


The main distribution panel is located behind the cover, 1, on the right-hand “B” pillar. To gain access to the panel, release the latches, 2, and remove the cover.

On the 70 Series, the panel has thirty fuse locations and seventeen relay locations.

On the 70A Series, the panel has thirty-two fuse locations and twenty relay locations.

Refer to the table for fuse and relay information including the circuit each controls.

NOTE: *Relays 18, 19 and 20 are for the 70A Series only.*




6

RELAYS


Relay No.	Circuit
M1	Lower front and side work lamps
M2	Lower cab rear work lamps
M3	Upper cab rear work lamps
M4	Upper cab front work lamps
M5	Power take-off
M6	Transmission directional interrupt
M7	Brakes
M8	Cold start
M9	Accessory
M10	Auxiliary power #2
M11	Transmission power
M12	Auxiliary power #1
M13	Flasher module
M14	NASO/ISO turn signal, flasher converter module
M15	NASO/ISO turn signal, flasher converter module
M16	Fuel solenoid - pull-in
M17	Implement power
M18	Remote valve electro-hydraulics
M19	Right-hand trailer lights
M20	Left-hand trailer lights

NOTE: *Fuses 31 and 32 are for the 70A Series only.*

Fuse No.	Rating	Color	Circuit
1	10A	Red	Accessory Socket
2	25A	Clear	Climate control
3	15A	Blue	Washer/wiper
4	20A	Yellow	Front/Mid work lamps
5	20A	Yellow	Lower cab rear work lamps
6	15A	Blue	Upper cab rear work lamps
7	15A	Blue	Upper cab front work lamps
8	7.5A	Brown	Right-hand park lamp
9	7.5A	Brown	Left-hand park lamp
10	25A	Clear	Main work lamp
11	15A	Blue	Cigar/horn/beacon
12	15A	Blue	Brake lamp
13	15A	Blue	Hazard lamp
14	5A	Tan	Interior lamp
15	7.5A	Brown	Movable console
16	20A	Yellow	Seat
17	7.5A	Brown	Radio power
18	20A	Yellow	Transmission shift control solenoids fuse #1
19	20A	Yellow	Transmission forward/reverse shift control solenoids fuse #2
20	15A	Blue	Transmission forward/reverse shift control solenoids - PTO
21	5A	Tan	Right-hand console
22	5A	Tan	Front console
23	10A	Blue	Control modules switched power (VPWR)
24	15A	Blue	Turn signal
25	5A	Tan	Unswitched power - direct from battery (KAPWR)
26	10A	Yellow	Ignition switch
27	15A 20A	Blue (BSND407000) Yellow (ASND406999)	Cold start aid
28	15A	Blue	Road lamp high beam
29	15A	Blue	Road lamp low beam
30	15A	Blue	Implement monitor
31	10A	Red	Remote valve electro-hydraulics
32	20A	Yellow	Trailer lights



70A Series



70 Series

70-540-297

7

SERVICE DIAGNOSTICS

The 70/70A Series tractors have several modes to aid in troubleshooting, calibration and adjusting tractor performance. Some of the modes can only be accessed with the engine off while other modes allow the operator to drive the tractor and monitor its performance as it occurs.

The modes are accessed by holding the SET UP/SELECT switch for three seconds with the key switch on. The TPM display will show _ _ _ 1 indicating that the operator is at the 1st of 12 different diagnostic and calibration modes. By touching the DIGIT SELECT button, the menu will advance to the different modes, 1,2,3 etc.

To enter the desired mode, the operator must again hold the SET UP/SELECT switch for three seconds. The information in the mode can now be viewed or utilized for diagnostics and/or calibration purposes.

The modes available are:

- MODE 1, Operator calibrations *
- MODE 2, View stored fault codes
- MODE 3, All module input diagnostics
- MODE 4, EIC output diagnostics
- MODE 5, RHC output diagnostics
- MODE 6, EDC output diagnostics
- MODE 7, ETC output diagnostics
- MODE 8, EIC display lamp/LCD test
- MODE 9, Hardware/software revision ID
- MODE 10, Transmission calibration and programming menu*
- MODE 11, 3-pt hitch EDC calibration menu *
- MODE 12, Tractor features, configuration
- MODE 13, TerraLock™ (70A Series only)

* These modes can be accessed with engine running or stopped. All other modes cannot be accessed with the engine running.

NOTE: *MODE 13 is for 70A Series only.*

MODE 1, OPERATOR CALIBRATIONS

This mode allows the operator to change different constants to match the tractor to implements and change service information as follows:

- Implement width
- Slip alarm
- Set Service Interval I
- Set Service Interval II
- Set ground speed constant
- Set Area Preset
- Fault Codes display On/Off

MODE 2, VIEW STORED FAULT CODES

This mode allows the technician to view stored fault codes for each of the four microprocessors. Fault codes can be stored for each module resulting in an overall storage of 30 Fault codes. The codes will be displayed sequentially in the lower right-hand display (TPM) along with the hour of occurrence in the EIC hour meter display area. The most recent code will be displayed first and the oldest code last. Repeat codes will have the number of times they occurred displayed in the transmission gear shift display area.

MODE 3, ALL MODULE INPUT DIAGNOSTICS

In this mode the technician can view the state of all sensors on the tractor. An audible tone will be heard when a switch is activated and a 4 digit Parameter ID number (P_ _ _) will be displayed for that sensor or switch. When it is returned to its original position, a different tone will be heard.

MODE 4, EIC OUTPUT DIAGNOSTICS

In this mode, all Electronic Instrument Cluster (EIC) outputs can be activated with the SET UP/SELECT function switches to verify its associated actuators function.

MODE 5, RHC OUTPUT DIAGNOSTICS

In this mode, all Right-Hand Control (RHC) module outputs can be activated with the SET UP/SELECT function switches to verify its actuators function.

MODE 6, EDC OUTPUT DIAGNOSTICS

In this mode, all Electronic Draft Control (EDC) module outputs can be activated with the SET UP/SELECT function switches to verify its actuators function.

MODE 7, ETC OUTPUT DIAGNOSTICS

In this mode, all Electronic Transmission Control (ETC) module outputs can be activated with the SET UP/SELECT function switches to verify its actuators function.

MODE 8, EIC FULL DISPLAY TEST

When this mode is selected, the EIC will light each lamp in succession and all segments of the LCD's will be displayed simultaneously or individually.

MODE 9, HARDWARE/SOFTWARE REVISION IDENTIFICATION

In this mode, the technician can sequentially view the four modules to display their current hardware and software revision identification numbers followed by the serial number of the tractor in which they were originally installed.

MODE 10, TRANSMISSION CALIBRATION AND PROGRAMMING

In this mode, tractor transmission calibration values required for consistent shift quality can be viewed and shift programming can be completed.

See Transmission Calibration in Section 21, Chapter 6, for more information.

MODE 11, 3-PT HITCH EDC CALIBRATION

This mode will allow the EDC to be calibrated for best overall performance or to recalibrate the EDC if components are replaced in the system. This mode also allows the technician to view EDC draft load levels while operating in the field.


MODE 12, TRACTOR FEATURES, CONFIGURATION

This mode allows the technician to configure the microprocessors to match the electronics to the tractor options present.

MODE 13, TERRALOCK

When mode 12's feature 14 is set to 1, then mode 13 is present and the system is looking for the steering angle sensor. Depending on the position of the steering angle sensor, the four wheel drive and difflock will be turned on and off.

ELECTRONIC INSTRUMENT CLUSTER (EIC)



8

1. Liquid crystal displays (LCD) (3)
2. Indicator lamps (18)
3. Bar graphs (2)
4. Tractor performance monitor (TPM)
5. Touch-sensitive programming switches (11)
6. Indicator lamps (3)
7. Touch-sensitive light control switches (5)
8. Bar graphs (2)

INTRODUCTION

The electronic instrument cluster (EIC) is shown above with a normal operating display.

When the key-start switch is turned on, a self-test of all the Liquid Crystal Display (LCD) segments is activated, the audible alarm will sound for one second and all lamps will be illuminated briefly, to confirm that the bulbs are functioning. The LCD background areas are illuminated when the tractor key switch is turned on. They also have dimmer controlled back lighting.

The EIC is divided into the following areas:

1. The central LCD has transmission gear information at the top. Engine speed appears in the middle display and the bottom displays operating hours, ground speed or PTO speed, as selected.
2. The upper section consists of colored indicator or warning lamps, which provide operating information or give warning of system malfunctions.
3. Coolant temperature and exhaust temperature are displayed in the right bar graphs.
4. The Tractor Performance Monitor (TPM) is displayed on the right side of the cluster. The TPM provides information on 3-point hitch and other selected system information. Fault code information is also displayed.
5. Eleven touch-sensitive switches select different EIC functions for display on the central display and TPM. The switches are also used for calibration purposes.
6. The indicator lamps provide operating information and give warning of system malfunctions.
7. Five touch-sensitive switches are used to control the work lights and instrument cluster back-lighting brightness.
8. Fuel level and engine oil pressure are displayed in the left bar graphs.

CENTRAL LCDS


The main, central panel, 1, Figure 8, is divided into 3 multi-function LCDs. The lower LCD is selectable and is activated by the right-hand function selector switches. A numerical readout of the following functions may be displayed:

Gear shift position (continuous display), 1.

Engine speed (RPM) continuous display, 2.

Selectable in the lower display, 3:

- Engine hours accumulated (actual time)
- Tractor ground speed (MPH or km/h)
- PTO speed (RPM)
- Two Service alert indicators may be programmed into the lower display as a reminder to the operator that the next scheduled service is due.



9

TRACTOR PERFORMANCE MONITOR


Information provided by the Tractor Performance Monitor is displayed in the right-hand panel, 1. The display includes:

Automatic Displays

- Hitch enabled (with Electronic 3-point Hitch Control only)
- Hitch position (with Electronic 3-point Hitch Control only)
- Hitch disabled (with Electronic 3-point Hitch Control only)
- Fault code indicator

Selectable Displays

- Area per hour forecaster (acres or hectares)
- Area accumulated in acres or hectares
- Wheel slip percent (if equipped)
- Battery voltage
- 540 PTO speed in RPMs (if equipped)
- 1000 PTO speed in RPMs
- Distance measurement in feet or meters




10

Fault Codes
In the event that a fault occurs within the tractor electrical circuits, a malfunction warning symbol "Read Your Manual," 1, will be flashing. See Mode 1, "Operator Calibrations" for additional information.

The fault codes, 2, consist of a simple three-digit number preceded by the letter "F."

The code indicates the tractor circuit or sensor in which the fault lies and the type of fault, e.g., short circuit, open circuit, sensor failure, etc. If these codes should occur, see Section 55, Chapter 2 of the Repair Manual for more details.




11

Audible Alarm
Depending on the severity of the problem, the alarm will sound as follows:

Non-critical alarm: A momentary audible alarm sounds for one second only. The tractor will continue to operate but the cause of the alarm should be investigated.

Critical alarm: Continuous pulsating tone until the fault is located and corrected. The alarm will sound and the engine STOP message, 1, will flash for 30 seconds before automatic engine shutdown occurs. The critical alarm will continue until the fault is corrected or the engine is switched off. The cause of the fault should be located immediately to prevent damage to the tractor.


The audible alarm has a volume control located on the left side of the steering column below the front controls. Rotate the alarm cover to adjust the volume.



12

AUTOMATIC ENGINE SHUTDOWN

An automatic engine shutdown feature is standard equipment. This feature will automatically shut down the engine within 30 seconds if engine oil pressure falls below or engine coolant temperature rises above predetermined levels. The engine will also shut down after 30 seconds if the transmission low-pressure lamp or the transmission high-temperature lamp are on during tractor operation. This feature protects the engine and drivetrain of an unattended tractor carrying out stationary PTO work. (See also "Shutdown Override" switch operation in Section 55, Chapter 3).



13


70 SERIES DASH

1. Left turn signal
2. Trailer 2 turn signal
3. Trailer 1 turn signal
4. Air filter restricted
5. Automatic differential lock engaged
6. Cold start assist
7. Coolant level low
8. Alternator charge indicator
9. Intercooler overheated
10. Transmission pressure low
11. Transmission, rear axle/hydraulic oil temperature high
12. Hydraulic/transmission filters restricted
13. PTO engaged
14. Programmable up shift
15. Programmable down shift
16. FWD On
17. FWD Auto
18. Right turn signal
19. Parking brake status
20. System status
21. Headlight high beam on

70 SERIES INDICATOR, WARNING LAMPS, AND AUDIBLE ALARM

The twenty-one colored status lamps, shown above, provide operating information or give warning of system malfunction. The malfunction warning lamps are accompanied by an audible alarm.

Each indicator or warning lamp is discussed under the corresponding heading found on the following pages.



14

70A SERIES DASH


1. Left turn signal
2. Trailer 2 turn signal
3. Trailer 1 turn signal
4. Air filter restricted
5. Automatic differential lock engaged
6. Cold start assist
7. Coolant level low
8. Alternator charge indicator
9. Intercooler overheated
10. Transmission pressure low
11. Transmission, rear axle/hydraulic oil temperature high
12. Hydraulic/transmission filters restricted
13. PTO engaged
14. Programmable up shift
15. Programmable down shift
16. Differential lock auto
17. FWD Auto
18. Right turn signal
19. Parking brake status
20. System status
21. Headlight high beam on

70A SERIES INDICATOR, WARNING LAMPS AND AUDIBLE ALARM

The twenty-one colored status lamps, shown above, provide operating information or give warning of system malfunction. The malfunction warning lamps are accompanied by an audible alarm.

Each indicator or warning lamp is discussed under the corresponding heading found on the following pages.

The status lamps/audible alarm function as follows:



15

1. LEFT TURN INDICATOR

Lamp will flash in unison with tractor left-hand turn signal. An audible alert will sound if the turn signals are left on for more that two minutes.

2. TRAILER 2 TURN SIGNAL (NON-NORTH AMERICAN ONLY)


Lamp will flash in unison with tractor/trailer turn signals if two trailers are attached.

3. TRAILER 1 TURN SIGNAL (NON-NORTH AMERICAN ONLY)

Lamp will flash in unison with tractor/trailer turn signals if one trailer is attached.

4. RIGHT TURN INDICATOR

Lamp will flash in unison with tractor right-hand turn signal. An audible alert will sound if the turn signals are left on for more that two minutes.



16

1. HAZARD WARNING LIGHT SWITCH

The switch is internally illuminated and when actuated by pushing the top of the switch will flash in unison with all the tractor and trailer turn signals and the green indicator lamps in the EIC.

Push the bottom of the switch to turn off.

NOTE: *North America only: Hazard warning lights are used when driving on the public highway. When a turn signal is made, the lights on one side of the tractor will flash, indicating a turn, while the lights on the other side will be lighted continuously. For your protection, use the hazard warning lights when traveling on public roads unless prohibited by law.*

2. MULTI-FUNCTION SWITCH


The stalk-type switch operates the horn, turn signals, headlight flash and is also used to select HI or LOW beam.

See Chapter 5 of this section for more details.

AIR FILTER RESTRICTION

Lamp, 1, will illuminate accompanied by the non-critical alarm if the fault has existed for 10 seconds. Stop the tractor and service the air cleaner to prevent engine damage.

The air cleaner restriction switch, 2, is located in the air cleaner at the turbocharger tube and is coupled to the front main wiring harness by two spade-type connectors. The switch is normally open and closes when the vacuum in the air intake tube exceeds 25 in. of water. The air cleaner restriction warning lamp is illuminated when the switch is closed.



17

DIFFERENTIAL LOCK

NOTE: *70 Series art shown in Figure 18.*


Lamp, 1, will illuminate only when automatic differential lock is engaged.

Normal Operation

An electro-hydraulic, self-holding differential lock is installed on all models. In conditions inducing wheel slip, momentarily press the front (orange) part of the switch, 2, to lock the rear wheels together. When the differential lock is engaged, the switch is internally illuminated.

NOTE: *Diff-lock will automatically disengage if one brake is applied. Both modes of diff-lock will automatically disengage if the tractor is operated above 16 km/h (10 MPH).*

If the tractor is equipped with TerraLock (70A Series only) the front four wheel drive differential will also disengage and engage in a similar manner along with hard turn angles.




18

Automatic Operation

Touch the front of the switch, 2, twice within one second for automatic diff-lock. When in this mode the diff-lock will automatically disengage and reengage when one brake is applied then released, or when the 3-point hitch Raise/Work switch is activated to raise then lower the hitch. This function allows the diff-lock to disengage on end rows when turning and reengage when the implement is again lowered.

Depress the rear of the switch, 2, to disengage diff-lock.

The diff-lock solenoid, 3, is located at the rear of the tractor and has a resistance of 9.4 ohms.




19

COLD START ASSIST (ETHER)
BSN D414635


Lamp, 1, will illuminate when the Cold Start Assist function is activated by the push switch, 2, at the left of the steering post.

Depressing then releasing the switch, 2, actuates the ether injection system, 3. The ether switch can be activated while cranking for at least one second. It can only be activated once every six seconds.

The ether cold start system only operates when coolant temperature is below 20° C (68° F). The EIC monitors the coolant temperature and engine speed. Current is provided to the cold start system at these lower temperatures with engine speed of 50+ RPM present.




20



21

COLD START ASSIST (AIR INLET)
ASN D414634


Lamp, 1, will illuminate when the Cold Start Assist is activated by the pushing switch, 2, at the left of the steering post.



22

The air inlet cold start assist system is activated when the key switch is turned to position, 3, the ambient air temperature is below 14°C (57°F), and engine speed is less than 50 RPM. If all three conditions are met the air inlet heater will activate when the cold start switch, 2, is depressed and released.

The system can only be activated once per starting attempt. If the engine fails to start, the key switch must be turned off and the process started over.




23

COOLANT LEVEL LOW

Lamp, 1, will illuminate when coolant drops below the sender level. A non-critical alarm will sound.

The sender, 2, acts as a normally open switch having a lower resistance when immersed in coolant.




24

ALTERNATOR CHARGE INDICATOR

Lamp, 1, will illuminate continuously if alternator, 2, is not charging the batteries. The lamp will flash and the non-critical alarm will sound if an undercharge or overcharge condition occurs.

The I terminal, 2, of the alternator supplies signal via the CCM module to the EIC indicator lamp. Voltage is below 11 volts if the lamp is on solid and above 16 volts if the lamp is flashing.




25

INTERCOOLER OVERHEATED

Lamp, 1, will illuminate and the non-critical alarm will sound when an overheat condition occurs. The cause of the alarm should be determined and corrected before further operation or engine damage may occur.

The sender, 2, supplies a temperature signal to the CCM which will generate an alert at greater than 82°C (180°F) and cause the lamp to be illuminated.




26

TRANSMISSION PRESSURE LOW

Lamp, 1, illuminated accompanied by the critical alarm, indicates that the transmission low- pressure circuit was low for at least eight seconds. The engine Stop message will flash for 30 seconds before automatic engine shutdown occurs.

Stop the engine and investigate the cause.

The sender, 2, is a normally closed switch that opens at greater than 8.2 bar (120 PSI) which causes the lamp to go out under normal conditions.



27


TRANSMISSION, REAR AXLE/ HYDRAULIC OIL TEMPERATURE

Lamp, 1, illuminated accompanied by the critical alarm indicates high oil temperature. The engine Stop message will flash for 30 seconds before automatic engine shutdown occurs.

Stop engine and investigate the cause.

The sender, 2, supplies a temperature signal to the CCM which generates an alert at a temperature above 107°C (224°F) BSN D408025 and 116°C (240°F) ASN D408024 which causes the lamp to illuminate if the condition occurs for eight seconds or more.

NOTE: *To increase the temperature limit from 107 °C (224 °F) to 116 °C (240 °F) on tractors BSN D408025, download software package EIC level 06.37 or more recent.*




28

HYDRAULIC/TRANSMISSION FILTERS RESTRICTED

Lamp, 1, continually illuminated indicates that the hydraulic intake filter, 3, is blocked or partially blocked.

A flashing lamp, 1, indicates that the transmission filter, 2, is blocked or partially blocked.

Both are non-critical alarms and the filters should be serviced as soon as practicable and certainly within 1 hour of operation.




29

The switches, 2 and 3, are normally closed and opens when a pressure differential of 2.76 bar (40 PSI) is created by the oil passing through the filter.

The switch contacts will remain open until the pressure differential drops below 1.79 bar (26 PSI)

NOTE: *The filter restriction circuits only monitor the filters when the rear axle oil temperature is 38°C (100°F) or greater, as sensed by the rear axle temperature sensor Figure 25.*

This feature allows for some normal filter bypass valve operation that occurs with thick oil during cold weather startup conditions.



30


NOTE: *70 Series art shown in Figures 31 and 33.*

PTO ENGAGED

Lamp, 1, will illuminate whenever the engine is running and PTO is engaged. The lamp will flash and a 5-second alarm will sound if the operator leaves the seat while the PTO is engaged.


Depressing the button in the center of the switch, 2, and pulling upwards on the knob will engage the PTO. A lamp in the EIC and a PTO status light, 3, beside the switch will be illuminated. To disengage the PTO, push the knob down.

NOTE: *The PTO has a non-critical overspeed alert. If 540 PTO speed is greater than 630 RPM or 1000 PTO speed is greater than 1152 RPM, the "PTO ON" status lamp, 1, will flash and a 1-second audible alarm will occur. The green system status lamp will also flash when the PTO status "overspeed" alert occurs.*



31

The PTO solenoid, 1, is located at the rear of the tractor. It has a resistance of 7.6 ohms.



32


PROGRAMMABLE UP SHIFT

Lamp, 1, will illuminate when programmable up shift is selected.

PROGRAMMABLE DOWN SHIFT

Lamp, 2, will illuminate when programmable downshift is selected.

Depressing the front of the switch, 3, will allow an increase of 1, 2, or 3 gears depending on how the transmission is programmed. Pressing the back of the switch will reduce gear speeds by 1, 2, or 3 gears. This function is for field use in gears F1 - F12. See "Transmission Operation" Section 21, Chapter 1, for more details.




33

70 SERIES FWD ON

Lamp, 1, will illuminate when FWD is selected.

FWD AUTO

Lamp, 2, illuminates when switched to automatic Four Wheel Drive mode and the FWD clutch is driving.




34

70A SERIES FWD ON

The lamp, 1, will not illuminate when FWD is in the ON position. The switch, 3, will be illuminated.

FWD AUTO

The lamp, 1, illuminates when switched to automatic Four Wheel Drive mode or Terralock mode and the FWD clutch is driving. The lamp, 1, will not illuminate when the FWD is not engaged.




35

FOUR WHEEL DRIVE (FWD) SWITCH (if equipped)

Four wheel drive engagement is controlled by an electrical solenoid, 4, activated by a three-position rocker switch, 3. From OFF, press the front of the switch to the first position to engage AUTO FWD. In this position the FWD and lamp, 2, will turn off when one brake is used to assist turning and at speeds above 24.2 km/h (15 MPH). Terralock (70A Series only) will also disengage at speeds of 10 kph (6 MPH) or below at turn angles of 30° and higher or between 10 - 20 kph (6 - 13 MPH) at turn angles of 25° or higher and reengage at angles less than 30° or 25° respectively. As well as completely disengage at any angle above 24 kph (15 MPH) and reengage under 24 kph (15 MPH). Press to the full forward position to engage ON which will keep the FWD engaged full time at speeds below 24.2 km/h (15 MPH).

The FWD solenoid, 4, is located at the rear of the tractor and has a resistance of 9.4 ohms. The FWD is disengaged hydraulically. The solenoid is energized to disengage the FWD.

NOTE: *FWD is automatically engaged when the parking brake is applied with the engine running regardless of the FWD switch position. This assists in holding the tractor in a stationary position. FWD is also automatically engaged to assist in braking when both brakes are applied.*



36

HEADLIGHT HIGH BEAM

Lamp, 1, will illuminate when the tractor lights are switched to high beam.

High beam is selected with the headlights on using the multifunction switch, 2, Figure 15. Pull handle rearward to switch between High and Low beam.

SYSTEM STATUS

Lamp, 2, is illuminated when all systems are normal. It flashes when there is an out of range condition detected by the instrument panel while the engine is running.

PARKING BRAKE

With the key-start switch on, a continually illuminated lamp, 1, indicates that the parking brake is applied. If the gearshift lever is moved from neutral to a gear position with the parking brake applied, the alarm will sound, the transmission is disabled and a “P” operator prompt will flash.

Move the shift lever to neutral, release the parking brake and reselect a transmission gear.


If the key-start switch is turned off and the parking brake is not applied, a pulsating alarm will sound continuously in unison with the flashing parking brake lamp for approximately two minutes or until the parking brake is applied.

The switch, 2, is a push-button switch. With the lever lowered the switch is open. As the lever is raised the switch is closed. This illuminates the warning light. The audible alarm also sounds if the vehicle speed is in excess of 0.8 km/h (0.5 MPH) with the parking brake on.

⚠ WARNING ⚠


To avoid personal injury, always apply the parking brake before leaving the tractor seat.

If the operator leaves the seat with the engine running and gear shift in neutral, the parking brake pulsating audible alarm will signal in unison with the flashing parking brake lamp for 2 minutes or until the brake is applied.



70-550-686

37



70-550-687

38

BAR GRAPH DISPLAYS (LCD)

The four bar graphs each consist of twenty LCD segments and are located in the EIC.

All bar graph sensors are continuously tested for faults and will be displayed as a fault code in the TPM if a fault occurs. All segments of the bar graph will also flash.


Fuel Level

The outside left bar graph, 1, shows fuel level. Each segment of the bar graph display represents approximately one-twentieth (5 percent) of the total fuel content of the tanks.

When the fuel level falls so that only two segments of the bar graph are displayed, the bar graph will flash and the non-critical alarm will sound for one second.

The sender, 2, is located in the top of the fuel tank in front of the left cab door.

Changing fuel level causes movement of the float past reed switches, varying the resistance of the sender, which is sensed by the CCM and transmitted to the EIC. (see the following chart).




39

Bars Displayed	Fuel Reserve	Sender Resistance ± 5
1	5 %	440
2	10 %	418
3	15 %	396
4	20 %	374
5	25 %	352
6	30 %	330
7	35 %	308
8	40 %	286
9	45 %	264
10	50 %	242
11	55 %	220
12	60 %	198
13	65 %	176
14	70 %	154
15	75 %	132
16	80 %	110
17	85 %	88
18	90 %	66
19	95 %	44
20	Full	22

Engine Oil Pressure
The inside left bar graph, 1, indicates engine oil pressure. With normal engine oil pressure, up to sixteen segments of the bar graph will be displayed. This is represented by the green area of the adjacent range display.

Should engine oil pressure fall below a designated level with respect to ERPM, (see chart) the bar graph will flash. The critical alarm will sound, the word STOP will flash in the central display for 30 seconds before the engine will automatically shut down.

Stop the engine immediately and investigate the cause.



40

STOP AND AUDIBLE ALARM CONDITIONS

The STOP message will be be displayed if the engine oil pressure is less than indicated at engine speeds listed.

Bars Displayed	Oil Pressure	ERPM
2	<0.55 bar (< 8 PSI)	500-1500
4	<1.10 bar (< 16 PSI)	1500-2000
5	<1.65 bar (< 24 PSI)	2000-3000


The sender, 2, monitors the pressure of the engine lubricating oil in the pump delivery gallery and operates on a +5.0 V power supply from the CCM. Changes in engine oil pressure cause the sender to generate a signal voltage proportional to the oil pressure which results in a corresponding number of bar graph segments on the EIC display (see chart).

Bars Displayed	Pressure		Sender Voltage ± 0.15
	Bar ± 0.28	PSI +5,-0	
1	< 0.55	< 5	< 1.50
2	0.85	5	1.59
3	1.16	10	1.78
4	1.46	15	1.96
5	1.77	20	2.15
6	2.07	25	2.33
7	2.38	30	2.52
8	2.68	35	2.71
9	2.99	40	2.89
10	3.29	45	3.08
11	3.60	50	3.26
12	3.90	55	3.45
13	4.21	60	3.54
14	4.51	65	3.82
15	4.82	70	4.00
16	5.12	75	4.19
17	5.43	80	4.37
18	5.73	85	4.56
19	6.04	90	4.74
20	>6.35	>95	>4.93

Engine Coolant Temperature

The right inside bar graph, 1, relates to coolant temperature. One segment of the bar graph will be displayed if the engine is cold. The number of segments displayed will increase as the engine warms up. With the engine at normal operating temperature, up to fifteen segments will be displayed. The normal working range is indicated by the green area of the adjacent range display.

Should the coolant temperature exceed a 112° C (235° F) predetermined level, the coolant symbol and the bar graph will flash. The critical alarm will sound, the word STOP will flash in the central display for 30 seconds before the engine will automatically shut down.



41

Stop the engine immediately and investigate the cause.

The sender, 2, monitors the temperature of the engine coolant and operates on a +5.0 V power supply from the CCM which transmits a signal to the EIC.

The sender resistance will increase as the temperature decreases at 20° C (68° F). The resistance will be approximately 2500 ohms.

Changes in coolant temperature cause the resistance of the sender to alter resulting in a varying voltage to the CCM (see the following chart).

Bars Displayed	Temperature		Sender Resistance ± 10
	°C + 1.5/- 0	°F + 5/- 0	
1	<65	<150	> 560
2	66	150	543
3	68	155	505
4	71	160	458
5	73	165	420
6	76	170	388
7	79	175	358
8	82	180	334
9	85	185	313
10	87	190	290
11	90	195	270
12	96	200	250
13	98	205	235
14	101	210	223
15	103	215	205
16	105	220	193
17	107	225	183
18	110	230	170
19	112	235	163
20	> 115	> 240	<160

Exhaust Temperature


The right outside bar graph, 1, relates to engine exhaust temperature. The number of segments displayed will increase as the engine warms up. With the engine at normal operating temperature, up to fifteen segments will be displayed which is represented by the green area of the adjacent operating display. With an exhaust temperature overheat condition, a non-critical alarm will sound and the bar graph will flash.

For the 8670/8670A, 8770/8770A and 8870/8870A, the bar graph will fill within 2 bars of the top and will begin to flash and the alarm will sound.

For the 8970/8970A, the bar graph will fill completely and begin to flash and the alarm will sound.

Reduce the engine load until the temperature returns to the normal operating range.

The sender, 2, monitors the temperature of the exhaust gas and supplies a signal to the CCM which is transmitted to the EIC. (See the following chart.)



42

Bars Displayed	Temperature		Sender Voltage Millivolts ± 1 mv
	°C ± 12	°F ± 20	
1	<398	<750	< 16.10
2	398	750	16.63
3	412	775	17.22
4	426	800	17.81
5	440	825	17.39
6	454	850	18.96
7	468	875	19.58
8	482	900	20.17
9	496	925	20.76
10	510	950	21.35
11	523	975	21.94
12	537	1000	22.54
13	551	1025	23.13
14	565	1050	23.72
15	579	1075	24.31
16	593	1100	24.90
17	607	1125	25.49
18	621	1150	26.08
19	635	1175	26.67
20	>650	>1200	> 27.02

CENTRAL DISPLAY (LCD)


Three liquid crystal displays (LCD) are located in the center of the instrument cluster.

At the top of the display is the digital transmission gear shift position display, 1.

In the center is the digital engine speed display, 2.

The bottom LCD, 3, will display:

- Engine hours accumulated (actual time)
- Tractor ground speed (MPH or km/h)
- PTO speed (RPM) as selected using the touch-sensitive switches at the right of the display.
- Service alert intervals I and II.



43

Transmission Gear Shift Position Display


NOTE: *70 Series art shown in Figure 44.*

The upper LCD, 1, provides a display of the gear ratio selected.

- Left digit, 2, displays a letter as follows:
  - F -- Forward gear selected *
  - N -- Neutral selected
  - R -- Reverse gear selected *
  - C -- Creeper gear speeds selected (If equipped)
  - A -- Automatic shift selected
  - P -- Parking brake applied *
  - U -- Upshift selected *
  - d -- Down shift selected *
  - The right digits, 3, display gear speeds 1 -16.

  * If the digit is flashing, the display is indicating an “Operator Prompt.” To return to normal operation, the shift control lever must be returned to neutral.


The display will change when the gear shift control lever, 4, is moved to change speeds or direction.



44

Engine Speed - Digital Display

With the engine running, the RPM legend, 2, will be displayed together with a digital value, 1, of the engine RPM in the main LCD. The engine LCD will register in increments of 10 RPM. If a critical engine or driveline fault should occur, the word STOP will flash for 30 seconds in the display area and the engine will shut down automatically.




45

The engine speed sender, 3, is located in the front top of the transmission on the right side. This reluctance sensor contains a small wire coil and a magnet at the tip.

The sender is positioned so that it is close to the teeth of the transmission input gear. When the gear rotates, each gear tooth induces a pulse of electric current which is transmitted to the ETC.


The sender resistance is approximately 2500 ohms.



46

LOWER SELECTABLE DISPLAY

The lower display will allow the operator to select one of 3 displays as follows:



47

Engine Hour Meter

When the key-start switch is turned on, the hour meter symbol, 1, will display and the hours the engine has operated will appear in the LCD, 3.

The operator may manually select another function such as ground speed or PTO. Driving the tractor will cause the display to change automatically to ground speed. The hour meter display may be recalled at any time by touching switch, 6.

With the engine running, the hour meter will accumulate hours in increments of 0.1 hour until 1999.9 hours are reached. After that time, the hour meter will accumulate complete hours only, e.g., 2000, 2001 hours, etc.


NOTE: *Accumulated hours are stored in the computer permanent memory which is not affected by disconnecting the tractor batteries.*

The hour meter may be programmed to remind the operator when the next scheduled service is due. When a “Service Alert” is reached, the word “SERVICE,” 2, will flash along with the selected display. See Mode 1, Operator Calibration for programming the Service alert interval.

Ground Speed Display (Speedometer)

Touch switch, 4, to show the ground speed, 1, in the main display. The MPH, 2, or km/h legend, 3, as appropriate, will also be displayed.

NOTE: *The electronic instrument panel is set at the factory to display either Metric (km/h & METERS) or English (MPH & FT.). If required, the display may be reprogrammed to show the desired values by holding the E/M switch, 7, for three seconds. The display will change and convert the digits to the new values.*




48

NOTE: *The speedometer senses rotation of the rear axle and may be subject to errors caused by the effects of wheel slip, tire pressures/condition, etc. If the optional radar sensor is installed, the tractor senses true ground speed for greater measurement accuracy.*

NOTE: *The lower central display will automatically show ground speed if the tractor is travelling at more than 20 km/h (12.4 MPH). If required to display any other function, the appropriate selector switch must be continuously depressed.*

The sensor, 1, is screwed into the right lower side of the transmission housing and contains a small wire coil and a magnet in the tip. The sensor is positioned so that the coil is close to the teeth of the gear of the transmission output shaft. When the gear rotates, each tooth of the gear induces a pulse of electrical current into the coil which is transmitted to the electronic transmission controller (ETC). The pulse frequency is directly proportional to vehicle ground speed and is converted to ground speed (km/h or MPH) to display when the ground speed selection switch, 4, is pressed (units less radar only). If the tractor is equipped with radar speed sensing the magnetic sensor is only used for computing wheel slip or determining tractor movement. This reluctance sensor resistance is approximately 2500 ohms.



49

Power Take-Off Display


540/1000 RPM PTO Equipped Units (Model 8670/8670A)

Touch switch, 5, and the PTO 540 legend, 3, will display, together with the PTO speed, 1, in the LCD. If the 1000 RPM PTO shaft is in use, touch the selector switch again and the 1000 PTO legend, 2, will display together with a digital display of PTO speed.

The PTO drive has a non-critical overspeed alert that will signal the operator if the PTO 540 shaft reaches a speed of greater than 630 RPMs, or the PTO 1000 shaft exceeds 1152 RPMs.

1000 RPM PTO Equipped Units (Models 8770/8770A, 8870/8870A, 8970/8970A)

Touch switch, 5, and the 1000 PTO legend, 2, will display, together with the PTO speed in the LCD.




50

ELECTRONIC INSTRUMENT CLUSTER - TRACTOR PERFORMANCE MONITOR (TPM)

INTRODUCTION

The Tractor Performance Monitor (TPM), 1, is displayed in the right-hand panel. The display includes:



51


Automatic Display Information

- Hitch enabled (with 3-point Hitch Control only)
- Hitch position digital value (with 3-point Hitch Control only)
- Hitch disabled (with 3-point Hitch Control only)
- Tractor fault code indicator

Selectable Displays

- Area per hour forecaster (acres or hectares)
- Area accumulated (acres or hectares)
- Wheel slip percent (optional feature)
- Battery voltage
- 540 PTO speed in RPMs (if equipped)
- 1000 PTO speed in RPMs scale
- Distance measurement in feet or meters

AUTOMATIC DISPLAY INFORMATION



52

Hitch Disabled Symbol (with 3-Point Hitch only)
The hitch disabled symbol, 1, is displayed when the 3-point linkage is out of phase with the 3-point hitch control lever. See “Electronic 3-Point Hitch Control.”

NOTE: *If the Hitch Disabled Symbol and 3-point status lamp on the right-hand console are flashing, a 3-point hitch control fault requires attention before proper operation of the tractor hitch can occur.*

Hitch Position Display (with 3-Point Hitch only)
The hitch position display, 2, advises the operator of the position of the lower links and implement by means of numbers ranging from “0” (fully lowered position) to “99” (maximum height position). See “Electronic 3-Point Hitch Control.”


Hitch Enabled Symbol (with 3-Point Hitch only)
The hitch enabled symbol, 3, is displayed to advise the operator when the three-point linkage is in phase with the 3-point hitch control lever. See “Electronic 3-Point Hitch Control.”

Fault Code Indicator
In the event that a fault occurs within the tractor’s electrical circuits, a malfunction warning symbol “READ YOUR MANUAL,” 4, will flash.

Fault codes can be reviewed using the procedure detailed in Mode 1, Operator Calibration.

If the fault code indicator or fault codes are displayed, refer to Mode 1, Operator Calibration, for information on retrieving and clearing the display.

SELECTABLE DISPLAY INFORMATION



53

Area Per Hour Forecaster

Touch the AREA/HR switch, 4. The “Area/Hour” legend, 1, will display, together with a forecast of the area that will be worked in one hour, 2, if the current rate of work is continued.

This forecast is based on the last five seconds running average. The forecast may be in hectares (METERS) or acres (FT.), 3, and can be changed by holding the E/M switch for three seconds.

“0” will be displayed whenever the tractor is stopped.

NOTE: *If the radar option is not installed, area per hour calculations are based on axle speed and are subject to inaccuracies caused by the wheel slip that may be present.*

Area Accumulator

Accumulated area (total area worked), 1, can be displayed by depressing the AREA switch, 2. Area is displayed in hectares or acres. “AREA” and “ON,” 6, will be displayed. Touch the “START/STOP” switch, 3, and the word “OFF,” 5, will display indicating the area counter is shut off.

If the 3-point hitch is raised with the lift control lever, or the RAISE/WORK switch, the word “OFF” should appear to stop area accumulation. Lower the 3-point hitch to again display “ON” and begin accumulating area.


NOTE: *A remote implement status switch can also be added to the tractor by use of a purple wire (CM40) located behind the operator’s seat, under the floormat. By adding a contact switch to a trailing implement, the area counter can be turned on and off by lowering and raising the implement.*

English display, designated by “FT” legend, 4, starts to accumulate in increments of 0.1 acres. When 1000 acres is reached, area accumulation continues in whole acres. When 9999 acres is reached, the display will reset to zero.

Metric display, designated by METERS legend, starts to accumulate in increments of .01 hectares. When 100.0 hectares is reached, area accumulation continues in increments of 0.1 hectares until 1000 is reached. The display will then accumulate whole hectares. When 9999 hectares is reached, the display will reset to zero.

Area accumulation can be reset to zero at any time by holding down the START/STOP switch, 3, until a “beep” is heard from the audio alarm (approximately three seconds).

NOTE: *If the radar option is not installed, area calculations are based on axle speed and are subject to inaccuracies caused by wheel slip that may be present.*




54

Wheel Slip (with Radar Option)
Touch the % SLIP selector switch, 4. The “% SLIP” legend, 1, will display together with a two-digit slip value, 2, in the main TPM display if the tractor has the optional radar sensor. The slip value is determined by the comparison of theoretical ground speed (axle rotation sensor) with true ground speed (radar sensor).

Slip ”zero” calibration occurs automatically. However, when widely differing soil conditions are encountered, it may be necessary to manually zero the wheel slip ratio, as follows:

Drive the tractor in the soil conditions to be worked, with implement raised, at a constant speed of less than 16 km/h (10 MPH). This will determine the minimum wheel slip under light operating conditions to be used as a 0% reference point. With % SLIP function, selected, hold down the START/STOP switch, 5, for at least 3 seconds.

A “beep” from the alarm and “0” in the display indicates that the computer has been calibrated to the minimum slip condition.



55


Slip Alarm (with Radar Option)
A slip alarm point may be entered - See Mode 1, Operator Calibration. When wheel slip exceeds the value entered, the alarm will sound for one second. If wheel slip is selected, the “% SLIP” legend, 1, will be displayed. In addition, the “ALARM” legend, 3, will flash and continue to flash until wheel slip is reduced below the present level.

WARNING

The radar ground speed sensor emits a low intensity microwave signal which will not cause any ill effects in normal use.


Although the signal intensity is low, do not look directly into the face of the radar sensor while in operation so as to avoid possible eye damage.

***IMPORTANT**: Before carrying out arc welding on the tractor or on any equipment attached to the tractor, disconnect all power and ground leads from the batteries in order to avoid possible damage to electronic components.*



56


Battery Voltage
Touch the SET UP/SELECT switch, 3. The “VOLTS” legend, 1, will display, together with a digital display of battery voltage, 2, to the nearest tenth volt.



57


PTO Speed 540 RPM Scale
(Model 8670/8670A ONLY)
Touch the SET UP/SELECT switch, 4, again and the “540 PTO” legend, 1, will be displayed, together with a digital display of PTO speed, 2. This feature allows the operator to view both PTO speed and ground speed while operating.

PTO Speed 1000 RPM Scale
Touch the SET UP/SELECT switch, 4, again and the “1000 PTO” legend, 3, will be displayed, together with a digital display of PTO speed, 2. This feature allows the operator to view both PTO speed and ground speed while operating.



58

Distance Measurement
Touch the SET UP/SELECT switch, 6, again and the “DIST FT,” 1, or “DIST METERS” legend will be displayed. The tractor will now measure distance in feet or meters. Operate the tractor normally and press the “START/STOP” switch, 5, at the point where distance measuring is to begin. The ON legend, 2, will be displayed along with a digital display of distance traveled, 3. At the end of the distance, again press the “START/STOP” switch, 5. A digital display of distance traveled in feet or meters will be displayed with the OFF legend, 4. If the “START/STOP” switch is again pressed, additional feet or meters will be added to the existing measurement. Pressing the START/STOP switch, 5, for more than three seconds will zero the display.



59

EIC LIGHTING DISPLAY

LIGHTING DISPLAY

The lighting display, 1, is located at the lower left corner of the EIC.


It is used to activate and monitor the dash and four work light circuits on the tractor.

The operation of the lighting display is covered under the Section 55, Chapter 5, “Lighting Circuits.”

The display will indicate that the lights are on by illuminating the hood light, 2, in the monitor.

The light will be on any time the rotary light switch is in any position other than the OFF position regardless of the key position.


NOTE: *An audible alarm will sound for five seconds if the lights are on and the key switch is turned off.*



70-550-373

60

TROUBLESHOOTING AND DIAGNOSTICS




Mode 13 (70A Series only) is only present when the tractor has a steering angle sensor and in Mode 12, feature 14 is set to 1.

* Can be accessed with engine running.

+ Hold SET-UP/SELECT 3 seconds to save new values.

EIC HARNESS TOOL

EIC harness tool, 1, part #FNH00549, allows the technician to pull EIC, 2, from the dashboard to provide better access for servicing the EIC. This is a recommended tool.



61

MODE 1, OPERATOR CALIBRATIONS


This mode is accessed by the operator to change data to provide accurate area measurement and service information.

ELECTRONIC INSTRUMENT CLUSTER - PROGRAMMING

Operator Calibration


In order that the computer may correctly calculate and display work done (area per hour, area accumulated, etc.) various factors must be entered into the computer. This is done by using the TPM programming switches:

START/STOP RESET, 1; SET UP/SELECT, 2; DIGIT SELECT, 3; DIGIT SET, 4.



62

1. To access the programming mode, with the key-start switch on, hold down the SET UP/SELECT switch, 2, (approximately 3 seconds) until a “beep” is heard from the alarm.
2. The TPM display, 1, will indicate _ _ _ 1, which means the EIC is at the first of 12 programming and diagnostic modes. Touching the DIGIT SET switch, 3, will cycle through modes 1 - 12 (13 if present). Mode _ _ _ 1, is for operator calibrations.
3. To enter Mode 1, again hold the SET UP/SELECT switch, 2, for 3 seconds. The TPM display will show IMP. WIDTH and a flashing left-hand digit.
4. When in the set up mode, repeatedly touching the SET UP/SELECT switch, 2, will cause the computer to run through the various set up functions in the following order:
    1. Implement width
    2. Slip alarm point (option)
    3. Service Alert Indicator I
    4. Service Alert Indicator II
    5. Ground speed calibration
    6. Area Preset
    7. Fault Codes ON/OFF
    8. Implement Calibration (Rev. 5 software only)



63


Setting Implement Width

1. In order that the computer may calculate the work done, the working width of the implement in use must be entered into the memory.
2. Implement width is a four-digit display and will appear as “000.0” feet, 2, or “00.00” meters with the left-hand digit, 1, flashing. “IMP WIDTH CAL,” 7, and either “FT,” 6, or “METERS” will also be displayed.
3. Touch the digit select switch, 4, to move the flashing digit to the right. Touch the digit set switch, 5, to increase the numerical value of the flashing digit.

   For example: To set an implement working width of 12.5 feet, a display of “012.5” is required.
4. Touch the DIGIT SELECT switch, 4, to cause the second digit from the left to flash.
5. Touch the DIGIT SET switch, 5, to change the flashing digit from “0” to “1.”
6. Use the DIGIT SELECT, 4, and DIGIT SET, 5, switches to change the remaining digits until “012.5” is displayed.

NOTE: *The area measured will only be accurate if there is no implement overlap when the tractor turns around at the end of a run to make another pass. Alternatively, the implement width entered into the computer memory may be reduced by the estimated amount of overlap.*

7. With the required implement width displayed, touch the SET UP/SELECT switch, 3, to enter the Implement Width into memory and change the display to the % SLIP alarm point if the tractor is radar equipped.




64

Setting the Slip Alarm Point (Option)

NOTE: *If the optional radar unit is not installed, the slip alarm function will be omitted from the sequence.*

1. The slip alarm point will appear as a two-digit display with the left-hand digit, 1, flashing. “% SLIP,” 2, and “ALARM,” 3, will also be displayed with the word CAL, 4.
2. Use the DIGIT SET, 7, and DIGIT SELECT, 6, switches to change the value to the required setting.
3. If the slip alarm is not required, set the display, 1, to “00.”
4. With the required slip alarm point displayed, touch the SET UP/SELECT switch, 5, to enter the alarm point into the memory and change the lower display to show the first Service Alert Indicator “I.”




65

Programming the "Service Alert Indicators"
During normal tractor operation, the hour meter, 2, will reach preprogrammed service intervals.

This causes the word "SERVICE," 1, to flash next to the hour meter symbol, 3, whenever the key is on, if service is due. The symbol will flash until the specific service is completed and the display is reset or for 10 hours of operation.

The operator can program one, two or no "Service Alert Indicators" into the lower selectable LCD.


Example: The operator wants the hour meter to signal for minor service every 50 hours and major service to be performed every 300 hours.



66

The letter "l," 1, and the three-digit number, 2, in the display corresponds to the "next service due" interval previously entered into the memory. If l 025 is displayed, the hour meter will signal the operator every 25 hours that service is due. A "l 000" programmed into the display will disable the "Service Alert Indicator."


1. The left-hand digit of the display will be flashing. If the digit is already reading "0," there is no need to change it.
2. Touch the DIGIT SELECT switch, 3, to select the next digit to the right. The second digit will now flash.



67


3. Each touch of the DIGIT SET switch, 6, will increase the value of the flashing digit, 1, by one.
4. When the digit reaches "5," touch the DIGIT SELECT switch, 5, which will cause the next digit, 2, in the display to flash.
5. Change the value of this digit, if necessary, using the DIGIT SET switch, as previously described until it reaches "0."
6. With "l 050" displayed, enter the display into the memory by turning the key-start switch off or touching the SET UP/SELECT switch, 4.
7. The "Service Alert" Indicator II can now be programmed for the 300-hour service interval.

   Every 50 hours of tractor operation the word "SERVICE" will flash when the key is on. The display will continue to flash until the START/ STOP, RESET switch, 3, is used to cancel the flashing display after reentering the "Service Alert" programming mode.



68

To program the “Service Alert Indicator II,” the process is the same as for ”Service Alert I” but when the SET UP/SELECT switch, 3, is touched, the left digits will be “II,” 1. The next digit, 2, will be flashing indicating that the operator can now program the 300-hour “Service Alert Interval II.” To store the 300-hour service alert, momentarily depress the SET UP/SELECT switch, 3.




69

CANCEL FLASHING “SERVICE” INDICATOR

1. To identify which service is due and to cancel the alert after the service has been completed, reenter the service alert programming menu.
2. If the word “SERVICE,” 1, is flashing and a single I is displayed, complete the 50-hour service as described in the maintenance section and cancel alert by holding the START/STOP, RESET switch, 3, for three seconds.
3. The left digit will begin flashing indicating that the service hour interval can now be changed.
4. If no change is desired, touch the SET UP/SELECT switch, 4, to select the service alert II indicator.
5. If the word “SERVICE,” 1, is flashing and II, 5, is displayed, the 300-hour service, 2, is required.
6. To cancel the alert, after the service has been completed, hold the START/STOP RESET switch, 3, for three seconds.

NOTE: *If the START/STOP, RESET switch, 3, is held for an additional three seconds, the previously stored service alert interval will be reset to 0. To reprogram a new interval, review the previous programming steps.*


7. After the service intervals have been entered, touch the SET UP/SELECT switch, 4, to view and change the “Ground Speed Calibration” constant.



70

Ground Speed Calibration


The ground speed in the display is calibrated at the factory to suit the static radius of the rear tires. However, should tires of a different size be installed, weights or equipment permanently installed on the tractor that would alter the static radius of the tires by more than 13 mm (0.5″), the EIC should be recalibrated to display a more accurate ground speed using the following method:



71

1. Ensure that the tire pressures are correct for the load being carried. (See Tire Load/Inflation Tables in the Operator's Manual).
2. Park the tractor on a firm level surface and carefully measure the distance from the center of the rear axle shaft to the ground. This is the static radius.
3. While in the programming mode, ensure that the word "CAL," 4, the "FT, 3, or METERS" legend and the previously entered calibration number, 2, is displayed with the left-hand digit, 1, flashing.
4. If required, change the value of the flashing digit using the DIGIT SET switch, 7, as described previously in "Programming The Service Alert Indicator."
5. Enter the actual static radius, 1, of the tire in inches to the closest 0.1 inch or the closest mm if using metric units.

NOTE: *The minimum allowable number is 609 mm (24 inches) depending on the unit of measure selected.*



72

6. To select the next digit to the right, use the DIGIT SELECT switch, 6, and when that digit is flashing use the DIGIT SET switch, 7, to change the value.
7. Repeat for the remaining digits.
8. When the required calibration number is displayed, enter it into the memory by holding the SET UP/SELECT switch, 5, for three seconds. (The number is saved in the CCM.)

All tractors equipped with a radar gun will automatically recalculate the tire-loaded radius whenever the tractor speed exceeds 10 mph.

This automatic recalculation program runs constantly and can easily cause an incorrect radius number to be stored in the ECM. The number will change if the tractor is driven in a right-hand turn, left-hand turn, or in a straight line.

This automatic recalculation program makes it unnecessary to manually enter the loaded radius number in mode 1 on radar-equipped tractors. The manual process actually adds to the confusion.

Software has been developed that revised the recalculation process. This software, Version 6.37, has been installed at the factory since December 4, 1995, starting with tractor serial number D408025. This new software delays the automatic recalculation process until the tractor has been traveling above 10 mph for more than 20 seconds. It will take 15 minutes of sustained operation above 10 mph to see a change to the new valve.

If manually entering a loaded radius number is desired, it can best be done by performing a “zero” wheel slip function. This function will automatically write the current loaded-radius number into the CCM.

NOTE: *The loaded-radius number is stored in the CCM, NOT the EIC. The EIC reads the number from the CCM for display purposes.*

It has also been found that holding the SETUP/SELECT switch down too long after entering mode 1, the EIC will lock up. This lock-up condition automatically erases the loaded radius number written in the CCM and enters the start-up number (24.0). Press the E/M switch twice to unlock the EIC. The new software eliminates this condition.

The 400 ft. calibration tests can cause incorrect radar gun operation if the test is performed incorrectly. The 400 ft. calibration test will automatically add a compensation factor to the radar gun computations to allow for slight mounting irregularities. If the calibration test is not correctly performed, the radar gun distance measuring and ground speed numbers will not be correct.


EXAMPLE: You drove the tractor 360 ft. but told the radar the tractor traveled 400 ft. This caused an incorrect compensation factor to be added to the radar gun computations that resulted in indicated speeds being 10% fast (i.e. the radar measures a known 400 ft. course as 440 ft., which results in ground speed being calculated as 22 mph instead of the actual 20 mph). This error is easy to correct. Just redo the 400 ft. calibration on a known 400 ft. course.

To minimize confusion, do NOT perform the 400 ft. calibration test on tractors equipped with radar guns. Leave the radar equation at its factory setting. This equation cannot be read with the PDT or the EIC.

On tractors without a radar gun, the 400 ft. calibration test will calculate the loaded radius and is still a useable function.

For improved accuracy in calibrating ground speed, use the following procedure for tractors WITHOUT a radar gun.

1. Ensure the EIC is in the ground speed calibration mode.
2. Drive the tractor, 1, to the start of a measured 121.83 m (400 ft) course, 2. Depress the START/STOP switch, 3, at the start of the course and again at the end of the course.
3. The EIC will store a calibration number for accurate ground speed.
4. Touch the SET UP/SELECT switch, 4, again to cycle to the next calibration step which is “Area Preset.”




73

Area Preset

Normally, area would be reset to zero by holding the START/STOP switch, 3, down until a “beep” is heard from the alarm (approximately three seconds). When in the AREA PRESET calibration mode however, it is possible to enter a value other than zero. Area measured during a previous operation can be entered.

1. The area preset will appear as a four-digit display with the left-hand digit, 1, flashing. “AREA,” 8, will also be displayed in the LCD along with the CAL legend, 2, and FT., or METERS legend, 7.
2. Use the DIGIT SET, 6, and DIGIT SELECT, 5, switches, as previously described, to change the value to the required setting or to zero.
3. Touch the SET UP/SELECT switch, 4, to enter the value into memory and view the “Fault Codes ON/OFF” selection.




74

Fault Codes On/Off

Fault codes can be viewed during tractor operation or stored to allow full operation of the TPM. Fault codes occur in the following areas of the tractor control modules:

CODE NUMBERS	CONTROL MODULE
F000-099	EDC-Electronic Draft Control
F100-199	RHC-Right Hand Controls
F200-299	EIC-Electronic Instrument Cluster
F300-399	ETC-Electric Transmission Contr.
F400-499	Engine faults
F600-699	Engineering development and may be ignored. If desirable, delete in normal fashion as described below.


1. To view fault codes as they occur, press the START/STOP switch, 4.
2. The display will show the Read Your Manual symbol, 1, and the ON legend, 2.
3. Press the START/STOP switch again and the Read Your Manual legend, 1, and OFF legend, 3, will be displayed.
4. When ON, 2, is displayed, fault codes will appear as they occur.
5. When OFF, 3, is displayed, the fault code will not be displayed.
6. Touch the SET UP/SELECT switch, 5, and the display will cycle back to the first programming step for “Setting Implement Width” review or further programming.



75

When fault code “ON” is selected and faults are detected, the fault codes will flash sequentially in the lower right TPM display.

NOTE: *The fault codes can be temporarily cleared to return to a normal display by holding the START/STOP switch, 2, for three seconds. When the key switch is turned to OFF and the tractor is restarted, the fault code(s) will reappear. Use the START/STOP switch to again temporarily cancel the display of the fault codes. The Read Your Manual symbol will continue to flash.*



76

Implement Calibration


The implement calibration feature allows the operator to program and identify the on/off point of the Tractor Performance Monitor (TPM) when using the 3-point hitch mounted implements. This means you can program the hitch so it turns on or off at a given height.

NOTE: *The tractor needs to have Rev. 5 software for the implement calibration feature. The software download is available on the dealer Intranet.*

See Dealer Intranet/Service/Product Software Updates/Ag Tractors/70 Series/70-70A Series Rev. 5.

To use the implement calibration feature, follow these steps:


1. Verify the height limit switch allows the hitch to lift to a position greater than 60 on the digital display.
2. Operate the hitch with implement and identify the hitch digital position to turn the TPM ON and OFF. This is usually just as the implement clears the ground or is about to come out of the ground. For example, this might be 45.
3. Go to the 8th position, implement calibration.
4. The TPM will display the abbreviations “IMP,” and “CAL,” Figure 77. It will also show two digits just below the 3-point arm position.
5. Use the DIGIT SET, 1, and DIGIT SELECT, 2, switches, Figure 12, to change the digits to the hitch position you found at step 2, which in this case would be 45.
6. Exit Mode 1 by pressing the E/M switch, 3, two times.
7. Press the AREA switch, 4.
8. Operate the hitch up and down. The acreage counter will indicate ON or OFF as the hitch is lowered through the set position or raised through the set position.



77

Exiting The Operator Calibration Mode


1. To exit the operator calibration mode, touch the E/M switch, 2. The display, 1, will show _ _ _ 1.
2. To enter modes 2-12, use the DIGIT SET switch, 3, to select the mode desired.
3. Touching the E/M switch again will return the display to normal operation.
4. To exit the set up mode at any time, the key-start switch can also be turned off.



78

MODE 2, VIEW STORED FAULT CODES


When this mode is entered, the displays will indicate where the fault has occurred and at what hour to the nearest tenth.



79

1. To enter the mode, hold the SET UP/SELECT switch, 2, to enter the mode selection menu. The display will show _ _ _ 1.
2. Touch the DIGIT SET switch, 3, to advance from mode 1 to mode 2.
3. The TPM display, 1, will show _ _ _ 2.
4. Hold the SET UP/ SELECT switch, 2, for three seconds.
5. Stored fault codes will now be displayed in the TPM display sequentially starting with the most recently occurring fault (F_ _ _) as follows:

CODE NUMBERS	SYSTEM MODULE
F000-099	EDC-Electronic Draft Control
F100-199	RHC-Right Hand Controls
F200-299	EIC-Electronic Instrument Cluster
F300-399	ETC-Electric Transmission Contr.
F400-499	Engine faults
F600-699	Engineering development and may be ignored. If desired, delete in the normal fashion as described below.



80

6. The hour that the fault occurred will be displayed in the lower central display, 2, with the hour legend.
7. If the fault has occurred more than one time, the number of times that it has repeated will appear in the gear display area, 1.
8. To cycle through the fault codes, 3, touch the SET UP/SELECT switch, 4, to view the next code.
9. All fault codes should be reviewed before troubleshooting any system.
10. After the codes have been reviewed and recorded, they can be erased by touching the START/STOP switch, 5, for three seconds (shutdown codes can't be erased).
11. The tractor should again be operated after repairs to insure that the fault does not reoccur. See Chart 1 for a complete diagnostic fault code list.
12. Touch the E/M switch, 6, to exit this mode and transfer to the mode selection menu.

CHART 1 - FAULT CODES

3PT HITCH/ EDC

Fault Codes	Description
F001	3PT TRANSIENT RESET
F002	3PT A to D CHANNEL LOCKUP
F003	TRUE GROUND SPEED > WHEEL SPEED
F004	AXLE SPEED > MAX SPEED
F006	SLIP LIMIT POT. FAILED LOW / SHORT
F007	SLIP LIMIT POT. FAILED HIGH / OPEN
F008	RAISE-WORK SWITCH - CONTACTS SAME
F009	FENDER 3PT SWITCHES - CONTACTS SAME
F010	HEIGHT LIMIT POT FAILED LOW / SHORT
F011	HEIGHT LIMIT POT FAILED HIGH / OPEN
F012	DROP RATE POT FAILED LOW / SHORT
F013	DROP RATE POT FAILED HIGH / OPEN
F014	RIGHT DRAFT PIN FAILED LOW / OPEN
F015	RIGHT DRAFT PIN FAILED HIGH / SHORT
F016	LEFT DRAFT PIN FAILED LOW /OPEN
F017	LEFT DRAFT PIN FAILED HIGH / SHORT
F018	DRAFT PINS BOTH DISCONNECTED/FAILED
F019	8 VOLT PINS SUPPLY FAILED LOW / OPEN
F020	8 VOLT PIN SUPPLY FAILED HIGH / SHORT
F021	SENSITIVITY (MIX) POT. FAILED LOW / SHORT
F022	SENSITIVITY (MIX) POT. FAILED HIGH/OPEN
F023	RHC 5 VOLT SUPPLY FAILED (5/2) / SHORT
F024	PERFORM HITCH CALIBRATION (MODE 11)
F025	QUAD LEVER POT FAILED LOW / SHORT
F026	QUAD LEVER POT FAILED HIGH / OPEN
F027	ROCKSHAFT POT FAILED LOW / SHORT
F028	ROCKSHAFT POT FAILED HIGH / OPEN
F029	3PT SOL.VALVE SHORT OR OPEN
F030	RHC 3PT POTS.SIGNAL GROUND FAILURE
F031	3PT MAIN REAR HARNESS DISCONNECTED
F057	3PT SOLENOIDS BOTH ON W/O COMMAND
F058	EDC 3POINT SIGNAL GROUND FAILED
F059	RAISE-WORK SWITCH - CONTACTS SAME
F063	3 POINT LOWER COIL SHORT OR OPEN
F064	3 POINT RAISE COIL SHORT OR OPEN
F098	ROCKSHAFT POT VALUES CHANGING
F099	3 POINT POT. VALUES CHANGING

RIGHT HAND CONTROLS (RHC)

Fault Codes	Description
F100	RHC SENSOR 5V SUPPLY (5/2) LOW, SHORTED
F101	RHC SENSOR 5V SUPPLY (5/2) HIGH
F102	TRANS UP SHIFT SWITCH OPEN
F103	TRANS UP SHIFT SWITCH SHORT
F104	TRANS DOWN SHIFT SWITCH OPEN
F105	TRANS DOWN SHIFT SWITCH SHORT
F106	TRANS REVERSE SWITCH OPEN
F107	TRANS REVERSE SWITCH SHORT
F108	TRANS FORWARD SWITCH OPEN
F109	TRANS FORWARD SWITCH SHORT

ELECTRONIC INSTRUMENT CLUSTER (EIC)

Fault Codes	Description
F200	EIC 5 VOLT SUPPLY LOW (5/1) / SHORT
F201	OUTPUT CIRCUIT SHORT
F202	EIC ERROR RHC CAN COMM. FAULT
F203	EIC ERROR EDC CAN COMM. FAULT
F204	EIC ERROR TCM CAN COMM. FAULT
F205	FEATURES SETUP-EIC/MODULES DISAGREE
F206	COLD START OUTPUT SHORT
F207	BOTH BRKES ENGAGED WHILE MOVING
F208	EIC SENSOR 5V SUPPLY HIGH (5/1)
F209	COLD START SWITCH

ELECTRONIC TRANSMISSION CONTROL (ETC)

Fault Codes	Description
F300	TRANS SOLENOID #1 SHORT
F301	TRANS SOLENOID #2 SHORT
F302	TRANS SOLENOID #3 SHORT
F303	TRANS SOLENOID A SHORT
F304	TRANS SOLENOID B SHORT
F305	TRANS SOLENOID C SHORT
F306	TRANS SOLENOID F1 SHORT
F307	TRANS SOLENOID F2 SHORT
F308	TRANS SOLENOID MC1 SHORT
F309	TRANS SOLENOID MC2 SHORT
F310	TRANS SOLENOID REV SHORT
F311	TRANS SOLENOID CREEP SHORT
F312	FWD SOLENOID SHORT
F313	FUEL HOLD-IN SOLENOID SHORT
F314	PTO SOLENOID SHORT
F315	DIFF-LOCK SOLENOID SHORT
F316	RELAY FUEL PULL-IN SHORT
F317	CONNECTOR 003 OPEN
F318	CONNECTOR 002 OPEN
F319	CONNECTOR 001 OPEN
F320	TRANS SOLENOID #1 OPEN
F321	TRANS SOLENOID #2 OPEN
F322	TRANS SOLENOID #3 OPEN
F323	TRANS SOLENOID A OPEN
F324	TRANS SOLENOID B OPEN
F325	TRANS SOLENOID C OPEN
F326	TRANS SOLENOID F1 OPEN
F327	TRANS SOLENOID F2 OPEN
F328	TRANS SOLENOID MC1 OPEN
F329	TRANS SOLENOID MC2 OPEN
F330	TRANS SOLENOID REV OPEN
F331	TRANS SOLENOID CREEP OPEN
F332	FWD SOLENOID OPEN
F333	FUEL HOLD-IN SOLENOID OPEN
F334	PTO SOLENOID OPEN
F335	DIFF-LOCK SOLENOID OPEN
F336	RELAY FUEL PULL-IN COIL OPEN
F337	TRAILER BRAKE FAULT (ISO ONLY)
F338	CCM 5 VOLT SUPPLY FAILED (5/3) / LOW
F339	CCM 5 VOLT SUPPLY FAILED (5/3) / HIGH
F340	AXLE SPEED SENSOR OPEN
F341	AXLE SPEED SENSOR SHORT
F342	ENGINE RPM SENSOR OPEN
F343	ENGINE RPM SENSOR SHORT
F344	ENGINE RPM SENSOR FAIL
F345	AXLE SPEED SENSOR FAIL
F346	INCH PEDAL (CLUTCH) SHORT TO GROUND
F347	INCH PEDAL (CLUTCH) OPEN CKT OR +VBAT
F348	INCH PEDAL (CLUTCH) CAL ERROR LOW
F349	INCH PEDAL (CLUTCH) CAL ERROR HIGH
F350	INCH PEDAL DOWN SWITCH/POT,DISAGREE
F351	INCH PEDAL UP SWITCH/POT. DISAGREE
F360	TRANS F1(FORWARD)CALIBRATION OFFSET CONSTANT
F361	TRANS F2(FORWARD)CALIB OFFSET CONSTANT
F362	TRANS R(REVERSE)CALIB OFFSET CONSTANT
F363	PROGRAMMABLE SHUTTLE CONSTANT
F365	TRANS F1/F2 SHIFT CAL.CONSTANT ERROR
F366	TRANS F2/F1 SHIFT CAL.CONSTANT ERROR
F370	STEERING ANGLE SENSOR SHORT TO GROUND
F371	STEERING ANGLE SENSOR CIRCUIT OPEN
F377	TRANS CONFIG BYTE 0 ERROR
F378	TRANS CONFIG BYTE 1 ERROR
F379	TRANS CONFIG BYTE 2 ERROR
F380	PROTOTYPE HARDWARE REV. ERROR
F381	PRODUCTION HARDWARE REV. ERROR
F382	PROG UPSHIFT CONSTANT ERROR
F383	PROG DOWNSHIFT CONSTANT ERROR
F386*	TRANS OIL TEMP HIGH (Shutdown)
F387*	TRANS OIL PRESSURE LOW (Shutdown)
F388	TRANS OIL PRESS. SENSOR FAILED LOW
F389	TRANS OIL TEMP SENSOR FAILED LOW
F390	TRANS OIL TEMP SENSOR FAILED HIGH
F391	HYDRAULIC FILTER STATUS
F392	TRANS FILTER STATUS
F393	POWER ON DIRECTIONALS
F399	ETC TRANSIENT RESET

ENGINE CONTROL

Fault Codes	Description
F400*	COOLANT TEMP TOO HIGH (Shutdown)
F401*	OIL PRESSURE TOO LOW (Shutdown)
F402	EGT TEMP TOO HIGH
F403	INTERCOOLER TEMP TOO HIGH
F404	FUEL LEVEL FAIL LOW
F405	FUEL LEVEL FAIL HIGH
F406	COOLANT TEMP FAIL LOW
F407	COOLANT TEMP FAIL HIGH
F408	ENGINE OIL PRESSURE FAIL LOW
F409	EGT SENSOR FAILED LOW
F410	EGT SENSOR FAILED HIGH
F411	INTERCOOLER Temp Sensor Failed Low
F412	INTERCOOLER Temp Sensor Failed High
F413	RADAR SENSE FAULT
F414	RADAR SIGNAL FAULT
F415	COOLANT LEVEL Sensor Failed Low
F416	COOLANT LEVEL Sensor Failed Off High
F417	ENGINE AIR FILTER STATUS
F418	COOLANT LEVEL STATUS
F419	ALTERNATOR NOT CHARGING
F420	ALTERNATOR OVERCHARGING (> 16 V)
F421	EIC ERROR VPOWER LOW
F422	CONNECTOR 008 DISCONNECTED

SOFTWARE DEVELOPMENT


F6XX NOT RELATED TO ANY CONCERN

* These faults cannot be erased from memory.

MODE 3, ALL MODULE INPUT PARAMETERS

Mode 3 allows the technician to check inputs (switches, potentiometer and sensors) to all modules without using additional testing equipment.

1. To enter this mode, touch the DIGIT SET switch 4, to advance from mode 2 to mode 3. The TPM display, 1, will show _ _ _ 3.
2. Hold the SET UP/SELECT switch, 3, for three seconds.
3. The technician can now operate all switches and potentiometers to see if they are functional.
4. As a technician touches any switch or rotates any potentiometer, the lower right TPM display will automatically switch to a parameter identifier number. An audible signal will be heard to indicate the switch and circuit are working.




81

5. The TPM will display the sensor identifier preceded by the letter "P _ _ _", 1, and signal if it is working.

   Example: P109 will be displayed when the shift control lever is moved to the left.
6. Input parameters are displayed in the following format:


IDENTIFIER	SYSTEM MODULE
P000-P049	EDC-Elec. draft contr., 3PT
P100-P149	RHC-Right hand controls
P200-P249	EIC-Elec. Instr. cluster
P300-P349	ETC-Elec. Trans. control
P400-P449	ETC-Engine control

7. Identifiers of "Lo" or "Hi" will be displayed in the 3-point hitch display area, 2, of the TPM display.
8. Identifiers of "Lo" means the sensor voltage is low at the module input connector (such as in an open switch). A single audible tone will sound. "Hi" means the voltage is high as in a closed or working circuit switched to +12V. A pulsating audible tone will sound when "Hi" is displayed.



82


9. Rotary controls (potentiometers), 1, are displayed in the same area but the identifier shown in the 3 point hitch display area, 2, of the TPM will be a digital value from 0-99 indicating the % of full scale. See chart 2, for identification of all switches and potentiometers.



83

10. To look at one parameter only, touch the SETUP/SELECT switch, 3.
11. The TPM display will show P000, 1, with the first "0" flashing.
12. Use the DIGIT SET, 5, and DIGIT SELECT, 4, switches to change the parameter to the switch, sender or potentiometer to be tested using chart 2.
13. To re-select automatic parameter selections, touch SET UP SELECT switch, 3, you can then return to one parameter selection by again touching the SET UP SELECT switch.

NOTE: *If no change is noticed when a circuit is activated, an input fault is present. Troubleshoot that half of the circuit.*




84

14. After a parameter, 1, is selected, activate the circuit and the 3-point hitch display, 2, will respond with Hi or Lo with the appropriate tone or a digital display for a potentiometer.

    In this example the 3-point hitch draft position sensitivity knob, (P121) has been rotated which will display a digital reading from approximately 7 - 89. No other switches, senders or potentiometers will change the display.

NOTE: *Insure that all potentiometers have a smooth transition of digits from low to high.*

15. Touch the E/M switch, 3, to exit this mode and transfer to the mode selection menu.



85

CHART 2 - ALL MODULE INPUT PARAMETERS

3PT HITCH / EDC INPUT PARAMETERS

I D	Description
P001	RIGHT DRAFT PIN
P002	LEFT DRAFT PIN
P003	ROCKSHAFT POTENTIOMETER

RIGHT HAND CONTROLS (RHC) INPUT PARAMETERS

I D	Description
P101	FRONT WHEEL DRIVE ON
P102	FRONT WHEEL DRIVE AUTO
P103	DIFF-LOCK OFF
P104	DIFF-LOCK ON
P106	PTO START / STOP
P107	TRANSMISSION ENABLE
P108	NEUTRAL (WHEN CRANKING ENGINE)
P109	DOWNSHIFT
P110	UPSHIFT
P111	REVERSE
P112	FORWARD
P113	PROGRAMMABLE DOWNSHIFT
P114	PROGRAMMABLE UPSHIFT
P115	AUTOSHIFT
P119	WORK SWITCH
P120	RAISE SWITCH
P121	SENSITIVITY (MIX) POT.
P122	DROP RATE POTENTIOMETER
P123	HEIGHT LIMIT POTENTIOMETER
P124	SLIP LIMIT POTENTIOMETER
P125	QUADRANT LEVER POT.

ELECTRONIC INSTRUMENT CLUSTER (EIC) INPUT PARAMETERS

I D	Description
P201	WORK LAMP SENSE
P202	LEFT BRAKE
P203	RIGHT BRAKE
P204	PARK BRAKE
P205	FENDER 3PT RAISE CIRCUIT
P206	FENDER 3PT LOWER CIRCUIT
P207	MAIN BEAM
P208	RIGHT TURN
P209	LEFT TURN
P210	CREEPER
P211	SHUT DOWN OVERRIDE
P212	COLD START
P213	TRAILER 1
P214	TRAILER 2
P215	INCHING PEDAL POTENTIOMETER
P216	PARK LIGHT SENSE
P217	540 PTO
P218	1000 PTO
P219	WHEEL SLIP
P220	AREA
P221	AREA / HOUR
P222	DISTANCE
P223	GROUND SPEED
P224	ENGINE HOURS
P225	VOLTS
P226	IMPLEMENT WIDTH
P227	SLIP ALARM
P228	ENGINE RPM

ELECTRONIC TRANSMISSION CONTROL (ETC) INPUT PARAMETERS

I D	Description
P300	RADAR SPEED SENSOR
P301	AXLE SPEED SENSOR
P302	Unassigned
P303	Unassigned

ELECTRONIC ENGINE CONTROLS INPUT PARAMETERS


I D	Description
P400	ENGINE COOLANT TEMP
P401	ENGINE OIL PRESSURE
P402	FUEL LEVEL
P403	ENGINE EXHAUST TEMPERATURE
P404	INTERCOOLER TEMPERATURE
P405	TRANS OIL TEMPERATURE
P406	COOLANT LEVEL
P407	TRANS OIL FILTER
P408	HYDRAULIC FILTER
P409	ENGINE AIR FILTER
P410	TRANS OIL PRESSURE
P411	RADAR SENSE
P412	SEAT SWITCH
P413	REMOTE IMPLEMENT STATUS
P414	STEERING ANGLE SENSOR

MODE 4, EIC OUTPUT DIAGNOSTICS

In this mode, the technician can power circuits* that are controlled by the EIC module.

If the circuit can be powered in this mode, the output portion on the circuit is functioning. If the circuit isn't working, the input or switching part of the circuit is at fault.


1. To enter this mode, touch the DIGIT SET switch, 5, to advance from mode 3 to mode 4. The display, 1, will show _ _ _ 4.
2. Hold the SET UP/SELECT switch, 4, for three seconds to enter mode 4.
3. Use the DIGIT SET switch, 5, to cycle through the different circuits available and then use the START/STOP switch, 3, to turn the circuit on or off.



86

4. The circuit selected will be displayed, 1, in the TPM and the word "Hi or Lo", 2, will be displayed in the 3-point hitch display to indicate the status of the circuit. Hi = ON and Lo = OFF.
5. See Chart 4 for circuit identification.
6. Touch the E/M switch, 3, to exit this mode and transfer to the mode selection menu.

*The cold start assist output drive is not accessible in mode 4.



87

CHART 4 - EIC OUTPUT DIAGNOSTICS

ELECTRONIC INSTRUMENT CLUSTER (RHC) OUTPUT PARAMETERS


I D	Description
P250	WORK LAMP 1 DRIVE
P251	WORK LAMP 2 DRIVE
P252	WORK LAMP 3 DRIVE
P253	WORK LAMP 4 DRIVE
P254	SOUND ALERT DRIVE
P255	THERMOSTART RELAY

MODE 5, RHC OUTPUT DIAGNOSTICS

In this mode, the technician can power all circuits that are controlled by the RHC module.


If the circuit can be powered in this mode, the output portion on the circuit is functioning. If the circuit isn't working, the input or switching part of the circuit is at fault.

1. To enter this mode, touch the DIGIT SET switch, 5, to advance from mode 4 to mode 5. The display, 1, will show _ _ _5.
2. Hold the SET UP/SELECT switch, 4, for three seconds to enter mode 5.
3. Use the DIGIT SET switch, 5, to cycle through the different circuits and then use the START/STOP switch, 3, to turn the circuit on or off.



88

4. The circuit selected will be displayed in the TPM, 1, and the word "Hi or Lo" will be displayed in the 3-point hitch display to indicate the status of the circuit. Hi = ON and Lo = OFF.
5. See Chart 5 for circuit identification.
6. To exit this mode, touch the E/M switch, 3, and transfer to the mode selector menu.



89

CHART 5 - RHC OUTPUT DIAGNOSTICS

RIGHT HAND CONTROLS (RHC) OUTPUT PARAMETERS


I D	Description
P150	FWD STATUS LAMP DRIVE
P151	DIFF LOCK STATUS LAMP DRIVE
P152	PTO STATUS LAMP DRIVE
P153	EDC STATUS LAMP DRIVE
P154	SLIP LIMIT STATUS LAMP DRIVE

MODE 6, EDC OUTPUT DIAGNOSTICS

In this mode, the technician can power all circuits that are controlled by the EDC module.


If the circuit can be powered in this mode, the output portion on the circuit is functioning. If the circuit isn't working, the input or switching part of the circuit is at fault.

1. To enter this mode, touch the DIGIT SET switch, 5, to advance from mode 5 to mode 6. The TPM display, 1, will show _ _ _6.
2. Hold the SET UP/SELECT switch, 4, for three seconds to enter mode 6.
3. Use the DIGIT SET switch, 5, to cycle through the different circuits and then use the START/STOP switch, 3, to turn the circuit on or off.



90

4. The circuit selected will be displayed in the TPM, 1, and the word "Hi or Lo" will be displayed in the 3-point hitch display, 2, to indicate the status of the circuit. Hi = ON and Lo = OFF.
5. When the display, 2, shows Hi, the solenoid can be checked for current to insure it is working.
6. See Chart 6 for circuit identification.
7. To exit this mode and transfer to the mode selection menu, touch the E/M switch, 3.



91

CHART 6 - EDC OUTPUT DIAGNOSTICS

3PT HITCH / EDC OUTPUT PARAMETERS


I D	Description
P050	RAISE SOLENOID DRIVE
P051	LOWER SOLENOID DRIVE

MODE 7, ETC OUTPUT DIAGNOSTICS

In this mode, the technician can power all circuits that are controlled by the ETC module.


If the circuit can be powered in this mode, the output portion on the circuit is functioning. If the circuit isn't working, the input or switching part of the circuit is at fault.

1. To enter this mode, touch the DIGIT SET switch, 5, to advance from mode 6 to mode 7. The display, 1, will show _ _ _ 7.
2. Hold the SET UP/SELECT switch, 4, for three seconds to enter mode 7.
3. Use the DIGIT SET switch, 5, to cycle through the different circuits and then use the START/STOP switch, 3, to turn the circuit on or off.



92

4. The circuit selected will be displayed in the TPM, 1, and the word "Hi or Lo", 2, will be displayed in the 3-point hitch display to indicate the status of the circuit. Hi = ON and Lo = OFF.
5. When the display, 2, shows Hi, the solenoid can be checked for current and or magnetism to insure they are working.
6. See Chart 7 for circuit identification.
7. To exit this mode, touch the E/M switch, 3.



93

CHART 7 - ETC OUTPUT DIAGNOSTICS

ELECTRONIC TRANSMISSION CONTROL (ETC) OUTPUT PARAMETERS

I D	Description
P350*	TRANS SOLENOID F1 DRIVE
P351*	TRANS SOLENOID F2 DRIVE
P352*	TRANS SOLENOID R DRIVE
P353	TRANS SOLENOID 1 DRIVE
P354	TRANS SOLENOID 2 DRIVE
P355	TRANS SOLENOID 3 DRIVE
P356	TRANS SOLENOID A DRIVE
P357	TRANS SOLENOID B DRIVE
P358	TRANS SOLENOID C DRIVE
P359	TRANS SOLENOID CREEPER DRIVE
P360	TRANS SOLENOID MC1 DRIVE
P361	TRANS SOLENOID MC2 DRIVE
P362+	TRANS SOLENOID PTO DRIVE
P363	TRANS SOLENOID DIFFLOCK DRIVE
P364	TRANS SOLENOID FWD DRIVE
P450	FUEL HOLD SOLENOID DRIVE


* Parameter will only work when shift lever is in forward position.

\+ Parameter will only work when PTO switch is in the "ON" position

MODE 8, EIC FULL DISPLAY TEST


When this mode is selected, the EIC will light each lamp in succession and all segments of the LCDs will be displayed.

1. To enter this mode, touch the DIGIT SET switch, 4, to advance from mode 7 to mode 8. The TPM display, 1, will show _ _ _8.
2. Hold the SET UP/SELECT switch, 3, for three seconds to enter mode 8.The indicator lamps will now start to illuminate one at a time and all LCDs should be on.



94

NOTE: *70 Series art shown in Figure 95.*




95

3. To view each LCD segment one at a time, touch the SET UP/SELECT switch, 4.
4. Each LCD segment will go out and come back on one at a time until all segments have been tested.
5. The bar graphs, 1, will cycle first followed by the central display, 2, then the TPM, 3.
6. Touch the E/M switch, 5, to exit the mode and transfer to the mode selection menu.

MODE 9, HARDWARE/SOFTWARE REVISION LEVEL


This mode will allow the technician to sequentially view hardware and software revision levels of each of the 4 modules on the tractor and review the tractor serial number recorded during production.

1. To enter this mode, touch the DIGIT SET switch, 4, to advance from mode 8 to mode 9. The TPM display, 1, will show _ _ _9.
2. Hold the SET UP/SELECT switch, 3, for three seconds to enter mode 9.




96

3. The hardware level (h), 2, for each module will be displayed then the software level (S) followed by the tractor serial number or build (b) number by repeatedly touching the SET UP/SELECT switch.
4. The module identification, 1, will be displayed in the engine speed LCD and the revision level, 3, or part of the tractor serial number will be shown in the lower selectable display area.



97



98

5. The tractor serial number or build number, 1, is stored in each module. The number is displayed as a letter, 6, followed by six digits- three digits in the TPM, 2, and three in the lower display, 5.
6. Touch the SETUP/SELECT switch, 4, to advance through the eleven displays and touch the E/M switch, 3, to exit this mode and return to the mode selection menu.

The hardware and software will be displayed in this sequence and format:

MODULE	DISPLAY ENGINE RPM	AREA GROUND SPEED	TPM
EIC HARDWARE	E i c h	XX.XX	
EIC SOFTWARE	E i c S	XX.XX	
EIC BUILD	E i c b	dXXX	XXX
EDC HARDWARE*	E d c h	XX.XX	
EDC SOFTWARE*	E d c S	XX.XX	
ETC HARDWARE	E t c h	XX.XX	
ETC SOFTWARE	E t c S	XX.XX	
ETC BUILD	E t c b	dXXX	XXX
RHC HARDWARE	r h c h	XX.XX	
RHC SOFTWARE	r h c S	XX.XX	
RHC BUILD	r h c b	dXXX	XXX

* If equipped.


X denotes a number 0-9

MODE 10, TRANSMISSION CALIBRATION REVIEW AND PROGRAMMING

NOTE: *For optimum operation, the transmission directional clutches must be recalibrated after the first 50 hours of use and every 250 - 300 hours thereafter.*


In this mode the operator or technician can view calibration values for clutch packs, change reverse shuttle selections and change the programmable up shift/down shift constants. See Chart 8 for available information.

1. To enter this mode, touch the DIGIT SET switch, 4, to advance from mode 9 to mode 10. The display, 1, will show _ _10.
2. Hold the SET UP/SELECT switch, 3, for three seconds to enter mode 10.




99

3. The 3-point hitch position display, 1, will show C1 which indicates the calibration number, 2, for the F1 directional clutch. This is only for review. The clutches can only be calibrated using the shift lever.
4. Touch the SET UP/SELECT switch, 3, again. The 3-point hitch position display, 1, will show C2 which indicates the calibration number, for the F2 directional clutch. Touch the SET UP/SELECT switch, 3, again to display C3 which will show the calibration number for the Reverse directional clutch. These numbers are only for review. The clutches can only be calibrated using the shift lever.



100

5. Touch the SET UP/SELECT switch, 3, and the 3-point hitch display, 1, will show C4. The TMP display, 2, will show the current Forward to Reverse shuttle shift offset. To change the offset, use the DIGIT SET switch, 4, to increase or decrease the offset.
6. If a -1 is displayed, the transmission will select one lower gear when shifted from Forward to Reverse. If the TPM shows 3, the transmission will increase three gears when shifted from forward to reverse. If “L” is displayed, the tractor will always select R3 (Reverse low).
7. Again touch the SET UP/SELECT switch to enter the C5 and C6 menus which allow programming changes to the Programmable Up shift and Down shift constants respectfully from 0 to 3 gears. Change the constants the same as changing the reverse shuttle programming.



101

8. Touch the SET UP/SELECT switch, 4, to advance to the C7 menu, 1. This menu allows fine tuning of the F9 to F10 transmission up shift. The tractor is programmed at the factory with a number of 10 as indicated in the TPM display, 2. The number can be increased to 19 or decreased to 1 to effect the fill timing of the F2 directional clutch.


NOTE: *Install the PDT (Portable Diagnostic Tool) and use the Data Monitor function and ETC (Electric Transmission Control) feature to monitor transmission oil temperature. Make sure the oil temperature is at least 48.8° C (120° F).*

NOTE: *The F2 clutch will normally have a lower number than F1 and Reverse.*

9. To change the F9 to F10 shift constant, use the DIGIT SELECT switch, 5, and the DIGIT SET switch, 6, to increase or decrease the stored number.
10. After any number has been changed, hold the SET UP/SELECT switch, 4, for three seconds to save the new number.
11. Always adjust the number by three or more digits to insure that the shift quality is better or worse than the previous number. The tractor must be operated after every adjustment to evaluate the shift quality. If the tractor shift is better, the digits may be adjusted one at a time to further fine tune the shift. If the shift is worse, change the number by six digits in the opposite direction to improve the shift. Make sure that the new number is saved after every adjustment.

NOTE: *Cold oil, improper ballast and tire pressure will adversely affect the transmission shift.*

12. Touch the SET UP/SELECT switch, 4, to advance to the C8 menu. This menu allows fine tuning of the F8 to F7 transmission down shift. The adjustment procedure is the same as for the C7 menu. Follow steps 8 through 11.
13. When programming is complete in this mode, touch the E/M switch, 3, to exit and return to the mode selection menu.



102

CHART 8, TRANSMISSION CALIBRATION REVIEW AND PROGRAMMING

3PT HITCH DISPLAY	TPM DISPLAY	TRANSMISSION FUNCTION	FACTORY SETTING
* C1	21-99	F1 Clutch Calibration Number	Random
* C2	21-99	F2 Clutch Calibration Number	Random
* C3	21-99	Reverse Clutch Calibration Number	Random
C4	3,2,1,0, -1,-2,-3,L	Forward to Reverse shuttle offset	0
C5	0,1,2,3	Programmable Up Shift Constant	2
C6	0,1,2,3	Programmable Down Shift Constant	2
C7	1-19	F9-F10 Up Shift Constant	10
C8	1-19	F8-F7 Down Shift Constant	10


* For review only. Not adjustable in Mode 10.

All others (C4-C8) can be changed using the DIGIT SET and DIGIT SELECT switches and saved using the SET UP/SELECT switch.

MODE 11, 3 PT HITCH AND EDC CALIBRATION

The technician can view 3-point hitch information such as response when operating in the field in this mode and recalibrate the hitch if any components have been repaired or replaced.


1. To enter this mode, touch the DIGIT SET switch, 4, to advance from mode 10 to mode 11. The TPM display, 1, will show _ _ 11.
2. Hold the SET UP/SELECT switch, 3, for three seconds to enter mode 11.



103

3. When in mode 11, the Lift Disable symbol and "H1" (hitch) will be displayed in the 3-point hitch position LCD, 1.

   "H1" function indicates the 3-point hitch raise solenoid threshold. This is the minimum current in milliamps required to just shift the valve allowing hydraulic fluid to flow.
4. Use the SET UP/SELECT switch, 3, to cycle from H1 through H6.
5. When "H5" is selected, hold the SET UP/SELECT switch, 3, for three seconds to clear the 3-point hitch calibration values from memory. The display will FLASH EE. Hitch calibration will be required to resume normal 3-point hitch operation.



104

NOTE: *The nonvolatile memory reset "H5" clears the "H1" and "H2" calibration value to a preset valve threshold (900 milliamps), and clears the upper and lower limits for the quadrant lever and rockshaft potentiometers. When the memory is cleared the TPM (tractor performance monitor) identifies the current quadrant lever and rockshaft positions as "0".*

NOTE: *To re-establish the limits of the 3-point quadrant lever potentiometer, the quadrant lever must be moved fully forward then rearward immediately after clearing the memory with the tractor running.*

6. See Chart 9 for identification of each menu and its function.
7. To exit mode 11, touch the E/M switch and return to the mode selection menu.

CHART 9, 3-POINT HITCH AND EDC CALIBRATION

DISPLAY	DESCRIPTION	PURPOSE
H1	Raise valve threshold display	Solenoid calibration value in milliamps
H2	Lower valve threshold display	Solenoid calibration value in milliamps
H3	Right draft pin load display	1/10 value of pin horizontal load in Kn (lbs)
H4	Left draft pin load display	1/10 value of pin horizontal load in Kn (lbs)
H5	Nonvolatile memory reset (hold SET UP/SELECT 3 seconds)	Clears “H1” and “H2” calibration value to a preset valve threshold and clears both potentiometers upper and lower values. Creates fault code F024 (requires hitch calibration)
H6	Calibration Status	Single digit reflects calibration status as follows: 0 - O.K. for valve calibration 1 - Valve calibration is not enabled 2 - Rockshaft position too low for valve calibration 3 - The hitch is disabled (hardwarefailure detected) 4 - Hitch not captured 5 - In fender switch mode 6 - The soil is engaged (draft signal too high) 7 - The drop rate is being limited 8 - Raise error too large 9 - Calibrations complete (system has performed 3 calibration cycles)

NOTE: *The H1 and H2 solenoid calibration value is the current in milliamps required to just shift the valve, allowing hydraulic fluid to flow.*

NOTE: *3-point calibration to clear fault code F024 can be accomplished in any of the “H” functions.*

NOTE: *Clearing “H1” and “H2” calibration values to the preset valve threshold may prevent the 3-point from lowering completely when using the quadrant lever and when using the fender switches the 3-point movement may be slower than normal.*

3 PT HITCH CALIBRATION CHECKS

Three-point hitch calibration is necessary if:

1. Full travel from 0 - 99 on the TPM does not occur with the height limit turned fully clockwise.
2. Cylinder rods are not fully retracted when the TPM indicates “0”.
3. The 3-point loses capture during normal tractor operation.
4. Any 3-point hitch components are changed.

When any of these conditions occur, the 3-point hitch requires calibration.

EDC Calibration - Pre-steps

1. Place mix knob fully counterclockwise (position mode)
2. Turn the height limit knob fully clockwise. A flashing HL on the 3-point hitch display, during the calibration pre-steps, indicates the height limit knob is not turned fully clockwise.
3. Put RAISE/WORK switch in WORK position.
4. Start the tractor with parking brake applied.

EDC Calibration - Resetting Nonvolatile Memory

1. Enter mode 11 and index to “H5”. Hold The SET UP/SELECT switch for three seconds to clear the 3-point hitch calibration values from memory. The TPM will index to “H6” then back to “H5” and “EE” will flash. The “H1” and “H2” values will have reset to “900” and the hitch position will reset to “0”.
2. Exit mode 11 by depressing the E/M switch once to display hitch position.
3. Move the quadrant lever fully forward. This establishes the quadrant lever lower limit.

NOTE: *The three-point hitch will not move when the quadrant lever is moved forward.*

NOTE: *After cleaning the nonvolatile memory with “H5”, the quadrant lever must be moved fully forward establishing the quadrant lever lower limit first. Failure to move quadrant lever fully forward will result in not establishing a true lower limit causing the hitch to loose capture when ever the quadrant lever is moved below this point.*

4. Move the quadrant lever fully rearward. This establishes the quadrant lever upper limit. The three-point hitch will raise to the full up position.

NOTE: *Since the rockshaft limits have been cleared the hitch will not slow down as the cylinders approach maximum extension and bottom out. The force of the cylinders bottoming out may be felt and heard in the cab.*

5. Move the quadrant lever fully forward again. The three-point hitch will lower to the position it was at when the memory was reset. Use the fender switches to lower the hitch until no chrome is showing on the lift cylinders.

NOTE: *On tractors, below serial #D403821 (flat top right-hand console), the 3-point quadrant lever must be placed in the EXTEND position before using the fender switches. On tractors after serial #D403820, the raise/work switch must be cycled to the RAISE position, then the WORK position before the quadrant lever will capture the hitch and allow you to proceed to the next step.*

NOTE: *Steps 3 - 5 establish the lower and upper limits of the quadrant lever and rockshaft potentiometers.*

6. Capture the hitch and slowly move the quadrant lever rearward to the full up position.
7. Complete the 3-point hitch calibration by following the EDC VALVE CALIBRATION.

EDC Valve Calibration

1. To calibrate the 3-point hitch valve, select mode 11 and enter it by holding the SET UP/SELECT switch for three seconds.
2. When “H1” appears, advance to “H6” using the SET UP/SELECT switch. The “H6” calibration status should be “0” indicating the system is ok for valve calibration.

NOTE: *If “0” does not appear in “H6” the system will not calibrate. If “H6” indicates any other value, exit mode 11 and repeat the pre-steps and verify system status.*

3. Exit mode 11 by depressing the E/M switch once to display hitch position.
4. Lower the hitch below the 3-point hitch position display of 60 and then raise it above 60, but less than 90. You will observe the hitch moving slightly at this time. It will cycle up and down about one position count to find the valve raise and lower thresholds.


NOTE: *The hitch will cycle up/down three or more times until three cycles are verified by the microcontroller. This will take several minutes.*

5. Enter mode 11 and index to “H6” while the hitch is cycling up and down. The “H6” calibration status should still be “0”, indicating the system is OK for calibration. When three cycles are verified by the microcontroller, the status will change from “0” to “9”, showing the system performed 3 calibration cycles.
6. Exit mode 11 and return to “NORMAL” display. Move the quadrant to full UP. “99” will be on the display, and when the quadrant is moved down to the bottom stop, “0” will be displayed.
7. The three-point hitch calibration is now complete.


MODE 12, TRACTOR FEATURES CONFIGURATION

This mode is used to reconfigure the Electronic System to match the tractor's features when a module has been replaced or an additional option has been added.

1. To enter this mode, touch the DIGIT SET switch, 4, to advance from mode 11 to mode 12. The TPM display, 1, will show _ _ 12.
2. Hold the SET UP/SELECT switch, 3, for 15 seconds to enter mode 12.



105




106

3. Twelve tractor features, 1, will be identified in the engine RPM display with the value for the variable shown in the lower selectable display, 2.
4. See Chart 10 for the feature identification and the correct configuration value.
5. Use the SET UP/SELECT switch, 5, to select the feature.
6. Use the DIGIT SET switch, 6, to change the feature value.
7. A fault code, 3, of "F205" will flash when a new value for the feature is selected. It will clear when the new value is saved in memory and the EIC, RHC, and CCM agree.
8. SAVE ALL THE NEW FEATURE VALUES BY DEPRESSING THE SET UP/SELECT SWITCH, 5, FOR THREE SECONDS.
9. Touch the E/M switch, 4, to exit this mode.
10. Touch it a second time to return to normal operation.

70A Series, Mode 12 now has a 14th feature that allows the tractor to be configured for Terralock™.

- A 0 (zero) indicates the steering angle sensor is not present and Terralock™ is turned off. Units equipped with a limited slip front axle will be configured as 0. When 0 is selected, the new Mode 13 is hidden. Mode 13 is used for steering angle sensor operation and calibration, and is explained under the next heading.
- A 1, indicates the steering angle sensor is present and allows you to enter Mode 13. When 1 is selected, Terralock™ will engage or disengage the front and rear differential lock and four wheel drive. This depends upon the position of the diff. lock and four wheel drive switches, the tractor speed, and wheel angle.

If the tractor is configured for TerraLock and the steering angle sensor is not present, error codes F370 and F371 will occur.



107

CHART 10, TRACTOR FEATURES CONFIGURATION

FEATURE NUMBER	DESCRIPTION		VALUE
1	DOES TRACTOR HAVE 540 RPM PTO?	NO YES	0 1
2	DOES TRACTOR HAVE 1000 RPM PTO?	NO YES	0 1
3	WHAT TYPE OF COLD START IS USED?	ETHER THERMOSTART AIR INLET*	0 1 2
4	IS TRACTOR USED WITH LIGHTED TRAILERS? (Enables EIC trailer indicator lamps–ISO)	NO YES	0 1
5	TRANSMISSION TYPE? North America ISO ++ ISO special application ++ ISO special application	16X9, 30 KPH 0 18X9, 40 KPH 1 18X9, 30 KPH (temp) 18X9, 40 KPH (perm)	0 1 2 3
6	DOES TRANSMISSION HAVE CREEPER?	NO YES	0 1
7	WHAT FRONT AXLE?	2 WHEEL DR FRONT WH DR SUPER STR FWD	0 1 2
8	WHAT IS THE TRACTOR MODEL?	8670/G170 8770/G190 8870/G210 8970/G240	0 1 2 3
9	WHAT 3 POINT HITCH OPTIONS?	NONE POSITION ONLY POSITION/DRAFT	0 1 2
10	SLIP OVERRIDE EQUIPPED? (RADAR REQUIRED)	NOT INSTALLED INSTALLED	0 1
11	EDC GAIN? (RESPONSE)	LOW –LOWER MED – BASE+ HI – HIGHER HI – HIGHEST	0 1 2 3
12	FWD BRAKING?	ENABLED DISABLED	0 1
13	HYDRAULIC OIL TEMPERATURE SHUTDOWN:+++ NORMAL NO SHUTDOWN	 ENABLED DISABLED	0 1
14	TERRALOCK PRESENT? (Rev. 5 software only)	ENABLED DISABLED	1 0

***** Can not be set using PDT special tool diagnostic cartridge version 1.0

+ Factory setting


++ Can be set/changed only with PDT special tool

+++ Feature only available on tractors with EIC software level 06.37 or more recent.

MODE 13: STEERING ANGLE SENSOR OPERATION/CALIBRATION (70A SERIES)


When Mode 12's feature 14 is set to 1, then Mode 13 is present and the system is looking for the steering angle sensor. To enter Mode 13, you must hold the SET UP/SELECT switch for 15 seconds.

The Mode 13 display will have a 4d at the top of the TPM and either the letters CEn, or an R or L with a number.



108

- The 4 indicates four wheel drive equipped.
- The "d" indicates diff lock equipped.
- "CEn" indicates the front wheels are centered.
- "R" indicates the wheels are turned to the Right and the number indicates the turning diameter in feet.
- "L" indicates the wheels are turned to the Left and the number indicates the turning diameter in feet.




109

Checking the Steering Angle Sensor Using Mode 13, Terralock™ Calibration

To check the steering angle sensor with the tractor running and standing still, follow these steps:


1. Start the tractor and make sure the front wheels are pointing straight ahead.
2. Enter Mode 13 on the dash.
3. Depress the SET UP/SELECT switch for 15 seconds until you see 4d and CEn, or an R or L with a two- or three-digit number, on the display. This is the calibration mode for Terralock™ feature.



110

4. Rotate the wheel left or right slowly until the steering stop is reached. The display will show the letter R or L followed by numbers, as you turn the steering wheel. The numbers represent the turn around diameter of the tractor.
5. Watch the numbers in the display. They should rise or drop evenly as you rotate the wheel from left to right and back. If the numbers being displayed are irregular, have blank spots, or cannot be repeated, replace the steering sensor.

NOTE: *The numbers to the extreme right and left may be different due to the steering stops positions. The steering stops can be set evenly right and left using this feature.*



111

Calibrating the Steering Angle Sensor

You can also calibrate the steering angle sensor in Mode 13. The preferred method for calibration is with the tractor moving because it is more accurate. To calibrate the tractor while sitting in a shop service bay, the following procedure can be used with wheels pointing straight ahead and not driving the tractor.

1. Start the tractor.
2. Enter Mode 13 on the dash.
3. Start driving the tractor in a straight line. Use the line of sight ornament on the front of the hood to follow a predetermined straight line on the ground.

NOTE: *If the tractor wheels are not pointing straight ahead and you continue to follow this calibration procedure, the system will record the wheel position as centered (CEn), and Terralock ™ will engage and disengage at different steering angles left to right.*

4. While driving in a straight line, depress the SET UP/SELECT switch for 3 seconds until you see CAL on the display. This is the calibration mode for Terralock™ feature.
5. Release the button. When the display shows 4d and CEn, the system has recorded that the current position of the front wheels is centered, and calibration is complete.
6. Rotate the wheel left or right slowly until the steering stop is reached. The display will show the letter R or L followed by numbers as you turn the steering wheel. The numbers represent the turn around diameter of the tractor.
7. If the calibration is correct and the steering stops are equally adjusted, you should get equal numbers from left to right.

NOTE: *The numbers to the extreme right and left may be different due to the steering stops positions. The steering stops can be set evenly right and left using this feature.*

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 2 – Fault Codes and Diagnostics

CONTENTS

Section	Description	Page
55 000	Description of Operation	2
	70/70A Series Diagnostics Procedure Overview and Checklist	2
	System Grounds	3
	70 Series Electrical System Grounds	4
	Troubleshooting Checklist	5
	Special Tool for Testing Electrical Systems	7
	Electrical Test Procedures #1 through #4	8
	Fault Codes F001 to F099, 3-Point Hitch/EDC	14
	Fault Codes F100 to F199, Right-hand Controls	88
	Fault Codes F200 to F299, EIC Module	112
	Fault Codes F300 to F399, ETC Transmission Control	134
	Fault Codes F400 to F499, Engine Control	292

DESCRIPTION OF OPERATION

70/70A SERIES DIAGNOSTICS PROCEDURE OVERVIEW AND CHECKLIST

The purpose of the diagnostic procedure is to determine which part or parts have failed. Diagnostics procedures progress from most likely points of failure to least likely and are prioritized as follows:

1. Switch/sensor/sender/part is bad
2. Wiring or connector is bad
3. Electronic module is bad

Each procedure or flow chart assumes the following:


1. No previous troubleshooting or tampering has been performed on system.
2. The fault code is currently being displayed.

   Is the Fault Code Indicator symbol “ON” displayed in the TPM?


   If the indicator is on, review the tractor operator’s manual to turn on fault codes.
3. No other fault codes are reporting. If multiple codes exist, each code must be diagnosed independently.

NOTE: *Loose connectors and grounds can cause multiple fault codes.*

4. Modules are working sufficiently enough to report the fault code in the first place. Are the RHC and CCM module LEDs flashing? Is the EIC status lamp on or flashing?
5. Self-diagnostics will work correctly to identify the fault. Create a fault by unplugging a sender for a particular module. Does the appropriate fault code appear?



1



2


1. “Read your manual” symbol
2. On legend
3. Off legend
4. START/STOP switch

Assume for repair:

1. Shop conditions are preferable to in field diagnostics. Additional time will be required to troubleshoot in the field.
2. The batteries are fully charged and the charging system is operating properly.
3. Extension connectors, connector probes, digital metering, and power supplies are available.
4. *Portable Diagnostics Tool (PDT) is available and the technician is trained on PTD operation.
5. Spare sensors are available such as oil pressure sensor, engine coolant temp., trans oil temp., intercooler temp., draft pins, exhaust temp. sensor. Devices that cannot be tested with a meter should be on hand for diagnosis.
6. Spare modules available - EIC, RHC, CCM.

*Information recorded on the PDT can be transferred to any PC with Microsoft Windows. This may be helpful for evaluating and correcting service or operational problems. Portable Diagnostic Tool Instruction Manual, part #FNH00507 dated 5/95, contains information regarding transfers to a PC.

NOTE: *If using a DB25-to-DB9 adapter from Radio Shack, the two nuts and attaching plate must be carefully removed from the adapter. If this is not done, they will contact the PC serial port cable retaining nuts.*


70-580-881


3

SYSTEM GROUNDS

Multiple fault codes, erratic lighting system operation, and systems stopping to function when the lights are turned on may be the result of tractor ground connections that are loose, corroded, or have poor contact due to excessive paint.

If any of these conditions should occur, inspect the tractor ground connections for proper assembly and make sure they are tight. Figure 4 shows locations for the harness grounds.

70 SERIES ELECTRICAL SYSTEM GROUNDS




4

	Identification		Location
1.	Cab Roof-All CR wires		Right side of cab top under roof.
2.	Cab Main, rear-All rear CM wires.		Right rear corner of floor.
3.	Rear Main-All RM wires,	Early Tractors	Right rear cab mount (8670 3-pt. top cover).
		Current Tractors	Rear axle housing by right trumpet housing.
4.	Cab Main, front-All front CM wires		Front right corner behind EIC
5.	Front Main-All FM wires		Front left engine block by AC comp.
6.	Cab to Chassis ground strap		Same as number 3.
7.	Battery Ground		Rear axle housing below right-hand front corner of the cab.


TROUBLESHOOTING CHECKLIST

1. Check for current fault codes using MODE 1, Operator Calibration, and list the codes if multiples exist.



5

2. Enter MODE 2, Stored Fault Codes, and record all stored codes, the hour they occurred, and the number of times they repeated.
3. After the faults have been recorded, clear the faults from memory, and again, operate the tractor.
4. Only troubleshoot current fault codes. Earlier faults may be the cause of subsequent faults, i.e., the first fault(s) to occur may have something to do with faults that occur later. Use the portable diagnostic tool whenever possible (if available).
5. Have other technicians or owner(s)/ operators performed repairs prior to your diagnosis? Get all of the facts about what has been done before attempting to diagnose faults in the electrical system. Make sure all prior work has been performed with authorized replacement parts and proper repair/installation procedures. Be wary of any prior temporary repairs, which could potentially be causing fault codes to report. Fault code diagnostic procedures do not consider conditions where improper parts are used, nor conditions where improper previous repairs have been performed.




6

6. Each flow chart approaches the diagnostic task as if there were only one fault code, and the condition has just occurred, or is currently flashing on the EIC. Conditions with multiple faults must be diagnosed by the repair technician's judgment using information in all involved flow charts and diagrams. This will involve studying all of the reported fault code flow chart procedures and diagrams, prior to performing any diagnostic task. Whenever dealing with multiple fault codes, do not assume priority should be given to the lowest, or highest fault code number. If all codes occurring have the same engine hour time of occurrence, priority should be given to circuitry problems that affect, or influence all of the circuits involved in the reported fault codes. For instance, if a power supply, or signal ground fault code is reported, give it priority over codes for individual components.
7. During the course of diagnosing the system, it is important to note whenever using the PDT to observe fault codes, the user must not forget many codes are key reset only. In other words, you can correct the problem, but the fault code will continue to report until the keyswitch is turned 'off' and then back 'on'.
8. Also, the PDT does not continuously scan the system for fault codes, it only reports with a list what the on-board computers are currently reporting when a request is made. Fault codes can be cleared or even new ones occur without being displayed on the tool. For updates, the user must scan the system after each fix or attempt to repair the system.
9. It is important to follow each fault code diagnostic procedure step by step, since skipping steps may lead to erroneous results, lengthier troubleshooting time, or replacement of functional components. The proper sequence for troubleshooting the system is to begin with components or parts such as switches, potentiometers and sensors, progress to the harness and connectors, and finally resolve the problem to the modules. If a module must be replaced, use care in handling the new modules, verify hardware and software revision levels for compatibility and remember to enter mode 12 at the electronic instrument cluster, to program the proper setup and to save the setup.
10. In dealing with complex fault codes where multiple conditions must occur in order for a fault code to report, a repair must be followed by testing to the required conditions. Several faults, such as engine coolant temperature, take up to 20 minutes before reporting a fault condition, and others require the tractor to be in motion, or in gear, or engine running etc., before reporting a fault code. Before verifying a fix, make sure all fault conditions are met first.
11. Before replacing any modules (EIC, RHC, or CCM), download the latest version of software into all the modules. Interference from electromatic frequencies (EMF) or loss of software information may be corrected by reconfiguring the software preventing replacement of a module.

SPECIAL TOOL FOR TESTING ELECTRICAL SYSTEMS


Special tool #FNH00550 consists of a set of four electrical circuit test adapters that are used to measure voltage in electrical circuits. The end of the connectors is designed to be inserted into the electrical connector, as shown, so the operating voltage can be checked while the circuit is being operated.

The opposite end of the connector will accept any standard voltmeter probe. There are two red wires and two black wires in the set.



7


Most hydraulic and transmission control systems use electrical solenoids operating in the 2.5 to 6.0 volt range. To obtain accurate measurements, these circuits must be checked with the solenoids connected to the electronic control systems. 70 Series tractors use these solenoid control systems.



8

These tools are extremely helpful in troubleshooting electrical systems.

The test adaptors make checking electrical circuits easier and improve accuracy. In addition, electrical system connectors are not damaged by the probe tool. Damaged connectors can cause additional concerns.



9

ELECTRICAL TEST PROCEDURES

Four electrical tests will be required to properly troubleshoot electrical concerns on the tractor.


Each test is described in detail. Ensure all steps are reviewed and followed when testing.

1. Continuity Test, short to ground
2. Voltage measurement, short to 12 volts
3. Resistance test for components
4. Continuity test, open circuits

ELECTRICAL TEST PROCEDURE 1: CONTINUITY TEST - SHORT TO GROUND

Conditions For Performing Tests:

1. Power OFF, Keyswitch OFF, (sometimes battery disconnected or fuse pulled out if specified in procedure).
2. Connectors at each end or ends of circuit disconnected to prevent false readings.
3. Set meter to measure resistance or ohms, and measure circuit resistance. Use black lead to make contact with a plated metal part on the chassis such as the jump start post. Make sure the surface of the part is not corroded. Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors.
4. Determine if measured resistance falls within guidelines specified in the procedure. Three to four ohms indicates a direct short to chassis ground, and must be located and repaired. Higher resistances usually indicate circuit paths through modules, and an additional connector needs to be disconnected to perform the test. More than 100K ohms indicates the circuit is free of shorts to ground.




70-580-884

10

ELECTRICAL TEST PROCEDURE 2: VOLTAGE MEASUREMENT OR SHORT TO POSITIVE SUPPLY VOLTS

Conditions For Performing Short To Ground Tests:

1. Keyswitch ON (sometimes OFF, if specified in procedure).
2. Connectors at sensor, switch or potentiometer end disconnected. All other connectors must be reconnected to perform test.
3. Set meter to measure DC VOLTS, and measure circuit voltage as illustrated. Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors. Use the black lead to make contact with a plated metal part on the chassis such as the jump start post. Make sure the surface of the part is not corroded.
4. Determine if measured voltage falls within guidelines specified in the procedure.



70-580-885

11


ELECTRICAL TEST PROCEDURE 3: RESISTANCE TEST FOR ELECTRICAL PARTS

Conditions For Performing Resistance Test:

1. Disconnect tractor part by unplugging electrical connectors to expose the part assembly connector for testing.
2. Set electrical meter to measure resistance or ohms and insert test probes into connector terminals specified in procedure. When checking potentiometers, measure from wiper terminal to each of the other terminals while TURNING THE POT SHAFT. This will ensure no open spots escape detection. When checking rocker or rotary switches, actuate the switch while measuring for opens and shorts.
3. Compare measured values to values specified in the fault code procedures. Allow plus or minus 5 percent of range tolerance for all measurements.

BECAUSE OF ACTIVE DEVICES INSIDE OF CERTAIN TRACTOR PARTS, THE FOLLOWING PARTS CANNOT BE TESTED BY MEASURING RESISTANCE:

TEMPERATURE SENSORS (ENGINE COOLANT, INTERCOOLER, TRANS. OIL)
ENGINE OIL PRESSURE SENSOR
DRAFT PINS
FLASHER RELAY MODULE
NASO CONVERTER MODULE
GEARSHIFT ASSEMBLY
ELECTRONIC INSTRUMENT CLUSTER
RIGHT-HAND CONSOLE MODULE
CHASSIS CONTROL MODULE



70-580-886

12


ELECTRICAL TEST PROCEDURE 4: CONTINUITY TEST - CHECK FOR OPEN CIRCUITS

Conditions For Performing Continuity Tests:

1. Keyswitch OFF (sometimes disconnect battery or pull fuses).
2. Connectors at both ends of the circuit disconnected. All other connectors must be reconnected to perform test.
3. Set meter to measure resistance or ohms, and measure circuit resistance as illustrated.

   Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors.

   Use the black lead to make contact with the connector pin at the other end of the circuit. Avoid contact with other pins in the connector and the connector case, if it is metal.
4. Determine if measured resistance falls within guidelines specified in the procedure. If the resistance is no more than 3 to 4 ohms, the circuit is continuous. More resistance usually indicates dirty or corroded terminals in connectors, and 100K ohms indicates an open circuit.



70-580-887

13

CHART 1 - FAULT CODES

3 PT HITCH/ EDC

Fault Codes	Description
F001	3PT TRANSIENT RESET
F002	3PT A to D CHANNEL LOCKUP
F003	TRUE GROUND SPEED > WHEEL SPEED
F004	AXLE SPEED > MAX SPEED
F006	SLIP LIMIT POT. FAILED LOW / SHORT
F007	SLIP LIMIT POT. FAILED HIGH / OPEN
F008	RAISE-WORK SWITCH - CONTACTS SAME
F009	FENDER 3PT SWITCHES - CONTACTS SAME
F010	HEIGHT LIMIT POT FAILED LOW / SHORT
F011	HEIGHT LIMIT POT FAILED HIGH / OPEN
F012	DROP RATE POT FAILED LOW / SHORT
F013	DROP RATE POT FAILED HIGH / OPEN
F014	RIGHT DRAFT PIN FAILED LOW / OPEN
F015	RIGHT DRAFT PIN FAILED HIGH / SHORT
F016	LEFT DRAFT PIN FAILED LOW /OPEN
F017	LEFT DRAFT PIN FAILED HIGH / SHORT
F018	DRAFT PINS BOTH DISCONNECTED/FAILED
F019	8 VOLT PINS SUPPLY FAILED LOW / OPEN
F020	8 VOLT PIN SUPPLY FAILED HIGH / SHORT
F021	SENSITIVITY (MIX) POT. FAILED LOW / SHORT
F022	SENSITIVITY (MIX) POT. FAILED HIGH/OPEN
F023	RHC 5 VOLT SUPPLY FAILED (5/2) / SHORT
F024	PERFORM HITCH CALIBRATION (MODE 11)
F025	QUAD LEVER POT FAILED LOW / SHORT
F026	QUAD LEVER POT FAILED HIGH / OPEN
F027	ROCKSHAFT POT FAILED LOW / SHORT
F028	ROCKSHAFT POT FAILED HIGH / OPEN
F029	3PT SOL.VALVE SHORT OR OPEN
F030	RHC 3PT POTS.SIGNAL GROUND FAILURE
F031	3PT MAIN REAR HARNESS DISCONNECTED
F057	3PT SOLENOIDS BOTH ON W/O COMMAND
F058	EDC 3POINT SIGNAL GROUND FAILED
F059	RAISE-WORK SWITCH - CONTACTS SAME
F063	3 POINT LOWER COIL SHORT OR OPEN
F064	3 POINT RAISE COIL SHORT OR OPEN
F098	ROCKSHAFT POT VALUES CHANGING
F099	3 POINT POT. VALUES CHANGING

RIGHT HAND CONTROLS (RHC)

Fault Codes	Description
F100	RHC SENSOR 5V SUPPLY (5/2) LOW, SHORTED
F101	RHC SENSOR 5V SUPPLY (5/2) HIGH
F102	TRANS UP SHIFT SWITCH OPEN
F103	TRANS UP SHIFT SWITCH SHORT
F104	TRANS DOWN SHIFT SWITCH OPEN
F105	TRANS DOWN SHIFT SWITCH SHORT
F106	TRANS REVERSE SWITCH OPEN
F107	TRANS REVERSE SWITCH SHORT
F108	TRANS FORWARD SWITCH OPEN
F109	TRANS FORWARD SWITCH SHORT

ELECTRONIC INSTRUMENT CLUSTER (EIC)

Fault Codes	Description
F200	EIC 5 VOLT SUPPLY LOW (5/1) / SHORT
F201	OUTPUT CIRCUIT SHORT
F202	EIC ERROR RHC CAN COMM. FAULT
F203	EIC ERROR EDC CAN COMM. FAULT
F204	EIC ERROR TCM CAN COMM. FAULT
F205	FEATURES SETUP-EIC/MODULES DISAGREE
F206	COLD START OUTPUT SHORT
F207	BOTH BRKES ENGAGED WHILE MOVING
F208	EIC SENSOR 5V SUPPLY HIGH (5/1)
F209	COLD START SWITCH

ELECTRONIC TRANSMISSION CONTROL (ETC)

Fault Codes	Description
F300	TRANS SOLENOID #1 SHORT
F301	TRANS SOLENOID #2 SHORT
F302	TRANS SOLENOID #3 SHORT
F303	TRANS SOLENOID A SHORT
F304	TRANS SOLENOID B SHORT
F305	TRANS SOLENOID C SHORT
F306	TRANS SOLENOID F1 SHORT
F307	TRANS SOLENOID F2 SHORT
F308	TRANS SOLENOID MC1 SHORT
F309	TRANS SOLENOID MC2 SHORT
F310	TRANS SOLENOID REV SHORT
F311	TRANS SOLENOID CREEP SHORT
F312	FWD SOLENOID SHORT
F313	FUEL HOLD-IN SOLENOID SHORT
F314	PTO SOLENOID SHORT
F315	DIFF-LOCK SOLENOID SHORT
F316	RELAY FUEL PULL-IN SHORT
F317	CONNECTOR 003 OPEN
F318	CONNECTOR 002 OPEN
F319	CONNECTOR 001 OPEN
F320	TRANS SOLENOID #1 OPEN
F321	TRANS SOLENOID #2 OPEN
F322	TRANS SOLENOID #3 OPEN
F323	TRANS SOLENOID A OPEN
F324	TRANS SOLENOID B OPEN
F325	TRANS SOLENOID C OPEN
F326	TRANS SOLENOID F1 OPEN
F327	TRANS SOLENOID F2 OPEN
F328	TRANS SOLENOID MC1 OPEN
F329	TRANS SOLENOID MC2 OPEN
F330	TRANS SOLENOID REV OPEN
F331	TRANS SOLENOID CREEP OPEN
F332	FWD SOLENOID OPEN
F333	FUEL HOLD-IN SOLENOID OPEN
F334	PTO SOLENOID OPEN
F335	DIFF-LOCK SOLENOID OPEN
F336	RELAY FUEL PULL-IN COIL OPEN
F337	TRAILER BRAKE FAULT (ISO ONLY)
F338	CCM 5 VOLT SUPPLY FAILED (5/3) / LOW
F339	CCM 5 VOLT SUPPLY FAILED (5/3) / HIGH
F340	AXLE SPEED SENSOR OPEN
F341	AXLE SPEED SENSOR SHORT
F342	ENGINE RPM SENSOR OPEN
F343	ENGINE RPM SENSOR SHORT
F344	ENGINE RPM SENSOR FAIL
F345	AXLE SPEED SENSOR FAIL
F346	INCH PEDAL (CLUTCH) SHORT TO GROUND
F347	INCH PEDAL (CLUTCH) OPEN CKT OR +VBAT
F348	INCH PEDAL (CLUTCH) CAL ERROR LOW
F349	INCH PEDAL (CLUTCH) CAL ERROR HIGH
F350	INCH PEDAL DOWN SWITCH/POT,DISAGREE
F351	INCH PEDAL UP SWITCH/POT. DISAGREE
F360	TRANS F1(FORWARD)CALIBRATION OFFSET CONSTANT
F361	TRANS F2(FORWARD)CALIB OFFSET CONSTANT
F362	TRANS R(REVERSE)CALIB OFFSET CONSTANT
F363	PROGRAMMABLE SHUTTLE CONSTANT
F365	TRANS F1/F2 SHIFT CAL.CONSTANT ERROR
F366	TRANS F2/F1 SHIFT CAL.CONSTANT ERROR
F370	STEERING ANGLE SENSOR SHORT TO GROUND
F371	STEERING ANGLE SENSOR CIRCUIT OPEN
F377	TRANS CONFIG BYTE 0 ERROR
F378	TRANS CONFIG BYTE 1 ERROR
F379	TRANS CONFIG BYTE 2 ERROR
F380	PROTOTYPE HARDWARE REV. ERROR
F381	PRODUCTION HARDWARE REV. ERROR
F382	PROG UPSHIFT CONSTANT ERROR
F383	PROG DOWNSHIFT CONSTANT ERROR
F386*	TRANS OIL TEMP HIGH (Shutdown)
F387*	TRANS OIL PRESSURE LOW (Shutdown)
F388	TRANS OIL PRESS. SENSOR FAILED LOW
F389	TRANS OIL TEMP SENSOR FAILED LOW
F390	TRANS OIL TEMP SENSOR FAILED HIGH
F391	HYDRAULIC FILTER STATUS
F392	TRANS FILTER STATUS
F393	POWER ON DIRECTIONALS
F399	ETC TRANSIENT RESET


ENGINE CONTROL

Fault Codes	Description
F400*	COOLANT TEMP TOO HIGH (Shutdown)
F401*	OIL PRESSURE TOO LOW (Shutdown)
F402	EGT TEMP TOO HIGH
F403	INTERCOOLER TEMP TOO HIGH
F404	FUEL LEVEL FAIL LOW
F405	FUEL LEVEL FAIL HIGH
F406	COOLANT TEMP FAIL LOW
F407	COOLANT TEMP FAIL HIGH
F408	ENGINE OIL PRESSURE FAIL LOW
F409	EGT SENSOR FAILED LOW
F410	EGT SENSOR FAILED HIGH
F411	INTERCOOLER Temp Sensor Failed Low
F412	INTERCOOLER Temp Sensor Failed High
F413	RADAR SENSE FAULT
F414	RADAR SIGNAL FAULT
F415	COOLANT LEVEL Sensor Failed Low
F416	COOLANT LEVEL Sensor Failed Off High
F417	ENGINE AIR FILTER STATUS
F418	COOLANT LEVEL STATUS
F419	ALTERNATOR NOT CHARGING
F420	ALTERNATOR OVERCHARGING (> 16 V)
F421	EIC ERROR VPOWER LOW
F422	CONNECTOR 008 DISCONNECTED

SOFTWARE DEVELOPMENT

F6XX NOT RELATED TO ANY CONCERN

* These faults cannot be erased from memory.



14

FAULT CODE F001


1. Chassis Control Module
2. Memory Unswitched Power (MDP-F25)
3. Control Modules Switched Power (MDP-F23)
4. Cab Ground


1/99

F001

FAULT CODE F001 - 3-POINT HITCH MODULE TRANSIENT RESET

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





15

FAULT CODE F002


1. Chassis Control Module
2. Memory Unswitched Power (MDP-F25)
3. Control Modules Switched Power (MDP-F23)
4. Cab Ground


1/99

F002

FAULT CODE F002 - 3-POINT HITCH MODULE ANALOG TO DIGITAL CHANNEL LOCKUP

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





16

FAULT CODE F003


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor


1/99

FAULT CODE F003 - TRUE GROUND SPEED IS GREATER THAN AXLE SPEED

F003

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





17


FAULT CODE F004


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F004

FAULT CODE F004 - AXLE SPEED IS GREATER THAN MAXIMUM SPEED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





18

FAULT CODE F006


1. Right-Hand Controls Module


2. Slip Limit Potentiometer

1/99 F006

FAULT CODE F006 - SLIP LIMIT POTENTIOMETER FAILED LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





19

FAULT CODE F007


1. Right-Hand Controls Module


2. Slip Limit Potentiometer

1/99 F007

FAULT CODE F007 - SLIP LIMIT POTENTIOMETER FAILED HIGH OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





20


FAULT CODE F008


1. Right-Hand Controls Module
2. Raise/Work Switch
3. Right-Hand Console Fuse (MDP-F21)

1/99 F008

FAULT CODE F008 - RAISE SWITCH AND WORK SWITCH BOTH HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





21


FAULT CODE F009

1. Right-Hand 3-Point Hitch Switch
2. Front Console Fuse (MDP-F22)
3. Left Hand 3-Point Hitch Switch
4. Electronic Instrument Cluster

1/99 F009

FAULT CODE F009 - FENDER 3-POINT HITCH SWITCHES-RAISE/LOWER BOTH ENGAGED


***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.




1/99 F009

FAULT CODE F009 - FENDER 3-POINT HITCH SWITCHES-RAISE/LOWER BOTH ENGAGED (CONTINUED FROM PREVIOUS FRAME)

*Note: Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



(This page is intentionally blank.)



22

FAULT CODE F010

1. Right-Hand Controls Module


2. Height Limit Potentiometer


1/99

F010

FAULT CODE F010 - HEIGHT LIMIT POTENTIOMETER FAILED LOW OR SHORT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





23

FAULT CODE F011


1. Right-Hand Controls Module


2. Height Limit Potentiometer

1/99 F011

FAULT CODE F011 - HEIGHT LIMIT POTENTIOMETER FAILED HIGH OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





24

FAULT CODE F012

1. Right-Hand Controls Module


2. Drop Rate Potentiometer


1/99

F012

FAULT CODE F012 - DROP RATE POTENTIOMETER FAILED LOW OR SHORT

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





25

FAULT CODE F013


1. Right-Hand Controls Module


2. Drop Rate Potentiometer

1/99 F013

FAULT CODE F013 - DROP RATE POTENTIOMETER FAILED HIGH OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





26

FAULT CODE F014


1. Chassis Control Module


2. Right Draft Pin

1/99 F014

FAULT CODE F014 - RIGHT DRAFT PIN FAILED LOW OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





27

FAULT CODE F015


1. Chassis Control Module


2. Right Draft Pin

1/99

F015

FAULT CODE F015 - RIGHT DRAFT PIN FAILED HIGH OR SHORT





28

FAULT CODE F016

1. Chassis Control Module


2. Left Draft Pin


1/99

F016

FAULT CODE F016 - LEFT DRAFT PIN FAILED LOW OR OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





29

FAULT CODE F017

1. Chassis Control Module


2. Left Draft Pin


1/99

F017

FAULT CODE F017 - LEFT DRAFT PIN FAILED HIGH OR SHORT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





30

FAULT CODE F018


1. Chassis Control Module
2. Right Draft Pin
3. Left Draft Pin


1/99

F018

FAULT CODE F018 - DRAFT PINS BOTH DISCONNECTED OR FAILED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





31


FAULT CODE F019


1. Chassis Control Module
2. Right Draft Pin
3. Left Draft Pin

1/99 F019

FAULT CODE F019 - 8 VOLT PIN SUPPLY FAILED LOW OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





32

FAULT CODE F020


1. Chassis Control Module
2. Right Draft Pin
3. Left Draft Pin


1/99

F020

FAULT CODE F020 - 8 VOLT PIN SUPPLY FAILED HIGH OR SHORT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





33

FAULT CODE F021

1. Right-Hand Controls Module


2. Mix Potentiometer


1/99

F021

FAULT CODE F021 - MIX POTENTIOMETER FAILED LOW OR SHORT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





34

FAULT CODE F022


1. Right-Hand Controls Module


2. Mix Potentiometer

1/99 F022

FAULT CODE F022 - MIX POTENTIOMETER FAILED HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





35

NOTE: *70 Series art shown in Figure 35.*


FAULT CODE F024


1. Raise/Work Switch
2. Mix Potentiometer
3. Drop Rate Potentiometer
4. Height Limit Potentiometer
5. Quadrant Lever
6. Slip Limit Potentiometer

1/99

FAULT CODE F024 - PERFORM HITCH CALIBRATION

F024





36


FAULT CODE F025


1. Right-Hand Controls Module

2. Quadrant Potentiometer

1/99 F025

FAULT CODE F025-QUADRANT POTENTIOMETER FAILED LOW OR SHORT





37

FAULT CODE F026


1. Right-Hand Controls Module


2. Quadrant Potentiometer

1/99 F026

FAULT CODE F026 - QUADRANT POTENTIOMETER FAILED HIGH OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.






38


FAULT CODE F027

1. Chassis Control Module

2. Rockshaft Potentiometer

1/99 **FAULT CODE F027 - ROCKSHAFT POTENTIOMETER FAILED LOW OR SHORT** F027






39


FAULT CODE F028

1. Chassis Control Module

2. Rockshaft Potentiometer

1/99 **FAULT CODE F028-ROCKSHAFT POTENTIOMETER FAILED HIGH OR OPEN** F028





40

FAULT CODE F029


1. Chassis Control Module
2. 3-Point Solenoid
3. 3-Point Lower Solenoid


1/99

FAULT CODE F029 - BOTH EDC VALVES SHORT OR OPEN

F029


***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





41

FAULT CODE F030



42

FAULT CODE F030


1. Right-Hand Controls Module
2. Drop Rate Potentiometer
3. Slip Limit Potentiometer
4. Height Limit Potentiometer
5. Mix Potentiometer
6. Quadrant Potentiometer

1/99


FAULT CODE F030 - RIGHT-HAND CONSOLE 3 POINT HITCH POTENTIOMETERS SIGNAL GROUND FAILURE

F030

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.



(This page is intentionally blank.)



43


FAULT CODE F057


1. Chassis Control Module
2. 3-Point Raise Solenoid
3. 3-Point Lower Solenoid

1/99 F057

FAULT CODE F057 - 3 POINT HITCH SOLENOIDS BOTH ON WITHOUT COMMAND

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





44

FAULT CODE F058


1. Chassis Control Module
2. Rockshaft Potentiometer
3. Right-Hand Draft Pin
4. Left-Hand Draft Pin


1/99

F058

FAULT CODE F058 - DRAFT PIN AND ROCKSHAFT POTENTIOMETER SIGNAL GROUND FAILED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





45

FAULT CODE F059


1. Right-Hand Controls Module
2. Raise/Work Switch
3. Right-Hand Console Fuse (MDP-F210)


1/99

FAULT CODE F059 - RAISE-WORK SWITCH - BOTH LOW

F059

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





46

FAULT CODE F063


1. Chassis Control Module
2. 3-Point Raise Solenoid
3. 3-Point Lower Solenoid


1/99

F063

FAULT CODE F063 - 3 POINT HITCH LOWER SOLENOID CIRCUIT SHORT OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





47

FAULT CODE F064


1. Chassis Control Module
2. 3-Point Raise Solenoid
3. 3-Point Lower Solenoid


1/99

F064

FAULT CODE F064 - 3 POINT HITCH RAISE SOLENOID CIRCUIT SHORT OR OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





48

FAULT CODE F098


1. Chassis Control Module
2. Cab Ground Post
3. Rockshaft Potentiometer


1/99

F098

FAULT CODE F098 - ROCKSHAFT POTENTIOMETER VALUES CHANGING

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





49

FAULT CODE F099

1. Right-Hand Controls Module


2. Cab Ground Post


1/99

F099

FAULT CODE F099 - 3 POINT HITCH POTENTIOMETER VALUES CHANGING


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





50

FAULT CODE F100



51

FAULT CODE F100


1. Right-Hand Controls Module
2. Drop Rate Potentiometer
3. Slip Limit Potentiometer
4. Height Limit Potentiometer
5. Mix Potentiometer
6. Quadrant Potentiometer

1/99


F100

FAULT CODE F100 - RHC SENSOR 5V SUPPLY (5/2) FAILED LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.




(This page is intentionally blank.)



52

FAULT CODE F101



53

FAULT CODE F101


1. Right-Hand Controls Module
2. Drop Rate Potentiometer
3. Slip Limit Potentiometer
4. Height Limit Potentiometer
5. Mix Potentiometer
6. Quadrant Potentiometer

1/99


F101

FAULT CODE F101 - RHC SENSOR 5V SUPPLY (5/2) FAILED HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.



(This page is intentionally blank.)



54

FAULT CODE F102


1. Right-Hand Controls Module


2. Shift Control Asy.

1/99

F102

FAULT CODE F102 - TRANSMISSION UP SHIFT SWITCH CIRCUIT OPEN





55

FAULT CODE F103

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F103

FAULT CODE F103 - TRANSMISSION UP SHIFT SWITCH CIRCUIT SHORT TO GROUND

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





56

FAULT CODE F104

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F104

FAULT CODE F104 - TRANSMISSION DOWN SHIFT SWITCH CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





57

FAULT CODE F105

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F105

FAULT CODE F105 - TRANSMISSION DOWN SHIFT SWITCH CIRCUIT SHORT TO GROUND

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





58

FAULT CODE F106

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F106

FAULT CODE F106 - TRANSMISSION REVERSE SHIFT SWITCH CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





59

FAULT CODE F107

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F107

FAULT CODE F107 - TRANSMISSION REVERSE SHIFT SWITCH CIRCUIT SHORT TO GROUND

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





60

FAULT CODE F108

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F108

FAULT CODE F108 - TRANSMISSION FORWARD SHIFT SWITCH CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





61

FAULT CODE F109

1. Right-Hand Controls Module


2. Shift Control Asy.


1/99

F109

FAULT CODE F109 - TRANSMISSION FORWARD SHIFT SWITCH CIRCUIT SHORT TO GROUND

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





62

FAULT CODE F200


1. Electronic Instrument Cluster


2. Clutch Potentiometer

1/99 F200

FAULT CODE F200 - SV REF 5/1 FAILED LOW

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.






63

FAULT CODE F201

7 Sound Alert
8 Cold Start Fuse (MDP-F27)
9 Upper Cab Front Work Lamp Fuse (MDP-F7)
10 Upper Cab Rear Work Lamp Fuse (MDP-F6)
11 Lower Cab Rear Work Lamp Fuse (MDP-F5)
12 FRT/MID LWR Work Lamp Fuse (MDP-F4)



64


FAULT CODE F201

1/99

F201

FAULT CODE F201 - EIC OUTPUT SHORT CIRCUIT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





1/99

FAULT CODE F201 - EIC OUTPUT SHORT CIRCUIT
(CONTINUED FROM PREVIOUS FRAME)

F201

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





65

FAULT CODE F202

1. Right-Hand Controls Module


2. Electronic Instrument Cluster


1/99

FAULT CODE F202 - CAN FAULT: LOSS OF COMMUNICATIONS WITH RIGHT-HAND CONTROLS MODULE

F202

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





66

FAULT CODE F203

1. Chassis Control Module


2. Electronic Instrument Cluster


1/99

F203

FAULT CODE F203 - CAN FAULT: LOSS OF COMMUNICATIONS WITH ELECTRONIC DRAFT CONTROL MODULE

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





67

FAULT CODE F204

1. Chassis Control Module

2. Electronic Instrument Cluster

1/99 F204

FAULT CODE F204 - CAN FAULT: LOSS OF COMMUNICATIONS WITH ELECTRONIC TRANSMISSION CONTROLLER

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




CHART 10, TRACTOR FEATURES CONFIGURATION

FEATURE NUMBER	DESCRIPTION		VALUE
1	DOES TRACTOR HAVE 540 RPM PTO?	NO YES	0 1
2	DOES TRACTOR HAVE 1000 RPM PTO?	NO YES	0 1
3	WHAT TYPE OF COLD START IS USED?	ETHER THERMOSTART AIR INLET*	0 1 2
4	IS TRACTOR USED WITH LIGHTED TRAILERS? (Enables EIC trailer indicator lamps–ISO)	NO YES	0 1
5	TRANSMISSION TYPE? North America ISO ++ ISO special application ++ ISO special application	16X9, 30 KPH 0 18X9, 40 KPH 1 18X9, 30 KPH (temp) 18X9, 40 KPH (perm)	0 1 2 3
6	DOES TRANSMISSION HAVE CREEPER?	NO YES	0 1
7	WHAT FRONT AXLE?	2 WHEEL DR FRONT WH DR SUPER STR FWD	0 1 2
8	WHAT IS THE TRACTOR MODEL?	8670/G170 8770/G190 8870/G210 8970/G240	0 1 2 3
9	WHAT 3 POINT HITCH OPTIONS?	NONE POSITION ONLY POSITION/DRAFT	0 1 2
10	SLIP OVERRIDE EQUIPPED? (RADAR REQUIRED)	NOT INSTALLED INSTALLED	0 1
11	EDC GAIN? (RESPONSE)	LOW –LOWER MED – BASE+ HI – HIGHER HI – HIGHEST	0 1 2 3
12	FWD BRAKING?	ENABLED DISABLED	0 1
13	HYDRAULIC OIL TEMPERATURE SHUTDOWN:+++ NORMAL NO SHUTDOWN	 ENABLED DISABLED	0 1
14	TerraLock PRESENT? (Rev. 5 software only)	ENABLED DISABLED	1 0

***** Can not be set using PDT special tool diagnostic cartridge version 1.0

\+ Factory setting

++ Can be set/changed only with PDT special tool

+++ Feature only available on tractors with EIC software level 06.37 or more recent.


FAULT CODE F205


1/99

F205

FAULT CODE F205 - FEATURES SETUP DISAGREE ERROR

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





68

FAULT CODE F206


1. Electronic Instrument Cluster
2. Cold Start Switch
3. Ignition Switch
4. Cold Start Relay (MDP-R8)


1/99

F206

FAULT CODE F206 - COLD START OUTPUT RELAY SHORT

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





69

FAULT CODE F207


1. Electronic Instrument Cluster
2. Right Brake Switch
3. Right-Hand Console Fuse (MDP-F22)
4. Auxiliary Power Relay (MDP-R12)
5. Main Fuse MFP-2
6. Left Brake Switch


1/99

F207

FAULT CODE F207 - BRAKES ENGAGED WHILE MOVING (FUSE F22 OPEN)

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





70

FAULT CODE F208

1. Electronic Instrument Cluster


2. Clutch Potentiometer


1/99

F208

FAULT CODE F208 - EIC 5 VOLT SUPPLY HIGH (5/1) / OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





71


FAULT CODE F209


1. Electronic Instrument Cluster
2. Cold Start Switch
3. Ignition Switch
4. Cold Start Relay (MDP-R8)

1/99 F209

FAULT CODE F209 - COLD START SWITCH STUCK ON

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





72

FAULT CODE F300


1. Chassis Control Module
2. Transmission Solenoid Reverse
3. Transmission Solenoid #1


1/99

F300

FAULT CODE F300 - TRANSMISSION SOLENOID CIRCUIT #1 SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





73

FAULT CODE F301


1. Chassis Control Module
2. Transmission Solenoid #2
3. Transmission Solenoid #3


1/99

F301

FAULT CODE F301 - TRANSMISSION SOLENOID CIRCUIT #2 SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





74

FAULT CODE F302


1. Chassis Control Module
2. Transmission Solenoid #2
3. Transmission Solenoid #3


1/99

F302

FAULT CODE F302 - TRANSMISSION SOLENOID CIRCUIT #3 SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





75

FAULT CODE F303


1. Chassis Control Module
2. Transmission Solenoid A
3. Transmission Solenoid B


1/99

F303

FAULT CODE F303 - TRANSMISSION SOLENOID CIRCUIT A SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





76

FAULT CODE F304


1. Chassis Control Module
2. Transmission Solenoid A
3. Transmission Solenoid B


1/99

F304

FAULT CODE F304 - TRANSMISSION SOLENOID CIRCUIT B SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





77

FAULT CODE F305

1. Chassis Control Module


2. Transmission Solenoid C


1/99

F305

FAULT CODE F305 - TRANSMISSION SOLENOID CIRCUIT C SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





78

FAULT CODE F306


1. Chassis Control Module
2. Transmission Solenoid F1
3. Transmission Solenoid F2


1/99

F306

FAULT CODE F306 - TRANS. SOLENOID CIRCUIT F1 SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





79

FAULT CODE F307


1. Chassis Control Module
2. Transmission Solenoid F1
3. Transmission Solenoid F2


1/99

F307

FAULT CODE F307 - TRANSMISSION SOLENOID CIRCUIT F2 SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





80

FAULT CODE F308


1. Chassis Control Module
2. Transmission Solenoid MC1
3. Transmission Solenoid MC2


1/99

F308

FAULT CODE F308 - TRANSMISSION SOLENOID CIRCUIT MC1 SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





81

FAULT CODE F309


1. Chassis Control Module
2. Transmission Solenoid MC1
3. Transmission Solenoid MC2


1/99

F309

FAULT CODE F309 - TRANSMISSION SOLENOID CIRCUIT MC2 SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





82

FAULT CODE F310


1. Chassis Control Module
2. Transmission Solenoid Reverse
3. Transmission Solenoid #1


1/99

F310

FAULT CODE F310 - TRANSMISSION SOLENOID CIRCUIT REVERSE SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





83

FAULT CODE F311

1. Chassis Control Module


2. Creeper Solenoid


1/99

F311

FAULT CODE F311 - TRANSMISSION SOLENOID CIRCUIT CREEPER SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





84

FAULT CODE F312

1. Chassis Control Module


2. FWD Solenoid


1/99

F312

FAULT CODE F312 - FWD SOLENOID CIRCUIT SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





85

FAULT CODE F313


1. Chassis Control Module
2. Fuel Pull-In Relay (MDP-R16)
3. Fuel Solenoid Asy.


1/99

F313

FAULT CODE F313 - FUEL HOLD SOLENOID CIRCUIT SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





86

FAULT CODE F314


1. Chassis Control Module
2. PTO Solenoid
3. Diff. Lock Solenoid


1/99

F314

FAULT CODE F314 - PTO SOLENOID CIRCUIT SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





87

FAULT CODE F315


1. Chassis Control Module
2. PTO Solenoid
3. Diff. Lock Solenoid


1/99

F315

FAULT CODE F315 - DIFF. LOCK SOLENOID CIRCUIT SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





88


FAULT CODE F316


1. Chassis Control Module
2. Fuel Pull-In Relay (MDP-R16)
3. Fuel Solenoid Asy.

1/99 F316

FAULT CODE F316 - FUEL PULL-IN RELAY CIRCUIT SHORTED

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





89

FAULT CODE F317


1. Chassis Control Module
2. Hydraulic Filter Switch
3. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
4. Transmission Filter Switch
5. Transmission Oil Pressure Switch


1/99

F317

FAULT CODE F317 - REAR MAIN HARNESS CONNECTOR C003 OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.






90


FAULT CODE F318

1/99 F318

FAULT CODE F318 - REAR MAIN HARNESS CONNECTOR C002 OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





91


FAULT CODE F319


1/99

F319

FAULT CODE F319 - REAR MAIN HARNESS CONNECTOR C001 OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





92

FAULT CODE F320


1. Chassis Control Module
2. Transmission Solenoid Reverse
3. Transmission Solenoid #1


1/99

F320

FAULT CODE F320 - TRANSMISSION SOLENOID #1 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





93

FAULT CODE F321


1. Chassis Control Module
2. Transmission Solenoid #2
3. Transmission Solenoid #3


1/99

F321

FAULT CODE F321 - TRANSMISSION SOLENOID #2 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





94

FAULT CODE F322


1. Chassis Control Module
2. Transmission Solenoid #2
3. Transmission Solenoid #3


1/99

F322

FAULT CODE F322 - TRANSMISSION SOLENOID #3 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





95

FAULT CODE F323


1. Chassis Control Module
2. Transmission Solenoid A
3. Transmission Solenoid B


1/99

F323

FAULT CODE F323 - TRANSMISSION SOLENOID A CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





96

FAULT CODE F324


1. Chassis Control Module
2. Transmission Solenoid A
3. Transmission Solenoid B


1/99

F324

FAULT CODE F324 - TRANSMISSION SOLENOID B CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





97

FAULT CODE F325

1. Chassis Control Module


2. Transmission Solenoid C


1/99

F325

FAULT CODE F325 - TRANSMISSION SOLENOID C CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





98

FAULT CODE F326


1. Chassis Control Module
2. Transmission Solenoid F1
3. Transmission Solenoid F2


1/99

F326

FAULT CODE F326 - TRANSMISSION SOLENOID F1 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





99

FAULT CODE F327


1. Chassis Control Module
2. Transmission Solenoid F1
3. Transmission Solenoid F2


1/99

F327

FAULT CODE F327 - TRANSMISSION SOLENOID F2 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





100

FAULT CODE F328


1. Chassis Control Module
2. Transmission Solenoid MC1
3. Transmission Solenoid MC2


1/99

F328

FAULT CODE F328 TRANSMISSION SOLENOID MC1 CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





101

FAULT CODE F329


1. Chassis Control Module
2. Transmission Solenoid MC1
3. Transmission Solenoid MC2


1/99

F329

FAULT CODE F329 TRANSMISSION SOLENOID MC2 CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





102


FAULT CODE 330


1. Chassis Control Module
2. Transmission Solenoid Reverse
3. Transmission Solenoid #1

1/99 F330

FAULT CODE F330 - TRANSMISSION SOLENOID REVERSE CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





103

FAULT CODE F331


1. Chassis Control Module


2. Creeper Solenoid

1/99 F331

FAULT CODE F331 - TRANSMISSION SOLENOID CREEPER CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





104

FAULT CODE F332


1. Chassis Control Module


2. FWD Solenoid

1/99 F332

FAULT CODE F332 - FWD SOLENOID CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





105

FAULT CODE F333


1. Chassis Control Module
2. Fuel Pull-In Relay (MDP-R16)
3. Fuel Solenoid Asy.


1/99

F333

FAULT CODE F333 - FUEL HOLD SOLENOID CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





106


FAULT CODE F334


1. Chassis Control Module
2. PTO Solenoid
3. Diff. Lock Solenoid

1/99 F334

FAULT CODE F334 - PTO SOLENOID CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





107

FAULT CODE F335


1. Chassis Control Module
2. PTO Solenoid
3. Diff. Lock Solenoid


1/99

F335

FAULT CODE F335 - DIFF. LOCK SOLENOID CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





108


FAULT CODE F336


1. Chassis Control Module
2. Fuel Pull-In Relay (MDP-R16)
3. Fuel Solenoid Asy.

1/99 F336

FAULT CODE F336 - FUEL PULL-IN SOLENOID CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.











C080

5. CT01-N-18







C195

A. RT01-N-18
B. RT02-Y-18


1. RT01-N-18
2. RT02-N-18
3. RT03-U-18
4. RT04-N-18






C194


1. CT01-N-18
2. CT02-Y-18
3. CT03A-W-18
4. CT07B-W-18






C196


A. RT03-N-18
B. RT04-N-18






C006

8. CT02-Y-18
22. CM274S-R-16
24. CM275T-B-16






C007

2. CM259S-R-16
3. CM260T-B-16

109

FAULT CODE F337

FAULT CODE F337 - TRAILER BRAKE FAULT (ISO)




19994118


2/02

F337

FAULT CODE F337 – TRAILER BRAKE FAULT (ISO)


***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.






111

FAULT CODE F338





112

FAULT CODE F338


1. Chassis Control Module
2. Air Filter Vacuum Switch
3. Engine Oil Pressure Sensor
4. Rockshaft Potentiometer

1/99


F338

FAULT CODE F338 – CCM 5 VOLT SUPPLY FAILED LOW (5/3)

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.




(This page is intentionally blank.)



113

FAULT CODE F339



114

FAULT CODE F339


1. Chassis Control Module
2. Air Filter Vacuum Switch
3. Engine Oil Pressure Sensor
4. Rockshaft potentiometer

1/99


F339

FAULT CODE F339 - CCM 5 VOLT SUPPLY FAILED HIGH (5/3)

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.



(This page is intentionally blank.)



115


FAULT CODE F340


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F340

FAULT CODE F340 - AXLE SPEED SENSOR CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





116


FAULT CODE F341


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F341

FAULT CODE F341 - AXLE SPEED SENSOR CIRCUIT SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





117


FAULT CODE F342


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F342

FAULT CODE F342 - ENGINE RPM SENSOR CIRCUIT OPEN

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





118


FAULT CODE F343


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F343

FAULT CODE F343 - ENGINE RPM SENSOR CIRCUIT SHORTED

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





119

FAULT CODE F344


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor


1/99

F344

FAULT CODE F344 - ENGINE RPM SENSOR CIRCUIT FAILED WHILE TRACTOR MOVING

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





120


FAULT CODE F345


1. Chassis Control Module
2. Axle Speed Sensor
3. Engine RPM Sensor

1/99 F345

FAULT CODE F345 - AXLE SPEED SENSOR CIRCUIT FAILED WHILE TRACTOR MOVING

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





121

FAULT CODE F346

1. Electronic Instrument Cluster


2. Clutch Potentiometer


1/99

F346

FAULT CODE F346 - CLUTCH POTENTIOMETER SHORT CIRCUIT TO GROUND

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





122

FAULT CODE F347

1. Electronic Instrument Cluster


2. Clutch Potentiometer


1/99

F347

FAULT CODE F347 - CLUTCH POTENTIOMETER OPEN CIRCUIT

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





123

FAULT CODE F348

1. Electronic Instrument Cluster


2. Clutch Potentiometer


1/99

F348

FAULT CODE F348 - CLUTCH CALIBRATION ERROR LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





124

FAULT CODE F349

1. Electronic Instrument Cluster


2. Clutch Potentiometer


1/99

F349

FAULT CODE F349 - CLUTCH CALIBRATION ERROR HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





125

FAULT CODE F350


1. Right Hand Controls Module
2. Clutch Switch
3. Directional Interrupt Relay (MDP-R6)
4. Clutch Potentiometer
5. Electronic Instrument Cluster


1/99

FAULT CODE F350 - CLUTCH SWITCH AND POTENTIOMETER DISAGREE WHEN PEDAL DEPRESSED OR DIRECTIONAL INTERRUPT RELAY CIRCUIT FAULT

F350

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





126

FAULT CODE F351


1. Right Hand Controls Module
2. Clutch Switch
3. Directional Interrupt Relay (MDP-R6)
4. Clutch Potentiometer
5. Electronic Instrument Cluster


1/99

FAULT CODE F351 - CLUTCH SWITCH AND POTENTIOMETER DISAGREE WHEN PEDAL RAISED

F351


***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





127

Refer to “Transmission Calibration” in Section 21, Chapter 5 of this Repair Manual for complete instructions.




128


1/99

F360

FAULT CODE F360 - F1 (FORWARD) CALIBRATION OFFSET CONSTANT


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





129

Refer to “Transmission Calibration” in Section 21, Chapter 5 of this Repair Manual for complete instructions.




130


1/99

F361

FAULT CODE F361 - F2 (FORWARD) CALIBRATION OFFSET CONSTANT


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





131

Refer to “Transmission Calibration” in Section 21, Chapter 5 of this Service Manual for complete instructions.




132

1/99


F362

FAULT CODE F362 - R (REVERSE) CALIBRATION OFFSET CONSTANT


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



Refer to “Transmission Programming” in Section 21, Chapter 5 of this Repair Manual for complete instructions.



133




134

1/99


F363

FAULT CODE F363 - PROGRAMMABLE SHUTTLE CONSTANT


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




Refer to “Transmission Calibration” in Section 21, Chapter 5 of this Repair Manual for complete instructions.



135



136




137

1/99


F365

FAULT CODE F365 - F1/F2 SHIFT CONSTANT ERROR


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




Refer to “Transmission Calibration” in Section 21, Chapter 5 of this Repair Manual for complete instructions.



138



139




140

1/99

F366


FAULT CODE F366 - F2/F1 SHIFT CONSTANT ERROR


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



2/02

F370





50022422


FAULT CODE F370 - STEERING ANGLE SENSOR SHORT TO GROUND

2/02

F370


FAULT CODE F370 - STEERING ANGLE SENSOR SHORT TO GROUND


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



2/02

F371





50022422

FAULT CODE F371 - STEERING ANGLE SENSOR CIRCUIT OPEN

2/02

F371

FAULT CODE F371 - STEERING ANGLE SENSOR CIRCUIT OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.




CHART 10, TRACTOR FEATURES CONFIGURATION

FEATURE NUMBER	DESCRIPTION		VALUE
1	DOES TRACTOR HAVE 540 RPM PTO?	NO YES	0 1
2	DOES TRACTOR HAVE 1000 RPM PTO?	NO YES	0 1
3	WHAT TYPE OF COLD START IS USED?	ETHER THERMOSTART AIR INLET*	0 1 2
4	IS TRACTOR USED WITH LIGHTED TRAILERS? (Enables EIC trailer indicator lamps–ISO)	NO YES	0 1
5	TRANSMISSION TYPE? North America ISO ++ ISO special application ++ ISO special application	16X9, 30 KPH 0 18X9, 40 KPH 1 18X9, 30 KPH (temp) 18X9, 40 KPH (perm)	0 1 2 3
6	DOES TRANSMISSION HAVE CREEPER?	NO YES	0 1
7	WHAT FRONT AXLE?	2 WHEEL DR FRONT WH DR SUPER STR FWD	0 1 2
8	WHAT IS THE TRACTOR MODEL?	8670/G170 8770/G190 8870/G210 8970/G240	0 1 2 3
9	WHAT 3 POINT HITCH OPTIONS?	NONE POSITION ONLY POSITION/DRAFT	0 1 2
10	SLIP OVERRIDE EQUIPPED? (RADAR REQUIRED)	NOT INSTALLED INSTALLED	0 1
11	EDC GAIN? (RESPONSE)	LOW –LOWER MED – BASE+ HI – HIGHER HI – HIGHEST	0 1 2 3
12	FWD BRAKING?	ENABLED DISABLED	0 1
13	HYDRAULIC OIL TEMPERATURE SHUTDOWN:+++ NORMAL NO SHUTDOWN	 ENABLED DISABLED	 0 1
14	TerraLock PRESENT? (Rev. 5 software only)	ENABLED DISABLED	1 0

***** Can not be set using PDT special tool diagnostic cartridge version 1.0

+ Factory setting

++ Can be set/changed only with PDT special tool

+++ Feature only available on tractors with EIC software level 06.37 or more recent.

Refer to “Mode 12, Tractor Feature Configuration” in Section 55, Chapter 1 of this Repair Manual for complete instructions.

FAULT CODE F377

1/99

F377

FAULT CODE F377 - TRANSMISSION CONFIGURATION BYTE 1 ERROR

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




CHART 10, TRACTOR FEATURES CONFIGURATION

FEATURE NUMBER	DESCRIPTION		VALUE
1	DOES TRACTOR HAVE 540 RPM PTO?	NO YES	0 1
2	DOES TRACTOR HAVE 1000 RPM PTO?	NO YES	0 1
3	WHAT TYPE OF COLD START IS USED?	ETHER THERMOSTART AIR INLET*	0 1 2
4	IS TRACTOR USED WITH LIGHTED TRAILERS? (Enables EIC trailer indicator lamps–ISO)	NO YES	0 1
5	TRANSMISSION TYPE? North America ISO ++ ISO special application ++ ISO special application	16X9, 30 KPH 0 18X9, 40 KPH 1 18X9, 30 KPH (temp) 18X9, 40 KPH (perm)	0 1 2 3
6	DOES TRANSMISSION HAVE CREEPER?	NO YES	0 1
7	WHAT FRONT AXLE?	2 WHEEL DR FRONT WH DR SUPER STR FWD	0 1 2
8	WHAT IS THE TRACTOR MODEL?	8670/G170 8770/G190 8870/G210 8970/G240	0 1 2 3
9	WHAT 3 POINT HITCH OPTIONS?	NONE POSITION ONLY POSITION/DRAFT	0 1 2
10	SLIP OVERRIDE EQUIPPED? (RADAR REQUIRED)	NOT INSTALLED INSTALLED	0 1
11	EDC GAIN? (RESPONSE)	LOW –LOWER MED – BASE+ HI – HIGHER HI – HIGHEST	0 1 2 3
12	FWD BRAKING?	ENABLED DISABLED	0 1
13	HYDRAULIC OIL TEMPERATURE SHUTDOWN:+++ NORMAL NO SHUTDOWN	 ENABLED DISABLED	 0 1
14	TerraLock PRESENT? (Rev. 5 software only)	ENABLED DISABLED	1 0

***** Can not be set using PDT special tool diagnostic cartridge version 1.0

+ Factory setting

++ Can be set/changed only with PDT special tool

+++ Feature only available on tractors with EIC software level 06.37 or more recent.

Refer to “Mode 12, Tractor Feature Configuration” in Section 55, Chapter 1 of this Repair Manual for complete instructions.


FAULT CODE F378

1/99

F378


FAULT CODE F378 - TRANSMISSION CONFIGURATION BYTE 2 ERROR

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



When the “Transmission Configuration” byte 3 error is present, it is possible to reset the static radius, 1, of the rear wheels to clear the fault code. If this does not clear the fault code, then the memory location for this information has been permanently damaged, and the chassis control module should be replaced.

Refer to “Mode 1, Operator Calibrations” in Section 55, Chapter 1 of this Repair Manual for complete instructions.




141

1/99

F379

FAULT CODE F379 - TRANSMISSION CONFIGURATION BYTE 3 ERROR


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



1/99 F380

FAULT CODE F380 - PROTOTYPE HARDWARE REVISION ERROR

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




1/99


F381

FAULT CODE F381 - PRODUCTION HARDWARE REVISION ERROR


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



Refer to “Transmission Programming” in Section 21, Chapter 5 of this Repair Manual for complete instructions.



142




143

1/99


F382

FAULT CODE F382 - PROGRAMMABLE UPSHIFT CONSTANT ERROR


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



Refer to “Transmission Programming” in Section 21, Chapter 5 of this Repair Manual for complete instructions.



144




145


1/99

F383

FAULT CODE F383 – PROGRAMMABLE DOWNSHIFT CONSTANT ERROR

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





146

FAULT CODE F386


1. Chassis Control Module


2. Transmission Oil Temperature Sensor

1/99 F386

FAULT CODE F386 - TRANSMISSION OIL TEMPERATURE HIGH ALARM (Shutdown)

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





147


FAULT CODE F387


1. Chassis Control Module
2. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
3. Transmission Oil Pressure Switch

1/99 F387

FAULT CODE F387 - TRANSMISSION OIL PRESSURE LOW ALARM (Shutdown)

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





148


FAULT CODE F388


1. Chassis Control Module
2. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
3. Transmission Oil Pressure Switch

1/99 F388

FAULT CODE F388 - TRANSMISSION OIL PRESSURE SWITCH CIRCUIT FAILED LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





149

FAULT CODE F389


1. Chassis Control Module


2. Transmission Oil Temperature Sensor

1/99 F389

FAULT CODE F389 - TRANSMISSION OIL TEMPERATURE SENSOR FAILED LOW

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





150

FAULT CODE F390


1. Chassis Control Module


2. Transmission Oil Temperature Sensor

1/99 F390

FAULT CODE F390 - TRANSMISSION OIL TEMPERATURE SENSOR FAILED HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





151

FAULT CODE F391


1. Chassis Control Module
2. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
3. Hydraulic Filter Switch


1/99

F391

FAULT CODE F391 - HYDRAULIC FILTER PLUGGED ALARM

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





152


FAULT CODE F392


1. Chassis Control Module
2. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
3. Transmission Filter Switch

1/99 F392

FAULT CODE F392 - TRANSMISSION FILTER PLUGGED ALARM


***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





153

FAULT CODE F393



154

FAULT CODE F393


1. Chassis Control Module
2. Directional Interrupt Relay
3. Transmission Control Fuse (MDP-F20)
4. Clutch Switch
5. Shift Control Asy.

1/99


F393

FAULT CODE F393 - POWER AVAILABLE ON DIRECTIONAL CLUTCHES

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.



(This page is intentionally blank.)



155


FAULT CODE F399


1. Chassis Control Module
2. Memory Unswitched Power (MDP-F25)
3. Control Modules Switched Power (MDP-F23)
4. Cab Ground

1/99 F399

FAULT CODE F399 - ELECTRONIC TRANSMISSION CONTROLLER TRANSIENT RESET

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





156

FAULT CODE F400

1. Chassis Control Module


2. Engine Temperature Sensor


1/99

F400

FAULT CODE F400 - ENGINE COOLANT TEMPERATURE HIGH ALARM (Shutdown)

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





157

FAULT CODE F401

1. Chassis Control Module


2. Engine Oil Pressure Sender


1/99

F401

FAULT CODE F401 - ENGINE OIL PRESSURE LOW ALARM (Shutdown)

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





158

FAULT CODE F402

1. Chassis Control Module


2. Exhaust Gas Temperature Sensor


1/99

F402

FAULT CODE F402 - EXHAUST GAS TEMPERATURE HIGH ALARM

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





159

FAULT CODE F403

1. Chassis Control Module


2. Intercooler Temperature Sensor


1/99

F403

FAULT CODE F403 - INTERCOOLER TEMPERATURE HIGH ALARM

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





160

FAULT CODE F404

1. Chassis Control Module


2. Fuel Level Sender


1/99

F404

FAULT CODE F404 - FUEL LEVEL SENDER CIRCUIT FAIL LOW

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





161

FAULT CODE F405

1. Chassis Control Module


2. Fuel Level Sender


1/99

F405

FAULT CODE F405 - FUEL LEVEL SENDER CIRCUIT FAIL HIGH

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





162

FAULT CODE F406

1. Chassis Control Module


2. Engine Temperature Sensor


1/99

F406

FAULT CODE F406 - ENGINE COOLANT TEMPERATURE CIRCUIT FAIL LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





163

FAULT CODE F407

1. Chassis Control Module


2. Engine Temperature Sensor


1/99

F407

FAULT CODE F407 - ENGINE COOLANT TEMPERATURE CIRCUIT FAIL HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





164

FAULT CODE F408

1. Chassis Control Module


2. Engine Oil Pressure Sender


1/99

F408

FAULT CODE F408 - ENGINE OIL PRESSURE CIRCUIT FAIL LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





165

FAULT CODE F409


1. Chassis Control Module


2. Exhaust Gas Temperature Sensor

1/99 F409

FAULT CODE F409 - EXHAUST GAS TEMPERATURE (EGT) SENSOR CIRCUIT FAILED LOW

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





166

FAULT CODE F410

1. Chassis Control Module


2. Exhaust Gas Temperature Sensor


1/99

F410

FAULT CODE F410 - EXHAUST GAS TEMPERATURE (EGT) SENSOR FAILED HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





167

FAULT CODE F411

1. Chassis Control Module


2. Intercooler Temperature Sensor


1/99

F411

FAULT CODE F411 - INTERCOOLER TEMPERATURE SENSOR FAILED LOW

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





168

FAULT CODE F412

1. Chassis Control Module


2. Intercooler Temperature Sensor


1/99

F412

FAULT CODE F412 - INTERCOOLER TEMPERATURE SENSOR FAILED HIGH

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.





169

FAULT CODE F413


1. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
2. Transmission Power Relay (MDP-R11)
3. Main Transmission Fuse (MFP-3)
4. DOP Radar
5. Chassis Control Module


1/99

F413

FAULT CODE F413 - RADAR SENSE LINE FAIL

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





170

FAULT CODE F414


1. Trans. F/R Control Solenoid/PTO Fuse (MDP-F20)
2. Transmission Power Relay (MDP-R11)
3. Main Transmission Fuse (MFP-3)
4. DOP Radar
5. Chassis Control Module


1/99

F414

FAULT CODE F414 - RADAR SIGNAL LINE FAIL

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





171

FAULT CODE F415


1. Chassis Control Module


2. Coolant Level Sensor

1/99 F415

FAULT CODE F415 - COOLANT LEVEL SENSOR CIRCUIT FAILED LOW

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





172

FAULT CODE F416

1. Chassis Control Module


2. Engine Temperature Sensor


1/99

F416

FAULT CODE F416 - COOLANT LEVEL SENSOR CIRCUIT FAILED OFF HIGH

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





173

FAULT CODE F417

1. Chassis Control Module


2. Air Filter Vacuum Switch


1/99

F417

FAULT CODE F417 - AIR CLEANER FILTERS STATUS

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





174

FAULT CODE F418

1. Chassis Control Module


2. Coolant Level Sensor


1/99

F418

FAULT CODE F418 - COOLANT LEVEL STATUS

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





175

FAULT CODE F419

1. Chassis Control Module


2. Alternator

1/99


F419

FAULT CODE F419 - ALTERNATOR NOT CHARGING

***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.



The “I” terminal, 2, is connected internally to the field circuit. The indicator light, 1, is connected in series with this terminal, the light will be on whenever there is a voltage difference between the “positive” side of the field circuit and the system voltage at the other side of the indicator light. During normal generator operation, the light will be off since the diode trio output voltage equals the system voltage.




176


1/99 F420

FAULT CODE F420 - ALTERNATOR OVERCHARGING (> 16V)


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.




To determine the condition of the battery, perform a battery load test after it is fully charged.



177



178




179


1/99

F421

FAULT CODE F421 - ELECTRONIC INSTRUMENT CLUSTER FAULT V POWER LOW


***NOTE:** Refer to “Diagnostics Procedure Overview and Checklist” (page 55-2 of this chapter) and “Troubleshooting Checklist” (page 55-5 of this chapter) before performing the procedures on this fault code.





180

FAULT CODE F422



181


FAULT CODE F422

1. Chassis Control Module
2. Air Filter Vacuum Switch
3. Engine Oil Pressure Sensor
4. Exhaust Temperature Sensor
5. Coolant Level Sensor

1/99 F422

FAULT CODE F422 - FRONT/REAR MAIN HARNESS CONNECTOR C008 OPEN

***NOTE:** Refer to "Diagnostics Procedure Overview and Checklist" (page 55-2 of this chapter) and "Troubleshooting Checklist" (page 55-5 of this chapter) before performing the procedures on this fault code.



SECTION 55 – ELECTRICAL SYSTEMS

Chapter 3 – Starting System


CONTENTS

Section	Description	Page
55 201	Specifications	2
	Description of Operation	3
	Introduction	3
	Batteries	4
	Cold Start System - Ether Operation (BSN D414644)	5
	Ether Cold Start Circuit Troubleshooting	7
	Cold Start System - Air inlet Heater (ASN D414643)	8
	Air Inlet Heater Troubleshooting	12
	Fuel Stop Solenoid and Override System	13
	Shutdown Override	14
	Troubleshooting the Cranking Circuit	15
	Disassembly and Repair	18
	Cleaning	22
	Armature Servicing	23
	Field Coil Checks	24
	Field Coil Removal	24
	Solenoid Checks	25
	Three-Terminal Solenoid	26
	Reassembly	27
	Lubrication	27
	PInion Clearance	28

SPECIFICATIONS

COMPONENT	IDENTIFICATION/DESCRIPTION
Starter	
Make	Delco Remy
Model	1993988
Series	37MT
Type	300
Power rating	6.0 HP (4.5 Kw)
Voltage	12
Stall torque	68 N·m @ 1800 /amps
Free spin current	120 amp minimum 160 amp maximum
Free spin speed	6000 RPM minimum 8700 RPM maximum
Minimum Battery Voltage	10 Volts
Hold-In Winding Current Draw	16-20 amps
Pull In Winding Current Draw	24-29 amps
Cold start aids	
BSN D414644	Ether injection system Below 20° C (68° F) 110 volt engine block heater 600 watt (single) 110 volt hydraulic oil heater (optional) 400 watt (single)
ASN D414643	Air inlet heater system Below 14° C (57° F) 110 volt engine block heater 600 watt (single) 110 volt hydraulic oil heater (optional) 400 watt (single)
Battery	12 volt, Negative ground
Quantity	2 per tractor
Capacity	950 CCA @ −18° C (0° F)
Reserve capacity	190 min. @ 25 amp load
Number of cells	6 per battery

DESCRIPTION OF OPERATION




1

INTRODUCTION

The starting system consists of two 12-volt, 950 CCA batteries, 2; a Delco Remy starting motor and solenoid assembly, 3; a starting relay, 4, located on the hood support casting; a transmission neutral safety start switch located in the transmission control lever, 5, heavy-duty circuit wiring and a key start switch, 1.

The heavy-duty cranking motor has a shift lever and solenoid plunger, 1, that are totally enclosed to protect it from exposure to dirt, icing conditions and splash. The nose housing can be rotated to obtain a number of different solenoid positions with respect to the mounting flange. High durability features include a newly designed drive, 2, solenoid, and brush rigging and one-piece brushes, 3, which provide extra long brush life. Also, the commutator end cap, 4, can be removed to inspect the brushes.

Lubrication is provided in the sintered bronze bushings by an oil saturated wick, 5. Oil can be added to each wick by removing an oil reservoir cup which is accessible on the outside of the motor.



2

When the key start switch is closed with the transmission control lever in neutral, the solenoid coils are energized and the solenoid plunger is magnetically attracted into the solenoid core. The magnetic switch contacts close, and the solenoid windings are connected to the battery.

The resulting plunger and shift lever movement causes the pinion to engage the engine flywheel ring gear and the solenoid main contacts to close, and cranking takes place. When the engine starts, pinion overrun protects the armature from excessive speed until the switch is opened, at which time the return spring causes the pinion to disengage. To prevent excessive overrun and damage to the drive and armature windings, the switch must open immediately when the engine starts. A cranking period should never exceed 30 seconds without stopping to allow the motor to cool for at least two minutes.

BATTERIES

Discharged Batteries

Tractor batteries will drain down during extended storage periods.

The key-off current drain was 58 milliamps on tractors built before September 15, 1994. Tractors built after September 15, 1994 had revised electronic hardware that lowered the key-off current drain to 22 milliamps. For early tractors, the best action is to disconnect the battery cables during long-term storage or use a low-rate battery charger connected to a daily timer to keep the batteries charged.

Battery Types

Two styles of batteries have been used – screw terminal and tapered top posts. Tapered top posts are low-maintenance batteries. The batteries with screw-type terminals are maintenance-free batteries. Maintenance-free batteries are very difficult to recharge if they are fully discharged during storage.


Low-maintenance batteries will require periodic checks on fluid levels because the water in the cells will gas off during hot weather operation.

COLD START SYSTEM - ETHER OPERATION (BSN D414644)

The EIC will allow the cold-start system to operate only if the following two conditions are met:


- Engine cranking speed is above 50 RPM (160 RPM on software before March, 1994) for one second, as sensed by the engine speed sensor).
- Engine coolant temperature is below 20° C (68° F) as sensed by the coolant temperature sender.

When activated, the EIC cold-start lamp, 1, will be on for 6 seconds. The cold-start system can be reactivated by pressing and releasing switch, 2, when the lamp is off.




3

The ether solenoid, 3, is located by the engine fan on the left side of the engine.



4



70-580-848

5

The cold-start system is powered from the main fuse MFP-2 through wires CM15B and CM16B and through the cold-start fuse MDP-F27. Power is delivered from fuse MDP-F27 to the cold-start relay MDP-R8 pin 3 through wire CM8.

Relay MDP-R8 is activated when the key switch is turned to ON or START and the cold-start push button is pressed. Power to energize relay MDP-R8 comes from the key-switch fuse MDP-F26 on wire CM26, through the key switch and then to the cold-start push button switch on wire CM3. When the cold-start push button is pressed, power is delivered to the EIC module J1 pin C12 through wire CM13. If the engine speed and coolant temperature are correct, as signaled through the CAN communications link, the EIC will send power from the J1 pin D8 to relay MDP-R8 pin 2 through wire CM10.

To complete the activation circuit, relay MDP-R8 pin 1 is connected to ground through wire CM9A.

When relay MDP-R8 is activated, the power at pin 3 is connected to pin 5. From pin 5, power goes to the ether solenoid pin A through wires CM7, RM7, FM7S, and FM11S. To energize the ether solenoid, pin B is connected to ground through wire FM8.

Engine speed data is sent from the engine speed sensor pin A to the CCM J2 pin 4 through wire RM80. Engine coolant temperature data is sent from the coolant temperature sensor pin B to the CCM J2 pin 2 through wires FM85 and RM85. Circuit common, for the speed and coolant sensors, is provided by wire RM67T connected to the CCM J2 pin 8. Wire RM75T connects the engine speed sensor pin B to wire RM67T. Wires FM16T and RM76T connect the coolant temperature sensor pin A to wire RM67T.

ETHER COLD-START CIRCUIT TROUBLESHOOTING

Use the following procedure to determine what part of the cold-start circuit is not working.

High-Amperage Circuit

1. Remove relay MDP-R8 and check for battery voltage at relay socket pin 3.
2. With the ether can removed, momentarily install, then remove, a jumper between relay socket pins 3 and 5. The ether solenoid should click and operate. If it doesn't, check the power circuit from fuse MDP-F27 to the solenoid and the ground circuit to the solenoid.

Control Circuit

3. If the high-amperage circuit is working, replace relay MDP-R8, remove the EIC connector C007, and very carefully install a jumper wire between connector sockets C12 and D8. With the ether can removed, turn the key switch on, momentarily press, then release the cold-start switch. The ether solenoid should click and operate. If it doesn't, check the key switch, relay ground, and activation circuits pins 1 and 2.
4. If the ether solenoid operates, reinstall the EIC. Check that the coolant temperature sender is working by entering MODE _ _ _ 3 and then disconnecting the sender. The coolant sender identifier is P400. The value for a disconnected sender is approximately 97. Reconnect the sender and record the value. The value for a cold sender is 84 or higher.
5. If the coolant temperature sender value is lower than 83, the cold start is not supposed to work. (Is the block heater plugged in?) If the engine speed sender doesn't send an above-50-RPM (160 RPM on software before March, 1994) signal for at least one second, the system won't work.

NOTE: *If the EIC RPM display shows 0 RPM while cranking, the ether system will not work.*

Ether Atomizer

6. If the ether solenoid clicks in the above tests, but no ether is being injected with the can installed, remove the ether injector atomizer from the intake manifold.
7. Operate the system with the nozzle attached but removed from the manifold. As the ether switch is pressed and released, while cranking the engine or running it cold, the EIC lamp will light and the ether canister will fill for 3 seconds. After 3 seconds, the ether will be released and a fine mist should spray from the side of the atomizer for about 3 seconds.
8. The ether injection nozzle has a red paint mark on the outer flange that is in line with the nozzle orifice hole. This hole is 0.2 mm (0.008″). The red mark should be aligned with the inlet hose to properly atomize the ether as it is injected. The canister outlet also has a 0.2 mm (0.008″) release orifice.


NOTE: *Do not attempt to enlarge the atomizer hole by drilling it out. Drilling the atomizer hole will only prevent atomization of the ether.*

COLD START SYSTEM - AIR INLET HEATER (ASN D414643)

The EIC will allow the Preheat Cycle of the cold-start system to operate only if the following conditions are met:


- Engine cranking speed is below 50 RPM.
- Engine coolant temperature is below 14°C (57°F)

When activated, the EIC cold-start lamp, 1, will be on and the heater will heat for 25 seconds. After the light goes out, the tractor can then be cranked to activate the Post Heat cycle. The Post Heat cycle will operate when engine speed is greater than 400 RPM. The post heat cycle will vary in length from 30 to 60 seconds depending on the coolant temperature.




6

The air inlet heater, 1, and heater relay, 2, are located on the intercooler tube, 3, on the right side of the engine.



7

This page is intentionally blank.


CCW
C002
J2 – 2
J2 – 8
J2 – 4
2
4
8
RM80–B–18
ENGINE SPEED SENSOR
C100
A
B
RM751–B–18
RM767–B–18
C006
S
X
FW85–P–18
FW767–B–18
FW167–B–18
SPLICE–T
ENG TEMP SENSOR
C104
A
B
MAIN FUSE (MFP – 2)
50 A
CW150–R–8
CW100–R–10
SPLICE B
KEY SW FUSE (MFP – F26)
10 A
CM26–R–18
IGNITION SW
1 – ACC
2 – OFF
3 – ACC / IGN
4 – IGN / START (WOW)
C080
COLD START FUSE (MFP – F27)
20 A
DC
C007
J1 – C12
CM13–Y–18
COLD START SW
C076
CM3-Y-18
COLD START RELAY (MDP – R8)
C003
C008
CM7-0-12
RM7-0-12
C6
J1 – D8
CM10–P–18
CM9A-B-18
FM7S-0-12
AIR
INLET HEATER
RELAY
AIR
INLET
HEATER
R–4
FM8–B–14
ALTERNATOR
FM5–R–2
STARTER
S
B+
M
BATTERY
BC2–R–2/0
BC1–B–2/0
BC1–B–2/0

70-580-848

The air inlet heater cold-start system is powered from the battery through wires BC2 and FM5 to the alternator terminal B+. Power then travels through a 4 gauge wire to the air inlet heater relay. When the relay is energized power flows from the relay through a 4 gauge wire to the air inlet heater then to ground.


The air inlet heater relay is energized from the main fuse MFP-2 through wires CM15B and CM16B and through the cold-start fuse MDP-F27. Power is delivered from fuse MDP-F27 to the cold-start relay MDP-R8 pin 3 through wire CM8.

The cold start relay MDP-R8 is activated when the key switch is turned to ON and the cold-start push button is pressed. Power to energize relay MDP-R8 comes from the key-switch fuse MDP-F26 on wire CM26, through the key switch and then to the cold-start push button switch on wire CM3. When the cold-start push button is pressed, power is delivered to the EIC module J1 pin C12 through wire CM13. If the engine speed and coolant temperature are correct, as signaled through the CAN communications link, the EIC will send power from J1 pin D8 to relay MDP-R8 pin 2 through wire CM10.

To complete the activation circuit, relay MDP-R8 pin is connected to ground through wire CM9A.

When relay MDP-R8 is activated, the power at pin 3 is connected to pin 5. From pin 5, power goes to the air inlet relay pin A through wires CM7, RM7, FM7S, and FM11S. To energize the air inlet relay pin B is connected to ground through wire FM8. Engine speed data is sent from the engine speed sensor pin A to the CCM J2 pin 4 through wire RM80. Engine coolant temperature sensor pin B to the CCM J2 pin 2 through wires FM85 and RM85. Circuit common, for the speed and coolant sensors, is provided by wire RM67T connected to the CCM J2 pin 8. Wire RM75T connects the engine speed sensor pin B to wire RM67T. Wires FM16T and RM76T connect the coolant temperature sensor pin A to wire RM67T.

AIR INLET HEATER TROUBLESHOOTING




*NOTE: To troubleshoot the system if coolant temperature is above 14 deg C (57 deg F) disconnect temperature sender then try the system. Troubleshoot the remaining circuit as described above then replace the temperature sender and clear fault code(s).

FUEL STOP SOLENOID AND OVERRIDE SYSTEM


NOTE: *70 Series art shown in Figure 9.*

The fuel stop solenoid circuit allows the engine to start and stop using the key switch, by activating and deactivating the solenoid, 1, mounted on the right side of the engine.




9

The override circuit allows the engine to be operated if a (STOP) engine shutdown condition occurs, by activating the override switch, 1.



10



11

The fuel stop solenoid and override systems are powered by main fuse MFP-2, 1, which is the supply for the fuel solenoid relay, 2, MDP-R16 pin 30 via wires CM15B, 4, and CM14B, 3.

When the key switch is turned to the ON position, wire CM23 provides power to the override switch at connector C083, pin 3. With the switch off, power is provided to the EIC module at connector C007, pin C11 via wire CM22. The EIC module sends a signal to the CCM module via the CAN system link. The CCM connector C006, pin 1 provides power to the relay MDP-R16 pin 85 via wire CM19 which then activates due to the ground provided at pin 86 via wire CM18A.

When the relay activates, power is provided from pin 30 to pin 87 and on to the pull in coil of the fuel stop solenoid connector C108, pin B via wires CM12, RM12 and FM12. The CCM provides power to the pull in coil for approximately two seconds.

At the same time the relay activates, the fuel solenoid hold in windings pin A are activated by the CCM module at connector C001, pin R via wires RM13 and FM13. Ground for the fuel stop solenoid is provided from pin C via wire FM10.

When an automatic shutdown condition occurs, the EIC “STOP” message will flash for 30 seconds. The tractor will then lose power to the solenoid hold circuit, pin A.

SHUTDOWN OVERRIDE

If the operator presses the override switch, power flows from connector C083, pin 3 to pin 2 and back into connector C045, pin 9 via wire CM27. From pin 9, power flows through the override lamp to ground at pin 10 via wire CM20. When the EIC loses power at connector C007, pin C11, the tractor will continue to run regardless of the EIC STOP display.

TROUBLESHOOTING THE CRANKING CIRCUIT

ENGINE DOES NOT TURN OVER WHEN KEY START IS OPERATED, TRANSMISSION IN NEUTRAL

PROBLEM	POSSIBLE CAUSE	CORRECTION
Engine doesn't turn over when key start is operated	Transmission lever in forward or reverse	Return lever to the neutral position
	Battery voltage low or discharged	Recharge and load test batteries
	Wiring connections damaged or loose	Inspect and repair as required
	Engine or drivetrain mechanical problem	Inspect components for damage or failure
	No power at key start switch	Check for battery voltage at RED wire CM26. Check for voltage at fuse MDP-F26
		Check for battery voltage at BROWN wire CM23 with key on. Check for voltage at fuse MDP-F26
		Check for battery voltage at ORANGE wire with key in the start position. Check continuity of ORANGE wire CM2 to start relay wire FM1
	No power at starter relay mounted at rear hood support	Check for battery voltage at RED wire.
		Check for battery voltage at BROWN wire with key on Check continuity of wire CM3
		Check for battery voltage at ORANGE wire with key in the start position. Check continuity of wire RH61A and neutral switch in shift lever

If the cranking system is not performing properly, make the following checks to help determine which part of the circuit is at fault.

Battery: To determine the condition of the battery, perform a battery load test after it is fully charged. Insure that the battery is fully charged. The wiring, switches, and cranking motor cannot be checked if the battery is defective or discharged.

Wiring: Inspect the wiring for damage. Inspect all connections to the cranking motor, solenoid, magnetic switch, ignition switch and battery, including all ground connections. Clean and tighten all connections as required. The cranking system cannot operate properly with excessive resistance in the circuit.


Magnetic Switch, Solenoid and Ignition Switches: Inspect all switches to determine their condition. From the wiring diagram, determine which circuits should be energized with the starting switches closed. Use a voltmeter to detect any open circuits.

Motor: If the battery, wiring and switches are in satisfactory condition and the engine is known to be functioning properly, remove the motor and follow the test procedures outlined below.

A cranking motor is designed for intermittent duty only and should never be operated for more than 30 seconds at a time. After 30 seconds, the cranking must be stopped for at least two minutes to allow the motor to cool.


With the cranking motor removed from the engine, the armature should be checked for freedom of rotation by prying the pinion with a screwdriver. Tight bearings, a bent armature shaft, or a loose pole shoe screw will cause the armature to not turn freely. If the armature does not turn freely, the motor should be disassembled immediately. However, if the armature does rotate freely, the motor should be given a no-load test before disassembly.

The no-load test may point to specific defects which can be verified with tests when disassembled. Also, the no-load test can identify open or shorted fields which are difficult to check when disassembled. The no-load test also can be used to indicate normal operation on a repaired motor before installation.



70-510-813


12


70-520-852

13

No-Load Test

Connect a voltmeter from the motor terminal to the motor frame, and use an RPM indicator to measure armature speed. Connect the motor and an ammeter in series with a fully charged battery of the specified voltage, and a switch in the open position from the solenoid battery terminal to the solenoid switch terminal. Close the switch and compare the RPM current and voltage reading with the specifications. It is not necessary to obtain the exact voltage specified as an accurate interpretation can be made by recognizing that if the voltage is slightly higher the RPM will be proportionately higher, with the current remaining essentially unchanged. However, if the exact voltage is desired, a carbon pile connected across the battery can be used to reduce the voltage to the specified value. Make disconnections only with the switch open. Interpret the test results as follows:




14

1. Rated current draw and no-load speed indicates normal condition of the cranking motor.
2. Low free speed and high current draw indicate:
   a. Too much friction - tight, dirty, worn bearings, bent armature shaft or loose pole shoes allowing armature to drag.
   b. Shorted armature. This can be further checked on a growler after disassembly.
   c. Grounded armature or fields. Check further after disassembly.
3. Failure to operate with high current draw indicates:
   a. A direct ground in the terminal or fields.
   b. “Frozen” bearings (this should have been determined by turning the armature by hand).
4. Failure to operate with no current draw indicates:
   a. Open field circuit. This can be checked after disassembly by inspecting terminal connections and tracing circuit with a test lamp.
   b. Open armature coils. Inspect the commutator for badly burned bars after disassembly.
   c. Broken brush springs, worn brushes, high insulation between the commutator bars or other causes which would prevent good contact between the brushes and commutator.
5. Low no-load speed and low current draw indicate:
   a. High internal resistance due to poor connections, defective leads, dirty commutator and causes listed under Number 4.
6. High free speed and high current draw indicate shorted field. If shorted fields are suspected, replace the field coil assembly and check for improved performance.

DISASSEMBLY AND REPAIR


Normally the cranking motor should be disassembled only so far as is necessary to make repair or replacement of defective parts. As a precaution, it is suggested that safety glasses be worn when disassembling or assembling the cranking motor.

1. Note the relative position of the solenoid, 2, lever housing, 1, and nose housing, 5, so the motor, 3, can be reassembled in the same manner. Scribe a line, 4, across seams.




15

2. Disconnect field coil connector from solenoid motor terminal by removing screw, 2.
3. Remove solenoid attaching screws, 1.




16

4. Separate solenoid, 1, from lever housing by pulling apart. Inspect the solenoid and terminals, 2, for damage.




17

5. Remove the attaching bolts, 1, and separate the commutator end cap, 2, from the field frame.




18

6. Inspect the end cap bushing, 1, and armature shaft, 2, for damage and wear.




19

7. Remove the two field to brush attaching screws, 1. The ground brush screws, 2, can be left in place.




20

8. With a lifting device, 1, raise the field brush springs, 2, and remove the brushes.




21

9. The brush plate, 1, can now be removed from the field housing, 2.




22

10. Separate the nose housing and field frame from lever housing by removing the “C” clip, 3, from the armature shaft, 4. The pinion, 1, and pinion retainer, 2, must be pushed away from the “C” clip. Use snap ring pliers to move the “C” clip from its groove.
11. Remove the nose housing attaching bolts, 5, and pull the nose housing from the motor, 6.




23

12. The nose, 2, and lever housing, 1, can be disassembled by removing the retaining bolts, 3.
13. The pinion stop, 4, and pinion, 5, can now be removed and inspected.




24

14. To disassemble the lever housing, 2, remove the pinion travel adjustment cap and seal, 3.
15. Remove the adjusting nut, 4, and pull the solenoid armature, 1, from the housing.




25

16. Remove the star washer, 3, from the lever housing, 1.
17. Drive the pivot pin from the housing using a suitable punch, 2.



26

18. The lever housing, 1, pivot pin, 2, and pinion lever, 3, can now be inspected for damage and wear.



27


CLEANING

The drive, armature and fields should not be cleaned in any degreasing tank, or with grease-dissolving solvents, since these would dissolve the lubricant in the drive and damage the insulation in the armature and field coils. All parts except the drive should be cleaned with mineral spirits and a brush. The drive can be wiped with a clean cloth.

If the commutator is dirty, it may be cleaned with No. 00 sandpaper. **NEVER USE EMERY CLOTH TO CLEAN COMMUTATOR.**

Brushes and Holders

Inspect the brushes for wear. If they are worn excessively when compared with a new brush, they should be replaced. Make sure the brush holders are clean and the brushes are not binding in the holders. The full brush surface should ride on the commutator to give proper performance. Check by hand to insure that the brush springs are giving firm contact between the brushes and commutator. If the springs are distorted or discolored, they should be replaced.




28

ARMATURE SERVICING

If the armature commutator is worn, dirty, out of round, or has high insulation, the armature should be put in a lathe so the commutator can be turned down. As a final step in this procedure, the commutator should be sanded lightly with No. 00 sandpaper.

The armature should be checked for opens, short circuits and grounds as follows:

1. Opens - Opens are usually caused by excessively long cranking periods. The most likely place for an open to occur is at the commutator riser bars. Inspect the points where the conductors are joined to the commutator bars for loose connections. Poor connections cause arcing and burning of the commutator bars as the cranking motor is used. If the bars are not too badly burned, repair can often be effected by welding the leads in the riser bars (using rosin flux), and turning down the commutator in a lathe to remove the burned material.
2. Short Circuits - Short circuits in the armature are located by use of a growler. When the armature is revolved in the growler with a steel strip such as a hacksaw blade held above it, the blade will vibrate above the area of the armature core in which the short circuit is located. Shorts between bars are sometimes produced by brush dust or copper between the bars. These shorts can be eliminated by cleaning out the slots.
3. Grounds - Grounds in the armature can be detected by the use of an ohmmeter, 3. If the ohmmeter shows no or little resistance when one lead is placed on the commutator, 2, with the other lead on the core or shaft, 1, the armature is grounded. Grounds occur as a result of insulation failure which is often brought about by overheating of the motor produced by excessively long cranking periods or by accumulation of brush dust between the commutator bars and the steel commutator ring.




29

FIELD COIL CHECKS

The field coils can be checked for grounds and opens by using an ohmmeter.

Grounds - If the motor has one or more coils normally connected to ground, the ground connections must be disconnected during this check. Connect one lead of the ohmmeter to the field frame and the other lead to the field connector. If the reading shows no or little resistance, at least one field coil is grounded which must be repaired or replaced. This check cannot be made if the ground connection cannot be disconnected.

Opens - Connect ohmmeter leads to ends of field coils. If the reading is high, the field coils are open.



70-520-869

30


FIELD COIL REMOVAL

Field coils can be removed from the field frame assembly by using a pole shoe screwdriver. A pole shoe spreader may also be used to prevent distortion of the field frame. Careful installation of the field coils is necessary to prevent shorting or grounding of the field coils as the pole shoes are tightened into place.

Where the pole shoe has a long lip on one side and a short lip on the other, the long lip should be assembled in the direction of armature rotation so it becomes the trailing (not leading) edge of the pole shoe.

SOLENOID CHECKS


A basic three-terminal solenoid circuit is shown. With all other leads disconnected, the solenoid windings can be checked by making test connections as covered below.



31


THREE-TERMINAL SOLENOID

Make connections to the “S” terminal, 2, and a clean metal ground, 1. If needed, use the carbon pile, 4, to decrease the battery voltage to the value specified and compare the ammeter reading, 3, with the holding winding specifications. A high reading indicates a defective winding (shorted or grounded hold-in or a grounded pull-in), and a low reading indicates excessive resistance.




32

To check the pull-in winding connect from the solenoid switch terminal, 2, to the solenoid motor terminal, 1. Compare with the pull-in winding specification. A high ammeter, 3, reading indicates a shorted pull-in winding, and a low reading indicates excessive resistance. To avoid excessive heating, leave the pull-in winding connected no more than 10 seconds at a time. The current will decrease as the heating increases.



33



70-520-872

34

REASSEMBLY

Reassembly is in the reverse order of disassembly. Make sure that all scribe marks line up during reassembly to insure that the starter will properly fit the tractor.

To reassemble the brush plate assembly with brushes onto the field frame with armature in place, lift the brushes up so the spring contacts the side of the brush. Assemble to the field frame with the attaching screws. Lift up springs, and position brushes onto commutator.

LUBRICATION

All bearings, wicks and oil reservoirs should be saturated with SAE No. 20 oil. Place a light coat of lubricant Delco Remy No. 1960954 on the washer located on the shaft between the armature and shift lever housing.

Sintered bronze bearings used in these motors have a dull finish, as compared to the early type machined, cast bronze bearings which had a shiny finish.

Before pressing the bearing into place, dip it in SAE No. 20 oil. Also, tangent wicks should be soaked with SAE No. 20 oil. Insert the wick into place first, and then press in the bearing.

DO NOT DRILL, REAM OR MACHINE sintered bearings in any way! These bearings are supplied to size. If drilled or reamed, the I.D. (inside diameter) will be too large; also the bearing pores will be sealed over.


It is not necessary to cross-drill a sintered bearing when used with a tangent wick. Because the bearing is so highly porous, oil from the wick touching the outside bearing surface will bleed through and lubricate the shaft.

Middle bearings are support bearings and prevent armature deflection during cranking. As compared to end frame bearings, the clearance between middle bearing and shaft is large and the clearance provides a loose fit when assembled.

PINION CLEARANCE

To check pinion or drive clearance follow the steps listed below.


1. Remove “M” terminal nut, 3, and insulator motor winding connector from “M” terminal stud. Push connector about 1/8″ away from back nut to clear nut and stud. Place insulating material (like cloth) between connector and nut and stud.
2. Connect battery to “S” terminal, 2, and to clean metal ground, 1, on solenoid case.
3. Momentarily flash a jumper lead from ground, 1, to terminal “M,” 3. The drive will now shift into cranking position and remain so until the battery is disconnected.
4. Push the pinion or drive back towards the commutator end to eliminate slack movement.



70-520-873


35

5. Measure the distance between pinion, 1, and retainer, 2.
6. Measure for clearance of 0.25 - 1.75 mm (0.010″ - 0.070″) with a feeler gauge, 3.



36

7. Adjust clearance by removing plug and turning shaft nut with a socket wrench.



37

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 4 – Charging System

CONTENTS

Section	Description	Page
55 301	Specifications	2
	Torque Specifications	3
	Description of Operation	4
	Introduction	4
	Features	4
	Operating Principles	5
	Troubleshooting and Diagnosis	6
	Disassembly and Repair	13
	Unit Repair	13
	Disassembly and Bench Checks	14
	Generator Assembly	19


SPECIFICATIONS

COMPONENT	IDENTIFICATION/DESCRIPTION
Generator	
Make	Delco Remy
Model	21-SI
Amp Rating @ 5000 RPM	130
Voltage Rating	12
Rotor field resistance	1.7-1.8 OHMS
Ground	Negative
Batteries	12 volt, Negative ground
Quantity	2 per tractor
Capacity	950 CCA @ −18° C (0° F)
Reserve capacity	190 min. @ 25 amp load
Number of cells	6 per battery
Number of plates per cell	27

TORQUE SPECIFICATIONS

Tighten and secure SRE component fasteners in following order:

1. Inside output terminal nut to 5.5 N·m (50 in. lbs.).
2. Rectifier bridge attaching screw (2 places) to 3.0 N·m (25 in. lbs.).
3. Insulated capacitor attaching screw to 2.5 N·m (22 in. lbs.)
4. “R” and/or “I” terminal (2 places) inside nuts to 2.5 N·m (22 in. lbs.). It may be necessary to hold terminal on outside while tightening.
5. Regulator mounting screw (grounding) to 2.0 N·m (20 in. lbs.).
6. Insulated regulator attaching screws (2 places) to 2.0 N·m (20 in. lbs.).
7. Regulator nut (if used) to 2.5 N·m (22 in. lbs.).
8. Brush holder attaching screw (pivot) to 2.0 N·m (20 in. lbs.).



1

Tighten rectifier bridge nuts (3 places) to 2.5 N·m (22 in. lbs.).

Tighten through bolts to 5.5 N·m (50 in. lbs.).

Torque retaining attaching bolts to 128 N·m (95 ft. lbs.).

Tighten retainer plate attaching screws to 3.0 N·m (26 in. lbs.).


Tighten shaft nut to 100 N·m (75 ft lbs).

DESCRIPTION OF OPERATION

INTRODUCTION

The 21-SI series Delcotron® Generator is a high-output integral charging system with built-in diode rectifier and voltage regulator, producing DC current for the electrical system.

The solid state, integrated circuit voltage regulator built into the 21-SI generator limits system voltage by switching the ground circuit for the rotor field on and off. When the ground circuit is on, field current passes from a diode trio through the rotor via brushes and slip rings on the rotor shaft. Nominal regulated voltages of 13.8, 14.0, and 14.2 volts are available for 12-volt systems.




2

FEATURES

The 21-SI Delcotron Generator is a one-wire output configuration. One-wire refers to the minimum number of lead wire connections required at the generator for operation.

The one-wire type requires only that the generator output (“BAT”) terminal, 1, be connected to the battery positive terminal, 3, and that a ground path be provided between the generator housing and the battery negative terminal. “I” terminal connection is optional and does not affect generator operation.


The key switch, 2, connects the output to all keyed power circuits or loads, 4.



3

The “I” terminal, 1, is connected internally to the field circuit. The indicator light is connected in series with this terminal, the light will be on whenever there is a voltage difference between the “positive” side of the field circuit and the system voltage at the other side of the indicator light. During normal generator operation, the light will be off since the diode trio output voltage equals the system voltage.


The large output wire is connected to the “BAT” terminal, 2.



4

OPERATING PRINCIPLES

A generator is a voltage-creating machine. The voltage regulator, 1, limits the maximum voltage that the generator will produce at the output (“BAT”) terminal by controlling the magnetic field present in the rotor, 6. The voltage produced allows current via the brushes to flow to satisfy the electrical loads placed on the system, up to a maximum current characteristic of the generator design.



5

A schematic of the generator circuity is shown. With the generator rotor, 6, turning, magnetic fields around the rotor induce voltages in the stator windings, 4. The faster the rotor turns, the higher the induced voltage will be. In a one-wire system, the voltages at start-up are generated by residual magnetism in the rotor.

As speed and output increase, voltage available at the diode trio, 5, becomes sufficient to supply field current for normal operation. When the output voltage exceeds the battery voltage, the generator begins to drive the system voltage. The presence of system voltage at the diode trio equalizes the voltage on both sides of the indicator light and the light goes out.

While the system voltage is below the voltage regulator setting, the regulator turns on the field current through the rotor and allows the generator to produce as much output as possible for the generator speed (rpm), temperature and system voltage. When the voltage setting is reached, the regulator, 1, turns the field current off. When the field current is turned off, the magnetic field in the rotor collapses and the generator output voltage begins to fall. A capacitor, 2, in the rectifier bridge, 3, protects the regulator, 1, from voltage spikes. The falling voltage causes the regulator to turn the field current back on and the magnetic field to rebuild. This switching action of the regulator continues rapidly, keeping the output and system voltage very close to the voltage setting. This will continue unless the electrical demands of the system cause the system voltage to fall below the voltage setting. Should this happen, the regulator will again allow full field current to flow so that the maximum output of the generator at the given speed, temperature and system voltage is realized.

One-wire systems use system voltage at the generator to control the output voltage, and extra sense wiring is not needed.

TROUBLESHOOTING AND DIAGNOSIS

Trouble in the charging system will normally be indicated by one of the following:

- Indicator light “on” with engine running.
- Indicator light “off” with key on, engine not running.
- Undercharged or overcharged battery.
- Short life of light bulbs or other electric equipment caused by abnormally high system voltage.
- System voltmeter readings outside normal range.


Diagnose the charging system as follows:

A. All Charging Systems

TEST EQUIPMENT NEEDED:


- Belt tension gage
- Battery State-of-Charge indicator

1. Check electrical system wiring and battery terminals for poor connections or other obvious conditions that might result in shorts, opens, grounds, or high resistance. Correct as necessary.
2. Check generator drive belt for proper tension. Adjust to specifications.



6

3. Check battery for state-of-charge. If low, recharge according to specifications and load test to establish serviceability. Further diagnostic tests require known good, fully-charged batteries for accurate results.



7

B. Indicator Light Fault Testing

TEST EQUIPMENT NEEDED:

- Jumper lead with 5-amp fuse


1. If indicator light, 2, is on with engine running:

   Stop engine. Turn key switch, 3, to “run” position. Indicator light, 2, should be on. If not, go to step 3.

   Disconnect indicator light lead, 4, at generator, 5. This will be the “I” terminal connector.

   If indicator light, 2, remains on, locate and correct shorted or grounded condition in indicator light circuit between the light and generator.

   If indicator light, 2, goes out, light is working properly. Proceed to “C” Checking System With Indicator Light Working Properly.




8

2. If indicator light, 2, does not come on with the key switch, 3, in the “run” position with the engine stopped (“bulb check” mode):

   Leave key in “run” position with engine stopped. Disconnect indicator light lead, 4, from generator, 6. This will be at the “I” terminal. Use fused (5-amp) jumper lead, 5, to ground indicator lamp circuit in harness connector to generator housing.

   If indicator light, 2, comes on with jumper lead in place, repair the generator, 6.

   If indicator light, 2, does not come on with jumper lead, 5, in place, locate and correct open circuit in indicator light circuit. Circuit may be open or light bulb may be burned out. Correct as necessary.




9

3. If indicator light, 2, comes on while engine is running, but is not on with the engine stopped and key switch, 3, in “run” position:

   Leave key, 3, in “run” position with engine stopped. Disconnect indicator light lead, 4, from generator, 6. This will be at the “I” terminal. Use fuse (5-amp) jumper lead, 5, to ground indicator lamp circuit to generator housing.

   If indicator light, 2, comes on with jumper lead in place, replace regulator as described under Unit Repair.

   If indicator light, 2, does not come on with jumper lead in place, locate and correct open circuit in indicator light circuit between battery, 1, and light. (With engine running, light is being powered by generator, 6, and grounded through other circuits connected in parallel to indicator light circuit.) Correct as necessary.




10

4. If indicator light, 2, is on with key switch, 3, in “off” position.

   Disconnect indicator light circuit, 4, at generator, 5.

   If indicator light, 2, remains on, locate and correct shorted condition between the light, 2 and generator, 5.

   If indicator light, 2, goes out, diode is shorted in rectifier bridge. Replace rectifier bridge as described under: Unit Repair.



11

C. Systems With Indicator Light Working Properly

TEST EQUIPMENT NEEDED:

- Voltmeter

1. If battery, 1, is undercharged, indicator light, 3 remains on while the tractor is running, or EIC voltmeter is below acceptable range:

   With engine stopped and all electrical loads turned off, use voltmeter, 2, to check voltage across the battery terminals, 1. Record voltage.

   Start engine and run at moderate speed. Check voltage across the battery terminals, 1, with the engine running.

   If voltage reading at the battery terminals varies by more than 5% from the reading showing at the EIC voltmeter, locate and correct cause of incorrect reading.

   If voltage is lower than reading previously recorded with the engine stopped, there is no generator output. Proceed to the section: No Output**.**


   If voltage with the engine running is higher than previous reading with the engine stopped, generator output is present. Proceed to section: Rated Output Check.

2. If battery is overcharged (as evidenced by excessive water use, or electrolyte spewing from the battery vents) light bulbs, or other electrical equipment having shortened life due to suspected high system voltage, or system voltage reads above normal range:

   With fully charged batteries, engine running at moderate speed, and all electrical loads off, use voltmeter, 2, to check voltage at the battery terminals.

   Readings should be stable, around 13.5 -14.5 volts and in no case go above 15 volts.

   If voltage is erratic or goes above 15 volts, replace the regulator as described under: Unit Repair.



12

D. No Output

TEST EQUIPMENT NEEDED:


- Voltmeter
- Jumper lead (18 ga. min.; no fuse)

Note that 21-SI generators, 6, must be connected to a battery, 1, for the voltage sensing circuit to allow initial turn on. When properly connected and system checks indicate a “no output” condition, use the following steps to determine if the generator requires repair:

1. For one-wire systems with an “I” terminal, 5, the indicator light current at this terminal will establish normal magnetism. With engine stopped and key switch, 4, on, use voltmeter, 2, to check for voltage present at this terminal. With “I” terminal connected and indicator lamp, 3, on, voltage will be less than battery voltage. If necessary to disconnect wiring at “I” terminal, 5, to make this check, check for battery voltage in harness wire. If voltage is present, proceed to step 2. If no voltage is present, check “I” terminal circuit for cause of voltage loss (bulb may be burned out.) Correct as necessary.

NOTE: *Residual magnetism in the rotor is sometimes lost during servicing of the generator, 6. The rotor can be re-magnetized without removing the generator. To re-magnetize the rotor, make sure the normal connections are made to the generator “bat” terminal. Momentarily connect a jumper lead, 7, from the battery positive to the generator “R” terminal. This will cause field current to momentarily flow through the rotor in the proper direction and restore magnetism. Recheck the generator for proper operation.*

2. If no conditions have been found that might prevent the generator from turning on, remove generator from engine and proceed to: Unit Repair**.**



13

E. Rated Output Check


TEST EQUIPMENT NEEDED:

- Voltmeter
- Ammeter (current capability at least 15 amps higher than generator rating)
- Variable carbon pile load test

CAUTION

Failure to disconnect negative battery cable at battery before removing or attaching generator "BAT" terminal lead may result in an injury. If a tool is shorted at generator "BAT" terminal, the tool can quickly heat enough to cause a skin burn.

1. If inductive pick-up ("clamp on") type ammeter, 3, is used, place current clamp on generator, 4, output lead and skip to step 4. If series ammeter is used, disconnect negative battery cable, 1, at battery.
2. Install ammeter in series with generator "BAT" terminal.
3. Reconnect negative battery, 1, cable at battery.
4. With load turned off, attach carbon pile load, 2, across the battery.
5. Attach voltmeter, 5, negative to grounded negative battery terminal, 1. Leave positive meter lead open for checks at various points.
6. Check and record voltage at battery positive terminal, 6. For multi-battery systems, check positive voltage of battery set connected as if in battery charging mode.
7. With all system electrical loads off, start engine and run at moderate speed (RPM).



14

8. Recheck voltage at battery positive terminal, 6. Voltage should be higher than previous reading, but below 15 volts.

   If reading is lower than previous reading (step 6), refer to section: No Output.

   If reading is higher than 15 volts, replace regulator as described under: Unit Repair.

9. Turn carbon pile load, 2, on and adjust to obtain maximum generator output on ammeter, 3, without allowing voltage at battery positive terminal to drop below 13 volts. Record maximum ampere output.


10. With generator still running at maximum output, check and record voltage drop, 5, in ground circuit between generator housing, 4, and battery negative terminal, 1. Turn carbon pile load, 2, off.

    Maximum ampere output, 3, should be within 15 amps of output rating stamped next to part number on generator drive end (DE) frame or as listed in Specifications section of this manual. Voltage drop should be 0.25 volts or less.

    If ground circuit voltage drop is over 0.25 volts, clean and tighten all ground circuit connections. If this does not correct excessive voltage drop, check ground circuit cables for high resistance conditions. Correct as necessary.

    If within 15 amps of rating, generator is good. Look elsewhere for cause of problem.

    If more than 15 amps below rating, repair the generator.



15

DISASSEMBLY AND REPAIR

⚠ CAUTION ⚠

Failure to disconnect negative cable at batteries, before removing or attaching generator "BAT" terminal lead, may result in an injury. If a tool is shorted at generator "BAT" terminal, the tool can quickly heat enough to cause a skin burn.

NOTE: *Always reinstall fasteners at original location. If necessary to replace fasteners, use only correct part number or equivalent.*


- If correct part number is not available, use only equal size and strength. For generator internal fasteners, refer to Delco Remy Standard Hardware Fasteners section in the Parts Catalog.
- Fasteners that are "NOT" to be reused will be noted in procedure.
- Fasteners requiring thread locking compound will be noted in procedure.
- Use specified torque values when shown.

Using or replacing fasteners in any other manner could result in part or system damage.

UNIT REPAIR


If diagnosis determines that generator repair is needed, remove generator from engine as follows:

1. Remove both negative battery cables.
2. Rotate fan belt tensioner, 2, clockwise to relieve tension.
3. Remove belt, 1, from generator.
4. Remove generator output and "I" terminal wires.



16

5. Remove retaining bolts, 1.



17


DISASSEMBLY AND BENCH CHECKS

TEST EQUIPMENT NEEDED:

- Ohmmeter


Generator

1. Place alignment mark, 1, across slip ring end (SRE) housing, 2, and drive end (DE) frame, 3, for assembly after repair.
2. Remove four through bolts, 4.



18

3. Separate DE frame, 1, (with rotor), 2, from SRE housing (with stator), 3. If necessary, carefully pry DE frame from edge of stator with screwdriver, 4. After separation, place tape over SRE bearing inside unit to prevent dirt from entering during checks.




19

SRE Housing and Components

4. Inspect SRE housing assembly, 3, for loose connections or other obvious conditions. Correct as necessary. If none are found, proceed with SRE checks.

5. Remove three rectifier bridge nuts, 1, to disconnect stator. Lift stator, 2, from SRE housing, 4. If necessary, carefully pry stator away from SRE housing with screwdriver, 3.
6. Inspect stator windings for a dark, burned appearance. View windings from inside of unit - black paint on outside of windings does not indicate burned windings. If all windings are uniform in color and varnish covering is not flaking off, proceed with electrical check. If some windings are dark and others are light, a shorted, open or grounded condition is indicated. Replace the stator. The stator should also be replaced if the windings are uniformly dark and burned, with the varnish coating flaking off to expose bare wires.




20

7. Perform electrical check on stator with ohmmeter, 2. There should be no continuity between any of the stator leads, 1, and the stator laminations, 3.

   If continuity is present, windings are grounded. Replace stator.

   If there is no continuity, stator is probably good. However, there is no service electrical check for shorted or open delta stator windings. If all other electrical checks are normal and the generator did not produce within 15-amps of the rated output, a shorted or open stator is indicated and the stator is to be replaced.




21

8. Remove insulated regulator attaching screw, 1, to disconnect diode trio, 2. Lift trio from SRE assembly, 4.
9. Use ohmmeter, 3, to check diode trio. Place negative ohmmeter lead on regulator strap, 5, and use positive ohmmeter lead to check for continuity to each of the three rectifier bridge straps.

   All three readings should indicate continuity. Reverse the ohmmeter leads and perform checks again. Readings should all indicate open circuits.

   If all readings are proper, diode trio is good. If any reading is wrong, replace diode trio.




22

10. Use ohmmeter, 2, to check rectifier bridge. The bridge may be checked in place in the SRE frame. Check six diodes as follows:

    Place negative ohmmeter lead on grounded heat sink, 1. Touch positive ohmmeter lead firmly to metal diode clips, 4, that surround each of the threaded studs. All three readings should be the same and indicate open circuits. Switch leads and repeat. All three new readings should indicate continuity.


    Repeat checks using insulated (positive) heat sink, 3, in place of grounded heat sink. With negative ohmmeter lead on insulated heat sink, all three readings should indicate continuity. Switch leads and repeat. All three new readings should indicate open circuits.



23


    If readings are correct, the rectifier bridge is good.

    If reading is wrong, an open or shorted diode is indicated and rectifier bridge, 3, should be replaced. To remove bridge, remove inside “BAT” terminal nut, 1, and connector, 2, from regulator stud, inside “R” (relay) terminal nut and connector, 8, two bridge attaching screws, 4, and insulated capacitor attaching screw, 5. Lift capacitor, 6, and rectifier bridge, 3, from SRE housing, 7.




24

11. The Brush holder assembly, 1, must be removed to service brushes, 2, or regulator, 10. Hold brushes in retracted position and insert brush pin, 4, to keep brushes in retracted position. Remove insulated regulator attaching screw, 5. Remove regulator nut and stud connector, 6. Loosen or remove inside “I” terminal nut to move “I” terminal connector, 7, as necessary for clearance. Finally, remove brush holder pivot screw, 3. Lift brush holder assembly, 1, from housing, 8, without bending regulator connector from diode trio or “I” terminal connector.
12. Check brushes, 2, and leads for excessive wear, breakage, etc. If necessary to replace, note routing of lead wires and position of lead clips for later assembly; brushes are identical but leads and clips are positioned differently. Carefully remove brush pin, 4, to release brushes. Remove brushes and spacer one at a time, placing fingers around springs to prevent loss. It may be necessary to spread the brush lead clips slightly to disengage retaining tabs.
13. Remove remaining regulator attaching (ground) screw, 9. If previous checks lead to an instruction to replace the regulator, 10, replace it. If it is not known whether regulator is good, use an approved tester for SI-type regulators.



25


14. Remove protective tape (see step 3) and check bearing in SRE housing, 1. Bearings, 3, are permanently lubricated; do not add grease. If the bearing is dry or damaged, replace it. If bearing is being replaced without removing brushes from SRE housing, use brush pin to hold brushes in retracted position while bearing is removed. To remove bearing, 3, use a tube, 2, slightly smaller than opening in SRE housing and drive bearing through to inside of housing. If bearing is not removed, place tape back over bearing.



26

DE Frame and Components


15. Use ohmmeter, 5, to check rotor field resistance. Place ohmmeter leads on the two slip rings, 3, on the rotor shaft, 4, to make this check. Refer to: **SPECIFICATIONS** for proper value. Also use ohmmeter to check for a grounded field by touching one lead to a slip ring, 3, and one lead to rotor frame, 2, or shaft, 4. Reading should be infinite (open) to show that field is not grounded. If field resistance is outside specifications or if field is grounded, replace rotor as described in following steps.
16. Hold DE frame, 1, and spin rotor, 2, by hand to see that it spins freely in ball bearing. Bearing is permanently lubricated; do not add grease. If movement is rough or wobbly, replace DE bearing as described in following steps.



27

17. Remove shaft nut, 5, by placing 5/16″ hex wrench, 4, in end of shaft to hold while removing nut with common wrench, 3. Turn nut counter-clockwise to remove. If hex wrench is not available, wrap rotor, 1, in shop cloth and place in vise, tightening just enough to hold while removing shaft nut.
18. Lift shaft nut, washer, 5, pulley, and fan, 6, from the rotor shaft, 1.
19. Pull rotor from DE bearings, 2.

    If rotor checked good electrically (step 15), inspect slip rings. If rough or out of round, turn in lathe, removing only enough material to make rings smooth and round. Maximum indicator reading for roundness is 0.05 mm (0.002″). Finish with 400 grain polishing cloth. Blow away all copper dust. Clean shaft of any grease that may have accumulated copper dust.
20. Remove three attaching screws and bearing retainer plate, 2, from DE frame.
21. Inspect DE bearing. If bearing appears dry or if rotor did not turn smoothly when checked during generator disassembly, replace DE bearing. Bearing is permanently lubricated. Do not attempt to add grease.



28


GENERATOR ASSEMBLY

Assembly of DE Frame and Components

1. Install the DE bearing and bearing retainer plate, 2, to DE frame, 7. Install the three attaching screws.

   Tighten retainer plate attaching screws to 3.0 N·m (26 in. lbs.).
2. Install the rotor shaft, 1, into DE bearing, 2.
3. Install the fan, pulley, 6, shaft washer, and nut, 5, onto rotor shaft, 1. Hold shaft with 5/16″ hex wrench, 4, in end or wrap rotor in shop cloth and tighten in vise just enough to hold while tightening shaft nut.


   Tighten shaft nut, 5, to 100 N·m (75 ft lbs).



29


Assembly of SRE Housing and Components

4. Install the SRE bearing, 1, into SRE housing, 3. Use a thin-wall socket or tube, 2, slightly smaller than the hole in SRE housing to drive bearing in from outside. Position bearing flush with outside lip, 4, of SRE housing. Cover opening in bearing with a piece of tape to prevent dirt from entering during the rest of the procedures.



30

5. Install rectifier bridge assembly, 2, to SRE housing, 1. Install one rectifier bridge attaching screw/washer assembly, 3, through grounded heat sink into SRE housing. Finger tighten.




31

Connect the relay “R” terminal, 3, to the SRE housing and hold in place. Place inside insulating washer, 2, over “R” terminal stud. Place relay terminal connector, 1, over stud on rectifier bridge and “R” terminal stud. Be sure inside insulating washer is between connector and SRE housing at terminal end. Connector must not touch SRE housing.


Also be sure outside insulator is properly centered in hole so terminal stud cannot touch SRE housing. Install inside nut/washer assembly, 4, onto “R” terminal stud, 3.

Tighten inside nut/washer assembly to 2.5 N·m (22 in. lbs.).



32

6. Install output (“BAT”) terminal, 5, to SRE housing, 6, being sure to seat square insulator flange in hole, then outside output terminal nut/washer assembly, 1, onto terminal stud. Finger tighten.
7. Connect capacitor, 4, to holes in end of rectifier bridge assembly, 7. Install rectifier bridge attaching screw/washer assembly, 2, through capacitor connector, grounded heat sink, and into SRE housing. Finger tighten.
8. Install insulated capacitor attaching screw, 3, through capacitor connector, insulated heat sink, and into SRE housing. Finger tighten.




33

9. Inspect regulator mounting area for presence of grease or dirt. Good electrical contact is necessary in this area.

NOTE: *Do not immerse or wet regulator with solvent. Internal damage to regulator could result.*


Clean regulator mounting bosses in SRE housing, metal base plate and contact rings on regulator by wiping with clean, dry cloth.

10. Install regulator, 1, to SRE housing, 3, with regulator attaching screw, 2, (grounding). Finger tighten.
11. If replacing individual brushes, proceed to step 12. If installing complete brush holder assembly, skip to step 13.




34

12. Install brush assemblies, 1, with springs, 6, and spacer, 5, to brush holder, 4. Brushes are identical, but leads and contact clips, 3, are positioned differently. Pin brushes in retracted position with retaining pin, 2.




35

13. Install the brush holder, 4, with brushes pinned in retracted position, to mounting holes in regulator and SRE housing, 5. Install brush holder attaching (pivot) screw, 2, and one insulated regulator attaching screw, 3. Finger tighten both screws.
14. Install diode trio, 1, onto the three threaded studs on rectifier bridge assembly. Position long connector strap on diode trio over closest mounting hole in brush holder, 4, and regulator.




36

15. For one-wire systems, hold outside output terminal, 9, and temporarily remove inside output terminal nut, 5. Install regulator stud connector, 6, to threaded stud and to inside output terminal stud, 9. Reinstall output terminal nut/washer, 5, and install regulator nut/washer assembly, 4, to threaded stud on regulator. Finger tighten.
16. Install the “I” terminal, 8, with outside insulator to SRE housing, 10, and hold in place. Install the inside insulator, 7, then regulator/indicator light connector, 3, over “I” terminal stud inside SRE housing. Position the other end of the connector over mounting hole in brush holder. Install the inside “I” terminal nut/washer assembly onto the “I” terminal stud, 8. Finger tighten.
17. Install second insulated regulator attaching screw, 2, to mounting hole in brush holder, passing through diode trio connector, 1, and “I” terminal connector, 3. Finger tighten.



37


18. Tighten and secure SRE component fasteners in following order:
    a. Inside output terminal nut to 5.5 N·m (50 in. lbs.).
    b. Rectifier bridge attaching screw (2 places) to 3.0 N·m (25 in. lbs.).
    c. Insulated capacitor attaching screw to 2.5 N·m (22 in. lbs.)
    d. “R” and/or “I” terminal (2 places) inside nuts to 2.5 N·m (22 in. lbs.). It may be necessary to hold terminal on outside while tightening.
    e. Regulator mounting screw (grounding) to 2.0 N·m (20 in. lbs.).
    f. Insulated regulator attaching screws (2 places) to 2.0 N·m (20 in. lbs.).
    g. Regulator nut (if used) to 2.5 N·m (22 in. lbs.).
    h. Brush holder attaching screw (pivot) to 2.0 N·m (20 in. lbs.).



38


19. Install the stator, 1, to SRE housing assembly, 4, placing the phase leads, 2, over the three threaded studs, 3, on rectifier bridge. Be sure stator is seated on register around edge of SRE housing.
20. Install rectifier bridge nuts to the threaded studs on rectifier bridge.

    Tighten rectifier bridge nuts (3 places) to 2.5 N·m (22 in. lbs.).




39

21. Clean slip rings on rotor shaft, 1, (if not previously cleaned) by spinning rotor while holding 400 grain polishing cloth, 2, around slip rings. Blow away all copper dust.
22. Clean the rotor shaft where it will slip into SRE bearing by wiping with soft cloth. Shaft must be free of dirt and other foreign material.
23. Clean the brushes by wiping with clean soft cloth. Contact surfaces of brushes must be free of grease and other contaminants. Be sure brushes are pinned in retracted position and that pin extends through SRE housing for removal after unit assembly. Remove protective tape from opening in SRE bearing.




40

24. Assemble the DE frame assembly, 1, to the SRE frame assembly, 2, using the aligning marks made earlier on SRE housing and DE frame. If mark was lost due to part replacement, use mark on old part or match mounting lugs to application to determine proper frame orientation.
25. Install the four through bolts, 3. Tighten through bolts to 5.5 N·m (50 in. lbs.).
26. For one-wire systems only, regulator terminal cover to regulator terminals.



41

27. Remove brush pin, 2, to release brushes onto slip rings inside unit.
28. Reinstall generator, 1, in reverse order of removal. Torque retaining bolts to 128 N·m (95 ft lbs).
29. Reinstall drive belt assembly.
30. Retest the charging system and generator after repairs.



42

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 5 – LIGHTING, AUXILIARY POWER AND RADIOS

CONTENTS

Section	Description	Page
55 404	Specifications	3
	Description of Operation	5
	Controls	5
	Multi-function Switch	6
	Hazard Warning Lights	6
	Light Operation	7
	Work Lights	8
	Auxiliary Power	10
	Auxiliary Control Mounting Locations	11
	Auxiliary Control Cable Routing	11
	Radio Installation	12
	Troubleshooting	13
	Fuse and Relay Identification	15
	Circuit Diagrams	16
	Brake Lights	17
	Head Lights	19
	Hazard Warning Lights	21
	70 Series Turn Signals	23
	70A Series Turn Signals	25
	Taillights	26
	Work Lights	27
	Work Lights #1	28
	Work Lights #2	29
	Work Lights #3	30
	Work Lights #4	31
	Interior Lights	32
	Auxiliary Power Sockets	33

70 Series Seven-pin Trailer Connector 34
70A Series Seven-pin Trailer Connector 35
Disassembly and Repair 36
Replace Headlight Assembly Bulbs 36
Replace Work Sealed Beam Units 36
Replace Roof Mounted Turn Signal Bulbs 37
Replace the Fender Mounted Turn Signal and Stop Light/Parking Light Bulbs 37
Electronic Instrument Cluster (EIC) Bulb Replacement 38
Harness Repair 39
Connector Repair and Replacement 39
Main Harness Routing 39

SPECIFICATIONS

ELECTRICAL CHARGING SYSTEM SPECIFICATIONS

COMPONENT	IDENTIFICATION/DESCRIPTION
Headlamps:	
Quantity	4
Rating	50 watts
Bulb type	886
Color	White
Location	Front center hood
Front turn signals:	
Quantity	2
Rating	26 watts
Bulb type	1156
Color	Amber
Location	Front outside edge of roof
Rear turn signals, upper:	
Quantity	2
Rating	26 watts
Bulb type	1156
Color	Amber
Location	Rear outside edge of roof
Rear turn signals, fender:	
Quantity	2
Rating	21 watts
Bulb type	P21W
Color	Amber
Location	Rear outside of fenders
Stop lamps:	
Quantity	2
Rating	21 watts
Bulb type	1077
Color	Red
Location	Outside rear fenders
Tail lamps:	
Quantity	2
Rating	5 watts
Bulb type	1077
Color	Red
Location	Outside rear fenders
*Work lamps:	
Rating	50 watts
Bulb type (9 of 11)	Sealed beam (flood)
Color	White

*Work lamps are controlled by 12-volt, 20-amp relays.

SPECIFICATIONS


ELECTRICAL CHARGING SYSTEM SPECIFICATIONS

COMPONENT	IDENTIFICATION/DESCRIPTION
Work lamps:	
Location	Quantity
Front center hood	2 (37.5 watt) Halogen
Front lower mid	2
Front roof	2 (optional)
Rear roof	2
Rear fender	2
Rear lower center	1 (with switch)
Trailer socket	7 pin
Location	Rear centerline
Battery 12-volt, Negative ground	
Quantity	2 per tractor
Capacity	950 CCA @ −18° C (0° F)
Reserve capacity	190 min. @ 25-amp load
Number of cells	6 per battery
Switches:	
Multi-function turn signal	
Rating	13.4 volts
Positions (6)	Off
	Left turn signal (6 amp)
	Right turn signal (6 amp)
	Main beam (10 amp)
	Dip beam (10 amp)
	Horn (10 amp)
Master light switch	
Rating	20 amp @ 14 volt
Positions (4)	Off
	Park lamps
	Head lamps
	Head work lamps
Hazard lamp switch:	
Rating	12 amps @ 13.5 volts
Stop lamp switch (2)	
Rating	20 amp relay
Ignition Switch:	
Positions (4), (rating)	Off
	Accessory (30 amp)
	Run (8-amp)
	Start (20-amp)
Fuel gauge resistance:	Full (22 ohms)
	Empty (462 ohms)

DESCRIPTION OF OPERATION

This chapter will explain the operating and repair of the lighting and auxiliary power circuits on the 70 Series tractors. The lights function as follows:

CONTROLS



1

Master Light Switch
Lights are controlled by the four-position MASTER LIGHT switch, 1, as follows:

A Full counterclockwise is off

*B Parking lights on

*C Headlights and parking lights on

*D Work lights, headlights and parking lights on. The work lights are selected by using the touch-sensitive switches, 2. The work light monitor, 3, will indicate which lights are selected on the electronic instrument cluster (EIC).

* Monitor lamp, 7, will be on in these positions.

The MASTER LIGHT switch will turn all work lights off. When the master switch is again turned to the work lights position, the same work lights will be illuminated.

NOTE: *A five second alarm will signal if the master switch is on and the key switch is turned off.*

Panel Dim Control
Dimmer control, 4, can be activated with the master lights on or off. Touch the DIMMER switch, 4, and the instrument console back lights will go from bright to dim. Hold the switch and the lights will dim to whatever level the operator requires.


Touch the switch again to select bright.

Rotary Beacon (dealer-installed accessory)
Push the top of the switch, 5, to actuate the rotary beacon. The top of the switch is illuminated when on. Push the bottom of the switch to turn the beacon off.

Hazard Warning Lights
The switch, 6, will be explained under: **Turn Signals.**

MULTI-FUNCTION SWITCH

The stalk-type multi-function switch operates the horn, turn signals, headlight flash and is used to select HI or LOW beam.



2

Turn Signals

Move the stalk to position 1 to indicate a right-hand turn. Move the stalk to position 4 to indicate a left-hand turn.

The turn signal warning light (and trailer lights, if connected) will also flash when the signals are operated.

Headlights High/Low Beams

With the headlights switched on, pull the stalk to position 3, to change from one beam to the other beam.

Headlight Flash

With low beam headlights on, pull the stalk to position 2, to flash the high beams. Release the stalk to return to low beams.

When the headlights are not on, pull the stalk to position 2 to flash the high beam headlights, and then release to turn off the high beams.

Horn


Press in the end of the stalk, 5, to actuate the horn.

HAZARD WARNING LIGHTS

The switch, 1, is internally illuminated and, when actuated by pushing the top of the switch, will flash in unison with all the tractor and trailer turn signals and the green indicator lamps in the EIC.


Push the bottom of the switch to turn off the hazard lights.

NOTE: *When a turn signal is activated, the activated lights will flash, indicating a turn, while the lights on the other side of the tractor will be, lighted continuously. For the operators protection, use the hazard warning lights when traveling on public roads, unless prohibited by law.*



3

LIGHT OPERATION



4


Front Lights

The headlights, 1, are illuminated when the MASTER LIGHT switch is in the headlight or work light position. All four lights are illuminated when high beam is selected. The outer headlights are illuminated when low beam is selected.

The side and lower work lights, 2, are illuminated by touching the work light selector switch, 1, Figure 6, with the master switch in the work light position.

The directional signals/hazard lights, 3, are selected with the hazard warning light switch or the multi-function switch.

The optional upper front work lights, 4, are illuminated by touching the work light selector switch, 4, Figure 6, with the master switch in the work light position.



5

Rear Lights

The parking lights, 1, are illuminated with the light switch in the park, headlight, or work light positions.

The brake lights, 1, are illuminated when both brake pedals are depressed.

The rear directional/hazard lamps, 2, flash in unison with the front directional/hazard lights.

The lower rear work lights, 3, are illuminated when the master switch is in the work light position and work light selector switch, 2, Figure 6, is selected. The center work light may be turned off while leaving the outer lamps illuminated. Use the toggle switch located on the rear of the center lamp's housing to turn off the light.

The upper rear work lights, 4, are illuminated when the master switch is in the work light position and selector switch, 3, Figure 6, is selected.

WORK LIGHTS

To activate the work lights, the master light switch must be turned to the work light position.

To operate the lower front and side work lights, 2, Figure 4, touch selector switch, 1. The indicator lights will illuminate at position 1 on the monitor to indicate the lights are activated.


To operate the lower rear work lights, 2, touch selector switch, 2. The indicator light will illuminate at position 2 on the monitor to indicate the lights are activated.

To operate the upper rear work lights, 3, touch selector switch, 3. The indicator light will illuminate at position 3 on the monitor to indicate the lights are activated. The center pin of the seven-pin auxiliary connector is also powered by switch, 2.


NOTE: *If the hazard lights are on, the rear work lights will automatically be turned off.*

To operate the optional upper front work lights, 4, Figure 4, touch selector switch, 4. The indicator light will illuminate at position 4 on the monitor to indicate the lights are activated.

Touch any switch a second time to turn the respective lights off.



6




7

Interior Lights
Two lights, 1, are provided to illuminate the cab interior. Each light switch can be set to one of three positions:

A On


B Off

C On when a door is opened




8

Control Console Illumination Lights (2)
Two lights, 1, are activated when the master light switch is on. The lights illuminate the cab controls.



9

AUXILIARY POWER



10

Single-Pin Auxiliary Connector
A 12-volt single pin power connector, 1, is located at the right rear of the cab. The connector has an 8-amp rating to power electrical monitoring equipment. The connector is activated by the KEY-START switch.


Three-Pin Auxiliary Connector
A 12-volt, three-pin connector, 2, is installed to allow the attachment and operation of electronic control boxes.

Terminal, 3, is controlled by the key switch. The terminal has a 30-amp rating.

Terminal, 4, is powered continually. The terminal has an 8-amp rating.

Terminal, 5, is ground.

Seven-Pin Auxiliary Connector
A standard SAE seven-pin connector, 1, is provided to operate the electrical system on implements and trailers. Pin information is as follows:




11

PIN NUMBER	CIRCUIT	WIRE NUMBER	TAPE COLOR
1	Ground	RM4	White
2	L Parking Light	RM162	Black
3	L Turn Signal	RM131	Yellow
4	Stop Light	RM55	Red
5	R Turn Signal	RM135	Green
6	R Parking Light	RM159	Brown
7	Work Light #2	RM141	Blue

AUXILIARY CONTROL MOUNTING LOCATIONS

Two 10 mm cap screws, 2, are located in the right rear panel for attaching an equipment monitor or control box.

An alternate mounting position is provided on the inner face of the right front “A” post. Remove the plastic plugs, 1, from the captive nuts and install 10 mm bolts to attach the control or monitor.



12


AUXILIARY CONTROL CABLE ROUTING

Two locations are provided for routing the operating cables from the control box to the attachment.

Rear Window Grommet

A rubber grommet, 1, is provided to allow equipment control cables, 2, to pass through the rear window frame, 3.


Pull the grommet plug, 1, up to remove. Slit the grommet plug from the bottom into the hollow center, 4. Route implement controls through the grommet plug, then reinstall the grommet plug.



13

Removable Panel

A removable panel, 1, is located below the rear window. Remove the panel to access the opening in the rear cab wall. Route the controls through the opening. Store the panel and attaching hardware for future use.



14

RADIO INSTALLATION

Radios are offered by New Holland to fit the 70 Series tractors. Installation time is approximately 15 minutes. When cutting the DIN-E radio connector harness to install will-fit radios, damage can occur to electronic control modules. If wires are cut to install other radios, warranty on damaged electronic modules and other electrical components will be void.

If an additional Citizen Band Radio or similar component is installed, use one of the two electrical connectors in the right “C” post of cab as outlined under the topic “Auxiliary Power” in this section. The single 8-amp connector is #D8NN-14N150-AA, and the three-pin connector is #86511459.

Electromagnetic Interference (EMI) with Electronic Modules

The electronic modules (EIC, RHC, and CCM) are subject to electromagnetic interference (EMI) concerns. New standards for electronic hardware operation have been imposed by the European Common Market. The EIC, RHC, and CCM were all modified to meet these new standards which went into effect in Europe on January 1, 1996.

The module changes reduced the potential for outside electromagnetic interference, particularly interference caused by FM business band radios. New modules were installed in production on December 4, 1995, starting with tractor serial number 408025.

Antenna and Radio Installation and Use

To further reduce electromagnetic interference, use the following guidelines when installing or using any radio equipment on the tractor. Remember, this is a drive-by-wire tractor!

1. Do not install the radio or antenna coaxial cable near the electronic modules or the CAN link system.
2. Mount the radio on the left side of the cab, away from the electronic systems.
3. Mount the radio antenna on top of the cab roof.
4. Make sure the antenna is properly grounded.
5. If it is not possible to mount the antenna on a suitable ground plane (consult the antenna installation instructions for recommended mounting procedures), consider using a zero-ground plane antenna.
6. Check the coaxial cable to make sure it is in good condition.
7. Check the antenna and antenna cable installation with a standing wave ratio (SWR) meter to make sure the coaxial cable is the right length (tuned) for the system.
8. DO NOT USE HAND-HELD RADIOS INSIDE THE CAB, unless the radio is connected to an outside antenna.
9. Operators must be made aware that, if the radio and/or antenna are incorrectly mounted, not only can problems be experienced with the electronic modules, but, they can expose themselves to high levels of radio frequency energy.

TROUBLESHOOTING

IMPORTANT: *Whenever effecting a repair, the cause of the problem must be identified and corrected to avoid repeat failures. The following table lists problems and their possible causes with recommended remedial action:*

PROBLEM	POSSIBLE CAUSE	CORRECTION
Several or all lights do not come on.	Battery discharged	Check battery and charge or replace
	Loose or defective battery cable connections	Inspect, clean and tighten connections
	Loose harness connectors	Check and be sure connectors are securely engaged
	Fuse(s) burned out	Inspect and replace, check circuit before reconnecting power
	Faulty wiring	Check lighting circuit wiring and repair or replace
	Defective light switch	Check and replace
	Several light bulbs burned out due to defective voltage regulation.	Check and replace voltage regulator if defective
Individual lights do not come on.	Burned out bulb	Check and replace
	Defective or corroded bulb contacts	Inspect, clean or replace
	Fuse burned out	Inspect and replace, check circuit before reconnecting power
	Loose or broken wires	Inspect, secure, repair or replace wiring
	Poor ground connection	Inspect, clean and tighten ground connections
Lights burn out repeatedly	Loose or corroded wiring connections	Inspect, secure, repair or replace wiring
	Loose bulb or lamp mounting bracket	Inspect, tighten or replace
	Faulty voltage regulator	Check and replace voltage regulator
Flasher lamps do not come on	Fuse blown	Inspect and replace, check circuit before reconnecting power
	Flasher unit inoperative	Check and replace ***NOTE:*** *Flasher module may be bypassed by interconnecting terminals 30 and 87A. This enables circuit continuity to be checked.*
	Flasher switch inoperative	Check and replace
	Defective wiring or connections	Inspect circuit, clean and tighten connections or replace wiring

PROBLEM	POSSIBLE CAUSE	CORRECTION
Individual flasher lamp does not come on	Burned out bulb	Check and replace
	Corroded or loose bulb contacts	Inspect, clean, tighten or replace
	Poor ground connection or damaged wiring	Inspect, clean and tighten connection, repair or replace wiring
Warning lights and gauges inoperative	Faulty key start switch	Inspect and replace
	Fuse(s) burned out	Inspect and replace, check circuit before reconnecting power
	Loose or broken wiring	Inspect circuit, tighten connector or replace wiring

FUSE AND RELAY IDENTIFICATION

CIRCUIT	MFP FUSE	AMP	MDP FUSE	AMP	MDP RELAY
1. Electro-hydraulics (70A Series only)	1	40	31	10	18
2. Turn Signals	2	50	24	15	14
3. Hazard Warning Lights	4	50	13	15	13
4. Taillight (left)	4	50	9	7.5	
Taillight (right)	4	50	8	7.5	
5. Brake Lights	4	50	12	15	7
Brake Switches	4	50	14	5	
6. Head Lights (low beam)	4	50	29	15	
7. Head Lights (high beam)	4	50	28	15	
8. Work Light #1	5	50	4	20	1
9. Work Light #2	5	50	5	20	2
10. Work Light #3	5	50	6	15	3
11. Work Light #4	5	50	7	15	4
12. Interior Lights (left)	4	50	9	7.5	
Interior Lights (right)	4	50	8	7.5	
13. Auxiliary Power Socket (1 pin)	7	50	1	10	9
14. Auxiliary Power Socket (3 pin) Battery Powered	8	40	30	15	
Keyed Power	8	40			17
15. Seven Pin Trailer Connector	All of the above				

CIRCUIT DIAGRAMS

Each of the lighting and auxiliary power circuits are fuse protected and relay controlled. Each circuit will be reviewed with all components required to operate the circuit in the following order:

1. Brake Lights
2. Head Lights (low beam)
3. Head Lights (high beam)
4. Hazard Warning Lights
5. Turn Signals
6. Taillight
7. Work Light #1
8. Work Light #2
9. Work Light #3
10. Work Light #4
11. Interior Lights
12. Auxiliary Power Circuit 1
13. Auxiliary Power Circuit 2
14. Seven-Pin Trailer Connector

WIRE HARNESS CODE:

CM	Cab main harness
CR	Cab roof harness
FM	Front main harness
LT	Front light harness
RH	Right hand console harness
RM	Rear main harness
EH	Electro-hydraulic

COLOR CODE:


Color	ID	Purpose
White	W	Accessories
Red	R	Battery power
Black	B	Ground
Dark Blue	U	Lighting
Dark Brown	N	Keyed power
Orange	O	Start system
Purple	P	Module, signal out
Yellow	Y	Module, signal in

CIRCUIT IDENTIFICATION CODE:

RM100-W-16

RM100	Rear main harness, circuit 100
W	Wire color white
16	Wire gauge

NOTE: *See also, Section 55, Chapter 6 for additional information on reading wiring diagrams, and component information.*



70-580-897


15

BRAKE LIGHTS

The brake light circuit is powered by main fuse MFP-4 which is the supply for road lights. Wire CM145 provides power from the fuse to the brake lamp fuse MDP-F12 which then supplies the brake lamp relay MDP-R7 at pin 3, via wire CM57.

Power to the brake lamp switches is provided at pin 2 from fuse MDP-F14, via wires CM50 and CM51. When both switches are closed by applying the foot brakes, power flows from pin 2 to pin 1 in both switches and onto the relay pin 1, via wire CM56. With the circuit complete, the relay provides power from pin 3 to pin 5 and powers both brake lamps, via wires CM52F, CM53F and CM54F.

The relay ground is provided by wire CM78J at pin 2. The lamps are grounded, via wires CM144 and CM139.


CIGAR\HORN\BEACON FUSE (MDP - F11)
15 A
CM148-R-14
C088
MAIN LIGHT SW
C081
RD LIGHT MN FUSE (MFP - 4)
50 A
CM145-R-8
WRK LAMP FUSE (MDP - F10)
25 A
CM146-R-10
TURN SIGNAL SW
L
O
R
CM149-R-16
C068
CM156-U-14
CM150-U-12
LOW BEAM FUSE (MDP - F29)
15 A
CM142-U-12
C009
FM170-U-14
C008
RM170-U-14
C003
CM170-U-14
2
K
P
HI BEAM FUSE (MDP - F28)
15 A
CM166-U-12
FM167-U-14
RM167-U-14
CM167-U-14
1
J
N
EIC
C007
CM193-U-16
HI BEAM
D13
RH LAMP LW - BM
LT172C-U-14
LT175D-B-14
C124
LH LAMP LW - BM
LT170C-U-14
LT171C-U-14
LT174D-B-14
LT176D-B-14
C009
FM176-B-14
SPLICE C
SPLICE D
C123
3
RH LAMP HI - BM
SPLICE B
SPLICE A
LT167B-U-14
LT169B-U-14
LT173A-B-14
LT177A-B-14
FM177-B-14
C122
7
LH LAMP HI - BM
LT168B-U-14
LT185A-B-14
C121

70-580-898

16

HEAD LIGHTS

The head light circuit has three different modes of operation: low beam, high beam flash, and high beam. The headlight circuit is powered by main fuse MFP-4 which is the supply for road lights. Wire CM145 provides power to fuse MDP-F10 which supplies the Master light switch at pin 1, via wire CM146.

Low Beam

When the switch is rotated to position 3 or 4, the circuit is completed from pin 1 to pin 4. From here power is provided to fuse MDP-F29, via wire CM142. From the fuse, power flows through connectors C003, C008 and C009 to the low beam head lamps in the front hood, via wire CM, RM, FM and LT170 to splice C, then continues to wires LT171C and LT172C, to the lamps. Ground is provided by wires LT174D, LT175D and LT176D through connector C009 to wire FM176 and to the engine block.

High Beam

When the turn signal (multi-function) switch is pulled towards the operator while the main (master) light switch is rotated to position 3, or 4, the high beam circuit is activated as follows:


From the light switch pin 4, wire CM156 provides power to the turn signal switch pin 4. An internal connection between pin 4 and pin 5 allows the hi beam fuse (MDP-F28) to receive power through wire CM166. From the fuse,power flows through connectors C003, C008 and C009 to the hi beam head lamps in the front hood, via wires CM, RM, FM167 and LT167B to splice B, then continues to wire LT169B and LT168B to the lamps. Ground is provided by wires LT185A, LT173A and LT177A through connector C009 to wire FM177 and to the engine block.

High Beam Flash

When the turn signal (multi-function) switch is pulled towards the operator while the main (master) light switch is rotated to the off position, the high beam flash circuit is activated by a momentary internal connection between pin 7 and pin 5 of the turn signal switch.

Power from cigar/horn/beacon fuse (MDP-F11 is provided to pin 7 by wires CM148 and CM149. From pin 5, power flow to the hi beam lamps as stated in “High Beam”, above.

Both high beam flash and high beam will be indicated when activated on the electronic instrument cluster. From the high beam fuse, MDP-F28 wire, CM193 provides power to the EIC at connector C007, D13, which turns the lamp on.


LH RR LWR FLASH LAMP
CM130Y-U-16
C034
CM139-B-16
LH RR FLASH LAMP
CR130Y-U-16
C091
CR131-B-16
LH FRT FLASH LAMP
CM128Y-U-16
C004
CR128Y-U-16
CR129Y-U-16
C090
CR132-B-16
SPLICE Y
A
SPLICE Y
RH FRT FLASH LAMP
SPLICE Z
CM136Z-U-16
CR136Z-U-16
SPLICE Z
CR138Z-U-16
C092
CR139-B-16
B
RH RR FLASH LAMP
RH RR LWR FLASH LAMP
CR137Z-U-16
CM138Z-U-16
C093
CR140-B-16
C035
CM144-B-16
C007
EIC
CM133Z-U-16
RH IND
C16
CM132Y-U-16
LH IND
D16
CM118-U-16
TRL IND 1
C14
CM119-U-16
TRL IND 2
C15
NASO MODULE (MDP - R14 & R15)
CM127Y-U-14
CM134Z-U-14
CM115-U-14
CM123A-B-16
CM121-U-14
HAZARD SW
C079
FLASHER MODULE (MDP - R13)
CM122-U-16
CM117-U-12
CM116-U-12
CM124A-B-16
C045
HAZARD LAMP FUSE (MDP - F13)
15 A
RD LGHT MN FUSE (MFP - 4)
50 A
CM113-R-12
CM145-R-8
CM114-B-16
70-580-894


HAZARD WARNING LIGHTS

The hazard warning light circuit is powered by main fuse MFP-4 which supplies battery voltage to the hazard light fuse MDP-F13 at all times via wire CM145. From the fuse, wire CM113 powers the Hazard switch at connector C079, pin 2. With the hazard switch off,there is no power flow.

With the hazard switch ON, power passes through the switch at pin 6 and enters the Flasher Module MDP-R13 at pin 30, via wire CM117. Wire CM122 is also connected to pin 30 and supplies power to the NASO module at pin 3. From pin 87A of the flasher module, pulsed power will return to pin 1 of the hazard switch, via wire CM116. Pin 1 is connected to pin 5 and pin 3 which supplies pulsed power to the NASO module pin 1 via, wire CM115 and pin 6, via wire CM121. The NASO module then flashes the left lamps, via wire CM127Y to spice Y from pin 5 and the right lamps, via wire CM134Z to spice Z from pin 10. Both indicator lamps are also powered this way, via connector C007.

Grounds are provided to the NASO module, via wire CM123A at pin 7. The flasher module ground is provided at pin 85, via wire CM124A. The hazard switch is illuminated when on and the lamp ground is provided by connector C045, pin 10, via wire CM114.

70 SERIES



70-580-895

70 SERIES TURN SIGNALS

The turn signal circuit is powered by main fuse MFP-2, which is the supply for auxiliary power relay MDP-R12 pin 30, via wire CM15B and CM17B. When the key switch is turned "ON," the relay is energized, via wire CM24 at pin 85. The relay ground is provided by wire CM31A at pin 86. When relay MDP-R12 is energized, pin 87, wire CM32 powers the hazard switch at pin 8, via wire CM112 after passing through fuse MDP-F24. With the hazard switch "OFF," power passes through the switch at pin 6 and enters the flasher module MDP-R13 at pin 30, via wire CM117. Also connected to pin 30 is wire CM122, which supplies power to the NASO module. The flasher module will create pulsed power at pin 87A, which returns to the hazard switch at pin 1, via wire CM116. Wire CM120 is also connected to pin 1, which then supplies the pulsed power to the turn signal switch at pin 1, connector C068.

LEFT TURN

When the turn signal switch is rotated to select a left turn, input pin 1 is connected to output pin 3, which supplies pulsed power from the flasher module through wire CM126 to pin 85 of the NASO module MDP-R14. The module will turn the right turn signal lamps on solid, via wire CM134Z to splice Z and onto all right-hand lamps from pin 10. The left lamps will receive the pulsed power supply from the NASO flasher module, pin 5, and flash, via wire CM127Y and onto splice Y.

RIGHT TURN


When the turn signal switch is rotated to select a right turn, input pin 1 is connected to output pin 2, which supplies pulsed power from flasher module through wire CM125 to pin 9 of the NASO Module MDP-R14 and R15. The module will turn the left turn signal lamp on solid, via wire CM127Y, and onto splice Y from pin 5. The right lamps will receive the pulsed power supply at spice Z from the NASO module, pin 10, via wire CM136Z.

Splice Y will connect left lights and the EIC left turn indicator lamp, via wire CM132Y at connector C007, pin D16.

Splice Z connects all right lights and the right turn EIC indicator, via wire CM133Z to connector C007, pin C16.

All light grounds are provided by wires CM139, CR131, CR132, CR140 and CM144.

70A SERIES



50021979

70A SERIES TURN SIGNALS

The turn signal circuit is powered by main fuse MFP-2, which is the supply for auxiliary power relay MDP-R12 pin 30, via wire CM15B and CM17B. When the key switch is turned "ON," the relay is energized, via wire CM24 at pin 85. The relay ground is provided by wire CM31A at pin 86. When relay MDP-R12 is energized, pin 87, wire CM32 powers the hazard switch at pin 8, via wire CM112 after passing through fuse MDP-F24. With the hazard switch "OFF," power passes through the switch at pin 6 and enters the flasher module MDP-R13 at pin 30, via wire CM117. Also connected to pin 30 is wire CM122, which supplies power to the NASO module. The flasher module will create pulsed power at pin 87A, which returns to the hazard switch at pin 1, via wire CM116. Wire CM120 is also connected to pin 1, which then supplies the pulsed power to the turn signal switch at pin 1, connector C068.

Left Turn

When the turn signal switch is rotated to select a left turn, input pin 1 is connected to output pin 3, which supplies pulsed power from the flasher module through wire CM126 to pin 85 of the NASO module MDP-R14. The module will turn the right turn signal lamps on solid, via wire CM134Z to splice Z and onto all right-hand lamps from pin 10. The left lamps will receive the pulsed power supply from the NASO flasher module, pin 5, and flash, via wire CM127Y and onto splice Y.


Right Turn

When the turn signal switch is rotated to select a right turn, input pin 1 is connected to output pin 2, which supplies pulsed power from flasher module through wire CM125 to pin 9 of the NASO Module MDP-R14 and R15. The module will turn the left turn signal lamp on solid, via wire CM127Y, and onto splice Y from pin 5. The right lamps will receive the pulsed power supply at splice Z from the NASO module, pin 10, via wire CM136Z.

Splice Y will connect left lights and the EIC left turn indicator, via wire CM132Y at connector C007, pin D16. In addition to connecting the left lights and left turn indicator lamp, splice Y supplies pulsed power to the left hand trailer lights module (MDP-R20) at pin 2.

Splice Z connects all right lights and the right turn EIC indicator, via wire CM133Z to connector C007, pin C16. In addition to connecting the right lights and right turn indicator lamp, splice Z supplies pulsed power to the right hand trailer lights module (MDP-R19) at pin 2.

All light grounds are provided by wires CM139, CR132, CR139 and CM144.



20


TAILLIGHTS

The tail/park light circuit is powered by main fuse MFP-4 which is the supply for road lights. Wire CM145 provides power to fuse MDP-F10 which supplies the Master light switch at pin 1, via wire CM146.

When the switch is rotated to position 2,3 or 4,the circuit is completed to pin 3 which provides power to the tail/park light fuses MDP-F9 (left) and MDP-F8 (right), via wires CM158 and CM157.

Wires CM160X and CM143X connect the fuse to the right lamp, via connector C034. Wire CM144 provides the ground.


Wires CM161M and CM163M connect the fuse to the left lamp, via connector C091. Wire CM139 provides the ground.



21

WORK LIGHTS

The work lights are controlled and monitored by EIC control panel. The headlight switch must be rotated to the work light position. All work lights are powered from fuse MFP-5 which then connects to the individual work light fuses, via wire CM176. All work lights are controlled by the EIC touch sensitive switches which are usable only when power is sensed from pin 2 of the main light switch when the switch is rotated to the work light position, via wire CM151 to pin D12 of the EIC connector C007.



70-580-900


22

WORK LIGHTS #1

When EIC switch #1 is touched, work lights #1 are activated as follows: Fuse MDP-F4 supplies the #1 work light relay MDP-R1 at pin 3, via wire CM177. When the EIC switch #1 is touched, power is supplied by the EIC module connector C007, pin D6 to pin 1 of the relay, via wire CM178. The relay terminal 2 is grounded, via wire CM186J, CM5A and CM4A.

When the relay is activated, pin 3 is connected to pin 5, which supplies power to the four front work lights, via wires CM185 and RM185F. The two mid-mount work lamps are powered from splice F to wires RM205F for the right lamp, and RM206F for the left lamp. Ground is provided by wires RM207 for the right lamp, and RM208 for the left lamp.

The two outer front hood work lamps are powered from splice F to wires RM184F, FM184F, and LT184G to splice G. The right hood lamp is powered from splice G, via wire LT183G, and the left lamp is powered from splice G, via wire LT182G. Ground is provided by wires LT179E to splice E for the right lamp and LT180E to splice E for the left lamp. From splice E, wire LT181E and FM181 complete the ground circuit to the engine block.



23


WORK LIGHTS #2

When EIC switch #2 is touched, work lights #2 are activated as follows: Fuse MDP-F5 supplies the #2 work light relay MDP-R2 at pin 3, via wire CM179. When the EIC switch #2 is touched, power is supplied by the EIC module connector C007 pin D5 to pin 1 of the relay, via wire CM180. The relay terminal 2 is grounded, via wire CM187J, CM5A and CM4A.

When the relay is activated, pin 3 is connected to pin 5, which supplies power to the three rear work lights, via wire CM188N. The three lower rear work lamps are powered from splice N to wire CM202N for the right lamp, and CM201N for the left lamp. The rear center lamp is powered from splice N, via wire CM203N through connector C003 and RM203. Ground is provided by wires CM174 for the right lamp, CM175 for the left lamp and RM204 for the center lamp.

NOTE: *The center lower rear work lamp can be switched off with a switch on the lamp assembly.*

NOTE: *Work lamp #2 also powers the center pin of the seven pin trailer connector.*




24

WORK LIGHTS #3

When EIC switch #3 is touched, work lights #3 are activated as follows:

Fuse MDP-F6 supplies the #3 work light relay MDP-R3 at pin 3, via wire CM181. When the EIC switch #3 is touched, power is supplied by the EIC module connector C007, pin D4 to pin 1 of the relay, via wire CM182. The relay terminal 2 is grounded, via wire CM189J, CM5A, and CM4A.

When the relay is activated, pin 3 is connected to pin 5, which supplies power to the two upper rear work lights, via wires CM190 and CR190U. The two upper rear work lamps are powered from splice U to wire CR189U for the right lamp and CR191U for the left lamp. Ground is provided by wires CR197 for the right lamp, CR198 for the left lamp.




25

WORK LIGHTS #4

When EIC switch #4 is touched, work lights #4 are activated as follows:

Fuse MDP-F7 supplies the #4 work light relay MDP-R4 at pin 3, via wire CM183. When the EIC switch #4 is touched, power is supplied by the EIC module connector C007, pin D3 to pin 1 of the relay, via wire CM184. The relay terminal 2 is grounded, via wire CM191J, CM5A and CM4A.

When the relay is activated, pin 3 is connected to pin 5 which supplies power to the two upper front work lights, via wires CM192 and CR192V. The two upper front work lamps are powered from splice V to wire CR194V for the right lamp and CR193V for the left lamp. Ground is provided by wires CR195 for the right lamp, CR196 for the left lamp.



26

INTERIOR LIGHTS

Dome Lamps

The dome light circuit is powered by main fuse MFP-4, which is the supply for road lights. Wire CM145 provides power from the fuse, via the MDP bus bar to the dome lamp fuse MDP-F14, which then supplies the right dome lamp via wire CM106. The left lamp is supplied, via wire CM105 from the right lamp.

Each lamp has a three-position switch, “OFF,” “ON,” or Door switch controlled. When “OFF” is selected, no ground is provided. When “ON” is selected, lamp ground is provided by wire CM108 and CM 109. When Door Switch control is used, the left or right door post switches provide ground, via wires CM107 (right) or CM110 (left). Wire CM111 connects the two lamps together to provide ground to either switch.


Console Lamps

The console light circuit is powered by main fuse MFP-4, which is the supply for road lights. Wire CM145 provides power to fuse MDP-F10, which supplies the master light switch at pin 1, via wire CM146.

When the switch is rotated to position 2, 3, or 4, the circuit is complete to pin 3, which provides power to the console, tail/park light fuses MD-P F8 and MD-PF9.

Wires CM160X and CM164X connect the fuse to the right console lamp. Wire CM171 provides the ground.

Wires CM161M and CM168M connect the fuse to the left console lamp. Wires CM169 and CM171 provide the ground.



70-580-905

27

AUXILIARY POWER SOCKETS

Single-Pin Socket

The single pin 8-amp acc socket power circuit is powered by main fuse MFP-7, which is the supply for accessory relay MDP-R9 pin 3, via wire CM240. The relay is activated by the key switch, via wire CM29, and ground is provided by wire CM241J. When activated, power from relay pin 3 is connected to pin 5, and supplies power to fuse MDP-F1, via wires CM239 and CM198. From the fuse, power flows to pin 2 of the single pin socket, via wire CM226. Ground is provided from the socket pin 1 to the frame, via wire CM225.


Three-Pin Socket

The three-pin 30-amp Implement socket power circuit is powered by main fuse MFP-8, which is the supply for the implement socket fuse MDP-F30, via wire CM246R and Implement socket relay MDP-R17 pin 30, via wires CM252R and CM258R.

Pin 2 of the implement socket is powered at all times from the 15-amp fuse MDP-F30, via wire CM247.

The relay MDP-R17 is activated by the key switch, via wire CM29 and CM30. The relay ground is provided by wire CM249J. When activated, power from relay pin 30 is connected to pin 87 and supplies power to the 30-amp implement socket pin 1, via wire CM248.

Ground is provided from the socket pin 3 to frame, via wire CM271.



28

70 SERIES SEVEN-PIN TRAILER CONNECTOR

The seven-pin trailer connector received power from the left and right park lights, the left and right turn signals, stop lights and work lights #2. Ground is also provided at pin 1.

The left park light circuit provides power to pin 2 of the connector from the fuse MDP-F9, via wires CM162M and RM162.

The right park light circuit provides power to pin 6 of the connector from the fuse MDP-F8, via wire CM159 and RM159.


The left turn signal light circuit provides power to pin 3 of the connector from splice Y, via wires CM131Y and RM131.

The right turn signal light circuit provides power to pin 5 of the connector from splice Z, via wires CM135Z and RM135.

The stop light circuit provides power to pin 4 of the connector from splice F, via wires CM55F and RM55.

The work light #2 circuit provides power to pin 7 of the connector from splice N, via wires CM141N and RM141.

Ground for the connector is provided at pin 1, via wire RM4 to the frame.



50021980

29

70A SERIES SEVEN-PIN TRAILER CONNECTOR

The seven-pin trailer connector received power from the left and right park lights, the left and right turn signals, stop lights and work lights #2. Ground is also provided at pin 1.

The left park light circuit provides power to pin 2 of the connector from the fuse MDP-F9, via wires CM162M and RM162.

The right park light circuit provides power to pin 6 of the connector from the fuse MDP-F8, via wire CM159 and RM159.

The left turn signal light circuit provides power to pin 3 of the connector from splice Y, via wire CM131Y to the left-hand trailer lights module (MDP-R20), pin 2. Then via wire CM286Y-R-16 from MDP-R20, pin 5.

The right turn signal light circuit provides power to pin 5 of the connector from splice Z, via wire CM135Z to the right-hand trailer lights module (MDP-R19), pin 2. Then via wire CM286Z-R-16 from MDP-R20, pin 5.

The stop light circuit provides power to pin 4 of the connector from splice F, via wires CM55F and RM55.

The work light #2 circuit provides power to pin 7 of the connector from splice N, via wires CM141N and RM141.

Ground for the connector is provided at pin 1, via wire RM4 to the frame.


DISSASSEMBLY AND REPAIR

REPLACE HEADLIGHT ASSEMBLY BULBS

***IMPORTANT**: All headlights have halogen bulbs. Never touch a halogen bulb with your fingers. Natural oil in the skin may cause the bulb to fail prematurely. Always use a clean cloth or tissue when handling halogen bulbs.*

To replace a bulb:


1. Disconnect the wire harness connector, 1, from the bulb assembly, 2.
2. Rotate the bulb assembly, 2, counterclockwise until it disengages from the housing, 3.
3. Remove the bulb assembly.
4. Install the new bulb assembly in the housing.
5. Rotate clockwise until the bulb assembly locks in the housing.
6. Connect the wire harness connector.
7. If more than one bulb assembly was replaced, check operation of lights with light switch to ensure harness was reconnected correctly.



30

REPLACE WORK SEALED BEAM UNITS

1. Remove the retaining screws, 1.
2. Pull the beam unit, 2, from the case, 3.
3. Disconnect the connectors, 4.
4. Connect the new beam unit to the connectors.
5. Install the new beam unit into the case.
6. Install the retaining screws.



31


REPLACE ROOF MOUNTED TURN SIGNAL BULBS

To replace the bulb:

1. Remove the retaining screws, 1, then remove the lens, 2.
2. Remove the bulb, 3, by pressing the bulb in and turning it counterclockwise.
3. Install a new bulb by pushing the bulb in and turning it clockwise until it locks in place.
4. Replace the lens and tighten the two screws.

IMPORTANT: *When replacing the lens, do not over tighten the retaining screws.*

NOTE: *The lens must fit inside the rubber seal, 4, to ensure a waterproof fit.*




32

REPLACE THE FENDER MOUNTED TURN SIGNAL AND STOP LIGHT/PARKING LIGHT BULBS

The turn signal bulb, 3, is behind the amber lens. The stop light and parking light bulb, 2, is behind the red lens on the rear fenders.

To replace the bulbs:

1. Remove the retaining screws, 1.
2. Remove the lens.
3. Remove the failed bulb by pressing the bulb in and turning it counterclockwise.
4. Install a new bulb by pushing the bulb in and turning it clockwise until it locks in place.
5. Replace the lens and tighten the retaining screws, while being careful to fit lens properly into the rubber gasket base.




33

ELECTRONIC INSTRUMENT CLUSTER (EIC) BULB REPLACEMENT


To replace a bulb:

1. Loosen the two retaining screws, 1, then pull the EIC away from the dash.




34

2. Disconnect the electrical connector, 1, and ground wire, 2, from the rear of the EIC.
3. Remove the rear cover retaining screws, 3, and remove the rear cover.



35


4. Remove the failed bulb assembly, 1, by rotating 1/4 turn counterclockwise with a small screwdriver. Install a new bulb.
5. Reinstall the rear cover.
6. Install the electrical connector and ground wire.
7. Install the EIC in the dash and tighten the two retaining screws.



36

HARNESS REPAIR

Splices and repairs to the harness should be soldered and sealed with heat shrink to prevent corrosion.




37

CONNECTOR REPAIR AND REPLACEMENT

Improper service techniques can damage connectors. Always use spoon connector special tool, part #FNH00550, when troubleshooting the wire harness ends. DO NOT PROBE THE INSIDE OF THE PIN. THIS CAN DISTORT THE PIN AND CAUSE SERIOUS ELECTRICAL MALFUNCTIONS.

When a connector is damaged, repair can be made by using connector repair kit FNH-01000, and parts listed in Service Bulletin 4-91, pg. 14. Other connectors not serviced can be obtained from connector suppliers. A list of supplier part numbers is located in Section 11 of the parts book.



38


MAIN HARNESS ROUTING

Improper routing can cause harness damage in areas such as the left rear cab mount area and across the top of the transmission.

The wiring harness can also be damaged by excessive heat being picked up from the hydraulic oil lines.


Several changes were made, starting with tractor serial number D406065.

The harness is now installed inside convoluted tubing which is tie-strapped directly to the hydraulic tubes. The right side piece, 1, is 18″ long, and the left side piece is 48″ long.




39

A plastic mounting block, 1, is used on the left side brake line.




40

A “P” clamp retains the harness on the left rear cab mount on the Models 8770, 8870, and 8970.




41

The harness is also routed differently at this location. The correct order of the parts positioned around the cab mount is; first the harness, then the brake cable, and then the dipstick tube.


GSG-95-973

42


Cable ties can be used to attach the harness to the hydraulic lines.



GSG-95-972

43

Model 8670 tractors use a welded rear cab mount assembly, so they require a 1.5″ spacer, 1, on the dipstick attachment.



44

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 6 – Wiring Diagrams

CONTENTS


Section	Description	Page
55 100	Description of Operation	1
	Harness and Connectors	2
	Wiring Diagram Index and Key	16
	Wiring Diagram Circuit Explanation	18
	Glossary of Terms/Abbreviations	19
	Component Index	20
	Naso Schematic (North American Version)	22
	Iso Schematic (European Version)	43

DESCRIPTION OF OPERATION

The wiring diagram used on the 70/70A Series tractor is designed for easy location of components to aid in faultfinding and troubleshooting.

This chapter is divided into two parts:

1. Harness and connector identification.
2. Wiring diagram with index and key.



1

ELECTRICAL WIRING HARNESS AND CONNECTOR IDENTIFICATION

The 70 Series tractor electrical system is made up of six harnesses and each wire in each harness has a two letter identifier on each wire as follows. On the 70A Series, 1 more harness is added for the Electro-hydraulics:

Identifier	Harness
1. CM	Cab Main
2. CR	Cab Roof
3. FM	Front Main
4. LT	Lights (Front)
5. RH	Right-Hand Console
6. RM	Rear Main
7. EH	Electro-hydraulics (70A only)


Eight wire colors are used throughout the harness. Each wire color is coded for a particular function and a single letter is used to identify the color on the diagram and connectors as follows:

COLOR	ID	FUNCTION
White	W	Accessories
Red	R	Battery Power
Black	B	Ground
Dark Blue	U	Lighting
Dark Brown	N	Keyed Power
Orange	O	Start System
Purple	P	Module Signal Out
Yellow	Y	Module Signal In

Each diagram and connector wire is identified by the harness, wire number, wire color and wire size as follows: RH59-Y-18, 1.

RH59	Right-hand console harness, wire 59
Y	Wire color yellow-module signal in
18	18 Gauge wire

All connectors, 2, are identified with a four-digit code beginning with the letter “C” such as C145.



2


HARNESS IDENTIFICATION

Each harness and its connectors will be shown in the following pages with the pin location and wire identification.

CM	Cab Main
CR	Cab Roof
FM	Front Main
LT	Light (Front)
RH	Right-Hand Console
RM	Rear Main
EH	Electro-hydraulics (70A only)


This page is intentionally blank.

CAB MAIN AND CAB ROOF HARNESS




3

CAB MAIN CONNECTORS




4

CAB MAIN CONNECTORS




5

CAB MAIN CONNECTORS




6

CAB MAIN CONNECTORS




7

CAB MAIN CONNECTORS




8

CAB ROOF CONNECTORS




9

FRONT MAIN AND LIGHT HARNESS




10

FRONT MAIN CONNECTORS




11

FRONT MAIN AND LIGHT CONNECTORS




12

RIGHT-HAND CONSOLE HARNESS




13

RIGHT-HAND CONSOLE CONNECTORS




14

RIGHT-HAND CONSOLE CONNECTORS




15

REAR-MAIN HARNESS



16


REAR MAIN CONNECTORS



70-580-1340

17


REAR MAIN CONNECTORS



70-580-1341

18


REAR MAIN CONNECTORS





19


ELECTRO-HYDRAULIC REMOTE CONNECTORS


Electro-Hydraulic Remote Connectors



















50021981

20


Electro-Hydraulic Remote Connectors



1. EHIK-R-18	13.EH25-OR-20	C531	26. EH27-VI-20	42. EH24-OR-20
2. EHIS-R-18	15. EH55-R-18		28. EH72-R-18	44. EH49-VI-20
3. EH25-B-18	16. EH56D-B-18		29. EH53-R-18	45. EH50-VI-20
4. EH56B-B-18	17. EH2K-B-18		30. EH6A-OR-20	46. EH22-VI-20
5. EH56C-B-18	18. EH-8-OR-20		31. EH5A-OR-20	47. EH30-OR-20
6. EH7-R-20	19. EH29-OR-20		32. EH21-R-20	51. EH23-VI-20
9. EH47C-VI-18	22. EH54-R-18		33. EHIL-R-18	52. EH9-VI-20
10. EH19-OR-20	23. EH56A-B-18		36. EH20-OR-20	53. EH31-OR-20
12. EH4A-OR-20	24.EH32-OR-20		39. EH3A-OR-20	55. EH28-VI-20



1. EHIN-R-18	13. EH39-OR-20	C532	26. EH41-VI-20	42. EH38-OR-20
2. EHIM-R-18	15. EH-60-R-18		28. EH57-R-18	44. EH51-VI-20
3. EH2M-B-18	16. EH61D-B-18		29. EH58-R-18	45. EH52-VI-20
4. EH61B-B-18	17. EH2N-B-18		30. EH14A-OR-20	46. EH36-VI-20
5. EH61C-B-18	18. EH16-VI-20		31. EH13A-OR-20	47. EH44-OR-20
6. EH15-R-18	19. EH43-OR-20		32. EH35-R-18	51. EH37-VI-20
9. EH48C-VI-18	22. EH59-R-18		33. EHIP-R-18	52. EH17-VI-20
10. EH33-OR-20	23. EH61A-B-18		36. EH34-R-20	53. EH45-OR-20
12. EH12A-OR-20	24. EH46-OR-20		39. EH11A-OR-20	55. EH42-VI-20



50022246

21

This page is intentionally blank.

WIRING DIAGRAM INDEX AND KEY

WIRING DIAGRAM INDEX

The diagram index is arranged alphabetically by component. When a component is located in the index, use the frame number to locate the component on the diagram.

DESCRIPTION	FRAME
ACCESSORY SOCKET	14
CHASSIS CONTROL MODULE	6–8
DAM CONNECTOR	1, 3–6

NOTE: *Some components and/or circuits will be located on more than one frame.*

The frame number is listed on the bottom of each diagram, Six frames are located on each fold-out: frames 1-6 on the first fold out, frames 7-12 on the second, and frames 13-16 on the third fold-out.

After the correct frame is located, find the component heading at the top of the page. The actual component and its circuit will be directly under the heading.


WIRING DIAGRAM KEY

Connectors

The connectors, 1, in the diagram are shown as a dotted box around a switch, module, or sender. The connector number is usually in the upper left corner of the component.

If only part of the connector is shown, a wavy dotted line, 2, will be shown at one, or both ends on the box to indicate part of the connector is missing, and located in another frame of the diagram.

The connectors will identify pins or sockets in each connector, 4. Female, 3, and male, 5, terminal connections are identified as shown.




22

Relay and Fuses

The Main Fuse Panel (MFP) and the Main Distribution Panel (MDP) are part of the Cab Main (CM) harness. The MFP and MDP both utilize power bus bars to supply fuses in the panel. The diagram identifies the bus bars, 5, as a bold line supplying fuses as shown.

All fuses will be identified MFP-#, 1, for the Main Fuse Panel fuses and MDP-F#, 2, for the Main Distribution Panel with the amperage rating.


Relays in the MDP are identified as MDP-R#, 3, with pin identification, 4, shown for each wire and contact.



23

Switches and relays will show positive contacts, 1, or momentary contacts, 2, and the connector or relay pin identification as shown.

A harness splice, 3, is shown as a dot where two or more wires cross or join.



24

WIRING DIAGRAM CIRCUIT EXPLANATION


Each circuit is powered by positive battery voltage.

The batteries are located on the left side of frame 1.

Positive voltage is routed to the top of frame 1 and onto the right side of frame 16 (70 Series) and 19 (70A Series).

Negative ground is returned from frame 16 (70 Series) and 19 (70A Series) to frame 1 at the bottom of the page and back to the battery negative post.

Each circuit is powered by positive voltage at the top of the frame through the circuit and components to ground at the bottom of the frame.



25

GLOSSARY OF TERMS/ABBREVIATIONS

A/C	Air Conditioner
A	Amp
ACC	Accessory
ASSY	Assembly
AUX	Auxiliary
B	Black (Ground)
BRK	Brake
BRN	Brown
C000	Connector Identification
CAN	Controller Area Network
CCM	Chassis Control Module
CLS	Closed
CM	Cab main
CNSL	Console
CNTRL	Control
COAX	Coaxial
CONN	Connector
CR	Cab roof
CRP	Creeper
CTW	Connects to Wire
DAM	Diagnosis and Maintenance
DIFF	Differential
DIR	Directional
DOP	Doppler
DWN	Down
EDC	Electronic Draft Control
EH	Electro-hydraulics
EIC	Electronic Instrument Cluster
ENG	Engine
EXT	Extend
EXT	External
F/R	Forward/Reverse
FM	Front Main
FR#	Frame Number
FRT	Front
FWD	Four Wheel Drive
GRD	Ground
GRN	Green
HD	Head
HI-BM	High beam
HVAC	Heat/Vent/Air Conditioner
IMP	Implement
IND	Indicator Lamp
ISO	International Sales Organization
KAPWR	Keep Alive Power
LH	Left-Hand
LMP	Lamp
LT	Lights (Front)
LVL	Level
LW-BM	Low Beam
LWR	Lower
MDP	Main Distribution Panel
MC	Modulation Clutch
MFP	Main Fuse Panel
MN	Main
MOM	Momentary
MTR	Motor
MV	Movable
N	Dark Brown (Keyed Power)
NASO	North American Sales Organization
NO	Normally Open
O	Orange (Start System)
P	Purple (Module Signal Out)
POT	Potentiometer
PRESS	Pressure
PRGM	Programmable
PTO	Power Take-Off
PWR	Power
R/L	Right/Left
R	Red (Battery Power)
RET	Retract
RH	Right-Hand
RHC	Right-Hand Controls Module
RM	Rear Main
RPM	Revolutions per Minute
RR	Rear
SCKT	Socket
SEN	Sensor
SHD	Shielded
SKT	Socket
SOL	Solenoid
SPD	Speed
SPL	Splice
SW	Switch
SYS	System
TEMP	Temperature
TRANS	Transmission
U	Dark Blue (Lighting)
U/D	Upshift/Downshift
W	White (Accessories)
WRK	Work
Y	Yellow (Module Signal In)
Yel	Yellow

COMPONENT INDEX

DESCRIPTION	FRAME
ACCESSORY SOCKET	14
AUDIBLE ALARM	2
BRAKE LAMP SYSTEM	9
CAN SYSTEM, CCM,	6
CAN SYSTEM, EIC	3
CAN SYSTEM, RHC	4–5
CHARGING SYSTEM	1
CHASSIS CONTROL MODULE	6–8
CIGAR LIGHTER	11
CLIMATE CONTROL SYSTEM	15
COLD START SYSTEM	1
CREEPER DRIVE	3&6
DIFFERENTIAL LOCK	5&7
DAM CONNECTOR	1, 3–6
ELEC. INSTRUMENT CLUSTER	3
ENGINE SWITCHES/SENDERS	7&8
ENGINE SHUTDOWN SYSTEM	2
4WD SYSTEM	4&7
FUEL SENDER	8
IGNITION SWITCH	2
HAZARDS/TURN SIGNALS	10&11
HORN	12
IMPLEMENT SOCKET	16
IMPLEMENT STATUS CONN.	6

DESCRIPTION	FRAME
LIGHTING-CONSOLE	12
LIGHTING-DOME	9
LIGHTING-ROAD	11&12
MOVABLE CONSOLE	16
PARK BRAKE	3
POWER TAKE OFF	5&6
RADAR	7
RADIO	15
RIGHT HAND CONTROL MOD.	4&5
ROTARY BEACON	11
SEAT SYSTEM	16
SHUTDOWN OVERRIDE	2
STARTING SYSTEM	1
STEERING ANGLE SENSOR 70A ONLY)	7
3PT HITCH-DRAFT PINS	8
3PT HITCH-RH CONSOLE	4
3PT HITCH-SOLENOIDS	7
3PT HITCH-EXT. SWITCHES	3
TRAILER SOCKET	9–12
TRANSMISSION SHIFT CONTR.	5
TRANSMISSION SOLENOIDS	6
TRANS. SENDERS/SWITCHES	7&8
WIPER/WASHER SYSTEM	14
TRAILER LIGHTS (70A only)	17
ELECTRO-HYDRAULICS (70A only)	18 & 19

CIRCUIT IDENTIFICATION CODE:

RM100-W-18

RM100 ----REAR MAIN HARNESS, CIRCUIT 100
W ------- WIRE COLOR WHITE
18 ------ WIRE SIZE, AMERICAN WIRE GAGE (AWG)

WIRE HARNESS CODE:

CM ---- CAB MAIN HARNESS
CR ---- CAB ROOF HARNESS
FM ---- FRONT MAIN HARNESS
LT ---- FRONT LIGHTS HARNESS
RH ---- RIGHT HAND CONSOLE HARNESS
RM ---- REAR MAIN HARNESS
EH ---- ELECTRO-HYDRAULICS (70A only)

CONNECTOR CODE:

FEMALE TERMINAL



MALE TERMINAL



TERMINAL CONNECTION




CONNECTOR



C078 ---- CONNECTOR CODE

BUS BAR AND FUSE



COLOR CODE:

WHITE ------ W --- ACCESSORIES
RED -------- R --- BATTERY
BLACK ------ B --- GROUND
DARK BLUE -- U --- LIGHTING
DARK BROWN - N --- KEYED POWER
ORANGE ----- O --- START SYSTEM
PURPLE ----- P --- MODULE, SIGNAL OUT
YELLOW ----- Y --- MODULE, SIGNAL IN

SWITCH CONTACT CODE:


CONSTANT CONTACT




MOMENTARY CONTACT



SWITCH



SPLICE CODE:



GROUND CODE:

CASE



CHASSIS



WIRE CONNECTION





MULTIPILE WIRE CONNECTION


70/70A


NASO SCHEMATICS


(NORTH AMERICAN VERSION)



START SYSTEM
CHARGE SYSTEM
COLD START SYSTEM
BC3-R-2
FM5-R-2
CM2-D-18
C005
RH2-D-18
C012
SHIFT CNTRL ASSY
NEUTRAL SW
CLOSED=NEUTRAL
RH61A-D-18
SPL-A
RH60A-D-18
RH1A-D-18
CM1-D-18
C003
RM1-D-18
C008
FM1-D-18
C101
START RELAY
30
85
86
87
FM3-D-8
FM2-R-8
BC2-R-2/0
BC1-B-2/0
BATTERY
JUMP START POST
STARTER
M
B+
S
RHC MODULE
NEUTRAL START
C001
J2-DB
DB
CM77-R-14
C022
DAM CONNECTOR
(1) B+ PWR
20 A
(MDP-F27)
COLD START FUSE
CM3-N-18
C076
COLD START SW.
CM13-Y-18
CM8-R-14
CAN SYS LINK
C012
J1-C12
C12
EIC MODULE
ALTERNATOR INDIC. LAMP (EIC)
VOLTAGE MISSING ALTERNATOR
COLD START CONTROL
J1-DB
DB
CM10-P-18
(MDP-R8)
COLD START RELAY
SEE FR #6
C006
21
28
VPWR
J3-21
ALT EXCITE
560HM 10W
A/D
J2-28
CCM MODULE
COOLANT TEMP LOW
VOLTAGE MISSING ALTERNATOR
C002
CM7-D-12
C003
(-E)
RM7-D-12
TEMP SENSOR FR#7
ENG COOLANT
RM6-N-18
C008
(-H)
FM6-N-18
R-4
FM7S-D-12
FM7S-D-12
SPL-S
DR
IND
I-INDIC
B+
GND-B+
R-RELAY
F+
F- REG GND
ALTERNATOR
GND
FM4-B-18
FM19S-D-14
C11
THERMOSTART HEATER
FM11S-D-14
C107
CONNECTOR NOT USED
AIR INLET HEATER RELAY
CM9A-B-18
FM8-B-14
R-4
AIR INLET HEATER
SPL-A
FR# 13
CTV
FM58V
FR# 7
CTV
FM240
FR# 15
FR 1



SHUTDOWN OVERRIDE
IGNITION SWITCH
FUEL SHUT OFF
BC3-R-2
CM29-W-18
CM14B-R-10
CM2-D-18
BUS BAR
CM3-N-18
CM24-N-18
POSITION:
1-----ACC
2-----OFF
3-----ACC/IGN
4-----IGN/START(MDM)
(MDP-F26)
KEY SW FUSE
10 A
CM26-R-18
IGNITION SWITCH
C080
FEED
ST
ACC
IGN
CM23-N-18
(MDP-R16)
FUEL SOL RELAY
85 DIRM
87A
CM12-D-12
C003
CM18A-B-18
C008
RM12-D-12
FM12-D-12
FM13-P-18
RM13-P-18
C108
FUEL SOL ASY
PULL
HOLD
FM10-B-12
CTV FM240 FR# 15
CTV CM SPL-A FR# 13
CM19-P-18
SYSTEMS MONITORED FOR ENGINE SHUTDOWN
ENG COOLANT TEMP
ENG OIL PRESS
TRANS TEMP
TRANS PRESS
SHUTDWN OVERRIDE SW
OVRRDE
OFF STATUS LAMP
OPEN TO ENABLE OVERRIDE OF AUTO SHUTDOWN & ENERGIZE
C045
C083
CM27-D-18
CM22-Y-18
CM11-B-18
CM20-B-18
C007
J1-C11
EIC MODULE
AUDIBLE ALARM CNTRL
SHUTDOWN OVERRIDE ENGAGED
J1-D7
D7
CM21-P-18
AUDIBLE ALARM
CAN SYS LINK
CCM MODULE
OVERRIDE ENGINE RUN
ENGINE START/RUN PERMIT
HOLD J1-R
PULL J3-1
C001
C006
CTV CM102 FR# 3
FR 2



CLUTCH POT
EXT R/LWR SW
DAM CONN
PARK BRAKE
CREEPER
MAIN BUS BAR
BUS BAR
BC3-R-2
50A
(MFP-2)
MAIN FUSE
CM29-W-18
CM25-N-18
CM36D-R-18
CM48D-R-18
CM14B-R-10
CM15B-R-8
CM16B-R-10
CM17B-R-10
CM36D-R-18
CM34C-N-18
CM24-N-18
5 A
(MDP-F22)
MEMORY (KAPWR)
UNSWITCHED POWER
AUX PWR RELAY
(MDP-R12)
CM32-N-10
CM35-R-18
10 A
(MDP-F23)
CONTROL MODULES
SWITCHED POWER (VPWR)
CM44E-N-18
CM45E-N-18
CM46E-N-18
CM43E-N-18
(MDP-F22)
FRT CNSL FUSE
SPL-E
LH EXT HITCH SWITCH
RH EXT HITCH SWITCH
RAISE
OFF
LOWER
CLOSE=BRAKE APPLIED
CM63H-Y-18
CM63G-Y-18
CM64G-Y-18
CM65H-Y-18
SPL-G
SPL-H
CTV CM20 FR# 2
CM102-B-18
CM48D-N-18
CM49-N-18
PARK BRAKE SWITCH
CM60-Y-18
CM103-Y-18
CM61-Y-18
CREEPER
ON
OFF
SWITCH (OPTION)
OPEN=BRAKE APPLIED
CM47-N-18
CM59-Y-18
CM58-Y-18
LH BRK LAMP SW
RH BRK LAMP SW
CLUTCH POT
+5V=REGULATED OUT
14K
CM37-N-18
CM38-Y-18
CM39-B-18
CM31A-B-18
CM33-N-18
J1-C13
J1-C7
J1-C5
J1-D14
J1-D15
J1-D9
J1-C10
J1-D11
J1-D10
ELECTRONIC INSTRUMENT MODULE (EIM)
SVREF (5A4X4)
SIGNAL GND
J1-C6
J1-D2
J1-D1
J1-C1
CAN(+) J1-C2
CAN(-) J1-C3
EIC-GND
CM42-B-16
CM199-B-16
CM68K-P-18
SEE FR# 6
CM100K-P-18
CM69K-P-18
RH69-P-18
(-19)
CM260T-B-16
CM259S-R-16
SPL-K
CM70K-P-18
CM269-Y-18
CM270-P-18
(3) VPP/IN
(11) IRS232 IN DAM CONNECTOR
(12) IRS232 OUT
(10) GROUND
CM204-B-16
CTV CM271 FR# 16
CTV CM SPL-A FR# 13
FR 3



ELECTRONIC DRAFT CONTROL SYSTEM DAM CONN RHC PWR RAISE/WORK SW 4WD
MAIN BUS BAR
CM29-W-18
CM25-N-18
CM36D-R-18
CM48D-R-18
CM75D-R-18
CM228D-R-18
CM93D-R-18
CM72C-N-18
CM34C-N-18
SPL-D
SPL-C
SPL-L
SPL-M
(M0P-F24) TURN SIGNAL FUSE 15 A
SEE FR# 10
RH43P-N-18
RH44P-N-18
RH28N-B-18
CTV SPL-N FR# 5
4WD SW (OPTION)
ON
AUTO
OFF
RAISE/WORK/FLOAT SWITCH
RAISE
WORK
FLOAT
RH86W-N-18
RH47W-N-18
RH87W-N-18
RH33-P-18
RH49-Y-18
RH59-Y-18
RH74-R-18
RH73-N-18
RH71-N-18
RH72C-N-18
RH73C-N-18
RH74D-R-18
RH9L-N-18
RH7L-N-18
RH8L-N-18
RH4L-N-18
RH6L-N-18
HEIGHT LIMIT POT
DRAFT/POSITION MIX POT
QUADRANT POT
SLIP LIMIT POT (OPTION)
DROP RATE POT
RH20-Y-18
RH16-Y-18
RH17M-B-18
RH10-Y-18
RH11M-B-18
RH14-Y-18
RH15M-B-18
RH12-Y-18
RH13M-B-18
RH21M-B-18
RH13L-N-18
RH76M-B-18
J2-D16 SVREF5/2VJ2-C16 SIGNAL GNDJ2-D6
J2-D15
J2-D13
J2-D12
J2-D11
J1-3 KAPWR
J1-2 VPWR
J1-1 VPWR
J2-C10
J2-C9
J2-C7
J2-C6
J2-C14 HAND CONSOLE MODULE (RHC)
J2-C5 RIGHT
J2-D14
VPP/IN J1-9
C GROUT-6
J1-5
J1-4
PWR GRN-7
PWR GRN-8
RH79-B-16
RH256-P-18
RH255-Y-18
RH23-P-18
RH24-P-18
HITCH SLIP IND (OPTION) SLIP IND
HITCH STATUS IND STATUS IND
RH26-B-18
RH69-P-18
CM79-B-16
CM256-P-18
CM255-Y-18
DAM CONNECTOR
(13) ORS232 IN
(14) ORS232 OUT
RH27N-B-18
RH77N-B-18
RH78N-B-18
CM260T-B-16
CM259S-R-16
CTV CM225 FR# 14
FR 4



DIFF LOCK
UP/DWN SHIFT
AUTO SHIFT
SHIFT CNTRL
CLUTCH PEDAL SWITCH
PTO
MAIN BUS BAR
CM29-W-18
CM25-N-18
CM75D-R-18
CM228D-R-16
CM93D-R-18
CM72C-N-18
RH40P-N-18
CM87-N-18
CM83-Y-18
(MDP-F2D)
RH CNSL FUSE 5 A
CM81-N-18
SPL-AA
RH30P-N-18
RH43P-N-18
RH44P-N-18
RH40P-N-18
CM87-N-18
CM83-Y-18
OPEN-CLUTCH APPLIED
CLUTCH SW
PTO SWITCH ENGAGE(MDM)
NEUTRAL
DISENGAGE (MDM)
RH62B-Y-18
RH25B-Y-16
RH84B-Y-16
SPL-B
CM87-N-18
RH85-Y-16
RH31B-Y-16
CM84-Y-18
PTO RELAY CM SPL-J CTV FR# 11
110 OHM
(MDP-R5)
CM76J-B-18
CM85-Y-16
RH85-Y-16
RH46P-N-18
RH45P-N-18
RH42P-N-18
RH41P-N-18
RH53N-B-18
DIFF LOCK SW (MDM)
U/D PRGM SHFT SW (MDM)
AUTO SHFT SW
SHIFT CNTRL ASSY F/R SW
CM82-Y-18
RH82V-N-18
SPL-V
RH58V-Y-18
RH57V-Y-18
RH50-P-18
RH51-Y-18
RH52-Y-18
RH54-Y-18
RH55-Y-18
RH56-Y-18
J2-C11
J2-D13
J2-D12
J2-D11
J2-D10
J2-D9
J2-D7
J2-D5
RIGHT HAND CONSOLE MODULE (RHC)
J2-C12
CAN+)J1-14
CAN-)J1-15
SPL-T
SPL-S
CM262T-B-16
CM261S-R-16
J2-C4
J2-C3
J2-C2
J2-C1
RH35-P-18
RH36-P-18
RH37-P-18
RH38-P-18
RH39-P-18
RH262-B-16
RH261-R-16
CM260T-B-16
CM259S-R-16
CM264T-B-16
CM263S-R-16
SPL-SHD GRD
CM268-B-16
SHIFT CNTRL ASSY FORWARD SW
500
2K
DOWNSHIFT SW
UPSHIFT SW
REVERSE SW
MP
PTD STATUS
PTD IND LAMP
RH265-BAR-18
RH29N-B-18
RH30N-B-18
SPL-N
RH27N-B-18
RH77N-B-18
RH78N-B-18
RH80N-B-18
(15) CAN(+)DAM
(16) CAN(-)CONNECTOR
CTV CM271 FR# 16
CM260T-B-16
CM259S-R-16
CTV CM225 FR# 14
CM80-B-16
FR 5



IMP STATUS CONN
DAM CONN
TRANS CNTRL SOL
MAIN BUS BAR
40 A
(MFP-3)
MAIN TRANS FUSE
CM29-W-18
CM25-N-18
CM75D-R-18
CM228D-R-16
CM93D-R-18
CM72C-N-18
CM83-Y-18
CM86-Y-16
CM91-R-10
CM104-N-16
CM28-N-18
CM92-N-10
CM94A-B-18
CTV SPL-A FR#11
(MDP-R11)
TRANS PWR RELAY
BUS BAR
(MDP-F20)
TRANS F/R CNTRL SOL /PTO FUSE
15 A
(MDP-F19)
TRANS SHFT CNTRL SOL FUSE #2
20 A
(MDP-F18)
TRANS SHFT CNTRL SOL FUSE #1
20 A
CM96-N-16
(MDP-R6)
DIR INTERRUPT RELAY
110 OHM
CM89J-B-18
CTV SPL-J FR# 11
CM97-N-16
CM88-N-14
CM95-N-14
DAM CONN
ERS232 IN (6)
ERS232 OUT (7)
CM273S-R-16
CM275T-B-16
CM253-Y-18
CM254-Y-18
J3-22 CAN(+)
J3-24 CAN(-)
J3-2
J3-10
J3-19
J3-24VPWR
J3-6KPWR
J3-9
J3-17
J3-18
CHASSIS CONTROL MODULE (CCM)
C001
C006
C022
C025
J1-M
J1-T
J1-E
J1-H
J1-D
J1-D
J1-U
J1-S
J1-V
J1-G
J1-Q
J1-K
J1-N
J1-X
J3-23
J3-15
J3-11
J3-3
J3-7
J3-13
J3-5
RM119-P-18
RM118-P-18
RM117-P-18
RM116-P-18
RM115-P-18
RM114-P-18
RM111-P-18
RM110-P-18
RM107-P-18
RM106-P-18
RM105-P-18
RM101-B-18
RM103-P-18
RM102-B-18
CM40-P-18
CM98-P-18
CM99-P-18
CM90-P-18
CM10K-P-18
CM6-B-16
CM10-B-16
C174 TRANS-F1 SDL
C175 TRANS-F2 SDL
C178 TRANS-R SDL
C168 TRANS-2 SDL
C170 TRANS-3 SDL
C171 TRANS-A SDL
C172 TRANS-B SDL
C173 TRANS-C SDL
C179 TRANS-CRP SDL(OPTION)
C176 TRANS-MC1 SDL
C177 TRANS-MC2 SDL
1.79 OHM
RM120-B-18
RM121-B-18
RM122-B-18
RM123-B-18
RM124-B-18
RM125-B-18
RM113-B-18
RM112-B-18
RM108-B-18
RM109-B-18
CTV SPL-K VPP/IN FR# 3
IMP STATUS
DAM CONNECTOR
(4) TRS232 IN
(5) TRS232 OUT
(2) VPP/GEN
CTV CM225 FR# 14
CTV CM208 FR# 13
CTV CM123 FR#6
FR 6



EDC R/L SOL
4WD, DIFF LK, AND PTO SOL
ENG WARNING SEN/SW
TRANS PRESS SW
RADAR
MAIN BUS BAR
STEERING ANGLE POT
RM77T-B-18
RM62U-N-18
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM104-N-16
C003
RM104J-N-16
C001
GRAYISH BROWN
GREEN
STEERING ANGLE POT
C201
5V
+5V=UP
5K
BLUE
C001
RM285-P-18
RM88J-N-16
RM87J-N-16
RM5J-N-16
RM50J-N-16
C158
DDP RADAR
VPWR 12V
SIG
SEN
GRD
TRANS OIL FLTR SW
OPEN=PLUGGED
HYD FLTR SW
TRANS OIL PRESSURE
OPEN= PRES
RM90-Y-16
RM89-Y-16
RM5L-Y-16
RM68T-B-16
RM52-Y-16
RM53-Y-16
C002
J2-11
J2-18
J2-13
J2-26
J2-1 +12V SENSE
J2-22
CHASSIS CONTROL MODULE (CCM)
J2-27
(+)Y J2-23
(-)R J2-7
J2-2
J2-25
C001
C002
RM86-P-18
RM65-BARE-18
RM82-Y-16
RM83-R-16
RM65-P-18
RM84-P-18
C008
(-T)
(-F)
(-P)
(-N)
(-S)
(-L)
FM65-BARE-18
FM65V-BARE-18
K WIRE
FM82-Y-16
FM83-R-16
FM85-P-18
FM84-P-18
J1-W
J1-C
J1-J
J1-L
J1-F
J1-P
J1-B
RM100-B-18
RM99-P-18
RM98-B-18
RM97-P-18
RM96-P-18
RM94-P-18
RM92-P-18
4WD SOL (OPTION)
7.6 OHM
9.4 OHM
PTO SOL
C166
C167
C164
C165
C163
C162
2.4 OHM
2.4 OHM
9.4 OHM
RM95-B-18
HITCH LOWER SOL
HITCH RAISE SOL
DIFF LOCK SOL
RM93-B-18
RM91-B-18
CTV RM208 FRM 13
CTV RM208 FRM 13
C102
C105
C104
C106
FM86-P-18
COOLANT LEVEL SENSOR
MAX R=LOW COOLANT
EXHAUST GAS TEMP SENSOR
ENG TEMP SENSOR
MIN R=HIGH TEMP
INTERCOOL TEMP SENSOR
MIN R=HIGH TEMP
FM58V-B-18
SPL-V (SHIELD GND)
FM16T-B-18
FM17T-B-18
FM17T-B-18
FM16T-B-18
FR 7



EDC PINS
ROCKPSHFT POT
TRANS WARN SEN/SW
ENG OIL PRESS SEN
MAIN BUS BAR
RM77T-B-18
RM62U-N-18
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
SPL-V
SPL-U
RM66U-N-18
FM66U-N-18
FM64U-N-18
RM62V-N-18
RM63V-N-18
RM64U-N-18
RM60U-N-18
RM61V-N-18
LH DRAFT PIN
RH DRAFT PIN
ROCKSHAFT POT
AIR FLTR VAC SW
ENG OIL PRESS SEN
+5V=MAX PRES
FM18U-N-18
FM81-Y-18
FM59-Y-18
FM14T-B-18
RM54-Y-18
RM56-Y-18
RM57-Y-18
RM59-Y-18
RM81-Y-18
RM69T-B-18
RM70T-B-18
RM71T-B-18
J2-3
J2-20
J2-10
J2-24
J2-31
CHASSIS CONTROL MODULE (CCM)
SIGNAL RTN
SVREF1 5V
SVREF2 5V
FM14T-B-18
RM71T-B-18
RM70T-B-18
RM69T-B-18
RM68T-B-16
J2-4
J2-9
J2-16
J2-17
RM80-P-18
RM79-P-18
RM78-P-18
RM77-P-18
RM67T-B-16
ENG SPD SENSOR
TRANS OIL TEMP SENSOR
FUEL LVL SENDER
21 REED SWITCHES
WHEEL SPD SENSOR
RM73T-B-18
RM72T-B-18
RM74T-B-18
RM75T-B-18
SPL-T
RM76T-B-18
FM17T-B-18
FM16T-B-18
FR 8



DOME LAMP
TRAILER SKT
BRAKE SYSTEM
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228-R-16
CM28-N-18
BUS BAR
(MDP-F14) DOME LAMP FUSE 5 A
(MDP-F12) BRAKE LAMP FUSE 15 A
CM50-R-18
CM106-R-18
CM50-R-16
LH BRK LAMP SW CLOSED=BRAKE APPLIED
RH BRK LAMP SW CLOSED=BRAKE APPLIED
CM51-U-18
CM56-U-18
CM105-R-18
LH DOME LAMP
RH DOME LAMP
CM109-U-18
CM111-U-18
(MDP-R7) BRAKE LAMP RELAY
CM110-U-18
CM108-B-18
CM107-U-18
CM52F-U-16
CM78J-B-18
CM55F-U-16
SPL-F
CM54F-U-16
CM53F-U-16
RM55-U-16
LH STOP LAMP
CM139-B-16
RH STOP LAMP
CM144-B-16
LH DOOR SW DOOR CLS=OPEN SW
RH DOOR SW DOOR CLS=OPEN SW
TRAILER SKT-STOP LAMP
STOP LAMP NASD-RED
GROUND NASD-WHITE
RM4-B-12
CM219 FR# 14
RM208 FR# 13
CM218 FR# 14
SPL-J FR# 13
FR #9



HAZARD SW.
TURN SIGNAL LAMPS
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
BUS BAR
(MDP-F13) HAZARD LAMP FUSE 15 A
CM113-R-12
SEE FR #4
(MDP-F24) TURN SIGNAL FUSE 15 A
CM112-N-12
CM120-U-16
CM115-U-14
CM122-U-16
CM121-U-14
CM123A-B-16
C045
C079
HAZARD SW
CM125-U-14
CM126-U-14
(MDP-R14 & R15) NASD/ISD MODULE
CM116-U-12
CM117-U-12
PN-09827783
(MDP-R13) FLASHER MODULE
CM134Z-U-14
CM127Y-U-14
SPL-Z
SPL-Y
CM140Z-U-16
CM133Z-U-16
CM132Y-U-16
CM134Y-U-16
RH RR FENDER FLASH LAMP
LH RR FENDER FLASH LAMP
C035
C034
CM136Z-U-16
CM128Y-U-16
CM139Z-U-16
CM135Z-U-16
CM131Y-U-16
CM137Y-U-16
C004 (-B)
C004 (-A)
C007
C16
D18
J1-C16
J1-D18
EIC IND
RH IND
LH IND
C185
C186
CR136Z-U-16
CR128Y-B-16
CM144-B-16
CM124A-B-16
CM18-U-16
CM19-U-16
C15
C14
J1-C15
J1-C14
EIC MODULE
TRL IND 2
TRL IND 1
CR137Z-U-16
CR138Z-U-16
CR129Y-U-16
CR130Y-U-16
(F001) -1
(F001) -2
NASD/ISD TRAILER PLUG
RHS EXTENDIBLE TAIL LAMP
LHS EXTENDIBLE TAIL LAMP
C093
C092
C091
C090
RH RR CAB ROOF FLASH LAMP
RH FRT CAB ROOF FLASH LAMP
LH RR CAB ROOF FLASH LAMP
LH FRT CAB ROOF FLASH LAMP
CR140-B-16
CR139-B-16
CR132-B-16
CR131-B-16
CM282-B-16
CM280-B-16
CM114-B-16
CTV CM555 FR# 11
CTV SPL-A FR# 13
FR #10



CIGAR LIGHTER
BEACON
TURN SW
HORN
ROAD LAMPS
FR #11


CONSOLE LAMP
TRAILER SKT
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM151-U-16
CM157-U-14
CM158-U-14
(MDP-F9)
LH PARK LAMP
FUSE
7.5 A
(MDP-F8)
RH PARK LAMP
FUSE
7.5 A
CM161M-U-18
CM160X-U-18
CM41M-U-18
CM172M-U-18
SPL-M
SPL-X
CM173X-U-18
CM162M-U-18
CM159-U-18
C007
C8
EIC ILLUM
LAMP
J1-C8
ILLUM
C004
(-H)
(-J)
NOT
USED
(LICENSE PLATE LAMP
ISO ONLY)
CM168M-U-18
C003
(-T)
(-)
RM162-U-16
RM159-U-16
C150
LH TAIL LMP
NASD-BLACK
RH TAIL LMP
NASD-BROWN
TRAILER SOCKET
CM164X-U-18
CM163M-U-18
CM143X-U-18
C031
LH CNSL LMP
C032
RH CNSL LMP
CM169-B-18
C035
RH TAIL LMP
CM171-B-18
CM144-B-16
C034
LH TAIL LMP
CM139-B-16
CTM
CM219
FR# 14
CTM
CM218
FR# 14
CTM
CM218
FR# 14
FR #12


WORK LAMPS
MAIN BUS BAR
50 A
(MFP-5) WRK LMP MN FUSE
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM151-U-16
CM176-R-8
EIC MICROPROCESSOR
EIC PROCESSOR CONTROL
EIC MODULE WRKLMP SW.
BUS BAR
15 A
(MFP-F7) UPPER CAB FRT WRK LMP FUSE
(MDP-F6) UPPER CAB RR WRK LMP FUSE
20 A
(MDP-F5) LWR CAB RR WRK LMP FUSE
(MDP-F4) FRT/MID WRK LMP FUSE
(MDP-R4) UPPER CAB FRT WRK LMP RELAY
(MDP-R3) UPPER CAB RR WRK LMP RELAY
(MDP-R2) LWR CAB RR WRK LMP RELAY
(MDP-R1) FRT/MID LWR WRK LAMP RELAY
110 OHM
CM186J-B-18
CM187J-B-18
CM189J-B-18
CM191J-B-18
CM5A-B-14
CM4A-B-12
SPL-J
SPL-A
SPL-N
SPL-V
SPL-U
SPL-F
SPL-G
SPL-E
RH FRT UPPER WRK LMP
RH RR UPPER WRK LMP
RH RR LWR WRK LMP
CNTR RR LWR WRK LMP
RH MID LWR WRK LMP
RH FRT LWR WRK LMP
LH FRT UPPER WRK LMP
LH RR UPPER WRK LMP
LH RR LWR WRK LMP
LH MID LWR WRK LMP
LH FRT LWR WRK LMP
WORKLAMP
TRAILER SOCKET
TO HORN SEE FR#11
FR 13


RR WIPER/WASHER
FRT WIPER/WASHER
ACC SOCKET
(MFP-6)
MAIN FUSE #2
40 A
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM205P-R-10
BUS BAR
(MDP-R10)
AUX #2 RELAY
85 OHM
85
30
87
87A
86
(MDP-F1)
ACC SOCKET FUSE
10 A
CM213-N-10
CM221A-B-18
CM226-N-16
(MDP-3)
WIPER/WASHER FUSE
15 A
CM208-N-14
CM207-N-14
C085
C084
WASHER
RR WIPER SW. (OPTION)
FRT WIPER SW.
OFF
ON
LOW
HI
CM215-N-14
CM216-V-14
CM206-V-14
CM214-V-14
CM210-V-14
CM273-V-14
CM212-V-14
CM211-V-14
CM209-V-14
C061
C086
C060
C087
C027
ACC SOCKET
RR WIPER MTR (OPTION)
RR WASHER PUMP MTR (OPTION)
FRT WIPER MTR
FRT WASHER PUMP MTR
GR
YW
R
P
PK
CM225-B-16
CM219-B-14
CM217-B-14
CM272-B-14
CM218-B-14
CT1V
CM218
FR# 14
FR 14


CLIMATE CONTROL SYSTEM
RADIO
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228D-R-16
BUS BAR
CM198-N-10
BUS BAR
FUSE 25 A
CLIMATE CNTRL
(MDP-F2)
CM245-N-12
RADIO POWER FUSE
7.5 A
(MDP-F17)
CM232-N-18
CM75D-R-18
C020
HVAC ASSEMBLY
BLOWER SW
LOW
MED
HI
A/C MODE SW
HI/LOW PRESS SW (HIGH SIDE)
RESISTOR ASSY
0.55
0.2
COMPRESSOR RELAY
THERMOSTAT
BLOWER MOTOR
CM244-V-14
CM243-B-14
C003 (-H)
RM244-V-14
C008 (-H)
FM244-V-14
C100
A/C CLUTCH
FM240-B-14
CTV CM272 FR# 14
C064
PWR-KEYSW
RADIO MEMORY PWR
ANT
SPKR+
SPKR-
SPKR+
SPKR-
COAX CABLE
ANTENNA
GROUND STRAP
CM237-V-18
CM236-B-18
CM235-B-18
CM234-B-18
CM233-V-18
C067
C066
RH SPEAKER
LH SPEAKER
CTV CM272 FR# 14
FR 15



SEAT SYSTEM
MOVABLE CONSOLE
IMPLEMENT SOCKET
MAIN BUS BAR
(MFP-7) ACC #1 MN FUSE 40 A
CM240-R-10
CM29-W-18
CM228D-R-16
CM30-W-18
BUS BAR
(MDP-R9) ACC #1 RELAY
CM239-N-12
(MDP-F16) SEAT FUSE 20 A
CM227-N-14
(MDP-F15) MV CONSOLE FUSE 7.5 A
(MFP-8) IMPL SCKT MN FUSE 40 A
CM252R-R-10
SPL-R
CM246R-R-10
(MDP-F30) IMP MONITOR FUSE 15 A
(MDP-R17) IMPL SOCKET RELAY
CM249J-B-18
CM248-N-10
CM247-R-14
CM241J-B-18
CM231-B-14
CM228D-R-18
CM229-W-18
C006 CCM MODULE J3-20
SEAT SWITCH STATUS
CM222-N-18
C005 (-4)
C065
AIR RIDE SEAT ASSEMBLY
BRN
RED
YEL
GRN
SEAT "OCCUPIED" SW (MDM) CLS=OCCUPIED
UP OFF DWN SW
SEAT RAISE LOWER SW
RH222-N-18 +12
RH221-N-18
RH220-B-18
K143
EXTEND OFF RETRACT
MOVEABLE CONSOLE SW
RH219N-B-18
RH223-V-18
RH224-V-18
C005 (-6)
C005 (-5)
CM223-V-18
CM224-V-18
CM291-R-18
7.5 AMP
30 AMP
C024
IMP SCKT
C062 EXT RET
DC LINEAR ACTUATOR
RIGHT HAND CONSOLE MOTOR
-EXT
+RET
CM271-B-10 PWR GRD
AIR RELEASE SOL
COMPRESSOR
LOWER HEIGHT LIMIT SWITCH
UPPER HEIGHT LIMIT SWITCH
FR 16


MAIN BUS BAR

CM291-R-18


CM291-R-18

FR 17


TRAILER LIGHTS
MAIN BUS BAR
40 A
(MFP-1)
EHR/TRAILER PLUG POWER
(MDP-F31)
EHR POWER
10A
20 A
(MDP-F32)
TRAILER PLUG LIGHTS POWER
CM293-R-18
CM289-R-16
SPL AB
CM285Z-R-16
CM311-U-16
CM310-U-16
CM285Y-R-16
CM285Z-R-16
F002
(-2)
(-1)
CM131Y-U-16
CONFIG ISO
CONNECT F003 TO F001 TO SEE FRAME 10
CM135Z-U-16
(MDP-R20)
LH TRAILER LIGHTS
(MDP-R19)
RH TRAILER LIGHTS
NASO EXT LIGHTS ONLY
CM287A-B-18
CM286Y-R-16
CM288A-B-18
CM286Z-R-16
CM313-R-16
SPL TP LHS
SPL TP RHS
CM288A-B-18
CM287Y
CM287Z
C003
CM313-R-16
CM312-R-16
F003
RM287Y-R-16
RM287Z-R-16
C150
LH FLASH LAMP NASO-YELLOW
TRAILER SKT
RH FLASH LAMP NASO-BROWN
CM289A-B-18
(MDP-R18)
ELECTROHYDRAULICS POWER
CM247EH-R-18
C541
(-1)
(-2)
EH1U-R-18
EH2S-B-18
CM292-R-18
C005
(-18)
CM291-R-18
CM291-R-18
C005
(-17)
RH291-R-18
C187
EHR ISOLATOR SWITCH
DISENGAGED
ENGAGED
RH292-R-18
RH292-R-18
CM294-B-18
CM271EH-B-18
CM289A-B-18
CTV SPL A FRAME 12
CTV SPL A FRAME 12
CTV SPL A FRAME 12
FR 18


ELECTRO HYDRAULICS
EH73-B-20
EH5D-B-18
EH26-B-18
EH10-B-18
POD 1 AXIS 1
C501
EH1U-R-18
EH38-R-18
EH1C-R-18
EH1A-R-18
SPL A
SPL T
EH7-R-20
EH3A-DR-20
EH8-DR-20
EH22-VI-20
EH30-DR-20
EH29-DR-20
EH19-DR-20
EH27-VI-20
EH5A-DR-20
EH1K-R-18
EH1L-R-18
EH1J-R-18
EH47C-VI-18
C531-1
C531-33
C531-2
C531-9
C531-6
C531-39
C531-18
C531-46
C531-47
C531-19
C531-10
C531-26
C531-31
EHR CONTROLLER 1
EH11B-R-18
EH2F-B-20
EXT CONTROL 1
C521
EH47B-VI-20
EH1F-R-20
C531-3
C531-17
C531-45
C531-44
C531-15
C531-222
C531-29
C531-28
EH50-VI-20
EH49-VI-20
EH25-B-18
EH2K-B-18
EH40-B-18
EH18-B-18
EH74-B-20
SPL H
SPL B
EH2C-B-18
SPL G
EH1H-R-20
EH48B-VI-20
EH2H-B-20
C522
EXT CONTROL 2
POD 2 AXIS 1
EH52-VI-20
EH51-VI-20
EH2N-B-18
EH2M-B-18
EH5-R-18
EH11A-DR-20
EH16-VI-20
EH36-VI-20
EH44-DR-20
EH2P-R-18
EH1N-R-18
EH1M-R-18
EH48C-VI-18
C532-33
C532-1
C532-2
C532-9
C532-45
C532-44
C532-17
C532-3
C532-6
C532-39
C532-18
C532-46
C532-47
EHR CONTROLLER 2
EH2A-B-18
EH2S-B-18
SPL U
EH14D-B-18
EH13D-B-18
EH6D-B-18
FR 19

ELECTRO HYDRAULICS





FR 20


70/70A


ISO SCHEMATICS


(EUROPEAN VERSION)



START SYSTEM
CHARGE SYSTEM
COLD START SYSTEM
BC3-R-2
FM5-R-2
CM2-D-18
C005 (-2)
RH2-D-18
C012
SHIFT CNTRL ASSY
NEUTRAL SW
CLOSED=NEUTRAL
C012
RH61A-D-18
RH60A-D-18
SPL-A
RH1A-D-18
C005 (-1)
CM1-D-18
C003 (-D)
RM1-D-18
C008 (-D)
FM1-D-18
C101
START RELAY
30
85
86
87
FM2-R-8
FM3-D-8
BC2-R-2/0
BC3-R-2
BATTERY
+
-
BC1-B-2/0
JUMP START POST
B+
S
STARTER
M
ALTERNATOR
B+
IND
I-MODE
GND-B-
R-RELAY
B+
F+
F- REG GND
GND
FM4-B-18
CTV FM59V FR# 7
FR 1
CM77-R-14
C022
DAM CONNECTOR
(1) B+ PWR
20 A
(MDP-F27)
COLD START FUSE
CM8-R-14
CM3-N-18
C076
COLD START SW.
CM3-Y-18
CAN SYS LINK
C12
C012
J1-C12
EIC MODULE
ALTERNATOR INDIC LAMP (EIC)
VOLTAGE MISSING ALTERNATOR
COLD START CONTROL
J1-38
C08
C012
CM10-P-18
(MDP-R8)
COLD START RELAY
2
3
4
5
SEE FR #6
C006
21
VPWR
J3-21
ALT EXCITE
56OHM 10W
J2-28
A/D
28
CCM MODULE
COOLANT TEMP LOW
VOLTAGE MISSING ALTERNATOR
C002
ENG COOLANT TEMP SENSOR FR#7
RM6-N-18
C008 (-4)
FM6-N-18
CM7-D-12
C003 (-E)
RM7-D-12
R-4
C008 (-E)
FM7S-D-12
FM7S-D-12
SPL-S
BR
FM19S-D-14
C111
THERMOSTART HEATER
FM11S-D-14
C107
CONNECTOR NOT USED
FM8-B-14
FM8-B-14
AIR INLET HEATER RELAY
R-4
AIR INLET HEATER
CTV FM240 FR# 15
CTV SPL-A FR# 13
CM9A-B-18
C001
D8
J2-D8
RHC MODULE
NEUTRAL START



ITALIAN TRAILER BRAKE SYSTEM
SHUTDOWN OVERRIDE
IGNITION SWITCH
FUEL SHUT OFF
BC3-R-2
CM29-W-18
CM14B-R-10
CM2-D-18
BUS BAR
CM3-N-18
CM24-N-18
(MDP-F26) KEY SW FUSE 10 A
CM26-R-18
POSITION: 1-----ACC 2-----OFF 3-----ACC/IGN 4-----IGN/START(MOM)
IGNITION SWITCH
CT 2-N-18
PARK BRAKE SWITCH
IF AIR BRAKES SEE FRAME (17)
CT4-N-18
CT 3-V-18
CT 11-N-18
CM23-N-18
TRAILER BRK PASSTHRU-RT
TRAILER BRK RELAY
PUMP PRESS SW
TRAILER BRK PRESS SW
SHUTDOWN OVERRIDE SW NOT INCLUDED ON ALL MODEL OFFERINGS.
SHUTDWN OVERRIDE SW
OVRRDE
OFF STATUS LAMP
OPEN TO ENABLE OVERRIDE OF AUTO SHUTDOWN & ENERGIZE
SYSTEMS MONITORED FOR ENGINE SHUTDOWN
ENG COOLANT TEMP
ENG OIL PRESS
TRANS TEMP
TRANS PRESS
(MDP-R16) FUEL SOL RELAY
CM12-D-12
CM18A-B-18
CM19-P-18
CM1-B-18
CM20-B-18
CM27-D-18
CM2-Y-18
EIC MODULE
CCM MODULE
CAN SYS LINK
AUDIBLE ALARM
CM21-P-18
RM12-D-12
RM13-P-18
FM13-P-18
FM10-B-12
FUEL SOL ASY
PULL
HOLD
SOLENOID ASY
CCM MODULE J3-8 TRAILER BRAKE
EIC MODULE TRAILER BRAKE LAMP
CTV CM02 FR# 3
CTV FM24D FR# 15
CTV CM SPL-A FR# 13
FR 2



CLUTCH POT
EXT R/LWR SW
DAM CONN
PARK BRAKE
CREEPER
MAIN BUS BAR
BC3-R-2
(MFP-C2) MAIN FUSE 50A
CM29-W-18
CM25-N-18
CM36D-R-18
CM48D-R-18
CM14B-R-10
CM15B-R-8
CM16B-R-10
CM17B-R-10
SPL-B
(MDP-F23) MEMORY (KAPWR) UNSWITCHED POWER
BUS BAR
CM24-N-18
CM34C-N-18
5 A
(MDP-F22) FRT CNSL FUSE
CM43E-N-18
CM44E-N-18
CM45E-N-18
CM46E-N-18
SPL-E
AUX PWR RELAY (MDP-R12)
CM32-N-10
CM35-R-18
10 A
CONTROL MODULES SWITCHED POWER (VPWR)
LH EXT HITCH SWITCH
RH EXT HITCH SWITCH
RAISE
OFF
LOWER
CLOSE=BRAKE APPLIED
CM63H-Y-18
CM62G-Y-18
CM64G-Y-18
CM65H-Y-18
SPL-G
SPL-H
CTW CM20 FR# 2
CM102-B-18
CM48D-N-18
PARK BRAKE SWITCH
CM49-N-18
OPEN=BRAKE APPLIED
CM47-N-18
LH BRK LAMP SW
RH BRK LAMP SW
CM58-Y-18
CM59-Y-18
CM60-Y-18
CM61-Y-18
CM103-Y-18
ON CREEPER OFFSWITCH (OPTION)
CLUTCH PDT
+5V=EFI/ATA OUT
4K
CM37-N-18
CM31A-B-18
CM33-N-18
CM38-Y-18
CM39-B-18
J1-C13
J1-C7
J1-C5
J1-D14
J1-D15
J1-D9
J1-C10
J1-D11
J1-D10
ELECTRONIC INSTRUMENT MODULE (EIM)
SVREF(5A/2A)
SIGNAL GND
J1-C6
J1-D2
J1-D1
J1-C1
CAN(+) J1-C2
CAN(-) J1-C3
EIC-GND
CM68K-P-18
SEE FR# 6
CM100K-P-18
CM69K-P-18
RH69-P-18
CM260T-B-16
CM259S-R-16
CM42-B-16
CM199-B-16
CM270-P-18
CM269-Y-18
CM70K-P-18
(10) GROUND
(12) IRS232 OUT
(11) IRS232 IN DAM CONNECTOR
(3) VPP/IN
CM204-B-16
CTW CM271 FR# 16
CTW CM SPL-A FR# 13
FR 3



ELECTRONIC DRAFT CONTROL SYSTEM DAM CONN RHC PWR RAISE/WORK SW 4WD
MAIN BUS BAR
CM29-W-18
CM25-N-18
CM36D-R-18
CM48D-R-18
CM75D-R-18
CM228D-R-18
CM93D-R-18
CM72C-N-18
CM34C-N-18
SPL-D
SPL-C
SPL-L
SPL-W
(MDP-F24) TURN SIGNAL FUSE 15 A
SEE FR# 10
RH43P-N-18
RH44P-N-18
RH28N-R-18
CTV SPL-N FR# 5
4WD SW (OPTION)
RAISE/WORK/FLOAT SWITCH
RAISE
WORK
FLOAT
RH86W-N-18
RH47W-N-18
RH87W-N-18
RH33-P-18
RH49-Y-18
RH59-Y-18
RH71-N-18
RH73-N-18
RH74-R-18
RH9-N-18
RH7L-N-18
RH8L-N-18
RH6L-N-18
RH4L-N-18
HEIGHT LIMIT POT C138
DRAFT/POSITION MIX POT
QUADRANT POT
SLIP LIMIT POT (OPTION)
DROP RATE POT
RH10-Y-18
RH1M-B-18
RH5M-B-18
RH4M-B-18
RH2-Y-18
RH14-Y-18
RH16-Y-18
RH17M-B-18
RH20-Y-18
RH2M-R-18
RH3L-N-18
RH76M-B-18
SVREF(S/2)J2-C16
J2-D16 SIGNAL GND J2-D6
VPP/IN J1-9
C GRDJ1-6
J2-D15
J2-D3
J2-D2
J2-D1
J1-3 KAPWR
J1-2 VPWR
J2-C10 VPWR
J2-C7
J2-C6
J2-C14 HAND CONSOLE MODULE (RHC)
J2-C5 RIGHT
J2-D14
PWR GRD J2-C8
PWR GRD J2-C7
J2-C9
J1-4
J1-5
RH79-B-16
RH255-Y-18
RH256-P-18
RH23-P-18
RH24-P-18
HITCH SLIP IND (OPTION) SLIP IND
HITCH STATUS IND STATUS IND
RH26-B-18
RH69-P-18
CM79-B-16
CM255-Y-18
CM256-P-18
DAM CONNECTOR
(13) ORS232 IN
(14) ORS232 OUT
RH78N-B-18
RH77N-B-18
RH27N-B-18
CM260T-B-16
CM259S-R-16
CTV CM225 FR# 14
FR 4



DIFF LOCK
UP/DWN SHIFT
AUTO SHIFT
SHIFT CNTRL
CLUTCH PEDAL SWITCH
PTO
MAIN BUS BAR
CM29-W-18
CM25-N-18
CM75D-R-18
CM228D-R-16
CM93D-R-18
CM72C-N-18
RH40P-N-18
CM87-N-18
CM83-Y-18
RH30P-N-18
SPL-AA
CM87-N-18
RH43P-N-18
RH44P-N-18
RH41P-N-18
OPEN=CLUTCH APPLIED
CLUTCH SW
PTO SWITCH
ENGAGE(MOM)
NEUTRAL
DISENGAGE
(MOM)
RH62B-Y-18
RH25B-Y-16
RH84B-Y-16
SPL-B
RH65-Y-16
RH31B-Y-16
RH85-Y-16
CM84-Y-18
CM76J-B-18
CM85-Y-16
110 OHM
PTO RELAY
CTV CM SPL-J FR# 11
(MDP-R5)
RH46P-N-18
RH45P-N-18
RH42P-N-18
SPL-P
RH53N-B-18
DIFF LOCK SW (MOM)
UP/D PRGM SHFT SW (MOM)
AUTO SHFT SW
SHIFT CNTRL ASSY F/R SW
RH82V-N-18
RH57V-Y-18
SPL-V
RH69V-Y-18
RH50-P-18
RH51-Y-18
RH52-Y-18
RH54-Y-18
RH55-Y-18
RH56-Y-18
J2-C11
J2-D13
J2-D12
J2-D11
J2-D10
J2-D9
J2-D7
J2-D5
RIGHT HAND CONSOLE MODULE (RHC)
J2-C12
CAN(+)J1-14
CAN(-)J1-15
SPL-T
SPL-S
CM262T-B-16
CM261S-R-16
J2-C4
J2-C3
J2-C2
J2-C1
RH35-P-18
RH36-P-18
RH37-P-18
RH38-P-18
RH39-P-18
RH262-B-16
RH261-R-16
CM259S-R-16
CM260T-B-16
CM263T-B-16
CM263S-R-16
SPL-SHD GRD
CM268-B-16
SHIFT CNTRL ASSY FORWARD SW
DOWNSHIFT SW
UPSHIFT SW
REVERSE SW
500
2K
MP
PTO STATUS
PTO IND LAMP
RH265-BAR-18
RH29N-B-18
RH30N-B-18
RH27N-B-18
RH77N-B-18
RH78N-B-18
RH80N-B-18
SPL-N
CM260T-B-16
CM259S-R-16
CM80-B-16
CTV CM225 FR# 14
(15) CAN(+) DAM
(16) CAN(-) CONNECTOR
CTV CM271 FR# 16
FR 5



IMP STATUS CONN
DAM CONN
TRANS CNTRL SOL
MAIN BUS BAR
40 A
(MFP-3)
MAIN TRANS FUSE
CM29-W-18
CM25-N-18
CM75D-R-18
CM228D-R-16
CM93D-R-18
CM72C-N-18
CM83-Y-18
CM86-Y-16
CM28-N-18
CM104-N-16
CM91-R-10
CM25-N-18
85
30
86
87
87A
85 OHM
(MDP-R11)
TRANS PWR RELAY
CM94A-B-18
CTV SPL-A FR#11
CM92-N-10
BUS BAR
15 A
20 A
20 A
(MDP-F20)
TRANS F/R CNTRL SOL /PTO FUSE
(MDP-F19)
TRANS SHFT CNTRL SOL FUSE #2
(MDP-F18)
TRANS SHFT CNTRL SOL FUSE #1
CM96-N-16
CM88-N-14
CM95-N-14
110 OHM
(MDP-R6)
DIR INTERRUPT RELAY
CM99J-B-18
CTV SPL-J FR# 11
CM97-N-16
DAM CONN
ERS232 IN (6)
ERS232 OUT (7)
C002
CM275T-B-16
CM274S-B-16
CM253-Y-18
CM254-Y-18
C006
J3-24 CANK(+)
J3-22 CANK(-)
J3-2
J3-10
J3-19
J3-6KPWR
J3-24VPWR
J3-9
J3-17
J3-18
CHASSIS CONTROL MODULE (CCM)
C001
J1-M
J1-T
J1-E
J1-H
J1-D
J1-D
J1-U
J1-D
J1-S
J1-V
J1-G
J1-Q
J1-K
J1-N
J1-K
J1-X
RM119-P-18
RM118-P-18
RM117-P-18
RM116-P-18
RM115-P-18
RM114-P-18
RM111-P-18
RM110-P-18
RM107-P-18
RM106-P-18
RM105-P-18
RM104-P-18
RM103-P-18
RM102-B-18
C174 TRANS-F1 SOL
C175 TRANS-F2 SOL
C178 TRANS-R SOL
C168 TRANS-2 SOL
C171 TRANS-A SOL
C173 TRANS-C SOL
C176 TRANS-MC1 SOL
C177 TRANS-MC2 SOL
C179 TRANS-CRP SOL(OPTION)
C172 TRANS-B SOL
C170 TRANS-3 SOL
C169 TRANS-1 SOL
1.79 OHM
RM120-B-18
RM121-B-18
RM122-B-18
RM123-B-18
RM124-B-18
RM125-B-18
RM112-B-18
RM113-B-18
RM108-B-18
RM109-B-18
CTV CM123 FR#6
CTV CM208 FR# 13
CTV CM123 FR#6
CTV CM123 FR#6
CTV CM225 FR# 14
CTV CM225 FR# 14
J3-C3
J3-3
J3-11
J3-15
J3-7
J3-13
J3-5
CM40-P-18
CM90-P-18
CM99-P-18
CM98-P-18
CM100K-P-18
CM6-B-16
CM101-B-16
CTV SPL-K VPP/IN FR# 3
C025
C022
IMP STATUS
DAM CONNECTOR
(4) TRS232 IN
(5) TRS232 OUT
(2) VPP/GEN
FR 6



EDC R/L SOL
4WD, DIFF LK, AND PTO SOL
ENG WARNING SEN/SW
TRANS PRESS SW
RADAR
MAIN BUS BAR
STEERING ANGLE POT
RM77T-B-18
RM62U-N-18
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM104-N-16
C003
RM104-J-N-16
C001
GRAYISH BROWN
GREEN
C201
STEERING ANGLE POT
5V
+5V=UP
SK
BLUE
RM285-P-18
RM88J-N-16
RM87J-N-16
RM5J-N-16
RM50J-N-16
C187
C180
C182
C158
DPF RADAR
VPWR 12V
SIG
SEN
GRD
TRANS OIL FLTR SW
HYD FLTR SW
TRANS OIL PRESSURE
OPEN=PLUGGED
OPEN= PRES
RM90-Y-16
RM89-Y-16
RM51-Y-16
RM68T-B-16
RM52-Y-16
RM53-Y-16
C002
J2-11
J2-18
J2-13
J2-26
J2-1 +12V SENSE
J2-22
CHASSIS CONTROL MODULE (CCM)
(+)Y12-23
(-)R J2-7
J2-27
J2-2
J2-25
J1-W
J1-C
J1-J
J1-L
J1-F
J1-P
J1-B
RM100-B-18
RM99-P-18
RM98-B-18
RM97-P-18
RM96-P-18
RM94-P-18
RM92-P-18
RM86-P-18
RM65-BARE-18
RM83-R-16
RM82-Y-16
RM85-P-18
RM84-P-18
C008
(-T)
(-F)
(-P)
(-N)
(-S)
(-L)
FM65-BARE-18
FM83-R-16
FM82-Y-16
FM85-P-18
FM84-P-18
FM86-P-18
FM65V-BARE-18
K WIRE
C164
2.4 OHM
HITCH LOWER SOL
C165
2.4 OHM
HITCH RAISE SOL
C166
9.4 OHM
4WD SOL (OPTION)
C167
7.6 OHM
PTO SOL
C168
9.4 OHM
DIFF LOCK SOL
RM95-B-18
RM93-B-18
RM91-B-18
CTM RM208 FR# 13
C102
COOLANT LEVEL SENSOR
MAX R=LOW COOLANT
C105
EXHAUST GAS TEMP SENSOR
FM58V-B-18
SPL-V (SHIELD GND)
C104
ENG TEMP SENSOR
MIN R=HIGH TEMP
FM16T-B-18
C106
INTERCOOL TEMP SENSOR
MIN R=HIGH TEMP
FM17T-B-18
FM17T-B-18
FM16T-B-18
FR 7



EDC PINS
ROCKPSHFT POT
TRANS WARN SEN/SW
ENG OIL PRESS SEN
MAIN BUS BAR
RM77T-B-18
RM62U-N-18
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
LH DRAFT PIN C155
RH DRAFT PIN C156
ROCKSHAFT POT C157
AIR FLTR VAC SW
ENG OIL PRESS SEN
+5V=MAX PRES
C008
C009
C103
C109
J2-3
J2-20
J2-10
J2-24
J2-31
CHASSIS CONTROL MODULE (CCM)
SVREF1 SIGNAL RTN
SVREF2 SIGNAL RTN
J2-40
J2-39
J2-16
J2-17
J2-30
J2-5
ENG SPD SENSOR C160
WHEEL SPD SENSOR C162
TRANS OIL TEMP SENSOR C161
FUEL LVL SENDER C159
21 REED SWITCHES
FLOAT
MAGNET
RM80P-P-18
RM79P-P-18
RM78P-P-18
RM77P-P-18
RM67T-B-16
RM68T-B-16
RM69T-B-18
RM70T-B-18
RM71T-B-18
FM14T-B-18
RM76T-B-18
RM72T-B-18
RM73T-B-18
RM74T-B-18
RM75T-B-18
FM17T-B-18
FM16T-B-18
SPL-T
FR 8



DOME LAMP
TRAILER SKT
BRAKE SYSTEM
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228-R-16
CM28-N-18
BUS BAR
(MDP-F14) DOME LAMP FUSE 5 A
(MDP-F12) BRAKE LAMP FUSE 15 A
CM50-R-18
CM106-R-18
CM50-R-16
C070
LH BRK LAMP SW CLOSED=BRAKE APPLIED
CM51-U-18
C071
RH BRK LAMP SW CLOSED=BRAKE APPLIED
CM56-U-18
CM105-R-18
C037
LH DOME LAMP
C040
RH DOME LAMP
CM109-U-18
CM111-U-18
(MDP-R7) BRAKE LAMP RELAY
CM110-U-18
CM108-B-18
CM107-U-18
CM52F-U-16
CM78J-B-18
CM55F-U-16
SPL-F
C003
CM54F-U-16
CM53F-U-16
C034
LH STOP LAMP
RM55-U-16
C035
RH STOP LAMP
C074
C075
C009
TRAILER SKT-STOP LAMP
ISO-6
ISO-3
RM4-B-12
CM139-B-16
CM144-B-16
LH DOOR SW DOOR CLS=OPEN SW
RH DOOR SW DOOR CLS=OPEN SW
CTV CM213 FR# 14
CTV RM208 FR# 13
CTV CM218 FR# 14
CTV SPL-J FR# 13
FR #9



HAZARD SW.
TURN SIGNAL LAMPS
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
BUS BAR
SEE FR #4
(MDP-F24) TURN SIGNAL FUSE
15 A
CM112-N-12
(MDP-F13) HAZARD LAMP FUSE
15 A
CM113-R-12
CM120-U-16
CM115-U-14
CM122-U-16
CM121-U-14
CM123A-B-16
C045
C079
HAZARD SW.
CM125-U-14
CM126-U-14
(MDP-R14 & R15) ISO CONVERTER MODULE
CM116-U-12
CM117-U-12
PN-09621783
(MDP-R13) FLASHER MODULE
CM134Z-U-14
CM127Y-U-14
SPL-Z
SPL-Y
CM140Z-U-16
CM133Z-U-16
CM132Y-U-16
CM134Y-U-16
RH RR FENDER FLASH LAMP
LH RR FENDER FLASH LAMP
C035
C034
CM136Z-U-16
CM139Z-U-16
CM135Z-U-16
CM131Y-U-16
CM128Y-U-16
CM133Y-U-16
C007
C16
D18
JI-C16
JI-D18
EIC IND
RH IND
LH IND
C004
(-9)
(-4)
C185
C186
CR136-U-16
CR128-U-16
CM144-B-16
CM139-B-16
RHS EXTENDIBLE TAIL LAMP
LHS EXTENDIBLE TAIL LAMP
(F001) -1
(F001) -2
NASD/ISD TRAILER PLUG
C092
C080
RH FRT CAB ROOF FLASH LAMP
LH FRT CAB ROOF FLASH LAMP
CR132-B-16
CR128-B-16
CM282-B-16
CM280-B-16
CM118-U-16
CM119-U-16
C15
C14
C007
JI-C15
JI-C14
EIC MODULE
TRL IND 2
TRL IND 1
CM124A-B-16
CM114-B-16
CTV CM151 FR# 11
CTV SPL-A FR# 13
FR #10



CIGAR LIGHTER
BEACON
TURN SW
HORN
ROAD LAMPS
MAIN BUS BAR
50 A
(MFP-4) RD LAMP MN FUSE
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM145-R-8
CM146-R-10
BUS BAR
15 A
(MDP-F11) CIGAR/HORN/BEACON FUSE
25 A
(MDP-F10) ROAD LAMP FUSE
SWITCH POSITION
1. OFF
2. PARK
3. ROAD/PARK
4. WORK/PARK
C081
MAIN LAMP SW
CM156-U-14
HD LAMPS
MRK LAMPS
CM157-U-12
WRK LAMPS
CM151-U-16
CM150-U-12
NASD CONNECTION
ISD CONNECTION
CM120-U-14
CM140-U-12
CM147-R-16
CM148-R-14
C068
TURN SIGNAL SW
L
0
R
CM166-U-12
CM140-U-12
CM142-U-12
(MDP-F28) HI BEAM FUSE
(MDP-F29) LOW BEAM FUSE
15 A
CM167-U-14
CM170-U-14
CM153-U-12
CM149-R-16
CM125-U-14
CM126-U-14
C003
RM167-U-14
RM170-U-14
RM153-U-12
C008
FM167-U-14
FM170-U-14
FM153V-U-12
SPL-V
C009
LT167-U-14
LT170-U-14
LT152V-U-14
LT153V-U-12
SPL-C
LT172C-U-14
LT171C-U-14
LT154C-U-14
LT155C-U-14
BEACON LAMP SWITCH (OPTION)
C069
OFF
ON
CM154-W-16
CM152-W-14
CM193-U-16
C007
J1-D13
HI BEAM
MODULE-EIC
CM165-V-14
RM165-V-14
FM165-V-14
LT165-V-14
C120
HORN
HIGH BEAM WRK LMP RELAY
LOW BEAM WRK LMP RELAY
85
30
86
87
87A
DHM
LT162B-U-14
LT190-U-14
LT191-U-14
LT196-U-14
LT160D-B-14
LT195-U-14
C193
C192
RH ROAD LAMP ASY
LH ROAD LAMP ASY
HI-BEAM
LO-BEAM
LT164-U-14
LT163A-B-14
C004
CR152-W-14
BEACON SOCKET (OPTION)
C088
CR153-B-14
C005
CIGAR LIGHTER
CM155-B-16
CM197-B-16
LT178E-B-14
CTV FR# 14
CTV FR# 10
CTV FR# 13
CTV SPL-E FR# 13
CTV SPL-D FR# 12
CTV SPL-A FR# 12
CTV SPL-D FR# 12
FR 11


FRT HOOD WORKLAMPS
CONSOLE LMP
TRAILER SKT
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM151-U-16
CM157-U-14
CM158-U-14
CM41M-U-18
(MDP-F9) LH PARK LAMP FUSE 7.5 A
(MDP-F8) RH PARK LAMP FUSE 7.5 A
CM161M-U-18
CM160X-U-18
CM172M-U-18
CM173X-U-18
SPL-M
SPL-X
C007
C8
J1-C8
EIC ILLUM LAMP ILLUM
LT162B-U-14
LT171C-U-14
LT172C-U-14
LH WRKLMP FRT HI BM
LH WRKLMP-FRT LOW BM
RH WRKLMP FRT HI BM
RH WRKLMP-FRT LOW BM
LT168B-U-14
LT169B-U-14
LT173A-B-14
LT174D-B-14
LT185A-B-14
LT175D-B-14
C123
C121
C122
C124
SPL-B
SPL-A
SPL-D
SPL-N
C004
(+D)
(-D)
CONNECTS WITH CONNECTOR C034
CR172M-U-18
CR173X-U-18
CR174X-U-18
CR175X-U-18
CR170M-U-18
LH FRT MARKER LAMP
RH LIC LMP
RH FRT MARKER LAMP
LH LIC LMP
C094
C095
CR132-B-16
CR141-B-18
CR142-B-18
CR139-B-16
LT177A-B-14
LT176D-B-14
C009
(-7)
(-3)
FM177-B-14
FM176-B-14
C031
C032
LH CNSL LMP
RH CNSL LMP
CM169-B-18
CM168M-U-18
CM164X-U-18
CM163M-U-18
CM162M-U-18
CM143X-U-18
CM159-U-18
C003
(-1)
RM162-U-16
RM159-U-16
C150
RH TAIL LMP ISD-5
LH TAIL LMP ISD-7
TRAILER SOCKET
C191
(-3)
(-4)
(-1)
(-2)
FR163M-U-16
FR164M-U-18
LH TAIL LMP
FR154-U-16
FR130-U-16
FR162M-U-18
FR140A-B-16
FR141A-B-16
FR139A-B-16
C189
C190
FENDER LIC LMP
FENDER HARNESS BELGUM, SPAIN, & ITALY ONLY
CM171-B-18
C035
RH TAIL LMP
CM144-B-16
C034
LH TAIL LMP
CM139-B-16
CTM FR# 12
CTM FR# 13
CTM FR# 14
FR 12



WORK LAMPS
MAIN BUS BAR
(MFP-5) WRK LMP MN FUSE
50 A
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM151-U-16
CM176-R-8
C007
D12
EIC MICROPROCESSOR
J1-D12
EIC MODULE WRKLMP SW.
PDS 4
PDS 3
PDS 2
PDS 1
EIC PROCESSOR CONTROL
J1-D3
J1-D4
J1-D5
J1-D6
D3
D4
D5
D6
BUS BAR
(MFP-F7) UPPER CAB FRT WRK LMP FUSE
15 A
(MDP-F6) UPPER CAB RR WRK LMP FUSE
15 A
(MDP-F5) LWR CAB RR WRK LMP FUSE
20 A
(MDP-F4) FRT/MID WRK LMP FUSE
20 A
CM184-U-18
CM183-R-16
CM182-U-18
CM181-R-16
CM180-U-18
CM179-R-14
CM178-U-18
CM177-R-12
(MDP-R4) UPPER CAB FRT WRK LMP RELAY
(MDP-R3) UPPER CAB RR WRK LMP RELAY
(MDP-R2) LWR CAB RR WRK LMP RELAY
(MDP-R1) FRT/MID LWR WRK LAMP RELAY
110 OHM
FR# 16 CM249J-B-18
FR# 16 CM241J-B-18
FR# 6 CM89J-B-18
FR# 5 CM76J-B-18
FR# 10 CM124A-B-16
FR# 10 CM123A-B-16
FR# 6 CM94A-B-18
FR# 3 CM31A-B-18
FR# 2 CM18A-B-18
FR# 1 CM9A-B-18
CM221A-B-18
CM186J-B-18
CM187J-B-18
CM189J-B-18
CM191J-B-18
CM5A-B-14
SPL-J
SPL-A
CM192-U-16
CM190-U-16
CM188N-U-14
CM185-U-12
C004
(-G)
(-F)
SPL-N
CM141N-U-14
CM203N-U-14
C003
(-G)
(-V)
(-V)
RM185F-U-12
RM184F-U-14
FM184-U-14
SPL-F
C008
C009
(-6)
(-5)
SPL-G
LT184G-U-14
CM4A-B-12
CR192V-U-16
CR190U-U-16
CR194V-U-16
CR189U-U-16
SPL-V
SPL-U
RM203-U-14
RM205F-U-14
RM206F-U-14
LT183G-U-14
LT182G-U-14
C098
C099
C045
C052
C053
C125
RH FRT UPPER WRK LMP
RH RR UPPER WRK LMP
RH RR LWR WRK LMP
CNTR RR LWR WRK LMP
RH MID LWR WRK LMP
RH FRT LWR WRK LMP
CR193V-U-16
CR191U-U-16
CM202N-U-14
RM141-U-14
CM201N-U-14
RM204-B-14
RM207-B-14
LT179E-B-14
LT180E-B-14
C015
LH FRT LWR WRK LMP
C150
WORKLAMP
TRAILER SOCKET
C095
C097
C050
C051
LH FRT UPPER WRK LMP
LH RR UPPER WRK LMP
LH RR LWR WRK LMP
LH MID LWR WRK LMP
CR195-B-16
CR197-B-16
CM174-B-14
CM175-B-14
RM208-B-14
CR196-B-16
CR198-B-16
LT178E-B-14
TO HORN SEE FR#11
C009
FM181-B-14
C014
CM225
FR# 14
FR 13


RR WIPER/WASHER
FRT WIPER/WASHER
ACC SOCKET
(MFP-6)
MAIN FUSE #2
40 A
CM29-W-18
CM75D-R-18
CM228D-R-16
CM28-N-18
CM205P-R-10
BUS BAR
(MDP-R10)
AUX #2 RELAY
85 OHM
85
30
87A
87
86
(MDP-F1)
ACC SOCKET FUSE
10 A
CM213-N-10
CM221A-B-18
CM226-N-16
(MDP-3)
WIPER/WASHER FUSE
15 A
CM208-N-14
CM207-N-14
C085
C084
WASHER
RR WIPER SW. (OPTION)
ON
OFF
FRT WIPER SW.
OFF
LOW
HI
C021
ACC SOCKET
CM215-N-14
CM216-V-14
CM206-V-14
CM214-V-14
CM210-V-14
CM273-V-14
CM212-V-14
CM211-V-14
CM209-V-14
C061
C086
C060
C087
RR WIPER MTR (OPTION)
RR WASHER PUMP MTR (OPTION)
FRT WIPER MTR
FRT WASHER PUMP MTR
PK
HI
LOW
GR
YW
R
P
CM225-B-16
CM219-B-14
CM217-B-14
CM272-B-14
CM218-B-14
CTV CM218 FR# 14
FR 14



CLIMATE CONTROL SYSTEM
RADIO
MAIN BUS BAR
CM29-W-18
CM75D-R-18
CM228D-R-16
BUS BAR
CM198-N-10
BUS BAR
FUSE 25 A
CLIMATE CNTRL
(MDP-F2)
CM245-N-12
RADIO POWER FUSE
7.5 A
(MDP-F17)
CM75D-R-18
CM232-N-18
C020
HVAC ASSEMBLY
C064
RADIO
ANT
SPKR+
SPKR-
MEMORY PWR
PWR-KEYSW
SPKR+
SPKR-
COAX CABLE
ANTENNA
BLOWER SW
LOW
MED
HI
LOW
MED
HI
A/C MODE SW
HI/LOW PRESS SW (HIGH SIDE)
RESISTOR ASSY
0.55
0.2
COMPRESSOR RELAY
87
87A
85
30
86
THERMOSTAT
BLOWER MOTOR
CM244-V-14
CM243-B-14
C003
(+)
RM244-V-14
C008
(+)
FM244-V-14
C100
A/C CLUTCH
FM240-B-14
CTV
CM272
FR# 14
CM237-V-18
CM236-B-18
CM235-B-18
CM234-B-18
CM233-V-18
C067
C066
RH SPEAKER
LH SPEAKER
GROUND STRAP
FR 15



SEAT SYSTEM
MOVABLE CONSOLE
IMPLEMENT SOCKET
MAIN BUS BAR
(MFP-7) ACC #1 MN FUSE
40 A
CM240-R-10
CM29-W-18
CM228D-R-16
CM30-W-18
BUS BAR
(MDP-R9) ACC #1 RELAY
CM239-N-12
(MDP-F16) SEAT FUSE 20 A
CM227-N-14
(MDP-F15) MV CONSOLE FUSE 7.5 A
(MFP-8) IMPL SCKT MN FUSE
40 A
CM252R-R-10
SPL-R
CM258R-R-10
CM246R-R-10
(MDP-F30) IMP MONITOR FUSE 15 A
(MDP-R17) IMPL SOCKET RELAY
85
30
87
87A
86
CM249J-B-18
CM248-N-10
CM247-R-14
CM241J-B-18
CM231-B-14
CM228D-R-18
CM229-V-18
CCM MODULE
C006
20
J3-20
SEAT SWITCH STATUS
CM222-N-18
C005 (-4)
C065
A
B
C
D
E
B
BRN
RED
YEL
GRN
AIR RIDE SEAT ASSEMBLY
RH222-N-18
+12
RH221-N-18
RH220-B-18
C143
RH219N-B-18
EXTEND
OFF
RETRACT
MOVEABLE CONSOLE SW
CM291-R-18
RH223-V-18
RH224-V-18
C005 (-6)
C005 (-5)
CM223-V-18
CM224-V-18
C062
EXT RET
DC LINEAR ACTUATOR
RIGHT HAND CONSOLE MOTOR
-EXT
+RET
7.5 AMP
30 AMP
C024
IMP SCKT
CM271-B-10
PWR GRD
SEAT 'OCCUPIED' SW. (MDM) CLS=OCCUPIED
UP
OFF
DWN
SEAT RAISE LOWER SW
AIR RELEASE SOL
COMPRESSOR
LOWER HEIGHT LIMIT SWITCH
UPPER HEIGHT LIMIT SWITCH
NC
SPL-L13 FR# 13
CM271-B-16 FR# 16
CTLR-M SPL-L5 FR# 5
CTLR-M SPL-L13 FR# 13
FR 16

AIR BRAKES - TRAILER




FR 17


TRAILER LIGHTS
(MFP-1)
EHR/TRAILER
PLUG POWER
40 A
(WDP-F31)
EHR POWER
10A
(WDP-F32)
TRAILER PLUG
LIGHTS POWER
20 A
CM293-R-18
CM289-R-16
SPL AB
CM285Z-R-16
CM311-U-16
CM310-U-16
CM285Y-R-16
CM285Z-R-16
C003
(-2)
(-1)
NASO EXT LIGHTS ONLY
(WDP-R20)
LH TRAILER LIGHTS
(WDP-R19)
RH TRAILER LIGHTS
CM287A-B-18
CM286Y-R-16
CM288A-B-18
CM286Z-R-16
CM313-R-16
SPL TP
LHS
SPL TP
RHS
CM288A-B-18
CM287Y
CM287Z
CM289A-B-18
C003
CM313-R-16
CM312-R-16
F003
(-1)
(-2)
CM135Z-U-16
CONNECT F003
TO F001 TO
CONFIG ISO
CM131Y-U-16
SEE FRAME 10
RW287Y-R-16
RW287Z-R-16
C150
LH FLASH
LAMP ISO-1
TRAILER SKT
RH FLASH
LAMP ISO-4
(WDP-R18)
ELECTROHYDRAULICS POWER
CM247EH-R-18
CM292-R-18
C541
(-1)
(-2)
(-18)
C005
CM291-R-18
CM291-R-18
(-17)
C005
EH1U-R-18
EH2S-B-18
CM294-B-18
CM271EH-B-18
RH291-R-18
C187
EHR ISOLATOR
SWITCH
DISENGAGED
ENGAGED
RH292-R-18
RH292-R-18
CM289A-B-18
CTV
SPL A
FRAME 12
CTV
SPL A
FRAME 12
CTV
SPL A
FRAME 12
FR 18


ELECTRO HYDRAULICS
EH73-B-20
EH5D-B-18
EH26-B-18
EH10-B-18
POD 1 AXIS 1
C501
EH1U-R-18
EH38-R-18
EH1C-R-18
EH1A-R-18
SPL A
SPL T
EH7-R-20
EH3A-DR-20
EH18-DR-20
EH22-VI-20
EH30-DR-20
EH29-DR-20
EH19-DR-20
EH27-VI-20
EH5A-DR-20
EH1K-R-18
EH1L-R-18
EH1J-R-18
EH47C-VI-18
C531-1
C531-33
C531-2
C531-9
C531-6
C531-39
C531-18
C531-46
C531-47
C531-19
C531-10
C531-26
C531-31
EHR CONTROLLER 1
EH11B-R-18
EH2F-B-20
EXT CONTROL 1
C521
EH47B-VI-20
EH1F-R-20
EH50-VI-20
EH49-VI-20
EH25-B-18
EH2K-B-18
C531-30
C531-17
C531-45
C531-44
C531-15
C531-22
C531-29
C531-28
EH40-B-18
EH18-B-18
EH74-B-20
SPL H
SPL B
EH2C-B-18
SPL G
EH1H-R-20
EH48B-VI-20
EH2H-B-20
POD 2 AXIS 1
C522
EXT CONTROL 2
EH52-VI-20
EH51-VI-20
EH2N-B-18
EH2M-B-18
EH15-R-18
EH11A-DR-20
EH16-VI-20
EH36-VI-20
EH44-DR-20
EH48C-VI-18
EH1P-R-18
EH1N-R-18
EH1M-R-18
C532-33
C532-1
C532-2
C532-9
C532-45
C532-44
C532-17
C532-3
C532-6
C532-39
C532-18
C532-46
C532-47
EHR CONTROLLER 2
EH2A-B-18
EH1U-R-18
EH2S-B-18
SPL U
EH14D-B-18
EH13D-B-18
EH6D-B-18
FR 19

ELECTRO HYDRAULICS



FR 20

SECTION 55 – ELECTRICAL SYSTEMS

Chapter 7 – Electro-Hydraulic Remote Valve Control System

CONTENTS

Section	Description	Page
55 301	System Description	2
	Electrical Operation	2
	Electro-hydraulic Remote Valve Switch Control Pod Locations	3
	The Switch Control Pod Components	3
	Remote Valve Solenoid Connections	4
	Programmable Controller Location	4
	Switch Valve Color-coding	5
	Electro-hydraulic Control Switch Function Positions	6
	Electro-hydraulic Flow Control Knob	7
	Manual Programmable Operation Switch	7
	Electro-hydraulic Remote Valve Engagement Switch	7
	Fuse Panel Location	8
	Fuse Panel Access	8
	Fuse Location	9
	Control Relays	10
	Main Fuse Panel Location	11
	Main Fuse Panel Access	11
	Main Fuses	12
	Manual Operation	12
	Programmable Mode	14
	Flow Control	17
	Continuity Test - Short to Ground	18
	EHR Electrical Test Procedures	18
	Continuity Test - Check for Open Circuits	19
	Voltage Measurement or Short to Positive Supply Volts	21
	Removal of the Electro-hydraulic Remote Control Valve Switch Pod Assembly	23
	Reassemble of the Electro-hydraulic Remote Control Valve Switch Pod Assembly	25
	Removal of the Electro-hydraulic Remote Control Valve Programmable Controller	25
	Installation of the Electro-hydraulic Remote Control Valve Programmable Controller	25

SYSTEM DESCRIPTION

The electro-hydraulic remote valve control system controls the hydraulics used for operating the remote hydraulic cylinders, motors and other external hydraulic equipment. The system can be operated in manual and automatic modes.

The system is composed of the electro-hydraulic control switch pods, the remote electro-hydraulic valves and a programmable controller. The system can be installed with up to four electro-hydraulic valves.

ELECTRICAL OPERATION

Power in the form of 12 VDC is supplied from the battery buss through fuses EHR / Trailer Plug Power (MFP-1) and IMPL SCKT MN FUSE (MFP-8). These fuses are both 40 amp fuses and located in the Main Fuse Panel.


Power for the Electro-hydraulic remote control valves is fed to fuse EHR POWER (MDP-F31) from MFP-1. Fuse MDP-F31, a 10 amp fuse, feeds power to the open contacts of the ELECTRO HYDRAULICS POWER relay (MDP-M18). The MDP-M18 relay is controlled by power from the EHR ENGAGEMENT SWITCH.

From the MAIN IMPL SOCKET fuse MSP-8 power is fed to contacts on the IMPL SOCKET RELAY (MDP-M17). The contacts on MDP-M17 are open until control voltage is fed to the coil of MDP-M17 from the ACC, accessory position on the tractor ignition switch.

When the contacts on the IMPL SOCKET RELAY close, power is fed to EHR ENGAGEMENT SWITCH C187. The EHR ENGAGEMENT SWITCH is a manually operated switch. The EHR ENGAGEMENT SWITCH must be in the ENGAGED position for the EHR system to function. When the EHR ENGAGEMENT SWITCH is in the ENGAGED position power is fed to the coil of the ELETRO HYDRAULIC POWER relay closing the contacts and allowing power to be fed to the control circuitry of the Electro-hydraulic remote control valves.

ELECTRO-HYDRAULIC REMOTE VALVE SWITCH CONTROL POD LOCATIONS


The electronic switch control pods, 1, are located on the right hand console of the tractor.



1

THE SWITCH CONTROL POD COMPONENTS

The electronic switch control pods consists of the electro-hydraulic control levers, 1, the electro-hydraulic flow control knobs, 2, and the manual-programmable operation switches, 3.




2

The electro-hydraulic control levers, 1, are used for controlling the remote valves manually and for programming the automatic valve controls in automatic mode.

The electro-hydraulic flow control knobs, 2, are used to meter the flow to the hydraulic implements connected to the valves. The knobs are labeled with vertical stripe decals. The decal size corresponds to the flow of oil to the implement. Large stripes correspond to increase flow and shorter stripes correspond to less oil flow to the implement.


The manual-programmable operations switch, 3, has two positions manual and program. The switch controls the mode of operation for the remote hydraulic valves.



3

REMOTE VALVE SOLENOID CONNECTIONS


The electro-hydraulic remote valves are located at the rear of the tractor. Each remote valve has an electric connector on each end of the remote valve solenoids,1.



4

PROGRAMMABLE CONTROLLER LOCATION

The programmable controller, 1, is located in the left rear corner of the tractor cab under the rubber protective floor mat.




5


SWITCH VALVE COLOR-CODING

The electro-hydraulic remote valve control switches and the remote valves are color coordinated to allow for coordinated switch valve hook-up and operation.

1 Blue	Valve 1
2 Green	Valve 2
3 Brown	Valve 3
4 Gray	Valve 4




6




7

ELECTRO-HYDRAULIC CONTROL SWITCH FUNCTION POSITIONS

The electro-hydraulic control switch has four function positions, neutral, 1, extend, 2, retract, 3, and float, 4. The corresponding label located on the top of the pod shows the function positions in symbol form.




8



9

ELECTRO-HYDRAULIC FLOW CONTROL KNOB

The electro-hydraulic flow control knob, 1, is part of the electro-hydraulic control switch pod. The flow control knob meters the flow of oil to the connected implement. Increased flow is shown by the large vertical stripe on the knob, 2. Decrease flow is indicated by the shorter vertical stripes on the knob, 3.




10

MANUAL PROGRAMMABLE OPERATION SWITCH

The manual-programmable operation switch, 1, is part of the electro-hydraulic switch control pod. The switch is used to control the manual or automatic mode of operation for the remote electro-hydraulic valves.


The switch also has an embedded indicator, 2, which illuminates to indicate operation and can illuminate in flash patterns to identify system faults.



11

ELECTRO-HYDRAULIC REMOTE VALVE ENGAGEMENT SWITCH


The electro-hydraulic remote valve engagement switch, 1, also referred to as the EHR ISOLATOR switch, is located on the right hand console. The electro-hydraulic remote valve engagement switch controls the remote electro-hydraulic valves. The switch can be used for an emergency electro-hydraulic remote valve shut-off switch. When the switch is depressed, all four remote valves are disengaged. To engage the valves press the center button, while pulling the switch, 1. Release the center button and the switch will remain extended until pressed down to shut-off the valves.



12

FUSE PANEL LOCATION


The fuse for the electro-hydraulic remote control valves is located in the main distribution panel, 1, located on the right “B” pillar of the cab.



13

FUSE PANEL ACCESS


To gain access to the main distribution panel (MDP), release the latches on the top and bottom, 2, and remove the cover, 1.



14

FUSE LOCATION


The electro-hydraulic remote valve fuse, 1, is labeled F31 on the main distribution panel.



15

CONTROL RELAYS

There are two relays that are used to supply power to the electro-hydraulic remote control valves, located on the main distribution panel. The relays are labeled MDP-M17, 2, IMPL SOCKET RELAY and MDP-M18, 1, ELECTRO-HYDRAULICS POWER. The relays are located as shown.




20015898

16

MAIN FUSE PANEL LOCATION


The electro-hydraulic remote control valve system receives it's power from the main fuse panel, 1, located at the base of the right hand console.



17

MAIN FUSE PANEL ACCESS


To gain access to the main fuse panel, 1, release the tabs, 2, and remove the fuse panel cover, 3.



18

MAIN FUSES

The main fuses used are the MFP-1, EHR / TRAILER PLUG POWER, 1, and the MFP-8, MAIN IMPL SOCKET, 2, fuses. The fuse location on the panel are as shown.




19

MANUAL OPERATION

To operate the system, the ignition switch must be in the RUN position or the tractor must be running. If the tractor is running, set the engine RPM to 2100 to provide the appropriate hydraulic flow to the implement. If the ignition switch is in the RUN position, the valves and system operates electrically but no hydraulic oil will flow. The RUN position may be used for electrical system calibration and testing.


To provide power to the electro-hydraulic remote control valve system, place the EHR ENGAGEMENT SWITCH, 1, in the ENGAGED (up) position. To engage the valves press the center button, while pulling the switch, 1. Release the center button and the switch will remain extended until pressed down to shutoff the valves.



20


Control for the electro-hydraulic remote control valves is provided through the electro-hydraulic switch pods, 2, located on the right hand console. The valve can be operated in either manual or automatic mode.

Before operating the electro-hydraulic remote control valves, insure the attached implement is connected to the proper hydraulic connections. Check that all hydraulic connections are tight. Start the engine on the tractor and warm up the hydraulic oil. When the oil is warm, operate the engine at 2100 RPM to insure proper hydraulic flow.



21

Select the manual mode of operation by placing the manual-programmable switch, 1, in the manual position. Press the top part of the switch to achieve this, 2.




22

The operator controls the four functions EXTEND, 2, NEUTRAL, 1, RETRACT, 3 and FLOAT, 4, on the electro-hydraulic control switch. In manual mode the control switch must be returned to the NEUTRAL position after each function. The primary function for the manual mode is to provide continuous flow of hydraulic oil to hydraulic motors. The manual mode may be used for cylinder operation however, the switch must be returned to the neutral position after full movement of the cylinder or the oil may become overheated by operating the hydraulic system in high pressure stand by.

IMPORTANT: *When operating a hydraulic motor it is important to stop the motor by placing the switch in the FLOAT position. This allows the motor to come to a slow stop rather than a sudden stop. A sudden stop can cause a hydraulic shock, possibly damaging the motor.*


NOTE: *Do not hold or fasten the switch in the extend or retract position after a remote cylinder has reached the end of its stroke. This will overheat the oil and may lead to a failure of hydraulic or drive line components.*



23

PROGRAMMABLE MODE


To operate the system, the ignition switch must be in the RUN position or the tractor must be running. If the tractor is running and the hydraulic oil is warm, set the engine RPM to 2100 to provide the appropriate hydraulic flow to the implement. If the tractor is not running and the ignition switch is in the RUN position, the valves and system operates electrically but no hydraulic oil will flow. The tractor not running and the RUN position may be used for electrical system calibration and testing.



24

To provide power to the electro-hydraulic remote control valve system, place the EHR ENGAGEMENT SWITCH, 1, in the ENGAGED (up) position. To engage the valves press the center button, while pulling the switch, 1. Release the center button and the switch will remain extended until pressed down to shutoff the valves.


To control the electro-hydraulic remote valves, use the electro-hydraulic switch pods, 1, located on the right hand console. The switch pods can be operated manually or can be programmed to operate in a timed mode.



25


Before operating the electro-hydraulic remote control valves, insure the attached implement is connected to the proper hydraulic connections. Check that all hydraulic connections are tight. Start the engine on the tractor and warm the hydraulic oil. When the oil is warm, operate the engine at 2100 RPM to insure proper hydraulic flow.

Select the programmable mode of operation by placing the manual-programmable switch, 1, in the programmable position. Press the bottom part of the switch to achieve this, 2.




26

When the switch is placed in the program mode, the indicator, 1, located in the bottom portion of the switch begins to flash. The indicator flashes for ten seconds to indicate the system is waiting for program information. During the ten seconds the operator programs the system by activating the control switch.



27

Move the control switch from the NEUTRAL position, 1, to either EXTEND, 2, or RETRACT, 3, position. When the switch is moved to either the EXTEND or RETRACT position, the indicator stops flashing. Hold the position until the attached implement is in the desired position for the desired time and then return the switch to the NEUTRAL position. When the switch is placed in the NEUTRAL position, the indicator begins flashing again to indicate the system is waiting for programming in the return function. Once again move the control switch to the appropriate position, EXTEND or RETRACT whichever is appropriate for returning the attached implement to the return position. The indicator stops flashing, signaling the system is now fully programmed.



28

Anytime the indicator begins flashing; the operator has ten seconds to begin programming. If the operator does not program the system during the ten seconds, the indicator stops flashing indicating the system is no longer in programming mode. In order to program the system the manual-programmable control switch must be cycled from programming position to manual position and back to the programming position to once again place the system in the program mode.

The system does not require a return programming function. If a second program command is not required allow the indicator to blink for ten seconds after the switch is in the NEUTRAL position. Once the indicator extinguishes the system is functional and ignores the return function.

Once the system is programmed, the system holds the programmed function as long as the manual-program control switch remains in the program position, even if the power is turned off the system.

When the system is programmed the operator places the control switch in the appropriate position to initiate the programmed function. The system holds the switch in the position for the programmed amount of time then returns the switch to the NEUTRAL position after the function is complete. The operator then initiates the return function, if required, and the system holds the switch for the allotted time and returns the switch to the NEUTRAL position completing the programmed cycle.


In order for the attached implement to work in the same function during the programmed mode, the engine must be run in the same RPM to allow for the proper oil flow to the implement. Otherwise the attached implement does not perform as it did when the system was programmed.

During programming mode, feathering of the attached implement is possible by moving the control switch lever only partially toward the EXTEND or RETRACT positions. The programmed function only activates when the control switch is moved to the full position.

In the FLOAT position no programmed mode is activated and the control switch must be returned to the NEUTRAL position manually.

FLOW CONTROL

The electro-hydraulic remote control switch pods contain flow control knobs, 1, one for each valve. The flow control knobs meter flow from 4 to 117 L/MIN (1 to 31 GPM). To increase flow turn the knob to the taller vertical stripes, 2, to decrease flow turn the knob to the shorter vertical stripes, 3.



29

⚠ WARNING ⚠

Before connecting or disconnecting hydraulic hoses at the remote cylinders, relieve the pressure in the circuit by first starting the engine and then move the control switches fully forward to the "float" position. Then stop the engine. Make sure no one will be injured by moving equipment when relieving pressure in the system. Before disconnecting cylinders or equipment make sure the equipment or implement is supported securely.

Never work under equipment supported by a hydraulic device because it may drop if the control is actuated (even with the engine stopped) or in the event of hose failure, etc. Always use a secure support for equipment, which must be serviced while in the raised position. Make sure that oil contained within the remote cylinders is clean and is of the correct grade.

EHR ELECTRICAL TEST PROCEDURES

Three electrical test will be required to properly troubleshoot the EHR electrical concerns on the tractor.


Each test is described in detail. Ensure all steps are reviewed and followed when testing.

1. Continuity test, short to ground
2. Continuity test, check for open circuits
3. Voltage measurement, short to 12 volts

CONTINUITY TEST - SHORT TO GROUND

Conditions For Performing Tests:

1. Power OFF, Keyswitch OFF, (sometimes battery disconnected or fuse pulled out if specified in procedure).
2. Connectors at each end or ends of circuit disconnected to prevent false readings.
3. Set meter to measure resistance or ohms, and measure circuit resistance. Use black lead to make contact with a plated metal part on the chassis such as the jump start post. Make sure the surface of the part is not corroded. Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors.
4. Determine if measured resistance falls within guidelines specified in the procedure. Three to four ohms indicates a direct short to chassis ground, and must be located and repaired. Higher resistances usually indicate circuit paths through modules, and an additional connector needs to be disconnected to perform the test. More than 100K ohms indicates the circuit is free of shorts to ground.
5. Perform the test according to the following table.



70-580-884

30

NOTE: *All checks are referenced to ground. Connect the black lead of the meter to an appropriate ground connection.*		
Check no.	**Pin or terminal Red lead connection**	**Description**
1	C501-B	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.1 CONNECTOR, RIGHT HAND CONSOLE
2	C501-C	
3	C501-M	
4	C502-B	
5	C502-M	
6	C531-3	EHR CONTROLLER NO. 1 CONNECTOR, LEFT REAR FLOOR OF THE CAB
7	C531-17	
8	C521-1	EXT. CONTROL 1 CONNECTOR, LEFT REAR FLOOR OF THE CAB
9	C503-B	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.2 CONNECTOR, RIGHT HAND CONSOLE
10	C503-C	
11	C503-M	
12	C504-B	
13	C504-M	
14	C532-3	EHR CONTROLLER NO. 2 CONNECTOR, LEFT REAR FLOOR OF THE CAB
15	C532-17	
16	C522-1	EXT. CONTROL 2 CONNECTOR LEFT REAR FLOOR OF THE CAB


CONTINUITY TEST - CHECK FOR OPEN CIRCUITS

Conditions For Performing Continuity Tests:

1. Keyswitch OFF (sometimes disconnect battery or pull fuses).
2. Connectors at both ends of the circuit disconnected. All other connectors must be reconnected to perform test.
3. Set meter to measure resistance or ohms, and measure circuit resistance as illustrated.

   Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors.

   Use the black lead to make contact with the connector pin at the other end of the circuit. Avoid contact with other pins in the connector and the connector case, if it is metal.
4. Determine if measured resistance falls within guidelines specified in the procedure. If the resistance is no more than 3 to 4 ohms, the circuit is continuous. More resistance usually indicates dirty or corroded terminals in connectors, and 100K ohms indicates an open circuit.
5. Perform the test according to the following table.



31

NOTE: *All measurements should show continuity with 2 ohms or less resistance.*

Check no.	Terminal or pin no.		Terminal or pin no.	
	Description	From	To	Description
1	EHR CONTROLLER NO.1. CONNECTOR, LEFT REAR FLOOR OF THE CAB	C531-6	C501-A	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.1 CONNECTOR 1, RIGHT HAND CONSOLE
2		C531-10	C501-J	
3		C531-18	C501-E	
4		C531-19	C501-H	
5		C531-26	C501-K	
6		C531-31	C501-L	
7		C531-39	C501-D	
8		C531-46	C501-F	
9		C531-47	C501-G	
10		C531-12	C502-D	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.1 CONNECTOR 2, RIGHT HAND CONSOLE
11		C531-13	C502-N	
12		C531-24	C502-G	
13		C531-30	C502-L	
14		C531-32	C502-A	
15		C531-36	C502-J	
16		C531-42	C502-C	
17		C531-51	C502-F	
18		C531-52	C502-E	
19		C531-53	C502-H	
20		C531-55	C502-K	

Continued on the next page.


NOTE: *All measurements should show continuity with 2 ohms or less resistance.*				
Check no.	**Terminal or pin no.**		**Terminal or pin no.**	
	Description	**From**	**To**	**Description**
21	EHR CONTROLLER NO. 1 CONNECTOR, LEFT REAR FLOOR OF CAB	C531-44	C521-3	EXT. CONT. 1
22		C531-45	C521-4	
23		C531-28	C511-1	REMOTE VALVE 1A
24		C531-4	C511-2	
25		C531-29	C512-1	REMOTE VALVE 1B
26		C531-23	C512-2	
27		C531-22	C513-1	REMOTE VALVE 2A
28		C531-16	C513-2	
29		C531-15	C514-1	REMOTE VALVE 2B
30		C531-5	C514-2	
31	EHR CONTROLLER NO. 2 CONNECTOR, LEFT REAR FLOOR OF CAB	C532-6	C503-A	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.2 CONNECTOR 1, RIGHT HAND CONSOLE
32		C532-10	C503-J	
33		C532-18	C503-E	
34		C532-19	C503-H	
35		C532-26	C503-K	
36		C532-31	C503-L	
37		C532-39	C503-D	
38		C532-46	C503-F	
39		C532-47	C503-G	
40		C532-12	C504-D	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO.2 CONNECTOR 2, RIGHT HAND CONSOLE
41		C532-13	C504-N	
42		C532-24	C504-G	
43		C532-30	C504-L	
44		C532-32	C504-A	
45		C532-36	C504-J	
46		C532-42	C504-C	
47		C532-51	C504-F	
48		C532-52	C504-E	
49		C532-53	C504-H	
50		C532-55	C504-K	
51		C532-44	C522-3	EXT. CONT. 1
52		C532-45	C522-4	
53		C532-28	C515-1	REMOTE VALVE 3A
54		C532-4	C515-2	
55		C532-29	C516-1	REMOTE VALVE 3B
56		C532-23	C516-2	
57		C532-22	C517-1	REMOTE VALVE 4A
58		C532-16	C517-2	
59		C532-15	C518-1	REMOTE VALVE 4B
60		C532-5	C518-2	

NOTE: *Place the EHR ENGAGEMENT SWITCH in the ENGAGED position.*

VOLTAGE MEASUREMENT OR SHORT TO POSITIVE SUPPLY VOLTS

Conditions For Performing Short To Ground Tests:

1. Keyswitch ON (sometimes OFF, if specified in procedure).
2. Connectors at sensor, switch or potentiometer end disconnected. All other system relays and fuses must be reconnected to perform test.
3. Set meter to measure DC VOLTS, and measure circuit voltage as illustrated. Use the red meter lead to touch the connector pins, one pin at a time, and avoid contact with the case of metal connectors. Use the black lead to make contact with a plated metal part on the chassis such as the jump start post. Make sure the surface of the part is not corroded.
4. Determine if measured voltage falls within guidelines specified in the procedure.
5. Perform the test according to the following table.




70-580-885

32

NOTE: All checks are referenced to ground. Connect the black lead of the meter to an appropriate ground connection. All measurements should read 12 VDC.		
Check no.	**Pin or terminal Red lead connection**	**Description**
1	C501-N	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO. 1 CONNECTOR, RIGHT HAND CONSOLE
2	C531-1	EHR CONTROLLER NO. 1 CONNECTOR, LEFT REAR FLOOR OF THE CAB
3	C531-2	
4	C531-9	
5	C531-33	
6	C521-2	EXT. CONTROL 1 CONNECTOR, LEFT REAR FLOOR OF THE CAB
7	C521-5	
8	C503-N	ELECTRO-HYDRAULIC CONTROL SWITCH POD NO. 2 CONNECTOR, RIGHT HAND CONSOLE
9	C532-1	EHR CONTROLLER NO. 2 CONNECTOR, LEFT REAR FLOOR OF THE CAB
10	C532-2	
11	C532- 9	
12	C532-33	
13	C522-2	EXT. CONTROL 2 CONNECTOR, LEFT REAR FLOOR OF THE CAB
14	C522-5	


2/02

EHR SYSTEM HAS NO POWER




REMOVAL OF THE ELECTRO-HYDRAULIC REMOTE CONTROL VALVE SWITCH POD ASSEMBLY

Press the front of the right side console position switch, 1, to move the right side console as far forward as it will go.




33

Lower the operator's seat with the button on the inside of the right arm rest, 1, and put the seat into the incline position with the handle on the left side of the seat, 2.




34

Lift the entire right side console, 1, up and lay it onto the seat to gain access to the under side.




35




36

Remove the connectors, 1, from the pod to be removed. Remove the connectors by twisting the connector a quarter turn in the counter clockwise direction and pulling the connector from the jack, 2, attached to the switch pod harness. The connectors are part of the tractor harness and remain in the cab while the jack is part of the switch pod assembly.



37

Remove the four mounting screws, 1, from the bottom of the switch pod. Remove the switch pod from the mounting hole in the right hand console by carefully pulling the switch pod assembly from the topside of the right hand console.




38

REASSEMBLE OF THE ELECTRO-HYDRAULIC REMOTE CONTROL VALVE SWITCH POD ASSEMBLY

To reassemble the switch pod, reverse the order of removal.

REMOVAL OF THE ELECTRO-HYDRAULIC REMOTE CONTROL VALVE PROGRAMMABLE CONTROLLER


To gain access to the EHR programmable controller, lift the rubber floor, 1, in the left rear of the cab.



39

There are two connectors on the EHR controller on either side of the unit. Remove the connectors, 1, from the EHR controller by pressing the retainer clip to the rear of the cab and pulling on the connector.

To remove the unit, remove the four mounting bolts, 2, and remove the unit.



40

INSTALLATION OF THE ELECTRO-HYDRAULIC REMOTE CONTROL VALVE PROGRAMMABLE CONTROLLER

To re-install the EHR controller, reverse the removal process.

SECTION 90 – PLATFORM, CAB, AND BODYWORK

Chapter 1 – Cab Components

CONTENTS

Section	Description	Page
90 000	Description	2
	Disassembly and Assembly	3
90 160	Headliner	3
90 160	Cab Trim	6
90 124	Seat	8
90 154	Door Removal	28
90 156	Rear Window	29
90 110	Instrument Cluster	30
41 204	Steering Column	30
35 204	Right-hand Console	34
	Procedures For Right-hand Console Upgrade	37

DESCRIPTION

The cab design for the 70/70A Series is common to all models.

The one-piece roof cap is made of a high- strength thermoplastic and bolts directly to the roof support structure. Under this protective cap is one plastic sheet and a welded steel plate, which divide the top of the cab into two halves.

Removing the front cover gives access directly to the heater/air conditioning unit and associated wiring.

Numerous acoustic pads, shields, and foams have been molded to achieve low cab sound levels. Whenever any panels have been removed, always replace any underlying pads.


DISASSEMBLY AND ASSEMBLY

HEADLINER

The cab headliner can be removed to gain access to the inner roof, wiring harness, and connectors. The headliner consists of three parts: the main plastic control panel, the rear panel, and the front panel.


Plastic Control Panel

1. Remove the two locating screws from the central overhead plastic grill and remove the grill, 1.




1

2. Remove the plastic knobs and the retaining nuts, 1, from the temperature control, fan speed, front wash/wiper and rear wash/wiper switches. Remove the air conditioner mode switch retaining bezel.




2

3. Remove the plastic cover on the left-hand and right-hand side “B” pillars.




3

4. Remove the remaining hardware to lower the main panel.



4


5. Remove the air conditioning mode switch, temperature control and fan speed switch from the left side of the main panel. Remove the wiper/washer switches and disconnect the cigarette lighter wires from the right side of the main panel.



5

Rear Panel


Remove the two allen screws retaining the grab rail/radio panel.



6


Carefully lower the front of the rear panel. Disconnect the two radio speakers and carefully disengage the rear panel from the flange above the rear window and remove the rear panel.

NOTE: *Do not remove the six self-tapping Phillips screws in the center of the rear panel as these are to retain the speakers only.*




7

Front panel
Remove the six Phillips screws retaining the panel.



8


With the panel lowered, disconnect the interior and courtesy lights and remove the panel.



9


CAB TRIM

Left-Hand Side
Remove the two screws, 1, holding the left-hand “B” pillar cover, then remove the cover, 2.




10

Remove the two Phillips screws, 1, securing the cup holder and remove the holder.



11


With the toolbox and the lid of the toolbox, 1, removed, the trim can be eased away from the cab frame and removed, 2.



12


Right-Hand Side (70 Series)
Remove the fabric retaining screws on the under side of the wheel well edge as with the left-hand side.

Remove the two bolts for the implement control bracket, 1, and the cover for the electrical power socket, 2.




13

Remove the two bolts and plate at the top of the console front pivot shaft.




14

Ease the trim away from the right-hand side of the cab frame. The Sidewinder™ console cover will have to be lifted or removed to aid removal.



15

Right-Hand Side (70A Series)
To work on the right hand side console and it's components, lift the entire console and lay it on the seat.



16

SEAT


NOTE: *70A Series art shown for seat removal.*

The seat is best removed through the rear window opening.

Disconnect the two gas struts from the rear window. Support the window in the horizontal position.

Remove the four nuts at the base of the seat, 1. Remove the electrical plug at the rear of the seat connecting it to the main harness and remove the seat through the rear window opening.

NOTE: *The seat is heavy and will require two people to lift it out of the cab.*




17

Seat Removal


NOTE: *The seat is best removed through the sidedoor. The seat is heavy and will require two people or a lifting device to lift it out of the cab.*

1. Remove the four nuts, 1, both sides, at the base of the seat, 2.



18


2. Remove the electrical plug, 1, at the rear of the seat connecting to the main harness, 2.



19


1. Open the rear window, 1, for more clearance, and fully recline the seat, 2, as shown.
2. Adjust the right arm rest, 3, fully back as shown.
3. Adjust the left arm rest, 4, fully forward and down as shown.
4. Adjust the right hand console, 5, to clear the right arm rest, 3.

NOTE: *Adjust the steering wheel to the forward position.*




20

5. Position the seat, 1, to the left door as shown.



21

6. One person should now go to the outside of the tractor to hold the seat, 1, steady. Now two people or a lifting device can safely lift the seat, 1, out of the tractor.




22

Seat Disassembly

The seat is made up of three distinct operating components as follows:


- Seat back and cushion
- Seat forward/aft adjustment rails (connected to the seat back and cushion).
- Seat suspension



23


1. Separate the seat back and cushion, 1 (adjustment rails are attached to the seat), from the suspension, 2, by removing the four nuts, 3.

NOTE: *Adjust the rails forward and aft as needed to access the two nuts in the front and two in the rear.*




24

2. Separate the seat back and cushion, 1, from the adjustment rails, 2, by removing the four bolts, 3, from the base of the cushion.




25

3. Remove the two nuts, 1, that hold the seat switch, 2, in position on the adjustment rails. Remove the switch from the rails.



26


4. Remove the three small plastic nuts, 1, on the rear of the seat that retain the suspension bellows, 2, in place on the suspension frame, pull the bellows upward to expose the seat wire harness connector.



27

5. Cut the small plastic tie strap, 1, that holds the seat harness, 2, in place. Unplug the seat compressor connector, 3, from the main harness.


   Cut the second plastic tie that retains the harness to the upper portion of the suspension and remove the seat cushion and seat back from the seat suspension.



28

6. To remove the rail from the adjustment handle, twist the rail, 1, so that the locating notch on the slide rail lines up with the raised locator on the adjustment lever rod, 2. Remove the rail from the handle.


   Repeat for the rail on the other side of the lever.



29


Inspection of the Seat Adjustment Rails/Lateral Isolator Components

1. On the bottom half of the pivoting seat base, inspect the nylon wear surfaces, 1, and the steel balls, 2, that the base pivots on. Replace if worn or damaged.



30


2. Inspect the seat swivel lever, 1, and components on the top half of the pivoting seat base, 2. Replace any worn components.



31

3. Check the swivel lever locking rod, 1, that is mounted in the top half of the pivot base. The rod should not be worn or bound up in the stanchion brackets, 2.

   Be sure that the cotter pin, 3, is in good condition.




32

4. Inspect the fore/aft adjustment lever, 1, and rails, 2, for wear. The locking pawl, 3, must not be worn so as not to engage the rail slots securely.

   Replace the rails or lever as necessary.

NOTE: *The rails are sold through Parts as a complete assembly only. No individual rail components are sold separately.*



33

Disassembly of the Seat Suspension


CAUTION

All air must be released from the air bag before any work begins on the suspension. Serious injury can result if the air pressure is not released from the air bag.

1. Carefully pull the bellows, 1, over the small plastic retaining clips, 2 at the top and bottom of the suspension. Be careful not to tear the holes in the rubber bellows.

   Remove the bellows from the suspension frame.


NOTE: *It is not necessary to remove the clips from the suspension unless they are damaged and need replacement.*



34


2. Obtain a wooden block, 1, approximately 165 mm (6 1/2″) long and place it at the rear of the seat between the upper and lower suspension plates, 2.

   The wood block will support the suspension when the air bag is removed.




35

3. Remove the compressor supply tube, 1, from the fitting, 2, at the top of the air bag.




36

4. Remove the bolt, 1, from the top of the air bag retaining plate. The fitting, 2, can stay in place on the air bag.



37

5. Flip the suspension over (leave the wood block in place) and remove the Phillips-head screw, 1, from the bottom of the air bag and suspension lower plate.
6. The air bag is now free from the suspension and can be removed by pulling it out the front of the suspension.




38

7. Remove the nut, 1, from the long retaining pin, 2, that spans the rear of the lower suspension plate, 3.

   The pin fits into a hollow tube on the bottom of the scissors suspension. Pull the pin from the suspension and plate.
8. Separate the scissors suspension linkage from the lower suspension plate by twisting it to the left or right enough to allow one of the front bottom rollers to come out from under the bottom plate guide track.


   Lift the scissors suspension from the bottom plate.



39

9. Cut the two plastic tie straps, 1, that retain the compressor wire harness, 2, to the scissors suspension.

   Remove the two small screws, 3, that hold the compressor, 4, in place and remove the compressor from the suspension.




40

10. Remove the retaining spring nut, 1, from the rod end of the dampening shock absorber, 2.


    Remove the nylon roller, 3, off of the base end of the shock absorber pivot and slide the shock absorber off of the suspension.

    Remove the nylon bearings from the shock absorber pivots. The white bearing, 4, is on the rod end, and the black bearing, 5, is on the base end.




41

11. Remove the two nuts, 1, that hold the base end (bracket end) of the fore/aft isolator shock absorber, 2, to the top plate, 3.




42

12. Remove the two screws, 1, that hold the fore/aft isolator locking lever, 2, to the top plate.
13. Flip the suspension so that the top plate is down. Remove the scissors suspension from the top plate by disengaging the front rollers from the guide track. Roll the rear rollers from their guide track and lift the scissors from the top plate.



43

14. Remove the fore/aft isolator shock absorber, 1, fore/aft isolation locking handle, 2, and remaining bushings and rollers from the scissors suspension by sliding them off of their respective pivot points.




44

Inspection of the Seat Suspension Components

1. Check the rubber bumpers, 1, on the top plate for wear. The bumpers do not need to be removed unless they show significant wear.

   The bumpers can be taken off of the top plate by removing the center screw.




45

2. Use an ohm meter, 1, to check the release solenoid coil, 2, for an open circuit and total coil resistance.


   Place the ohm meter leads across the two white wires in the compressor harness, 3. The meter should show continuity with a total resistance reading of approximately 31 ohms.

   If an open circuit or a circuit with high resistance is found, the entire compressor must be replaced as the solenoid coil is not sold separately from the compressor.




46

3. To remove and inspect the release solenoid valve, 1, unscrew the small nut, 2, and lift the solenoid coil, 3, off of the valve stem.



47

4. Unscrew the release valve, 1, from the compressor body, 2.



48

5. The release valve can be disassembled and cleaned by unscrewing the stem, 1, from the valve body, 2.

   The valve consists of an O ring, 3, a seat, 4, a spring, 5, a solenoid stem and a valve body.


   Clean any contamination from the valve. Make sure the holes in the valve body are clear of debris.

   None of the solenoid valve parts or the valve itself are available through Parts. If the valve is found to be faulty, the complete compressor must be replaced.

6. Reassemble the release valve and screw it into the compressor body. Use pipe thread sealant (such as part # L56531DS) on the valve threads. The outlet hole of the valve can point in any direction when tightened into the body.

7. Reassemble the solenoid coil to the release valve using the hardware removed.

NOTE: *There is a stepped washer and rubber seal under the solenoid. The step of the washer fits into the solenoid body.*




49

8. Use an ohm meter, 1, to check the compressor motor, 2, for an open circuit and total coil resistance.


   Place the ohm meter leads across the orange and black wires in the compressor harness, 3. The meter should show continuity with a total resistance reading of approximately 0.5 ohms.

   If an open circuit or a circuit with high resistance is found, the entire compressor must be replaced as the motor is not sold separately from the compressor.



50

9. On the bottom of the compressor, check the small fiber filter, 1, for contamination and clean as necessary. To clean the filter, remove the small center screw, 2.




51

10. Check the air bag supply tube, 1, and make sure that the ferrules and tubing are not damaged. Replace if necessary.

    Connect the air bag to the supply tube. Activate the compressor motor by applying 12 volts to the orange wire in the compressor harness connector. Attach the black wire to ground. The compressor will activate and inflate the air bag. Place the bag in a container of water and check for air leaks.

⚠ CAUTION ⚠


Do not over inflate the air bag using the compressor. Inflate only enough to check for leaks.



52

11. Check the fore/aft isolator locking handle, 1, for broken springs or damaged parts.

    The handle is available only as a complete assembly and must be replaced if damage is found to any of the components.




53

12. Remove the nut, 1, from the rod end of the fore/aft isolator shock absorber, 2. Remove the washers, 3, rubber bushings, 4, and bracket, 5.

    Inspect all components for wear and replace as necessary.


    Reassemble the washers, bushings and bracket to the rod end of the shock absorber and tighten the nut securely.

NOTE: *The "L" portion of the bracket (contains two square holes) faces away from the shock absorber body.*



54


13. Inspect the dampening shock absorber, 1, for wear or damage. If the adjustment knob, 2, requires replacement, drive the roll pin, 3, out of the knob and replace with new.
14. Inspect all the bushings and rollers on the suspension and replace any that are worn or damaged.
15. Inspect the scissors assembly for cracked welds or broken components. Replace if necessary.



55

Assembly of the Seat Suspension


1. Place a small amount of grease on the OD and ID of the tube bushings. Install the two bushings, 1, into the bottom rear tube, 2, of the scissors suspension.



56


2. Place a small amount of grease on the pivots for the dampening shock absorber. Install the nylon bearings onto the dampening shock absorber pivots. The white bearing, 1, is on the rod end and the black bearing, 2, is on the base end.

   Slide the dampening shock absorber, 3, onto the scissors suspension pivots and retain the rod end on the pivot with the spring nut, 4.



57


3. Lubricate the ID of the rollers (black in color). Install the rollers, 1, onto the front pivots of the scissors suspension, 2.



58

4. Place a small amount of grease on the guide tracks, 1, of the lower plate, 2.


   Install the scissors suspension, 3, into the lower plate of the seat by twisting the scissors suspension right or left and sliding the scissors into the plate rails.



59


5. Line up the holes in the lower plate with the tube at the rear of the scissors suspension. Install the long pivot pin, 1, into the rear tube of the suspension and install the nut, 2, on the pin. Tighten securely.

NOTE: *The bolt has a locating point on it to keep it from turning during assembly. Be certain to line up the raised point with the notch in the lower plate.*



60


6. Place a small amount of grease on the OD and ID of the bearing, 1, for the fore/aft isolator locking handle assembly, 2. Slide the bearing end of the handle onto the rear left pivot of the scissors suspension.



61

7. Lubricate (with grease) the ID and OD of the spacer, 1, and bearing, 2, for the fore/aft isolator shock absorber, 3. Install the spacer over the bearing for the shock absorber. Install the bearing and spacer on the right rear pivot of the scissors suspension. Install the base end of the shock absorber onto the bearing.


   Make sure that the bracket, 4, for the rod end of the shock absorber is facing upward.



62

8. Lubricate the ID and OD of the rollers for the upper pivots of the scissors suspension with grease. Install the rollers, 1, onto the upper pivots of the scissors suspension.


   Install a wooden block, 2, between the front bars of the scissors suspension to hold it up during assembly.



63


9. Install the compressor assembly, 1, onto the scissors suspension by attaching the plastic mount, 2, to the mounting tab using the two small screws. The compressor sits on top of the tab and the bolts come into the plastic mount from the bottom.

   Route the compressor wire harness, 3, under the air bag upper mounting plate, 4. Use two plastic tie straps, 5, to hold the compressor harness to the suspension.




64

10. Insert the air bag into place in the suspension. Install the top air bag mounting bolt, 1. Attach the supply tube, 2, to the top fitting on the air bag. Make sure that the supply tube fittings at the compressor and the air bag are tight.




65

11. Flip the assembly over so that the bottom plate is facing upward. Install the air bag bottom mounting screw, 1, into the bottom of the air bag.
12. Flip the assembly back over so that the four rollers are facing upward. Lubricate the guide tracks of the upper plate with grease. Install the plate onto the scissors assembly. Make sure the four top rollers enter the guide tracks properly.




66

13. Install the two screws, 1, that hold the fore/aft isolator locking lever, 2, to the top plate.



67


14. Install the two nuts, 1, that hold the base end (bracket end) of the fore/aft isolator shock absorber, 2, to the top plate, 3.
15. Remove the wood block from the suspension and allow it to collapse onto the air bag.



68

16. Reinstall the bellows, 1, around the suspension by hooking it onto the small retaining clips, 2.

    Leave the three small nuts off of the rear of the bellows for access to the wiring harness during reassembly of the three seat components.




69

Reassembly of the Seat Adjustment Rails/Lateral Isolator


1. Reinstall the adjustment rails, 1, onto the lever, 2, by lining up the notch on the handle and sliding the rail onto the handle.

NOTE: *The fore/aft adjustment lever has an offset to it that is to the right hand side of the seat when the rails are properly installed. The rails will be under the handle when assembled correctly.*



70


2. Reinstall the fore/aft slide rail and handle assembly onto the bottom of the seat using the four mounting bolts, 1, and spacers.



71

3. Reassemble the pivot handle, 1, to the top pivot plate using the bolt and nut, 2. Make sure the plastic washer is in proper position between the handle and plate.

   Install the pivot handle spring, 3, in position on the top plate and cotter pin, 4.




72

Seat Installation


NOTE: *The seat is best installed through the side door. The seat is heavy and will require two people or a lifting device to lift it up into the cab. Insure that the steering wheel is in the forward position, the right hand console is adjusted forward and the rear window is opened.*

1. With the seat in the reclined position as described in Figure 19, two people or a lifting device can lift the seat, 1, into the cab.




73

2. Position the seat in its place and replace the four nuts, 1.



74


3. Reconnect the electrical plug, 1, at the rear of the seat connecting to the main harness, 2.



75

DOOR REMOVAL


Remove the C clip, 1, from the bottom of the upper and lower hinge pins.



76

Take off the gas strut by removing the retaining clip, 1, and pulling the end of the strut from the ball joint, 2.


With the door well supported, punch out the upper and lower hinge pins on each door and remove the door.



77


REAR WINDOW

Disconnect the two struts, 1, from the rear window.



78


Remove the rear wiper plastic cover and disconnect the washer tube, 1, and electrical supply, 2, to the wiper motor, 3.



79

Unscrew the two bolts at the top of each hinge and remove the window.

NOTE: *The rear window is a one-piece sheet glass. Make sure that the window is well supported before the screws are removed.*




80

INSTRUMENT CLUSTER

Remove the two Phillips-head screws, 1, on either side of the instrument cluster.


With the cluster pulled out, disconnect the harness, 2, and ground strap, 3, and remove the cluster.



81


STEERING COLUMN

Remove the electronic instrument panel. Disconnect the harness, 1, and ground strap, 2, on the back of the panel and remove.




82

To gain better access to the steering column, remove the left-hand and right-hand plastic shield below the steering column.



83


Use a suitable puller to remove the steering wheel.



84


Disconnect the wires from the light switch, hazard warning switch and the ignition switch.

Remove the four bolts retaining the instrument cluster shroud and detach any remaining wires.




85

Remove the two halves of the small plastic cover, 1, surrounding the steering column containing the directional control and ether button, 2.




86

Remove the instrument cluster shroud.




87

Remove the two screws and the directional signal lever.




88

Remove the four retaining bolts supporting the tilt telescopic steering column.



89

Remove the column. The assembly procedure is the reverse of the disassembly procedure.




90

RIGHT-HAND CONSOLE

NOTE: *All the transmission and hydraulic controls are housed in the right-hand console control panel. For ease of servicing, the console can be removed as follows:*

70A Series


To work on the right hand side console and it's components, lift the entire console and lay it on the seat.



91


70 Series

1. Remove the lower plastic side panel, 1.
2. Remove all the control knobs to remote levers, potentiometer controls, PTO and throttle levers, 2, allowing the main console to be lifted.




92

3. Once lifted, disconnect all electrical plugs to the switches and potentiometers and remove the console top.




93

4. Disconnect the right-hand console wiring harness connector C005, 1, as shown.




94

5. Disconnect the remote cables at the lever, 1.




95

6. Disconnect the throttle cable,1, and remote cable double clamp, 2.




96

7. The complete console can now be removed by lifting squarely under the mounting frame. The rear bushing support,1, will separate first.



97


8. With the rear support out, the frame can swing out for removal of the front pivot, 1.
9. Remove the wiring harness, remote valve levers, right-hand controller, HPL potentiometer, HPL quadrant lever and linkages, and the transmission shift controller from the frame, 2.



98

Sidewinder fully removed.

NOTE: *The electric motor, 1, driving the sidewinder does not have to be removed.*




99


PROCEDURES FOR RIGHT-HAND CONSOLE UPGRADE (BEFORE SERIAL # D403821 70 SERIES)

NOTE: *Removal of the seat will give greater access in removing the right-hand console when upgrading to the new-style console, but is not necessary.*

Remove gusset, 1, at points A and B. Grind any rough edges from the frame created by cutting.




100




101

1. Remove lower plastic side shield, 1.
2. Remove all the control knobs to remote levers, potentiometer controls, PTO and throttle levers, 2, allowing the main console to be lifted.




102

3. Once lifted, disconnect all electrical plugs to the switches and potentiometers and remove the console top.




103

4. Disconnect the right-hand console wiring harness connector C005 as shown.




104

5. Disconnect the remote cables at the lever, 1.




105

6. Disconnect throttle cable, 1, and remote cable double clamp, 2.




106

7. The complete console can now be removed by lifting squarely under the mounting frame. The rear bushing support will separate first.



107


8. With the rear support out the frame can be swung out for removal of the front pivot, 1.
9. Remove the wiring harness, remote valve levers, right-hand controller, HPL potentiometer, HPL quadrant lever and linkages, and the transmission shift controller from the frame, 2.



108


To Modify The Old Frame

1. Remove gusset, 1, at points A and B. Grind any rough edges from the frame created by cutting.




109

2. Straighten the piece removed and weld into the frame assembly as shown.




110

3. Remove the quadrant lever stop bolts, and weld hole, 1, shut. Grind the surfaces flush. This will allow you to properly drill the correct hole locations identified in step 15.
4. Remove potentiometer mounting bracket, 2, from the frame by grinding off spot welds, 3.



111

5. Drill the following holes in the side plate, at the following locations, by measuring or using the template provided.
   a. A 9/32″ hole from the top, down 2-1/2″ and in 1/2″ from the right.
   b. A 7/16″ hole from the top, down 2-1/2″ and in 2-5/16″ from the right. File the hole to a 7/16″ square to accept the square shoulder of the carriage bolt.
   c. A 9/32″ hole from the top, down 2-15/16″ and in 5-13/32″ from the right.
   d. A 9/32″ hole from the top, down 2-15/16″ and in 6-3/16″ from the right.




112

6. Paint the frame, as required after modifications.


To Replace The Old Frame, Part #86501337, With a New Frame Part #86506517

1. Attach the new HPL quadrant lever, 1, part #86506512, nylon washers, 2, part #86504705 from the old quadrant, carriage bolt, 3, part #374892 from the old quadrant, plate, 4, part #86506513, spring, 5, part #47747, washer, 6, part #80702, lock nut, 7 part #100037, M6 x 30 bolt, 8, part #43117, and nut, 9, part #353308.




113

2. Attach potentiometer, 1, to support, 2, part #86506515, using M5 x 20 bolt, 3, part #86511827, and a nut.
3. Attach the potentiometer and support to the frame using two 1/4″ x 3/4″ self-tapping bolts, 4.
4. Connect potentiometer lever, 5, and rod, 6, to quadrant lever, 7.
5. Install the wiring harness, remote valve levers, the right-hand controller, and the transmission shift controller to the frame.
6. Install the assembled frame in the cab.




114

7. Reconnect the right-hand console wiring harness at connector C005.
8. Reconnect the remote cables at the lever.



115


9. Reconnect throttle cable, 1, and remote cable double clamp, 2.



116


10. Install the HPL quadrant stop knob, 1, part #86506579, stop block, 2, part #86506520, block, 3, part #86506532, and M6 locknut in the new console top, part #86506518.
11. Attach the necessary decals to the console top.
12. Transfer all switches, lights, and potentiometers from the old console top to the new console top.
13. Install the new console top.

NOTE: *To confirm the electrical connections to the proper switch, light, or potentiometer, refer to the Repair Manual, Section 55.*



117

14. Install lower plastic side shield, 1.
15. Install the seat, if removed.
16. Download the latest version of software for the HPL control to function properly.
17. Calibrate the HPL and verify proper operation.



118

SECTION 90 – PLATFORM, CAB, AND BODYWORK

Chapter 2 – Engine Hood Removal

CONTENTS

Section	Description	Page
90 100	Specifications	2
	Description of Operation	3
	Disassembly and Repair	4
	Hood	4
	Hood and Upper Engine Frame	9

SPECIFICATIONS

Material	Fiber glass
Lighting	4 Headlights 2 Work lights
Gas springs	2
Access doors	2
Safety latch	1

Torques

Rear pivot bolts	128 N·m (95 ft lbs)
Safety latch bolts	41 N·m (30 ft lbs)
Engine upper frame	81 N·m (60 ft lbs)
Alternator mount	61 N·m (45 ft lbs)
Exhaust pipe	43 N·m (32 ft lbs)

DESCRIPTION OF OPERATION

The engine hood is hinged at the rear to allow easy access to the engine components. Two access doors are provided for daily service. When the left door is open, the hood release can be activated by pushing forward and up.

The hood can open to one of two positions due to gas springs and is held in place by a slide latch. A side handle is provided to assist in opening the hood and to pull it closed.

To close the hood from the full open position, push up on the slide latch and pull the hood down using the handle until it latches in the down position.

DISASSEMBLY AND REPAIR


At times it may be advantageous to remove the engine hood to gain access to the engine and other assemblies.

HOOD REMOVAL

To remove the hood, two different procedures may be used - one involves removing the hood only, while the second involves removing the hood with the upper engine frame support.


HOOD ONLY

1. Park the tractor on a level surface and engage the parking brake.
2. Pull the hood release, 1, and open the hood to the Second position.




1

3. Support the hood with nylon straps, 1, and a suitable hoist.




2

4. Disconnect the electrical light connector, 1, at the left rear of the hood pivot.



3

5. With the weight supported by the hoist, remove the lower gas spring ends, 1 and 3, and the safety latch lower bolt assembly, 4.
6. Carefully remove the two pivot bolts, 2, and raise the hood and assembly from the tractor.



4

HOOD INSTALLATION


Reassemble in the reverse order.

Torque the pivot bolts to 128 N·m (95 ft lbs). Torque the safety latch bolt to 41 N·m (30 ft lbs).

REMOVE HOOD AND UPPER ENGINE FRAME ASSEMBLY


This procedure is required if the engine head is to be removed while the engine is in the tractor.

1. Park the tractor on a level surface and engage the parking brake.
2. Remove the battery cover and disconnect the negative battery cables, 1.




5

3. Open the hood to the first position, 1, and remove the left, 3, and right access doors and hinge mounts.




6

4. Disconnect the electrical light connector, 1, at the left rear of the hood pivot.




7

5. Remove the engine exhaust pipe from the right side of the tractor.




8

6. Support the hood and frame assembly with nylon straps at the rear eyelets using a steel rod and at the side handles with a suitable hoist.




9

7. Remove the turbo to muffler connection, 1.
8. Remove the turbo to intake, 2, or intercooler connector, and remove the air cleaner to turbo inlet hose, 3.
9. Remove the bolts at the front of the frame where it attaches to the engine.
10. Remove the water filter assembly, 4, but don't remove the hoses.




10

11. Loosen the fan belt and remove the alternator, 1.




11

12. Remove all wiring connections on both sides of the engine, then remove the front main harness from the support rail and route it through the frame opening at the rear.




12

13. Turn the cab heater valves, 1, off at both ends of the intake manifold. Disconnect the hoses and plug them to prevent coolant loss.
14. Route the two heater hoses through the back of the engine frame opening.



13


15. Remove the air cleaner intake horn, 1.
16. Remove the air-conditioner hose clamps and retainers, 2, from the hood frame and pull the hose away from the frame.



14


17. Remove the receiver/drier retainer from the left rear corner of the engine frame.

NOTE: *DO NOT remove the hose from the drier.*



15

18. With the hood and frame weight supported by the hoist, carefully remove the rear frame support bolts from the back of the engine head.
19. Raise the hood and frame assembly away from the tractor and store in a suitable location.



16

INSTALLING HOOD AND UPPER ENGINE FRAME ASSEMBLY

Reinstall the hood and frame assembly in the reverse order of disassembly. Refer to the torque specifications section of this chapter for assemble torques.

SECTION 90 – PLATFORM, CAB, AND BODYWORK

Chapter 3 – Cab Removal

CONTENTS

Section	Description	Page
90 150	Specifications	2
	Special Tools	2
	Description of Operation	3
	Disassembly and Repair	4
	Cab Removal	4
	Cab Installation	10

SPECIFICATIONS

Cab type	Unitized with ROPS
Doors	2 with locks
Cab glass	Tinted, tempered
Hinged windows	Rear, right, 2 position

Torques

Cab mounts		217 N·m (160 ft lbs)
Mount brackets to transmission		240 N·m (177 ft lbs)
Mount brackets to rear axle	8670	306 N·m (226 ft lbs)
	8770, 8870, and 8970	240 N·m (177 ft lbs)
Air-conditioner compressor mounts		55 N·m (40 ft lbs)
Exhaust pipe bolts		43 N·m (32 ft lbs)
Remote cable ends		7.6 N·m (6 ft lbs)

SPECIAL TOOLS

Description	Tool Number	Usage
Cab lifting fixture	FTC213997B	Remove cab

DESCRIPTION OF OPERATION


The cab is a unitized two-door assembly that is mounted on rubber pads to the tractor frame. The cab is a ROPS structure and no attempts to straighten or repair the frame should be considered if it is damaged.

The cab should only be removed for major repairs. If the transmission or rear axle required internal service, the cab should be removed. A cab lifting fixture is available to aid in cab removal.

DISASSEMBLY AND REPAIR


CAB REMOVAL

1. Remove the battery cover and disconnect the negative battery cables, 1.
2. Remove fuel tank as described in “Fuel Tank Removal,” - Section 10, Chapter 6.




1

3. Remove both doorsill plates, the cab floor mat, and the floor plate to gain access to the hydraulic hoses.




2

4. Each hose and line is identified, 1 - 9. Disconnect and cap each hose and line:
   - 1 Left-hand steering line
   - 2 Right-hand steering line
   - 3 Brake valve supply line
   - 4 Right-hand brake line
   - 5 Brake valve return to sump line
   - 6 Steering valve supply line
   - 7 Steering valve load sensing line
   - 8 Steering return to sump line
   - 9 Left-hand brake line



3

5. Disconnect the transmission hand brake cable from the actuator arm, 1, located on the left side of the rear axle housing.




4

NOTE: *DO NOT discharge the air- conditioning system. Remove the cab without discharging the air-conditioning system.*


NOTE: *70 Series art shown.*

6. **Without** disconnecting and evacuating the air-conditioning system, remove the condenser,1, from the front of the tractor and wrap in bubble wrap to protect the evaporator fins from damage.



5


7. Remove the receiver/drier, 1.
8. Remove the left hood access door and hinge mount, 2.



6


9. Remove the compressor. Do not remove the hoses.
10. Remove the tie wraps and clamps retaining the air-conditioning hoses.

NOTE: *70 Series art shown.*




7

11. Store the compressor, 1, and the condenser, 2, and hoses inside the cab.
12. Tie the receiver/drier, 3, to the cab grab handle using a plastic tie wrap.




8

13. Remove exhaust pipe. 1.
14. Remove the right hood access door, 2, and hinge mount. (Hood removed for clarity.)




9

15. Disconnect the hand throttle cable, 1, from the injection pump.




10

16. Disconnect the foot throttle cable ball and socket joint, 1, at the front of the cab.
17. Release the throttle cable, 2, from the retainer.




11

18. Close the heater taps, 1, on the left-hand side of the engine at each end of the intake manifold.
19. Disconnect and plug the hoses to prevent loss of coolant from the system.




12

20. Disconnect the connector, 1, and ground strap, 2, at the right-hand rear corner of the cab.
21. Disconnect the two connectors for the chassis control module at the left-hand rear corner of the cab.



13


22. On the 70A Series, Remove the remote valve solenoid connectors, 1, from all the remote valve sections. If the connectors are not marked, remark the connectors.



14


Remove the two allen screws securing each remote control valve sleeve, 1, to the valve assembly.

23. Unscrew the locknut, 2, at the end of each remote control valve sleeve.




15

24. Unscrew each sleeve, 1, and, using a suitable punch and hammer, remove the roll pin, 2, which holds the operating cable to the valve.



16

25. Disconnect the panel holding the remote valve flow control knobs, 1, from the rear of the cab or loosen the setscrews that hold the cables to the valve stems, 2.




17

26. Remove the two center bolts in the cab roof and attach the cab lifting fixture, 1, FTC213997B to the cab.


⚠ WARNING ⚠

When attaching the lifting fixture to the cab roof, only use the lifting bolts, 2, supplied with the fixture. The use of any other type of bolt may result in roof damage or the inability of the tool to support the cab.




18

27. Remove the cab mounting bolts, 1, at the front of the cab.



19

28. Remove the cab mounting bolts, 1, at the rear of the cab.
29. Using a suitable overhead hoist, carefully lift the cab from the tractor and place it on a suitable stand to prevent damage to the cables.



20


CAB INSTALLATION

1. Installation of the cab follows the removal procedure in reverse.

WARNING

Be sure that no cables or lines are pinched or damaged during cab installation. Assistance from additional personnel is recommended.

2. During installation, ensure the cab mounting bolts are correctly installed and tightened to a torque of 217 N·m (160 ft lbs). Install the mount assembly in order from 1 - 7. When installing all remaining components, tighten to the specified torque shown in the “Specifications” portion of this chapter.



21